

50th

VOLUME 25

OCTOBER, 1937

NUMBER 10

PROCEEDINGS
of
The Institute of Radio
Engineers



Application Blank for Associate Membership on Page XIX

Institute of Radio Engineers Forthcoming Meetings

ROCHESTER FALL MEETING

Sagamore Hotel
Rochester, New York
November 8, 9, and 10, 1937

ATLANTA SECTION

October 21, 1937

CINCINNATI SECTION

October 19, 1937

CLEVELAND SECTION

October 28, 1937

DETROIT SECTION

October 15, 1937

LOS ANGELES SECTION

October 19, 1937

NEW YORK MEETING

November 3, 1937

PHILADELPHIA SECTION

November 4, 1937

WASHINGTON SECTION

October 11, 1937

PROCEEDINGS OF
The Institute of Radio Engineers

VOLUME 25

October, 1937

NUMBER 10

Board of Editors

ALFRED N. GOLDSMITH, *Chairman*

R. R. BATCHER

B. E. SHACKELFORD

P. S. CARTER

K. S. VAN DYKE

F. W. GROVER

H. P. WESTMAN, *ex officio*

J. W. HORTON

L. P. WHEELER

G. W. PICKARD

L. E. WHITTEMORE

WILLIAM WILSON

CONTENTS

PART I

Institute News and Radio Notes.....	1241
Pacific Coast Meeting.....	1241
Committee Work.....	1241
Institute Meetings.....	1241

PART II

Technical Papers

A Negative Grid Triode Oscillator and Amplifier for Ultra-High Frequencies.....	1243
A. L. SAMUEL	
Sudden Disturbances of the Ionosphere.....	1253
J. H. DELLINGER	
Field Strength Observations of Transatlantic Signals, 40 to 45 Megacycles.....	1291
H. O. PETERSON AND D. R. GODDARD	
A Transformation for Calculating the Constants of Vacuum Tubes with Cylindrical Elements.....	1300
W. VAN B. ROBERTS	
Simple Method for Observing Current Amplitude and Phase Relations in Antenna Arrays.....	1310
JOHN F. MORRISON	
Radiation from Rhombic Antennas.....	1327
DONALD FOSTER	
Characteristics of the Ionosphere at Washington, D. C., August, 1937...	1354
T. R. GILLILAND, S. S. KIRBY, N. SMITH AND S. E. REYMER	
Contributors to This Issue.....	1357

The Institute of Radio Engineers

GENERAL INFORMATION

INSTITUTE. The Institute of Radio Engineers was formed in 1912 through the amalgamation of the Society of Wireless Telegraph Engineers and the Wireless Institute. Its headquarters were established in New York City and the membership has grown from less than fifty members at the start to several thousand.

AIMS AND OBJECTS. The Institute functions solely to advance the theory and practice of radio and allied branches of engineering and of the related arts and sciences, their application to human needs, and the maintenance of a high professional standing among its members. Among the methods of accomplishing this is the publication of papers, discussions, and communications of interest to the membership.

PROCEEDINGS. The PROCEEDINGS is the official publication of the Institute and in it are published all of the papers, discussions, and communications received from the membership which are accepted for publication by the Board of Editors. Copies are sent without additional charge to all members of the Institute. The subscription price to nonmembers is \$10.00 per year, with an additional charge for postage where such is necessary.

RESPONSIBILITY. It is understood that the statements and opinions given in the PROCEEDINGS are views of the individual members to whom they are credited, and are not binding on the membership of the Institute as a whole. Papers submitted to the Institute for publication shall be regarded as no longer confidential.

REPRINTING PROCEEDINGS MATERIAL. The right to reprint portions or abstracts of the papers, discussions, or editorial notes in the PROCEEDINGS is granted on the express condition that specific reference shall be made to the source of such material. Diagrams and photographs published in the PROCEEDINGS may not be reproduced without making specific arrangements with the Institute through the Secretary.

MANUSCRIPTS. All manuscripts should be addressed to the Institute of Radio Engineers, 330 West 42nd Street, New York City. They will be examined by the Papers Committee and the Board of Editors to determine their suitability for publication in the PROCEEDINGS. Authors are advised as promptly as possible of the action taken, usually within two or three months. Manuscripts and illustrations will be destroyed immediately after publication of the paper unless the author requests their return. Information on the mechanical form in which manuscripts should be prepared may be obtained by addressing the secretary.

MAILING. Entered as second-class matter at the post office at Menasha, Wisconsin. Acceptance for mailing at special rate of postage is provided for in the act of February 28, 1925, embodied in Paragraph 4, Section 412, P. L. and R., and authorization was granted on October 26, 1927.

Published monthly by

THE INSTITUTE OF RADIO ENGINEERS, INC.

Publication office, 450-454 Ahnaip St., Menasha, Wis.

BUSINESS, EDITORIAL, AND ADVERTISING OFFICES

Harold P. Westman, *Secretary*

330 West 42nd Street, New York, N. Y.

INSTITUTE SECTIONS

- ATLANTA—Chairman, N. B. Fowler; Secretary, G. S. Turner, Federal Communications Commission, 411 Federal Annex, Atlanta, Ga.
- BOSTON—Chairman, H. W. Lamson; Secretary, E. B. Dallin, 64 Oakland Ave., Arlington, Mass.
- BUFFALO-NIAGARA—Chairman, George C. Crom; Secretary, E. C. Waud, 235 Huntington Ave., Buffalo, N. Y.
- CHICAGO—Chairman, J. K. Johnson; Secretary, V. J. Andrew, 7221 San Francisco Ave., Chicago, Ill.
- CINCINNATI—Chairman, G. F. Platts; Secretary, M. M. Wells, Crosley Radio Corporation, 1329 Arlington St., Cincinnati, Ohio.
- CLEVELAND—Chairman, R. A. Fox; Secretary, R. L. Kline, Winteradio, Inc., 3014 Lorain Ave., Cleveland, Ohio.
- CONNECTICUT VALLEY—Chairman, F. H. Scheer; Secretary, C. E. Keeler, 59 Fairfield St., Springfield, Mass.
- DETROIT—Chairman, R. L. Davis; Secretary, H. S. Gould, 214 Tuxedo Ave., Detroit, Mich.
- EMPORIUM—Chairman, M. I. Kahl; Secretary, M. C. Hoffman, Hygrade Sylvania Corporation, Emporium, Pa.
- INDIANAPOLIS—Chairman, V. C. MacNabb; Secretary, I. M. Slater, 6433 E. Shelley Ave., Indianapolis, Ind.
- LOS ANGELES—Chairman, Douglas Kennedy; Secretary, F. G. Albin, United Artists Studios, 1041 N. Formosa Ave., Los Angeles, Calif.
- MONTREAL—Chairman, A. M. Patience; Secretary, S. Sillitoe, 1261 Shearer St., Montreal, Que., Canada.
- NEW ORLEANS—Chairman, L. J. N. Du Treil; Secretary, G. H. Peirce, Electrical Research Products, Inc., 1631 Canal Bank Bldg., New Orleans, La.
- PHILADELPHIA—Chairman, A. F. Murray; Secretary, R. L. Snyder, 103 Franklin Rd., Glassboro, N. J.
- PITTSBURGH—Chairman, R. T. Gabler; Secretary, A. F. Shreve, R. D. 9, Box 95, P. O. Box 16, Pittsburgh, Pa.
- ROCHESTER—Chairman, Lee A. Du Bridge; Secretary, H. A. Brown, 89 East Ave., Rochester, N. Y.
- SAN FRANCISCO—Chairman, V. J. Freiermuth; Secretary, C. J. Penther, 1000 Aileen St., Oakland, Calif.
- SEATTLE—Chairman, J. W. Wallace; Secretary, R. O. Bach, Pacific Telephone and Telegraph Company, Rm. 602, Northern Life Tower, Seattle, Wash.
- TORONTO—Chairman, R. H. Klingelhoefter; Secretary, N. Potter, Canadian National Carbon Co., Ltd., Davenport Rd., Toronto, Ont., Canada.
- WASHINGTON—Chairman, W. B. Burgess; Secretary, E. H. Rietzke, 3308 14th Ave., N. W., Washington, D. C.

GEOGRAPHICAL LOCATION OF MEMBERS
ELECTED SEPTEMBER 1, 1937

Elected to the Associate Grade

Alabama	Birmingham, 715 S 33rd St.	Dixon, J. T.
California	Chico, 3419-7th St.	Sherburne, C. J.
	Chico, Radio Station KHSL	Smithson, H.
Georgia	Los Angeles, 611½ W. 41st St.	Sessions, S. H.
	Atlanta, 1304 Northview Ave.	Franklin, E. C.
Illinois	Decatur, 811 Avery St.	Brown, A. L.
	Chicago, 1850 S. Avers Ave.	Andes, S. I.
	Chicago, 2240 S. Sacramento Ave.	Cerwin, S. S.
	Chicago, 7737 Colfax Ave.	Reid, J. G., Jr.
	Chicago, R.C.A. Institutes, 1154 Merchandise Mart.	Riggin, J. D.
	Glencoe, 1109 N. Sheridan Rd.	Sandy, L. G., Jr.
	Libertyville, 136 Newberry Ave.	Hudson, C. A.
	Riverside, 369 Blackhawk Rd.	Beatty, J. R.
	Sandwich, 119 N. Elm St.	Faber, L. A.
	Wilmette, 216-4th St.	Saville, R.
Massachusetts	Boston, c/o The Danish Consulate, 812 Statler Bldg.	Ingerslev, F. H. B.
Michigan	Benton Harbor, 833 Pearl St.	Rutz, W. C.
New Jersey	Camden, R.C.A. Manufacturing Company, Inc.	Olson, H. F.
	Harrison, R.C.A. Manufacturing Company, Inc.	Neustadt, H.
New York	Upper Montclair, Allen B. DuMont Labs., Inc.	Mezger, G. R.
	Buffalo, 61 W. Winspear Ave.	Lorenzen, H. O.
	New York, 126 E. 30th St.	Penel, W.
New York	New York, c/o Columbia Broadcasting System, 485 Madison Ave.	MacLeod, T. J.
	Scarsdale, 19 Chesterfield Rd.	Goodwin, C. W.
Ohio	Portsmouth, 844-6th St.	Ware, H. R.
Pennsylvania	Philadelphia, 333 S. 5th St.	Lipschutz, I. N.
Argentina	Buenos Aires, Pichincha 85	Cosentino, A. T.
Australia	Melbourne, Chief Engineer's Branch, P.M.G.'s Dept.	Stewart, E. J.
	Mullumbimby, North Coast, N.S.W.	Ainsworth, H. H.
Brazil	North Sydney, N.S.W., 123 High St.	Pritchard, J. W.
	Rio de Janeiro, P.O. Box 709	Velasco, A. N.
Burma	Rangoon, c/o Burmese Import House, 404 Dalhousie St.	Hlaing, M. B.
Canada	Halifax, N.S., 68 Jubilee Rd.	Murrough, J. P.
	Ottawa, Ont., 272 Fairmount Ave.	Nixon, F. G.
Colombia	Toronto, Ont., 356 Eastern Ave.	Ballard, A. G.
	Toronto, Ont., 652 Hillside Ave. E.	Paek, A. C.
England	Bogota, P.O. Box 3765 Aereo	Arboleda, C. E.
	Enderby, Leicester, 21 Mill Lane	Biggs, R. T.
England	London, 34 Clarendon Rd., Putney S.W. 15	Humphreys, T. D.
	London, Indian Students' Union and Hostel, 112 Gower St.	Weerasena, D. D. S.
France	Spalding, Lincs., Red Lion St.	Clifton, G.
	Weston Super Mare, Somerset, 64 Severn Rd.	Whenham, W. C.
France	Paris, 67 Boulevard de Courcelles	Mandel, P.
India	Bombay, c/o International General Electric Co. (India) Ltd., P.O. Box 992	Sreenivasaiengar, M.
	Calcutta, 18 Ashotush Mukerji Rd.	Alag, S. S.
Japan	Tatapuram, Cochin State, 27 Bungalow	Mundkur, B. S.
	Yokohama, Victor Talking Machine Co. of Japan, Ltd., P.O. Box 43	Murata, T.
New Zealand	Auckland, C. 3, 253 New North Rd.	Ferguson, G.
	Wellington, Kotari Rd., Day's Bay	Squires, N. L.
Puerto Rico	Santurce, Europa St. No. 36	Vazquez, J. R.
South India	Trivandrum, Travancore State, Main Rd.	Walsalam, E.
Venezuela	Ciudad Bolivar, Apartado 35	Long, F. V.

Elected to the Junior Grade

California	Oakland, 4014 Randolph Ave.	Gilbert, R. M.
Illinois	Berwyn, 1336 Harvey Ave.	Fistor, E.
	Chicago, 4242 N. Central Park Ave.	Gieffers, N. W.
	Chicago, 2705 S. Drake Ave.	Hajak, A. F.
	Chicago, 2643 S. St. Louis Ave.	Shonerock, R. C.
	Maywood, 1619 Washington Blvd.	Taylor, W. P.
New York	Jackson Heights, 3525-78th St.	King, W. B.
	New York, 4006 Pratt Ave.	Orbeck, M.
Pennsylvania	Philadelphia, 5743 Baltimore Ave.	Brown, J.
Wisconsin	Kenosha, 4617-19th Ave.	Kiertscher, H.

Geographical Location of Members Elected

Elected to the Student Grade

California	San Diego, Fleet Air Detachment, VS 2B.....	Born, A. S.
Florida	Coral Gables, P.O. Box 65.....	Epperson, W. H.
Indiana	West Lafayette, 110 South St.....	Weatherford, D. E.
Michigan	Petoskey, 822 Grove St.....	Saigeon, N. D.
New Jersey	Trenton, 314 Gardner Ave.....	Winterhalter, A. J., Jr.
New York	Fishers Island.....	Hansen, J. A.
Ohio	Troy, Walter Dormitory 22, Rensselaer Polytechnic Inst.....	Dufford, J. S., Jr.
Washington	Cincinnati, 611 Elliott Ave., Arlington Heights.....	Hoeper, H. B.
	Everett, 1509 Hewitt Ave.....	Swarm, H. M.



APPLICATIONS FOR MEMBERSHIP

Applications for transfer or election to the various grades of membership have been received from the persons listed below and have been approved by the Admissions Committee. Members objecting to transfer or election of any of these applicants should communicate with the Secretary on or before October 30, 1937. These applications will be considered by the Board of Directors at its meeting on November 3, 1937.

For Transfer to the Fellow Grade

Massachusetts	Cambridge, 30 State St.	Burke, C. T.
New York	New York, Bell Telephone Labs., Inc.	Lack, F. R.
Pennsylvania	Emporium, 220 E. Alleghany Ave.	Wise, R. M.

For Transfer to the Member Grade

New Jersey	Deal, Bell Telephone Labs., Inc.	Goodall, W. M.
	Oaklyn, 16 E. Oakland Ave.	Short, D. W.
New York	New York, 30 Rockefeller Plaza	Pitch, W. A.
	New York, Columbia Broadcasting System	Lodge, W. B.
	Schenectady, 2089 Plum St.	Bartelink, E. H. B.
Pennsylvania	St. Marys, Hygrade Sylvania Corp.	Dehlinger, W. H.
Canada	Toronto, 23 Old Orchard Grove	Poulter, R. C.
England	London, Northern Polytechnic	Hurren, S. A.

For Election to the Member Grade

Connecticut	New Haven, Yale University	Adams, N. I., Jr.
North Carolina	Charlotte, 912 Henley Pl.	Beloungy, J. J.

For Election to the Associate Grade

California	El Monte, 1621 Merced Ave.	White, C. E.
	Hollywood, Radio Station KNX	Bowman, L. H.
	Los Angeles, 65 Arcade Annex	Tomoda, F. J.
Florida	Miami Beach, 1241-13th St.	Cooagan, T. P.
	Tallahassee, Radio Station WTAL	Bailey, J. H.
Georgia	Blakely, Thompson House	Thompson, L., Jr.
Illinois	Downers Grove, 4819 Wallbank	Kay, R. A.
Iowa	Des Moines, Radio Station WHO	Loyet, P. A.
Louisiana	New Orleans, P. O. Box 1076	Dollit, A.
	Shreveport, P. O. Box 17	Maddox, C. H.
Michigan	Negaunee, 500 Jackson St.	Bleg, G. C.
New Jersey	Harrison, RCA Manufacturing Co., Inc., RCA Radiotron Div.	Hickok, W. H.
	Newark, 443 Jelliff Ave.	Sherman, B.
	New Brunswick, 152 Livingston Ave.	Evers, J. T.
New York	Brooklyn, 221 Westminster Rd.	Stodola, E. K.
	New York, 305 E. 183rd St.	Ponsolle, W. J.
	New York, c/o RCA Institutes, Inc., 75 Varick St.	Tam, G.
Ohio	Columbus, c/o Battelle Memorial Institute, 505 W. King Ave.	Sherwood, E. M.
	Dayton, 517 McLain St.	Senf, H. R.
Pennsylvania	Emporium, P. O. Box 226	Bachhuber, R. A.
	Emporium, 210 E. 4th St.	Herman, L. E.
	Emporium, 128 E. 5th St.	Schleimann, A.
	Norristown, 727 Buttonwood St.	Rehrer, W. E.
	Philadelphia, 1927 W. Airdrie St.	Sichel, A. T.
Texas	Knox City, c/o Geophysical Research Corp.	Day, C. E.
Washington	Seattle, 1802 Warren Ave.	Ruddell, L.
Wisconsin	Sheboygan, 914 Pennsylvania Ave.	Beck, H. M., Jr.
Australia	Laverton, Victoria, Royal Australian Air Force	Pither, A. G.
British West Indies	Bridgetown, Barbados, Manning and Co., Ltd.	Chandler, C. E.
England	Aylesbury, Bucks., 8 Chilton Rd., Wendover	Danielson, G. L.
	Chelmsford, Essex, Marconi College	Goolry, K. S.
Malay States	Muar P. O., Johore, Telegraph Eng. Dept., Posts and Telegraphs	Muthalaly, K. N. A.
South Africa	Johannesburg, 31 Lower Bldg., Plein St.	Krause, V. R.
	Pretoria, 480 V.D. Walt St.	Jones, O. B.

For Election to the Junior Grade

Illinois	Berwyn, 2506 S. Oak Park Ave.	Vinicky, J. A., Jr.
	Chicago, 4818 S. Parkway Ave.	Ford, E. V.

For Election to the Student Grade

California	Berkeley, 2634 Haste St.	Elliott, S. J.
	San Francisco, 2602 Sacramento St.	Faithorn, N. R.
Massachusetts	Waban, 46 Pine Ridge Rd.	Lamb, F. L.
New Jersey	Long Branch, R.F.D. 1	Maida, F. X.
North Dakota	Grand Forks, University Station	Kees, H.
South Carolina	Greenville, c/o Radio Station WFBC	Perry, C. S., Jr.

OFFICERS AND BOARD OF DIRECTORS

(Terms expire January 1, 1938, except as otherwise noted)

President

H. H. BEVERAGE

Vice President

P. P. ECKERSLEY

Treasurer

MELVILLE EASTHAM

Secretary

HAROLD P. WESTMAN

Editor

ALFRED N. GOLDSMITH

Directors

STUART BALLANTINE, *Past President*

T. A. M. CRAVEN

L. C. F. HORLE

C. M. JANSKY, JR.

C. B. JOLLIFFE

A. F. MURRAY

E. L. NELSON

HARADEN PRATT

B. J. THOMPSON

L. E. WHITEMORE

SERVING UNTIL JANUARY 1, 1939

E. H. ARMSTRONG

VIRGIL M. GRAHAM

ALAN HAZELTINE, *Past President*

SERVING UNTIL JANUARY 1, 1940

RALPH BOWN

H. M. TURNER

COMMITTEES OF THE INSTITUTE OF RADIO ENGINEERS
1937

ADMISSIONS COMMITTEE

C. M. JANSKY, JR., *Chairman*

F. W. CUNNINGHAM
MELVILLE EASTHAM
R. A. HEISING
L. C. F. HORLE

C. W. HORN
HARADEN PRATT
E. R. SHUTE
J. S. SMITH

A. F. VAN DYCK

ANNUAL REVIEW

A. F. VAN DYCK, *Chairman*

KEITH HENNEY
J. V. L. HOGAN
H. F. OLSON
HARADEN PRATT

J. C. SCHELLENG
B. J. THOMPSON
H. M. TURNER
H. A. WHEELER

L. E. WHITTEMORE

AWARDS COMMITTEE

ALAN HAZELTINE, *Chairman*

R. R. BEAL
L. M. HULL

HARADEN PRATT
L. E. WHITTEMORE

BOARD OF EDITORS

ALFRED N. GOLDSMITH, *Chairman*

R. R. BATCHER
P. S. CARTER
F. W. GROVER
J. W. HORTON
G. W. PICKARD

B. E. SHACKELFORD
K. S. VAN DYKE
H. P. WESTMAN, *ex officio*
L. P. WHEELER
L. E. WHITTEMORE

WILLIAM WILSON

CONSTITUTION AND LAWS COMMITTEE

H. M. TURNER, *Chairman*

AUSTIN BAILEY
RALPH BOWN

ALFRED N. GOLDSMITH
B. J. THOMPSON

H. A. ZEAMANS

MEMBERSHIP COMMITTEE

F. W. CUNNINGHAM, *Chairman*

NATHANIEL BISHOP
E. L. BOWLES
C. J. BURNSIDE
H. A. CHINN
T. H. CLARK
J. M. CLAYTON
I. S. COGGESHALL
E. D. COOK
ALFRED CROSSLEY
COKE FLANNAGAN
H. C. GAWLER
P. F. GODLEY
K. E. HASSELL

H. C. HUMPHREY
J. J. LONG, JR.
A. F. MURRAY
L. G. PACENT
M. E. PACKMAN
J. C. RANDALL
C. R. ROWE
W. A. SCHNEIDER
C. E. SCHOLZ
J. E. SMITH
H. J. VENNES
W. H. WEST
LESLIE WOODS

(Chairmen of Membership Committees of Sections, ex officio)

NEW YORK PROGRAM COMMITTEE

R. R. BEAL, *Chairman*

AUSTIN BAILEY
G. C. CONNOR
D. E. FOSTER

R. A. HEISING
KEITH HENNEY
L. G. PACENT

HARADEN PRATT

NOMINATIONS COMMITTEE

C. M. JANSKY, Jr., *Chairman*

STUART BALLANTINE
RALPH BOWN

J. V. L. HOGAN
C. B. JOLLIFFE

PAPERS COMMITTEE

WILLIAM WILSON, *Chairman*

M. A. ACHESON
H. A. AFFEL
EDMOND BRUCE
H. A. CHINN
J. K. CLAPP
T. A. M. CRAVEN
P. O. FARNHAM
E. B. FERRELL
T. R. GILLILAND
E. L. HALL

L. F. JONES
F. B. LLEWELLYN
DE L. K. MARTIN
A. F. MURRAY
H. O. PETERSON
R. K. POTTER
G. G. THOMAS
H. M. TURNER
H. A. WHEELER
W. C. WHITE

IRVING WOLFF

PUBLICITY COMMITTEE

O. E. DUNLAP, *Chairman*

C. E. BUTTERFIELD
O. H. CALDWELL
L. M. COCKADAY

KEITH HENNEY
R. C. POULTER
K. B. WARNER

SECTIONS COMMITTEE

VIRGIL M. GRAHAM, *Chairman*

J. E. BROWN
E. D. COOK
F. W. CUNNINGHAM

R. A. HACKBUSCH
L. C. F. HORLE
H. J. KLUMB

IRVING WOLFF

(*Chairmen of Sections, ex officio*)

STANDARDS COMMITTEE

L. C. F. HORLE, *Chairman*

J. H. DELLINGER
MELVILLE EASTHAM
VIRGIL M. GRAHAM
J. V. L. HOGAN
H. F. OLSON
HARADEN PRATT
J. C. SCHELLENG

F. E. TERMAN
B. J. THOMPSON
H. M. TURNER
H. J. VENNES
H. A. WHEELER
L. P. WHEELER
WILLIAM WILSON

TELLERS COMMITTEE

E. H. ARMSTRONG, *Chairman*

ARTHUR BATCHELLER

J. D. CRAWFORD

H. P. WESTMAN, *ex officio*

TECHNICAL COMMITTEES

BROADCAST COMMITTEE

C. M. JANSKY, Jr., *Chairman*

E. K. COHAN
G. D. GILLET
R. N. HARMON
J. V. L. HOGAN
C. W. HORN

C. B. JOLLIFFE
J. C. McNARY
R. E. POOLE
V. E. TROUANT
H. A. WHEELER

ELECTROACOUSTICS COMMITTEE

H. F. OLSON, *Chairman*

SIDNEY BLOOMENTHAL
J. T. L. BROWN
A. M. GRANUM
H. S. KNOWLES

KNOX McILWAIN
BENJAMIN OLNEY
HANS RÖDER
V. E. WHITMAN

HAROLD ZAHL

ELECTRONICS COMMITTEE

B. J. THOMPSON, *Chairman*

R. S. BURNAP	G. F. METCALF
E. L. CHAFFEE	J. W. MILNOR
A. M. GRANUM	A. F. MURRAY
F. R. LACK	G. D. O'NEILL
R. W. LARSON	H. W. PARKER
GEORGE LEWIS	O. W. PIKE
BEN KIEVIT, JR.	DAYTON ULREY
KNOX MCILWAIN	B. VAN DER POL

P. T. WEEKS

RADIO RECEIVERS COMMITTEE

H. A. WHEELER, *Chairman*

E. H. ARMSTRONG	D. E. FOSTER
C. R. BARHYDT	A. M. GRANUM
R. I. COLE	VIRGIL M. GRAHAM
W. F. COTTER	DAVID GRIMES
L. F. CURTIS	D. E. HARNETT
HARRY DIAMOND	J. K. JOHNSON
E. T. DICKEY	P. D. McKEEL
J. F. DREYER, JR.	H. O. PETERSON
MALCOLM FERRIS	F. X. RETTENMEYER
H. B. FISCHER	A. E. THIESSEN

LINCOLN WALSH

TELEVISION AND FACSIMILE COMMITTEE

J. V. L. HOGAN, *Chairman*

H. S. BAIRD	D. D. ISRAEL
STUART BALLANTINE	C. B. JOLLIFFE
R. R. BATCHER	E. F. KINGSBURY
J. L. CALLAHAN	E. H. LEE
E. K. COHAN	H. M. LEWIS
E. W. ENGSTROM	R. H. MANSON
P. T. FARNSWORTH	J. W. MILNOR
ALFRED N. GOLDSMITH	A. F. MURRAY
C. W. HORN	C. J. YOUNG

TRANSMITTERS AND ANTENNAS COMMITTEE

J. C. SCHELLENG, *Chairman*

RAYMOND ASSERSON	D. G. LITTLE
W. W. BROWN	R. E. POOLE
HARRY DIAMOND	E. G. PORTS
A. M. GRANUM	D. S. RAU
RAYMOND GUY	P. E. WATSON

J. E. YOUNG

WAVE PROPAGATION COMMITTEE

J. H. DELLINGER, *Chairman*

E. V. APPLETON	F. A. KOLSTER
S. L. BAILEY	H. R. MIMNO
L. V. BERKNER	K. A. NORTON
C. R. BURROWS	H. O. PETERSON
T. L. ECKERSLEY	G. W. PICKARD
G. D. GILLET	BALTH. VAN DER POL

INSTITUTE NEWS AND RADIO NOTES

Pacific Coast Meeting

The Pacific Coast meeting of the Institute which was held in conjunction with the Pacific Coast Convention of the American Institute of Electrical Engineers attracted an attendance of ninety-five Institute members. There were nineteen technical papers presented and the summaries of these were given in the August, 1937, PROCEEDINGS. September 1 and 2 were devoted to the technical sessions at which the papers were presented. The various technical sessions were presided over by H. H. Beverage, president of the Institute; F. E. Terman, chairman of the Pacific Coast Committee; A. V. Eastman, vice chairman of the committee; and J. W. Wallace, chairman of the Seattle Section. A number of those in attendance were present at the annual banquet of the American Institute of Electrical Engineers. Many also took advantage of the full-day trip to Grand Coulee Dam which was arranged by the electrical engineering group.

Committee Work

ADMISSIONS

A meeting of the Admissions Committee was held in the Institute office on September 14 and attended by R. A. Heising, acting chairman; F. W. Cunningham, L. C. F. Horle, C. W. Horn, E. R. Shute, A. F. Van Dyck, and H. P. Westman, secretary.

Three applications for transfer to Fellow grade were approved. Eleven applications for transfer to Member were accepted and two were rejected. There were two applications for admission to the grade of Member approved.

NEW YORK PROGRAM

R. R. Beal, G. C. Connor, D. E. Foster, R. A. Heising, Keith Henney, H. C. Likel (representing L. G. Pacent), and H. P. Westman, secretary, attended a meeting of the New York Program Committee which was held in the Institute office on September 2. The meeting was devoted to the preparation of a list of papers for presentation at the fall meetings of the Institute to be held in New York City.

Institute Meetings

INDIANAPOLIS SECTION

On June 24, V. C. McNabb, chairman, presided at a meeting of the Indianapolis Section held at the Indianapolis Athletic Club. There were eighty-six present.

A paper on "A New Inductive Tuning System" was presented by Paul Ware of P. R. Mallory and Company and discussed by Messrs. Callahan, French, and Passow. Described among the more important features of the system was a slide-contact variable inductance wherein the contact travels along the length of the turns of a rigid rotatable helix. A carriage assembly having insulated trolley wheels which ride on the wire is compressed between a fixed bar and the coil. The life of the contact is equal to several hundred miles of travel and corresponds to a million or more rotations. A terminal inductance having a Q superior to a mechanically stopped-off portion of the rotating coil considerably improves operation at the high-frequency end of the range when used with a fixed condenser as a resonant circuit. Two or three times the usual tuning range may be obtained. The effects of varying the axial pitch, various coil geometries, and the use of high-frequency iron were described. The operating range of the coil is limited by the natural period of the shorted unused portion and in the low-frequency region by the impedance obtained. High-frequency oscillator design is simplified as at the low-frequency end of the range the circuit impedance continuously rises. Feed-back coupling at the high-frequency end may be made sufficient to maintain approximately uniform oscillation strength through a reactive range of a hundred to one. Comparisons were made between inductance and capacitance tuned superheterodyne input systems. A new oscillator tracking expedient produces a fourth tracking crossover for wide range tuning. The large range of motion of the multiturn coil over the half turn of a variable condenser permits much more accurate scale indication particularly in the high-frequency ranges. The system is virtually nonmicrophonic so far as the variable inductance is concerned.

An ultra-high-frequency oscillator capable of supplying a strong uniform voltage to frequencies above one hundred and fifty megacycles was described. A signal generator using the inductive tuning system was described and covered the range from ninety kilocycles to thirty-five megacycles with long accurate scales and only three switch positions. A receiving set was demonstrated and covered all frequencies between five hundred and forty kilocycles and sixty-five megacycles with three switch positions. In the discussion, it was pointed out that the antenna step-up and the tuned radio-frequency gain in the broadcast region were of the order of three to four and ten to fifteen, respectively. These gains depend on the coil size and increase with the inductance of the rotatable coil.

TECHNICAL PAPERS

A NEGATIVE GRID TRIODE OSCILLATOR AND AMPLIFIER
FOR ULTRA-HIGH FREQUENCIES*

BY

A. L. SAMUEL

(Bell Telephone Laboratories, Inc., New York City)

Summary—A description is given of some negative grid triodes of unusual design which operate both as oscillators and as amplifiers at frequencies higher than those previously reported. These tubes differ from the conventional primarily in the number and arrangement of the leads. When used as oscillators the upper frequency limits are increased by this arrangement to approximately 1.3 times the values otherwise obtained. Stable operations are secured as amplifiers at somewhat lower frequencies, the stability outputs and distortion ratios being comparable with those obtained from pentodes of similar ratings.

IT IS an interesting and perhaps significant fact that the simple three-element vacuum tube is still used extensively as an oscillator and as a high power radio-frequency amplifier in spite of recent advances made in the design of multielement tubes. Some may see in this only the failure of the tube engineer to apply existing knowledge. The tube engineer, on the other hand, while not entirely unwilling to admit the truth of this accusation, is inclined to wonder if there may not still exist a field of usefulness for the triode. If such a field exists most certainly it must lie either in the region of very small tubes where the mechanics of fabrication prove difficult, or in the region of very large power tubes where the problems of the screen power dissipation become acute. What then could be more logical than to expect to find triodes used for power oscillators and amplifiers at ultra-high frequencies where the electron transit time considerations dictate small interelectrode spacings and where the relatively large power ratings require high dissipation rates?

As a matter of fact, the negative grid triode has appeared to lag behind the magnetron as an oscillator at frequencies above roughly 500 megacycles while the only successful power amplifiers which have been described for frequencies of the order of 300 megacycles are multielement tubes.¹ One is led to suspect that those factors which limit the

* Decimal classification: R330. Original manuscript received by the Institute, June 1, 1937. Presented before I.R.E.-U.R.S.I. Meeting, Washington, D. C., April 30, 1937.

¹ A. L. Samuel and N. E. Sowers, "A power amplifier for ultra-high frequencies," *Proc. I.R.E.*, vol. 24, pp. 1464-1483; November, (1936), also in *Bell Sys. Tech. Jour.*, vol. 16, pp. 10-34; January, (1937).

frequency range of the triode as an amplifier may also limit its frequency range as an oscillator.




Fig. 1—Experimental double-lead tubes.

The triode as used at radio frequencies differs from the multi-element tube chiefly in the manner in which interaction is prevented




Fig. 2—Section view of a double-lead tube showing lead arrangement.

between the input and output circuits. This is obviously a circuit limitation, as contrasted with the electron-transit-time limitation which has received so much attention.² The greatest opportunity for

² F. B. Llewellyn, "Operation of ultra-high-frequency vacuum tubes," *Bell Sys. Tech. Jour.*, vol. 14, pp. 632-665; October, (1935).

W. R. Ferris, "Input resistance of vacuum tubes as ultra-high-frequency amplifiers," *Proc. I.R.E.*, vol. 24, pp. 82-107; January, (1936).

D. O. North, "Analysis of the effects of space charge on grid impedance," *Proc. I.R.E.*, vol. 24, pp. 108-136; January, (1936).

H. Rothe, "Input and output resistance of thermionic valves at high frequencies," *Telef. Rohre Supp.*, July, (1936).

improvement, therefore, seems to be in the direction of improved circuit design. The tubes described in this paper were developed from this point of view.

Sample tubes are shown in Fig. 1. They differ from tubes previously described³ primarily in the lead arrangement. From the sketch of one of these tubes shown in Fig. 2, it will be observed that the grid and plate elements are supported by wires which in effect go straight




Fig. 3—Static characteristics of large tube.

through the tube envelope providing two independent leads to each of these elements. Although this arrangement has been used in Barkhausen tubes to reduce circuit losses,³ it apparently has not previously been applied to the case of the negative grid tube. The filament leads are at one end only and one of these leads is extremely short. This unusual lead arrangement possesses a number of unique advantages which will be discussed in detail later.

The operating characteristics of these three tubes are listed in

³ M. J. Kelly and A. L. Samuel, "Vacuum tubes as high-frequency oscillators," *Elec. Eng.*, vol. 53, pp. 1504-1517; November, (1934), also in *Bell Sys. Tech. Jour.*, vol. 14, pp. 97-134; January, (1936).

Table I. Special attention is directed to the values of interelectrode capacitances and lead inductances. The usual static characteristics,

TABLE I
CHARACTERISTICS

	Large Tube	Intermediate Tube	Small Tube
Filament current in amperes	10	8.5	4
Filament potential in volts	3	1.5	1
Anode potential in volts	750	500	300
Maximum anode dissipation in watts	150	50	25
Amplification factor	9	8	9
Transconductance in micromhos	4000	3000	2500
Direct grid-plate capacitance in $\mu\mu\text{f}$	3.5	1.6	0.9
Direct filament-grid capacitance in $\mu\mu\text{f}$	2	1.3	1
Direct filament-plate capacitance in $\mu\mu\text{f}$	1.3	0.9	0.7
Approximate grid-plate lead inductance in microhenrys (on each side)	0.05	0.03	0.01




Fig. 4—Static characteristics of intermediate size tube.

shown in Figs. 3, 4, and 5 are quite typical for tubes of comparable rating.

One or two constructional features aside from the lead arrangement are worthy of note. All of the grids are of the so-called fin type. The filament of the large tube is in the form of a ribbon. This shape was adopted to provide the necessary emitting area while keeping the filament heating current demands within bounds. It also minimizes the




Fig. 5—Static characteristics of small tube.

objectionable end cooling which occurs with large size filaments. The filament in the small tube, although in the form of a wire, is tapered near the ends, again to minimize end cooling. Carbon has been used for the anodes, primarily because of the ease of fabrication for a limited number of experimental tubes.

THE DOUBLE-LEAD TUBE AS AN OSCILLATOR

The double-lead arrangement is responsible for an increase in the upper frequency limit of the tube as an oscillator by a factor of from 1.2

to approximately 1.4. A typical oscillator circuit is shown in Fig. 6. Here the tube is mounted at the center of an equivalent half-wave Lecher system. It may be shown by a simple calculation that the natu-




Fig. 6—Typical oscillator circuit.

ral frequency of such a system is greater than the frequency of the equivalent quarter-wave system formed by removing one set of leads. Since only half of the total charging current to the interelectrode capacitances flows through each set of leads the losses due to the lead resistances are reduced. The balanced arrangement also results in a decrease in radiation losses. In the tubes under discussion the electron-transit-time limitation has been met by the use of extremely small interelectrode spacings so that full advantage may be taken of the increased frequency range.

For the purpose of confirming the above conclusion, output and efficiency curves have been obtained on the tubes when operated both single and double ended, and on tubes identical in every respect except




Fig. 7—Comparison plot of the efficiencies of a large tube operated single and double ended.

for omission of the extra set of leads. Typical results for the large tube are shown in Fig. 7. It will be observed that the efficiencies for double ended operation are always higher than for the single ended case over the range covered by the experimental data. In fact, usable outputs are

obtained at frequencies well beyond the point where the single ended tube fails to operate. The ratio of the cutoff frequencies for the two modes of operation happened to be 1.23 for the particular conditions under which these data were obtained.

Output and efficiency curves for the large size tube are shown in Fig. 8. The values of 60 watts at 300 megacycles and 40 watts at 400 megacycles compare quite favorably with outputs reported from radiation cooled magnetrons.⁴ When the problems of modulation and the complications of the magnetron's magnetic field are considered, the advantages of the negative grid triodes become more apparent. Fig. 9 is a comparison plot of the outputs obtainable from these tubes and




Fig. 8—Output and efficiency as a function of frequency for the large tube.

from some of the commercially available tubes. The sloping lines are for fixed values of the ratio of output to the square of the wave length, one line being for a ratio of four times that represented by the other line. The improvement in output made possible by the present departure in design is at once evident. Special attention is called to the output and the upper frequency limit of the small tubes. Typical values are 3 watts at 1200 megacycles, 2 watts at 1500 megacycles, and 1 watt at 1700 megacycles, with a limiting frequency of 1870 megacycles corresponding to a wave length of 16 centimeters. While the results so far obtained are obviously not conclusive, they do suggest that the negative grid tube is still a strong contender for the supremacy as an oscillator at frequencies as high as 1500 megacycles.

⁴ G. R. Kilgore, "Magnetron oscillators for the generation of frequencies between 300 and 600 megacycles," Proc. I.R.E., vol. 24, pp. 1140-1157; August, (1936).

THE DOUBLE-LEAD TUBE AS AN AMPLIFIER

The double-lead arrangement is also responsible for an increase in the upper frequency limit at which stable operation as an amplifier may be secured. To understand how this comes about it will be necessary to consider briefly the causes for instability as an amplifier.

The primary cause for instability of the triode is the interaction between the input and output circuits which results from the coupling between these circuits provided by the grid-plate capacitance. A second




Fig. 9—Comparison plot of the outputs of the double-lead tubes and of commercially available tubes.

source of coupling is that caused by common impedances in the two circuits in the nature of the self and mutual inductance of the tube leads. This second form of coupling will be referred to as impedance coupling as contrasted with admittance coupling caused by the inter-electrode capacitances. At moderately high frequencies this impedance coupling is usually of negligible importance. Stable operation is thus possible when suitable means are provided to compensate or “neutralize” the admittance coupling. At ultra-high frequencies impedance coupling can no longer be neglected. It may, of course, be minimized by the use of short leads. As a consequence, triodes designed for use as oscillators at ultra-high frequencies are also good amplifiers.

The ultimate solution to the problem is to provide independent

leads for the input, output, and admittance neutralizing circuits so that impedance coupling because of common leads is definitely eliminated. Coupling because of mutual impedances will still be present but may be minimized by the proper arrangement of the leads. The double-lead tube is an attempt to fulfill these conditions. It will be observed that the only common impedance remaining is that introduced by one filament lead and that this lead is extremely short.

One additional refinement in circuit design is required before full advantage may be taken of this lead arrangement. In general, two methods of neutralizing admittance coupling are possible. One is to compensate for the potential, which the disturbing admittance introduces in the input circuit, by means of another potential of opposite polarity derived from a second and similar admittance properly connected. All of the more common capacitance neutralization schemes fall in this category. The second method, first disclosed by H. W. Nichols in U. S. Patent 1,325,879, is to resonate the offending admittance at the desired operating frequency so that the resulting parallel admittance is reduced to a very low value. In the triode circuit this takes the form of an inductance connected between the grid and plate of the tube and adjusted to resonate with the grid-plate capacitance. For ease of adjustment a somewhat lower fixed inductance may be used and tuned by the adjustment of a small variable condenser in parallel. This form of neutralization is commonly referred to as "coil" neutralization. At ultra-high frequencies where unavoidable inductances are already present in the form of lead inductances, this "coil" scheme possesses outstanding advantages over the more usual "capacitance" schemes. These advantages become even more pronounced with the availability of the double-lead tube.

In order to verify this analysis a "coil-neutralized" two-stage amplifier was constructed by R. J. Kircher using two of the larger sized tubes. An output of 60 watts at 144 megacycles with an efficiency of 30 per cent for class B operation is obtained with this amplifier. For an output of 20 watts at 144 megacycles the third order distortion products are 43 decibels below the fundamental. The stability and band width are quite comparable with results obtained on a pentode of similar ratings. Results of a comparable nature have been obtained on the intermediate size tube. The full capabilities of the small size tube as an amplifier have not been completely evaluated. From a comparison of its characteristics and performance as an oscillator with data available for the larger tubes, it seems reasonable to assume that stable operation as an amplifier will prove possible at frequencies as high as 1000 megacycles.

The encouraging nature of these results leads one to suspect that the negative grid triode will prove to be a strong contender for supremacy as an amplifier at ultra-high frequencies particularly in the range of large outputs just as it is still supreme for very large outputs at somewhat lower frequencies. Of course, much remains to be done before even the results here reported on experimental laboratory tubes can be duplicated on a practical scale.

In conclusion the double-lead tube is seen to possess a number of distinct advantages as both an oscillator and an amplifier in the frequency range from 100 megacycles to 1000 megacycles. While the ultimate limit to which such developments may be pushed is entirely a matter of conjecture it seems safe to predict that the triode will be able to meet the demands of the circuit designer at least for some time to come.

ACKNOWLEDGMENT

The writer wishes to express his appreciation for the contributions of Mr. J. P. Laico toward the solution of the many difficult problems of mechanical designs and fabrication which have arisen in the course of this development.



SUDDEN DISTURBANCES OF THE IONOSPHERE*

By

J. H. DELLINGER

(National Bureau of Standards, Washington, D.C.)

Summary—The phenomenon described in this paper is the occurrence of a very sudden change in ionization of a portion of the ionosphere. It manifests itself by the complete fading out of high-frequency radio transmission for a period of a few minutes to an hour or more, and by perturbations of terrestrial magnetism and earth currents. The effect was discovered in 1935, and found to occur simultaneously everywhere throughout the illuminated half of the globe but not in the night half. The results of a world-wide investigation of the phenomenon which followed this discovery are presented in this paper.

The radio and magnetic effects have been shown to be of a distinct type, quite different from previously known vagaries in these fields. They are of maximum intensity in that region of the earth where the sun's radiation is perpendicular.

Many of the occurrences are simultaneous with great eruptions on the sun. Such eruptions emit vast quantities of ultraviolet light. These radiations are sometimes of such frequencies as to cause intense ionization of part of the ionosphere below the E layer. This sudden ionization causes the radio and other perturbations. Their characteristics are explained. Study of this effect is leading to new understanding of the nature of the ionosphere, the processes of radio wave transmission, the mechanisms of terrestrial magnetism, and the phenomena occurring in the sun.

I. INTRODUCTION

THIS paper presents the conclusions and data up to the end of 1936 of an investigation, started about the middle of 1935, of a hitherto unknown phenomenon. The phenomenon is the occurrence of a sudden intense increase in the ionization of a part of the earth's upper atmosphere, with resultant transient disturbances in such phenomena as radio wave transmission, terrestrial magnetism, and earth currents. The radio effect is of serious practical import, as it manifests itself principally as a sudden disappearance of radio signals received on high frequencies, the period of silence ranging from a few minutes to an hour or more. The whole phenomenon is of scientific interest particularly because it appears to have its origin in sudden bursts of radiation from the sun, and is opening the way to increased understanding of the sun, the ionosphere, radio transmission, terrestrial magnetism and related phenomena.

* Decimal classification: R113.5. Original manuscript received by the Institute, June 11, 1937. Presented before American Physical Society, Denver, Colo., June 25, 1937. Published in *Nat. Bur. Stand. Jour. Res.*, vol. 19, pp. 111-142; August, (1937). Publication approved by the Director of the National Bureau of Standards of the U. S. Department of Commerce.

In October, 1935, the author reported¹ the occurrence of radio fade-outs on March 20, May 12, July 6, and August 30 of that year. He pointed out that they occurred throughout the illuminated half of the globe but not the dark half, advanced the hypothesis that they depend on some solar emanation lasting only a few minutes, and suggested observations by workers in other sciences with a view to learning of the possible occurrence of effects in terrestrial magnetism, earth currents, solar radiation, etc., simultaneous with radio fade-outs. The suggestion met with widespread interest, and the author has had the collaboration of numerous individuals and organizations in this investigation.

Evidence followed rapidly that the postulated simultaneous effects do occur. The astronomers at Mt. Wilson Observatory of the Carnegie Institution of Washington were asked to examine their spectroheliographic data for the dates in question, and in November, 1935, R. S. Richardson of that Observatory informed the author that on July 6 and August 30 bright eruptions had been observed on the sun within a few minutes of the times of the radio fade-outs, and on the other two dates no observations had been made at the times of the fade-outs. These results were announced by Dr. Richardson and the author at the end of 1935.

The magnetograms of the Cheltenham, Maryland, Observatory of the U. S. Coast and Geodetic Survey were examined by the author for the times of all the fade-outs then known, and for several of them small abrupt pulses were found, beginning at a time within two minutes of the radio fade-out time. Also, H. H. Beverage of R.C.A. Communications, Inc., reported to the author the occurrence of a large sharp pulse on an earth-current recorder within a few minutes of the time of several of the radio fade-outs.

From these beginnings has grown an extensive research upon these interrelated phenomena. Through the kindness of many cordial co-operators I am able to present a summary of data on the known occurrences. Acknowledgments of the work of these co-operators are given in Section VII. Systematic recording of the phenomena has been carried on by the National Bureau of Standards, and complete reports have been furnished by a few other groups, but many of the reports from scattered places are sporadic and partial. Data are relatively meager for the Asiatic and Pacific regions. It is believed that the results are of sufficient value to provide encouragement for more widespread and systematic observations and for more intensive exploration of the several fields of inquiry opened up by this work.

Preliminary reports of the results, and explanation in terms of

¹ See first two references in Bibliography at end of paper.

ionosphere effects, were given by the author in papers presented at the Washington meeting of the American Section, International Scientific Radio Union, May 1, 1936, and at the Cleveland Convention of the Institute of Radio Engineers, May 11, 1936. A number of brief papers have been published by the author and others, giving some of the results and preliminary conclusions. (See Bibliography at end of paper.)

This paper presents a compressed summary of the known facts regarding 118 sudden disturbances of the ionosphere, many of which were accompanied by solar eruptions, many of which were manifested by perturbations of terrestrial magnetism and earth currents, and each of which was manifested by the wiping out of hundreds or thousands of radio transmissions.

II. DATA

In this Section a summary of the available data is presented. In Sections III, IV; and V the facts regarding particular aspects of the data are presented and discussed. In Section VI is given a discussion and explanation of the entire phenomenon.

The data considered in this paper are given in very condensed form in Table I, and are essentially for the years 1935 and 1936. One earlier occurrence is included, that of November 28, 1934, as it was clearly the same phenomenon. There is little reliable information on earlier occurrences of this type. Some records indicate occurrences which may or may not be the same phenomenon. Thus, the logs of radio operating companies show radio traffic interruptions on many occasions in 1934 and earlier but there is very little information at hand to judge whether they were of the type due to the sudden ionosphere disturbances here studied or to others of the various radio wave vagaries mentioned at the beginning of Section III below. Information on a number of such traffic interruptions in 1928 have been given by T. L. Eckersley.² From the data given in his paper, the failure of radio transmission on October 10, 1928, from 1100 to 1200, G.M.T., may have been a case of the phenomenon here studied. Likewise, from data reported to the author of the present paper, the failure of radio transmission from 1305 to 1400, G.M.T., on May 11, 1934, may also have been a case.

Similarly, there is some information on a few early occurrences of sudden terrestrial magnetic pulses simultaneous with visible solar eruptions, occasionally reported by astronomers many years ago. Some instances are given by G. E. Hale.³ Interesting ones were ob-

² "An investigation of short waves," *Proc. I. E. E.* (London), vol. 67, p. 992, (1929)

³ "The spectroheliograph and its work, Part III; Solar eruptions and their apparent terrestrial effects," *Astrophys. Jour.*, vol. 73, p. 379, (1931).

served on August 3 and 5, 1872, by Prof. C. A. Young, as described in his book, "The Sun," (1884). These occurrences may have been of the type associated with the sudden ionosphere disturbances here studied.

Table I summarizes the data from all sources. It is regretted that only a summary can be given; the complete details are so voluminous that it is not practicable to tell the whole story of each of the occurrences. The complete details would occupy hundreds of pages. Thus in the case of numerous publications listed in the Bibliography the entire article is devoted to observations at a single place of a single one of these occurrences. Table I includes some information based on published articles. Most of the data, however, were derived from observations made at the National Bureau of Standards and from reports sent by other observers to the author. Acknowledgments of this assistance are given in Section VII below.

Even though they represent very extensive observations, the data we have do not give comprehensive information on the occurrences. In some cases we have knowledge of the disturbance from only two places of observation (and effects reported from only one place are included in two or three cases, where radio waves were received over numerous paths and the effects were extremely intense and clearly authentic). It would be desirable that we have for each occurrence information from numerous points all over the world, on the effects which occurred in radio transmission, terrestrial magnetism, and earth currents. In no case have we such complete information, and in many cases we also lack certainty as to whether a solar eruption occurred at the time. The incomplete character of our knowledge should be remembered in interpreting the data.

This investigation has dealt primarily with the radio aspects of the sudden ionosphere disturbances, as the form of Table I indicates. The table gives, for each receiving location reporting a radio fade-out, the average time of the fade-out of high-frequency radio waves for each of the locations of transmitting stations whose emissions were affected. For the terrestrial magnetic and earth-current pulses, the effects upon atmospherics, and solar eruptions, only the times of occurrence are given. All times given in this paper are in G.M.T., i.e., Greenwich Mean Time. Eastern Standard Time is five hours less than G.M.T.

In the second column of Table I, the first time given on each line is the time of beginning of the radio fade-out. Where three times are given, the second is the time when the radio signals began to come in again and the third is the time when the intensities had risen to normal. Where two times are given, the second is in most cases the time when the radio signals had risen to approximately normal.

TABLE I
DATA ON RADIO FADE-OUTS AND OTHER MANIFESTATIONS OF SUDDEN IONOSPHERE DISTURBANCES

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1934 Nov. 28	1710-1740 1710-1745 1710-1730	Georgia New York Washington, D.C.	Eastern U.S.A. S. America D.C.*	Solar eruption, beginning about 1710. Terrestrial magnetic pulse, 1707-1730. Earth-current pulse, 1710-1740.
1935 Jan. 25	0335-0535	California	Asia, Philippines, Java	
Mar. 20	0150-0200 0148-0200	Philippines California	California Asia, Philippines, Java	
May 12	1157-1215 1156-1214 1200-1215	France New Jersey New York	(Numerous) England Europe, S. America	Ter. mag. pulse, 1157.
July 6	1409-1437 1408-1430	New York France	England, U.S.A., S. America N. & S. America, Asia	Solar eruption, 1358-1418. Ter. mag. pulse, 1407-1412. Earth-current pulse, 1400-1411.
Aug. 30	2320-2325-2335 2300-2329	California Philippines	Asia, Philip., Java, Western U.S.A., California.	Solar eruption 2312 to after 2330.
Sept. 13	1630-1640-1650	California	U.S.A., Manila, Shanghai, Tokyo	Solar eruption, 1635-1641. Ter. mag. pulse, 1630.
Sept. 27	1250-1350 1245-1315	New York England	Europe, S. America (Numerous)	Solar eruption, from before 1200 to after 1230. Ter. mag. pulse, 1250.
Sept. 29	2055-2120-0150 2050-2110	California D.C.	Tokyo, Shanghai, Hawaii, New York Massachusetts	
Oct. 24	1100-1200	New York	(Numerous)	Earth-current pulse, 1130-1215
Nov. 18	1755-1815 1757-1800	Porto Rico D.C.	U.S.A. Ohio	
Nov. 29	1405-1415 1405-1415	New York Brazil	S. America (All stations)	Solar eruption, from before 1431 to 1445.
Nov. 30	1721-1730-1815	D.C.	Ohio, Massachusetts	Solar eruption, 1751-1830.
Nov. 30	1850-1908-1930 1900-1925-1935	D.C. Hawaii	Ohio, Massachusetts California	
Dec. 16	2209-2230 2223-2225	D.C. Hawaii	Massachusetts California	Solar eruption, 2210-2238.
Dec. 17	1615-1630 1630-1700 1610-1618-1630 1620-1630-1655	New York New Jersey D.C. Texas	S. America England Massachusetts, Ohio Numerous amateur stations.	Solar eruption, beginning before 1609. Ter. mag. pulse, 1610-1630.
Dec. 18	0450-0615	California	Asia, Philippines, Java	
Dec. 23	1730-1826-2000 1730-2000 1730-1930 1740-1930 1745	D.C. California New York Georgia Porto Rico	Ohio, Mass., D.C.* Asia, Philippines, Java Europe, S. America Eastern U.S.A. U.S.A.	Solar eruption, from before 1757 to after 1805.
1936 Feb. 6	1520-1645-2040 1520-1550-1645 1515-1530-1700 1520-1620	D.C. Georgia New York England	Ohio, D.C.* Eastern U.S.A. S. America, Europe Numerous	Ter. mag. pulse, 1520. L-f atmos. increase, 1520-1600.
Feb. 8	0130-0310 0130-0230 0205-0300 0200-0315 0200-0325 0210-0330	Philippines Japan California Malaya Siam Fr. Indo China	China, Guam, Hawaii California, Brazil, Syria Asia, Philippines, Java Asia Asia Asia, Philippines, Java	

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936 Apr. 8	0920-0945	Holland	Austria, Hungary	Solar eruption, 0810-1000. Ter. mag. pulse, 0912-0925.
Apr. 8	1450-1520 1450-1520 1450-1520	D.C. Texas Arizona	Ohio, Mass., D.C.* U.S.A. U.S.A.	Ter. mag. pulse, 1450.
Apr. 8	1646-1726-1815 1650-1700 1645-1657-1720 1650-1658-1704 1645-1708	D.C. France New York New Jersey Holland	Ohio, Mass., D.C.* U.S.A., S. America England, S. Amer., U.S.A. England Japan, Europe, N. & S. America U.S.A.	Solar eruption, 1645-1703 Ter. mag. pulse, 1645-1705. Earth-current pulse, 1645-1700. L-f atmos. increase, 1650-1745
	1650-1706-1725 1648-1705 1645-1657-1720 1630-1655-1705 1630-1655-1705 1650-1710 1645-1740 1703-1738 1650-1712 1650-1703-1720 1645-1655-1715 1640-1720 1648-1704-1720 1658-1705-1730 1658-1704-1725 1655-1718	Georgia California England Quebec British Columbia Spain Peru Oklahoma Texas Florida Tennessee Illinois Indiana Iowa Nebraska Missouri	Asia, Philip., Java, U.S.A. N.Y., S. America, Africa England, Australia Quebec, Australia S. America Peru* (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous)	
Apr. 9	1320-1400 1320-1330-1430 1325-1335-1345 1340-1348	D.C. New York Holland England	Ohio, Massachusetts Europe Europe, N. & S. America (Numerous)	Solar eruption, from before 1330 to 1430. L-f atmos. increase, 1310-1440.
Apr. 25	1427-1500	D.C.	Ohio, Massachusetts	Solar eruption, 1428-1445.
Apr. 25	1653-1735	D.C.	Ohio, Mass., D.C.*	Solar eruption, 1650-1724. Ter. mag. pulse, 1650-1700. L-f atmos. increase, 1658-1755.
Apr. 30	0940-1100 1000-1100 1000-1100 1000-1110	Japan France Germany England	Europe Japan Japan Japan	
May 8	2020-2029-2037	D.C.	Ohio, Massachusetts	Ter. mag. pulse, 2020-2035. Earth-current pulse, 2020.
May 14	1755-1759 1750-1800-1817	New York D.C.	Europe, U.S.A. Ohio	
May 15	0550-0730 0550-0620 0600-0620	Japan Philippines France	Philippines, Asia, Europe Japan Japan	Solar eruption, from before 0704 to 8030.
May 25	1233-1240-1256 1232-1243-1257 1238 1235-1300 1232-1245 1237-1245	D.C. New York Florida Holland France England	Ohio, Mass., D.C.* (Numerous) U.S.A. Canada, Japan, Java U.S.A., S. America, Japan Europe, S. America, Japan	Ter. mag. pulse, 1233-1250 Earth-current pulse, 1233-1234-1236. L-f atmos. increase, 1228-1330
May 26	1130-1135 1130-1134 1132-1139 1131 1130-1145	New York D.C. Holland France England	(Numerous) Ohio Hungary (Numerous) (Numerous)	Solar eruption, 1115-1203. L-f atmos. increase, 1128-1158.
May 27	0335-0430 0355-0410 0350-0415	Holland California Japan	Japan, Java Asia, Philippines, Java Calif., Philip., Asia, Europe	
May 27	2345-2430 2345-2430 2345-2430	Japan Argentina California	N. & S. America Japan Japan	

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936				
May 28	0345-0415 0340-0420 0330-0420	California Holland Japan	Asia, Philippines, Java Japan, Java China, Philip., California	
May 28	0730-0745 0728-0743 0730-0800 0728-0730 0720-0745	Philippines California Holland France Japan	Hawaii Asia, Philippines, Java Japan, Austria, Java (Numerous) Europe, Philippines	Solar eruption, 0715-0800 Ter. mag. pulse, 0725-1738 L-f atmos. increase, 0726-0800
May 28	1403-1416-1430 1400-1409-1445 1402-1430 1405	D.C. New York Holland France	Ohio, Massachusetts Europe, S. Amer., California N. & S. America, Europe (Numerous)	L-f atmos. increase, 1400-1450.
May 28	1759-1840-2000	D.C.	Ohio, Massachusetts, Texas, Nebraska, Oklahoma Europe, N. & S. America (Numerous)	Ter. mag. pulse, 1800-1850. Earth-current pulse, 1758-1807. L-f atmos. increase, 1758-1907.
	1800-1808-1817 1800-1823 1800-1823 1800-1823 1758-1815 1800-1815 1800-1815-1830 1759-1820-1830 1800-1818-1828 1800-1818-1828 1800-2000 1758-1815 1800-1816 1800 1755-1825 1800-1813-1840	New York Oklahoma Texas Nebraska N. Dakota Illinois British Columbia Ohio Arkansas Kansas S. Carolina Missouri England France Japan Holland	Europe, N. & S. America (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) (Numerous) California, Europe New York, Argentina	
May 29	1020-1030 1020-1035 1025-1035 1023 1020-1027	Holland Japan England France New York	Java, Sweden, Austria Europe (Numerous) (Numerous) (Numerous)	L-f atmos. increase, 1015-1115.
May 30	1730-1800	Florida	(Numerous)	Ter. mag. pulse, 1728-1750.
June 3	0045-0130 0045-0130 0045-0130 0100-0110	Japan California Buenos Aires Philippines S.S. Gen. <i>Pershing</i> , long. 154°52'W	Calif., Philip., Europe, N. & S. America, Asia Japan Japan Japan (Numerous)	
June 3	1635-1655-1712 1636-1640-1720 1637-1650 1630 1630-1645-1700 1640-1700 1633-1650 1635-1650	D.C. New York Illinois Missouri Pennsylvania Holland France England	Ohio, Massachusetts Europe, N. & S. America (Numerous) (Numerous) (Numerous) U.S.A., Japan, Java (Numerous) (Numerous)	Solar eruption, 1629-1700. Ter. mag. pulse, 1635-1700. L-f atmos. increase, 1635-1718.
June 3	1830-1835 1823-1841	New York D.C.	Europe, S. America Ohio, D.C.*	Ter. mag. pulse, 1825
June 4	0440-0500 0442-0455 0440-0505	Japan California Holland	California, S. Amer., Asia Asia, Philippines, Java Java	
June 4	1154-1200-1210 1151-1206-1300 1155-1210 1153-1209 1155-1205	D.C. New York France Holland England	Ohio, D.C.* Europe, N. & S. America (Numerous) Japan, S. America, Europe (Numerous)	Ter. mag. pulse, 1153-1206 L-f atmos. increase, 1152.
June 5	0235-0250 0236-0250	California Japan	Asia, Philippines, Java California, S. Amer., Philip.	

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936				
June 9	0131-0150 0130-0155	Japan California	Asia Asia, Philippines, Java	
June 9	1424-1451-1512 1422-1441-1530 1425 1425-1440-1515 1426-1440-1500	D.C. New York France England Holland	Ohio, Massachusetts (Numerous) (Numerous) Europe, N. & S. America U.S.A., Java, Europe	Solar eruption, 1424-1432. L-f atmos. increase, 1425-1550.
June 9	1750-1845	Holland	N. & S. America	Solar eruption, from before 1755 to after 1805. Ter. mag. pulse, 1750-1805.
June 9	1859-1923-2023 1900-1930 1900-2030 1906 1900-1915 1900-1920	D.C. Missouri Ohio Illinois New York England	Ohio, Mass., D.C.* (Numerous) (Numerous) (Numerous) Europe, N. & S. America N. & S. America	Ter. mag. pulse, 1900. L-f atmos. increase, 1900.
June 10	2056-2136-2159 2105-2115-2150 2050 2056-2120 2058-2103-2107 2058-2103-2107 2053-2200 2051-2146 2045-2129	D.C. Oregon Nebraska Illinois Hawaii California California New York Guatemala	Ohio, Mass., D.C.* (Numerous) (Numerous) (Numerous) California Hawaii Asia, Philippines, Java (Numerous) (Numerous)	Ter. mag. pulse, 2055
June 11	0625-0710 0620-0700 0625-0700 0625-0700 0630-0640 0625	California Holland Japan Argentina England France	Asia, Philippines, Java Japan, Java California, S. America, Europe, Asia Japan Japan, India (Numerous)	L-f atmos. increase, 0620-0724.
June 11	1230-1250 1228-1240 1230-1243-1300 1230	Holland England D.C. France	N. & S. America, Norway, Java Asia, N. & S. America Ohio, Massachusetts (Numerous)	L-f atmos. increase, 1225-1330.
June 16	1330-1400 1330-1335-1400 1330-1349 1330-1337	Holland D.C. New York England	N. & S. America, Europe Ohio, Massachusetts England, Spain (Numerous)	Solar eruption, 1327-1348.
June 16	1713-1718-1733 1715-1728-1745	D.C. New York	Ohio, Massachusetts S. America, California	L-f atmos. increase, 1715.
June 16	1803-1808-1820 1800-1807	New York D.C.	S. America, California Ohio	Solar eruption, 1801-1809. Ter. mag. pulse, 1800. L-f atmos. increase, 1802.
June 17	0723-0740 0720	Japan France	S. America, Asia, Europe, Philippines (Numerous)	Solar eruption, 0727-0810 L-f atmos. increase, 0718
June 17	0908-0925 0908-0925 0908-0925	Japan Holland India	India, Holland, Norway Japan Japan	
June 17	1248-1254-1316 1248-1254 1246-1256	D.C. England New York	Ohio, Massachusetts India, Italy (Numerous)	
June 19	0907-0910-1000 0910-0920 0910 0910-0930	Holland England France Japan	Belgian Congo India, Egypt, N. & S. America (Numerous) Europe, India	Solar eruption, 0900-1100. L-f atmos. increase, 0905.

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936				
June 19	1633-1638 1610-1630	D.C. France	Ohio (Numerous)	Solar eruption, 1629-1637. Ter. mag. pulse, 1630.
June 19	1730-1815 1733-1737	Massachusetts D.C.	(Numerous) Ohio	Solar eruption, 1736-1800.
June 19	1936-1955-2115 1940-2000 1937-1945-2005	D.C. Idaho New Jersey	Ohio (Numerous) England	Solar eruption, 1938-1957
June 25	1030-1135 1045 1050-1100	Holland France England	Hungary, Norway (Numerous) (Numerous)	Solar eruption, 1051-1140. L-f atmos. increase, 1025.
June 25	1115-1125	England	(Numerous)	Solar eruption, 1110-1130.
July 1	0130-0150 0133-0150 0135-0155	Japan California China	N. & S. America, Philip- pines, Java, China Japan Japan	
July 15	1327-1331 1330 1328-1342 1322-1332	New York France England D.C.	S. America, Europe (Numerous) (Numerous) Ohio	Solar eruption, from before 1330 to 1340. Ter. mag. pulse, 1325-1330. L-f atmos. increase, 1328-1415.
July 30	1337-1347 1340 1342-1346-1400	New York France D.C.	(Numerous) (Numerous) Ohio	L-f atmos. increase, 1332-1432.
July 31	0015-0035 0018-0025 0015-0020-0030	Japan England California	Europe, N. & S. America, Asia (Numerous) (Numerous)	Solar eruption, 0011-0030.
Aug. 4	1727-1733-1746	D.C.	Ohio, Massachusetts	Solar eruption, 1719-1723 Ter. mag. pulse, 1725.
Aug. 5	1609-1615-1630 1606-1617-1621	New York D.C.	West Indies, S. America, Europe Ohio, D.C.*	Solar eruption, 1603-1630. Ter. mag. pulse, 1605.
Aug. 8	1725-1729-2000 1726-1730-1830	D.C. New York	Ohio, D.C.* S. America	Solar eruption, 1716-1834
Aug. 23	1130-1210	England	(Numerous)	T r. mag. pulse, 1149.
Aug. 25	1829-1851-1930 1830-1850-1955 1917-1945 1830-1905 1835-1850-1920 1828-1854-1925 1835-1908 1840-1855 1839-1855-1920 1800-2000 1800-2000	D.C. New York New Jersey Ontario, Canada France California Japan England Holland S. America British Columbia, Canada	Massachusetts Europe, M. & S. America Bermuda (Numerous) N. & S. America (Numerous) N. & S. America U.S.A. N. & S. America N. & S. America Canada	Solar eruption, from before 1858 to 1922. Ter. Mag. pulse., 1825-1930. Earth-current pulse, 1825-1910. L-f atmos. increase, 1831.
Aug. 26	0000-0020	Japan	Europe, Asia, California	Solar eruption, 2357-0001.
Aug. 28	0930-1020 0930 0930-0955-1020 0930-0955-1015 0929-0945	Italy France Holland England Japan	(Numerous) (Numerous) Japan, Java (Numerous) Europe	Solar eruption, 0920-1030. Ter. mag. pulse, 0920. L-f atmos. increase, 0923-1023.
Sept. 4	0147-0202-0230 0145-0215 0145-0200 0150-0200 0146-0208 0145-0210 0145-0215	California Java Philippines Argentina Siam England Japan	Asia, Philippines, Java (Numerous) (Numerous) Japan (Numerous) Japan, Australia Asia, Java, Europe, N. & S. America	Solar eruption, 0140-0256

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936				
Sept. 4	1238-1244-1252 1238-1250	D.C. England	Ohio, Mass., D.C.* (Numerous)	
Sept. 4	1713-1732-1740 1715-1720-1750 1714-1723-1740	D.C. New York California	Ohio, Massachusetts N. & S. America U.S.A.	Ter. mag. pulse, 1714-1721. Earth-current pulse, 1714.
Sept. 5	0902-0912-0932 0902-0915-0930 0905 0902-0930	Holland England France Japan	Japan, Java (Numerous) (Numerous) Europe	Ter. mag. pulse, 0900. L-f atmos. increase, 0859.
Oct. 9	1424-1440-1517 1422-1542 1435 1430-1450	D.C. New York France England	Ohio, Massachusetts (Numerous) (Numerous) (Numerous)	Solar eruption, from before 1454 to after 1503. L-f atmos. increase, 1417-1554.
Oct. 13	0342-0355	Japan	Asia, Europe	Solar eruption, 0250-0430.
Oct. 16	1733-1752-1820 1735-1750-1815 1740-1750 1736-1754-1834 1736-1754-1834 1720-1820	D.C. New York California Panama, C.Z. Florida Japan	Ohio, Mass., D.C.* Europe, N. & S. America (Numerous) N. America N. America Europe	Ter. mag. pulse, 1730.
Oct. 21	1535-1545-1600 1538-1550-1615 1536-1550-1555 1536-1550-1555 1538-1550	D.C. New York California Panama, C.Z. England	U.S.A. Panama, Spain England, N. & S. America D.C., Panama, West Indies D.C., California, West Indies (Numerous)	Solar eruption, 1600 Ter. mag. pulse, 1535-1550. Earth-current pulse, 1535. L-f atmos. increase, 1535-1645.
Nov. 4	1701-1715-1720	D.C.	Ohio	Solar eruption, beginning 1657.
Nov. 6	1610-1638-1700 1611-1630-1655 1609-1702 1614-1630-1645 1610-1625-1640 1610-1625-1640 1615-1650 1615 1612-1626-1630 1615-1625 1613-1620 1612-1645	D.C. New York Peru California Massachusetts Pennsylvania Illinois Japan Germany England Holland France	Ohio, Mass., D.C.* N. & S. America, Europe Peru* U.S.A., Philippines, China, Japan (Numerous) (Numerous) (Numerous) N. & S. America N. & S. America (Numerous) (Numerous) N. & S. America	Solar eruption, from before 1624 to 1650. Ter. mag. pulse, 1610-1645. Earth-current pulse, 1606-1616-1636.- L-f atmos. increase, 1612-1658.
Nov. 7	0344-0410 0345-0415 0347-0358	Japan Philippines California	Asia, N. & S. America (Numerous) (Japan)	
Nov. 7	1450-1523-1624 1452-1459-1620 1450-1505 1450-1530-1620 1450-1530	D.C. New York England Holland France	Ohio, Mass., D.C.* N. & S. America, Europe (Numerous) S. America, Japan S. America	Solar eruption, from before 1537 to 1600. L-f atmos. increase, 1451-1550.
Nov. 8	1819-1827-1834 1812-1834	D.C. California	Ohio, Mass., D.C.* Japan	Solar eruption, 1819-1827. Ter. mag. pulse, 1815-1825.
Nov. 16	1500-1545 1457-1530	New York D.C.	N. & S. America, Europe Ohio, Mass., D.C.*	Solar eruption, from before 1530 to after 1700. L-f atmos. increase, 1450-1605.
Nov. 24	1710-1749-1820 1720-1735-1800 1712-1744-1810	D.C. Holland New York	Ohio, Mass., D.C.*; Pana- ma, Porto Rico, California N. & S. America N. & S. America, Europe	
Nov. 24	1915-1930 1913-1945-2010 1915-1948 1915-1940 1914-1945-2015	Argentina D.C. W. Indies England California	Holland Ohio, Mass., Calif., D.C.,* Panama, West Indies (Numerous) (Numerous) N.Y., Wash., Philippines	Solar eruption, 1908 to after 1944. Ter. mag. pulse, 1914-1940.

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

TABLE I.—Continued

Date	Time, G.M.T.	Reported observed in	Reported locations of transmitting stations	Reported solar and magnetic effects, etc.
1936				
Nov. 24	1914-1935-2010 1845-1945 1920-1940-2000 1915-2000	New York Br. Col., Canada Holland France	N. & S. America, Europe Quebec S. America S. America	
Nov. 26	0900-0930 0900-0920-0940 0901-0925	England Holland France	(Numerous) (Numerous) (Numerous)	L-f atmos. increase, 0857-1000.
Nov. 26	1749-1835-1859 1750-1825-1840 1755-1820 1753-1810-1900 1755-1815	D.C. Br. Col., Canada England New York France	Ohio, Mass., D.C., * Pan- ama, W. Indies, Calif. Canada (Numerous) N. & S. America, Europe N. & S. America	Solar eruption, 1749-1828. Ter. mag. pulse, 1750.
Nov. 27	1651-1659-1713 1650-1724 1651-1654 1656-1715	D.C. New York Peru France	Ohio, D.C.* (Numerous) Peru* S. America	Solar eruption, 1650-1658. Ter. mag. pulse, 1650. Earth-current pulse, 1650. L-f atmos. increase, 1658.
Nov. 28	1500-1520 1510-1545	D.C. France	Ohio S. America	L-f atmos. increase, 1507-1537.
Nov. 29	1547-1602-1640 1546-1631	D.C. New York	Ohio, D.C.* (Numerous)	Solar eruption, from before 1555 to after 1637.
Nov. 30	1235-1315 1240-1300	England France	(Numerous) S. America	L-f atmos. increase, 1230-1400.
Dec. 3	1215-1330 1205-1245 1205-1242 1200-1320	Holland France England New York	N. & S. America, Europe S. America, Japan (Numerous) (Numerous)	Solar eruption, from before 1146 to after 1245. L-f atmos. increase, 1200-1302.
Dec. 9	1337-1517 1320-1700 1315-1330 1310-1355	New York Holland France England	(Numerous) S. America S. America (Numerous)	L-f atmos. increase, 1300.
Dec. 21	1817-1822-1828 1825-1829	D.C. California	Ohio Oregon, Wash., California	Ter. mag. pulse, 1815.
Dec. 22	1305-1315 1303	France Holland	(Numerous) (Numerous)	
Dec. 24	2202-2220	California	Western U.S.A., Japan, China, Philippines	Solar eruption, 2200-2218.
Dec. 24	2348-2400	California	Western U.S.A., Japan, China, Philippines	Solar eruption, 2349-2358. Ter. mag. pulse, 2348.
Dec. 26	1932-1958-2019 1944-1954-2015 1939-2016	D.C. New York California	Ohio, Massachusetts (Numerous) U.S.A., Japan, China, Philippines	
Dec. 28	1055-1100 1100 1100-1110	England Holland France	(Numerous) (Numerous) (Numerous)	L-f atmos. increase, 1103-1145
Dec. 29	0820-0835 0820 0848-0910	France Holland England	Africa, Asia Java (Numerous)	
Dec. 30	0852-0908	France	Africa, Asia	L-f atmos. increase, 0848-0920.
Dec. 30	1031-1045	England	(Numerous)	Solar eruption, from before 0944 to to 1056. L-f atmos. increase, 1030.
Dec. 30	1100-1120	England	(Numerous)	Solar eruption, from before 1053 to 1217. L-f atmos. increase, 1053.

* Disappearance or weakening of sky waves reflected vertically from ionosphere.

On account of the necessity of compressing the data into a table of reasonable length, the times given are in most cases averages. The individual times of beginning of the radio fade-out or other effect agree, however, in almost all cases within two or three minutes. For the radio fade-outs, the times of ending differed greatly. The times given are averages. (See Section III regarding the differences at different frequencies.)

The data on the radio fade-outs are based on: (a) experiences of operators receiving radio signals, (b) graphical records from field in-

FEB. 14, 1936




Fig. 1—Sudden disturbance of the ionosphere on February 14, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

tensity recorders, and (c) observations of echo signal pulses from the ionosphere. All the radio fade-outs which occurred at Washington, including practically all observable in the American hemisphere, after August, 1935, were recorded on automatic field intensity recorders maintained by the National Bureau of Standards at Meadows, Maryland, near Washington, D.C. These recorders made continuous records of the field intensities of certain high-frequency transmitting stations.

Typical fade-outs as recorded graphically are shown in Figs. 1 to 8. Note the sudden drop of intensity, and the subsequent gradual rise. As observed by a radio operator, a radio fade-out is simply the sudden disappearance of the signal from a distant high-frequency transmitting station. In most instances the intensity of the received signal was re-

APRIL 6, 1936




Fig. 2—Sudden disturbance of the ionosphere on April 6, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

APRIL 8, 1936




Fig. 3—Sudden disturbance of the ionosphere on April 8, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

duced to zero, in some it merely sank to an intensity so low as to be unreadable. Whenever echo signal pulses were being transmitted at the time of a fade-out in a given locality, the ionosphere echoes were weakened or disappeared. This is also illustrated in Figs. 1 to 8. The instances of these phenomena given in these eight figures are illustrative of many thousands of observations for which the author has data on file, which are in turn samples of the hundreds of thousands of observations on the 118 occasions listed.

MAY 28, 1936




Fig. 4—Sudden disturbance of the ionosphere on May 28, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

In the last column of Table I are numerous entries of increase of radio atmospherics at the same times as the other effects. These are all based on data published by R. Bureau of France. They refer to an increase in atmospherics as recorded on frequencies between twenty-seven and forty kilocycles per second, at observing points in France and Northern Africa.

The expression "ter. mag. pulse," in last column of Table I, means an abrupt change in one or more of the terrestrial magnetic elements, viz, horizontal intensity, vertical intensity, and declination, usually in all three. Some typical examples are shown in Figs. 1 to 8. Most of the data on terrestrial magnetic effects were obtained from the magnetograms of the Cheltenham Observatory of the U. S. Coast and Geodetic Survey, supplemented in some cases by information from other mag-

netic observatories, particularly the Mt. Wilson, California, Observatory of the Carnegie Institution of Washington. A comprehensive examination of the terrestrial magnetic and earth-current records from all observatories has not been made, so these data, like all the others, are decidedly incomplete.




Fig. 5—Sudden disturbance of the ionosphere on August 25, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

For the terrestrial magnetic and earth-current effects, the times of both beginning and ending as observed at different places are in almost all cases in agreement within about five minutes.

The information on the times of the solar eruptions coincident with the other effects was obtained from the "Bulletin for Character Figures of Solar Phenomena," published in Zurich, Switzerland, under the auspices of the International Astronomical Union, supplemented by data from R. S. Richardson of Mt. Wilson Observatory, from the Huancaayo Observatory of the Carnegie Institution of Washington, and from R. R. McMath of Pontiac, Michigan.

III. CHARACTERISTICS OF THE RADIO TRANSMISSION EFFECTS

In this Section the known facts regarding the effects of the sudden ionosphere disturbances upon radio transmission are summarized. Explanation and theory are given in Section VI.

Radio transmission is subject to so many vagaries that it is not surprising that the existence of this particular type of vagary was not recognized until the present investigation. The various vagaries cause large fluctuations in the field intensity received at a distance. These

NOV. 6, 1936




Fig. 6—Sudden disturbance of the ionosphere on November 6, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

vagaries include such things as fading, abrupt change of general level of intensity due to change of transmission from one ionosphere layer to another, disappearance or appearance of signals because of change of critical frequency at sunrise or other time of day, change associated with magnetic storms, and "fade-outs." The term "fade-out" is here reserved for the relatively sudden radio effect of the type described in this paper. Each of these kinds of vagary may produce marked diminution of received intensity of radio waves, and in the past they have not been clearly differentiated. A major result of the present research is the demonstration that the fade-out has a number of characteristics which marks it off as a distinct phenomenon.

The data here presented have to do essentially with relatively high frequencies, i.e., above about 1500 kilocycles. The limited information

for frequencies below 1500 kilocycles is mentioned below under "Frequencies Affected." Ordinarily the intensities of the waves received from radio stations on frequencies below about 1500 kilocycles are not

NOV. 8, 1936.




Fig. 7—Sudden disturbance of the ionosphere on November 8, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

NOV. 24, 1936




Fig. 8—Sudden disturbance of the ionosphere on November 24, 1936, as revealed by radio fade-out and terrestrial magnetic perturbation.

perceptibly affected during a fade-out. The outstanding and definite effect of a sudden ionosphere disturbance on radio transmission is thus the fade-out observed on frequencies over about 1500 kilocycles.

The fade-outs are characterized by simultaneity of beginning at all places affected, suddenness, very great change of intensity, differing duration and intensity change on different frequencies and at different distances, maximum effect where the sun's radiation is perpendicular, and no effect for all-dark paths. Details of these characteristics follow.

Geographic Simultaneity. Leaving aside the question of simultaneity of the radio fade-outs with other phenomena (solar, etc.), a distinguishing characteristic of the radio fade-out is the simultaneity of its beginning at the various places where it is observed. As shown in Table I, the beginning of a fade-out is in nearly all cases simultaneous within a few minutes. Variations of more than ten minutes are reported in only seventeen of the 118 cases, and these are probably due to incompleteness or inaccuracies of observation. It is likely that every fade-out began simultaneously within three minutes everywhere, and in many cases the simultaneity was doubtless well within one minute.

The time of ending of a fade-out, on the other hand, is very different at different radio frequencies, at different distances, and in different parts of the earth; this is discussed further under "Frequencies Affected" and "Geographic Distribution" below.

Suddenness. The suddenness of the radio fade-outs has astonished many radio observers, operators, and amateurs. Radio signals being received at normal intensity suddenly begin to diminish and the intensity falls to zero, usually within a minute. The effect is on some occasions preceded by a short period of unusually violent fading, echoes, and noise (of a type different from atmospheric), but the effect usually comes without warning. There is sometimes also a period of violent fading, echoes, and noise (different from atmospheric) after as well as before a fade-out.

The suddenness of commencement of a fade-out is vividly illustrated by numerous reports in which the observer stated he thought that the power had gone off in the receiving station, or that a fuse had blown, or that the stations to which he was listening had stopped transmitting, or that his receiving apparatus had developed a sudden fault. Many an observer has dissected his receiving equipment on such occasions in the vain effort to determine why it suddenly went dead.

As may be seen from the examples in Figs. 1 to 8, the received radio wave intensity drops from full value to zero, in most cases, within a minute. In some of the more intense fade-outs, like that of February 14, 1936, shown in Fig. 1, the cutoff occurs within a few seconds. The duration of the effect is greater for the lower frequencies of the frequency range affected; this is discussed further below under "Frequencies Affected." Sometimes the drop to zero is not quite so sudden

for the higher frequencies as for the lower; this is illustrated in Fig. 6 (November 6, 1936) and Fig. 8 (November 24, 1936). In a few rare cases, such as the extra fade-out at 1715, November 24, 1936, shown in Fig. 8, the drop to zero was gradual, lasting ten minutes or so; such a case was not one of the more intense fade-outs, and was not accompanied by a terrestrial magnetic effect.

Degree of Intensity Change. The sudden change of intensity in a fade-out is very great. In most fade-outs there is a certain band of radio frequencies throughout which the intensity drops from normal value to zero. Sometimes the intensity does not drop all the way to zero for the higher frequencies; see for example Fig. 7 (November 8, 1936). There is evidence that there is often a frequency limit above which radio transmission is merely weakened rather than reduced to zero, and sometimes a still higher limit above which radio transmission intensity is not perceptibly reduced. Such is not always the case, however, for sometimes the sky wave intensity is reduced to zero throughout the entire high-frequency radio spectrum.

The sudden reduction of the intensity to zero when a fade-out occurs is an extraordinary experience. Not only does the radio station appear to stop transmitting, but in the more intense fade-outs even the background noise due to atmospherics ("static") disappears. The impression of the observer is that reception goes dead. This enhances the effect of the suddenness of the fade-out and further impels the observer to look for trouble in his receiving equipment.

Frequencies Affected. The data on radio fade-outs indicate that they occur on all the high frequencies used for long-distance radio work; i.e., from about 1500 to 30,000 kilocycles. Reports are available on radio reception at lower frequencies during many of the fade-outs, and in nearly all cases they indicate that reception was not affected. Some automatic records made by the National Bureau of Standards indicated that the sky wave, at broadcast frequencies, was weakened during a fade-out. As the ground wave plays a large part in daytime transmission at broadcast and lower frequencies, and the ground wave is unaffected by ionosphere phenomena, fade-out effects would not be prominent and would tend to escape notice. In a very few cases there have been reports of a changed character of fading on broadcast or lower frequencies, or of an increase of intensity on the lower frequencies. R. Bureau of France (see Bibliography) has found that recorders of atmospherics on frequencies between twenty-seven and forty kilocycles show an increase in numbers of atmospheric pulses recorded during many of the fade-outs; the times of such occurrences are given in Table I.

For the frequency range in which fade-out effects are conspicuous, i.e., from about 1500 to 30,000 kilocycles, the effects are greater on the lower frequencies. This is true in regard to the duration of the effects and the degree of intensity change. The variation of intensity change with frequency is described in the Section just above on "Degree of Intensity Change." The variation of the duration of a fade-out with frequency is illustrated in Figs. 1 to 8.

As shown in the figures, the beginning of a fade-out is simultaneous on all frequencies. This simultaneity is exact in most cases, and where not exact the times of beginning seldom differ more than two or three minutes and the effect occurs first on the lower frequencies. As also shown conspicuously in the figures, the duration or time of ending of a fade-out is very different on different frequencies. The time during which the received intensity is zero, and the time of recovery to normal intensity, are both greater the lower the frequency, other factors being the same. Interpretation of the variation of the effect with frequency in particular cases is complicated by the variation of the effect (discussed in next section below) with geographic location of the radio transmission paths affected, and also by the variation with distance of transmission. Since in long-distance transmission the waves travel a much longer path through the lower ionosphere the effects are greater for long distances than for short distances. Thus, a fade-out for a long-distance transmission path, on a given frequency, will have a greater reduction of intensity and a greater duration than for a short-distance transmission path. Expressed otherwise, the fade-out effects for a long-distance path correspond to those at a lower frequency for a short-distance path. Bearing this in mind, the variation of fade-out effects with frequency is consistent in the figures and in all known fade-outs. H. A. G. Hess reported that during the intense fade-out of November 6, 1936, which happened to occur during a time when long-distance transmission on 40,000 kilocycles was possible, there was no diminution in transatlantic reception on about that frequency. This fade-out was not as intense as some others. It is believed that during the most intense fade-outs all high-frequency sky waves fail.

It is found, and it is consistent with the foregoing conclusion, that fade-outs which last longer are usually observed up to higher frequencies than those of shorter duration; where the duration is short, the higher frequencies are less affected. This is illustrated by a comparison of Fig. 1 and Fig. 7.

Geographic Distribution. All of the fade-outs known to date, listed in Table I, have the characteristic discovered by the author in 1935 for the fade-outs then known, that they occur throughout the hemi-

sphere illuminated by the sun and not in the dark hemisphere. More precisely stated, whenever a radio fade-out occurs some part of the radio transmission path is in the daylight hemisphere. The continuous automatic recorders of the National Bureau of Standards, recording the field intensities of domestic stations, and the normal incidence ionosphere reflections have detected no fade-outs between sunset and sunrise. Since many other observers throughout the world have been watching for the effects, the lack of any reports whatever of disturbances on all-dark paths may be taken as proof of their nonoccurrence. For many of the times when radio fade-outs were reported, there have also been specific reports from the dark hemisphere that radio transmission was unaffected. Sometimes a fade-out is reported as observed at a place where it is dark, but in every such case the fade-out occurs only on radio transmission paths which are partly in the hemisphere illuminated by the sun. Thus, fade-outs have in a few cases been observed at midnight in certain places, without violating this principle. Conspicuous examples are: Argentina, 0400, April 2, 1936; California, 0728, May 28, 1936; England, 0016, July 31, 1936.

A study has been made to determine more specifically the variation of intensity of the effect with latitude, longitude, and direction. It is found that the effects are most pronounced in localities where the sun's radiation is perpendicular to the earth's surface. Thus, they are most intense in the equatorial regions and diminish with increasing latitude. Similarly, they are most intense at longitudes where it is noon and diminish in both directions toward longitudes where it is night. These relations are true in respect to the suddenness of beginning of the radio fade-out, the time it lasts, the upper limit of frequency affected, and the degree of reduction of field intensity. A fade-out which, at the place where the sun's radiation is perpendicular, may be very intense and prolonged, may, for the same frequency, be a mere brief reduction of field intensity near the boundary of the illuminated hemisphere.

Variations with direction have not been completely analyzed, but they appear to be consistent with the foregoing relations. For example, at receiving points in the United States, reception from stations in the southern hemisphere usually exhibit greater effects than reception from other directions (because of passing the equatorial regions). Similarly, a disturbance occurring in the morning usually exhibits greater effects in reception from the east than from the west, and vice versa for the afternoon (because of passing the region where it is noon).

Interpretation of particular cases is complicated by the variation of the effect with the radio frequency and distance.

IV. CHARACTERISTICS OF THE TERRESTRIAL MAGNETIC AND EARTH-CURRENT EFFECTS

In this Section the known facts regarding the effects of the sudden ionosphere disturbances upon terrestrial magnetism and earth currents are summarized. The phenomena are explained in Section VI.

In many respects the terrestrial magnetic and earth-current effects have the same characteristics as the radio transmission effects. These similar characteristics include geographic simultaneity, suddenness, limitation of occurrence to the illuminated hemisphere, and the same variation of intensity of effect with latitude and longitude. They are similar also in being only one among the many types of vagaries of terrestrial magnetism and earth currents, such as diurnal and seasonal variations, irregular fluctuations, and magnetic storms. Also, as in radio, the effects due to the sudden ionosphere disturbances have in the past not been recognized as something different from the other classes of vagaries; this study has shown that they have characteristics which mark them off as a distinct and separate type of magnetic perturbation.

Limitation to Illuminated Hemisphere. The data on terrestrial magnetism in Table I are based principally on the magnetograms of the Cheltenham Observatory of the U. S. Coast and Geodetic Survey. These magnetograms were examined for the times of all the radio fade-outs. In a few cases data were available from the records of other observatories. In the more intense fade-outs, magnetic effects occurred simultaneously everywhere throughout the sun-illuminated hemisphere. In none of them did effects occur in the dark hemisphere.

The data on earth currents are highly fragmentary, as no systematic examination of earth-current records was made. The few entries of earth-current effects in Table I are based on occasional reports to the author by various collaborators. The phenomena of earth currents and terrestrial magnetism are so closely interrelated that very probably earth-current effects occurred whenever there were perturbations of terrestrial magnetism.

Simultaneity with Radio Fade-outs. Typical examples of the terrestrial magnetic effects are shown in Figs. 1 to 8, in which a few Cheltenham magnetograms are reproduced. The magnetic pulses, when they occur, are simultaneous with the radio effects, indicating that both are manifestations of an ionosphere change. As indicated in the table, the magnetic pulses occurred during many of the radio fade-outs but not all. The suddenness and the duration of the pulses may be judged from the figures.

Geographic Distribution. The geographic distribution of intensity of the terrestrial magnetic effects is, so far as the limited data indicate, the same as for the radio fade-outs. That is, they are most pronounced in the vicinity of that region of the earth's surface to which the sun's radiation is perpendicular, and diminish to zero at the boundary of the illuminated hemisphere. Thus the effects are greatest at low latitudes, and at longitudes where it is noon. They do not occur in the night hemisphere.

Comparison with Magnetic Storms. The geographic distribution of intensity of the effects is strikingly different from that of terrestrial magnetic and earth-current effects hitherto known. For example, a world-wide magnetic storm is characterized by a "sudden commencement," a pulse which is simultaneous over the whole earth. The magnetic storms and their sudden commencements thus differ markedly from the magnetic effects associated with sudden ionosphere disturbances in respect to distribution in longitude, since the latter occur only in the sun-illuminated hemisphere.

The two phenomena differ even more extraordinarily in respect to their distribution in latitude. Magnetic storms have minimum effects at the equator and maximum effects near the magnetic poles, just the opposite of the effects of sudden ionosphere disturbances. An interesting consequence of this is that the magnetic and earth-current pulses due to the sudden ionosphere disturbances are much more striking when observed in equatorial regions than in high latitudes. They may be of the same order of magnitude as the fluctuations due to magnetic storms in equatorial regions, relatively small in middle latitudes, and negligible in high latitudes.

Besides these differences in the geographic distribution of the effects magnetic storms and the sudden ionosphere disturbances differ in duration, the former lasting hours or days instead of the brief period of the latter.

A study has been made to determine whether there is any relation between times of occurrence of magnetic storms and the sudden ionosphere disturbances. It is concluded that there is none, and the occurrence of each is quite random with respect to the other. Sudden ionosphere disturbances usually occur during magnetically quiet times, but some have occurred during magnetic storms. In studying this subject, caution should be observed to consider the results observed at a number of different locations in order to be sure that an apparent effect of the sudden type really is one. Observations of the effect at a single location are often hard to distinguish from other types of vagaries.

One of the major results of this research is the discovery of a separate type of terrestrial magnetic disturbance, with remarkable charac-

teristics which clearly differentiate it from magnetic storms or any previously known types of magnetic perturbations. This is analogous to the discovery of the fade-out as a distinct type of radio vagary.

V. SOLAR PHENOMENA ASSOCIATED WITH SUDDEN IONOSPHERE DISTURBANCES

In this Section the known facts regarding solar phenomena having a bearing on the sudden ionosphere effects are summarized. Explanation and discussion follow in Section VI.

Exactness of Simultaneity. The times of the solar eruptions known to have occurred at the times of the sudden ionosphere disturbances are given in the last column of Table I. They were simultaneous in the sense that the reported time of the solar eruption overlapped the time of the sudden ionosphere disturbance.

The times stated for the solar eruptions are in most cases uncertain by many minutes. This is because of difficulties in their observation. They are sometimes seen with difficulty, and the observing astronomer cannot be sure when a solar disturbance begins or ends. They are often obtained by photographs which may be taken at intervals of fifteen minutes or more, so that the time of a phenomenon indicated by a difference between two successive photographs may be uncertain.

Because of the uncertainties of their observational material, different astronomers adopt different criteria. The conditions of seeing (presence of haze, etc.) are also different at different observatories at any one time. It results that different solar observers differ considerably in the times they report for the beginning and end of solar eruptions. For example, the solar eruption of August 5 listed in the table was reported by Mt. Wilson Observatory as ending at 1613 and by Zurich Observatory as ending at 1648. As another example, the eruption listed for August 28 was reported by Zurich Observatory as ending at 1030, and was reported by Greenwich Observatory as still in progress at 1130. Likewise, an eruption was reported by Zurich Observatory as having begun on July 4, 1936, at 1655, and the same eruption was reported by Mt. Wilson Observatory as having begun at 1707. These cases were all major eruptions, more easily visible than most solar eruptions. It is evidently impossible to determine the times of solar changes within a small number of minutes.

The lack of precision of the solar data thus makes it impossible to say how close is the correspondence of times of the solar eruptions and the terrestrial effects. All of the cases listed in Table I may reasonably be described as simultaneous occurrences within the limits of our knowledge.

Proportionate Number of Simultaneous Occurrences. Of the 118 ionosphere disturbances listed in Table I, fifty-nine (exactly half) are shown to have been coincident in time with solar eruptions. There may have been a much larger proportion than shown. The sun is not under continuous observation and hence it is not known whether a visible solar eruption occurred or not at the time of any ionosphere disturbance for which no solar eruption is reported. Most solar observatories have in the past carried on observations for not more than an hour each day. An arrangement is in effect by which observatories in different parts of the world stagger their times of observation with a view to a continuous watch on the sun. Cloudy weather and other conditions, however, prevent the full attainment of this program.

On the other hand, however, when we examine the solar records (in the "Bulletin for Character Figures of Solar Phenomena"), we find that many solar eruptions occur when no ionosphere disturbances are known to have occurred. For example, from January to June, 1936, the above-mentioned Bulletin lists 302 solar eruptions, and only twenty-nine of these were simultaneous with known disturbances of the ionosphere. A larger proportion of coincidences is found if we consider only the more intense solar eruptions (those of arbitrary intensities two or three); there were in the same period sixty-nine of these listed, of which seventeen were simultaneous with known disturbances of the ionosphere. It is probable that many of the visible solar eruptions were not accompanied by detectable ionosphere disturbances, although the converse may not be true. Many of these eruptions may rise high enough in the solar atmosphere to permit the escape of visible light but not high enough to permit the escape of the ultraviolet radiation responsible for the sudden bursts of ionization in the earth's atmosphere. The use of automatic radio and magnetic recorders continuously has assured knowledge of the occurrence of practically all ionosphere disturbances in the western hemisphere.

Character of Eruptions. The eruptions here discussed are bright chromosphere eruptions. They are visible as sudden increases of brightness of large bright patches on the sun's surface, and when occurring at the limb of the sun are seen as eruptive prominences. An eruption usually, but not always, takes place near an active sunspot group. Most of the eruptions simultaneous with sudden disturbances of the ionosphere are much brighter than the average.

Location of Eruptions on Sun. It is of interest to know whether the eruptions causing sudden ionosphere disturbances occur wholly or predominantly at any particular location on the sun's surface. It might be thought, for instance, that the radiation would be effective only when projected radially from the sun to the earth; i.e., when the erup-

tive area is in the center of the sun's disk. The solar locality of all the visually observed eruptions simultaneous with sudden ionosphere disturbances is known, and has been examined in this connection. It is found to be random, which means that the eruptions send out their radiations in all directions from the sun's surface; the terrestrial effects occur regardless of where the eruption takes place, near the sun's limb, at or near the center of the disk, or anywhere between.

The locations of the eruptive areas on the sun have also been examined to find out whether particular areas give rise to repeated effects, and especially whether such effects are repeated after one or more rotations of the sun. On a number of occasions, successive eruptions from a given solar area, accompanying sudden ionosphere disturbances, have occurred in the course of a day or two. Little evidence however has been found of any repetition of eruptions from a particular area after one or more rotations of the sun.

Recurrence Tendency. A possible periodic tendency in the times of occurrence of the sudden ionosphere disturbance was suggested by the occurrence of the ones first known to the author, and listed first in Table I, at intervals of approximately fifty-five days. This is shown graphically in Fig. 9, in which all the occurrences are plotted. The intensity of each occurrence was weighted on an arbitrary basis, having regard to the duration and magnitude of the effect, the number of places from which reported, etc. The intensities thus weighted by two persons independently agreed very well and were plotted as ordinates on an arbitrary scale in Fig. 9. The abscissas are time, each horizontal line being an interval of fifty-five days. In Fig. 10 is plotted an average curve for all the 55-day periods. The existence of a 55-day recurrence tendency is indicated. This should not be taken as proved, as two years is not considered to be a sufficient time to establish such a tendency with certainty. It may be mentioned that the 55-day recurrence tendency remains very marked even if the first seven cycles, in which it is so pronounced, be disregarded. Further analysis has indicated that the recurrence tendency averages slightly less than fifty-five days, but is closer to fifty-five than fifty-four.

It is of interest that there is no indication of a recurrence tendency of the order of twenty-seven days. The sun rotates on its axis in a remarkable way, rotating faster at the equator than elsewhere. The rotation period is about twenty-four days at the sun's equator and about thirty-six days near its poles. The average rotation period of the portion of the sun in which the eruptions take place, and also incidentally the period for which terrestrial magnetic disturbances show a recurrence tendency (presumably dependent upon some unidentified type of solar eruptions), is between twenty-seven and twenty-eight

days. Thus the tendency to a recurrence period of fifty-five days, of the ionosphere disturbances, is twice the well-known solar period of approximately twenty-seven days. Again, caution should be observed in any conclusions from this, since data are available for only two years.

Relation to Sunspots. In a general way, solar eruptions tend to be more prevalent in years when sunspots are more numerous, and thus




Fig. 9—Recurrence diagram of sudden ionosphere disturbances, arranged in 55-day periods; intensity of disturbance is approximately indicated by ordinate. (NOTE: By error, the first six days in each line are displaced one line too high. This error in drawing does not affect the accuracy of Fig. 10.)

their number may be expected to wax and wane in an 11-year cycle with the sunspots. There is no evidence, however, of any short-time correlation with sunspot numbers of the sudden ionosphere disturbances or the particular solar eruptions accompanying them. The number of sudden ionosphere disturbances certainly does not vary from day to day, or from month to month, in accordance with the sunspot numbers. Data are not available over a long enough time to permit a conclusion as to whether there is any correlation of yearly averages.

VI. DISCUSSION AND EXPLANATION

The foregoing facts clearly outline a phenomenon which is some type of sudden change somewhere in the ionosphere. Whenever the phenomenon occurs, it is most intense in that region of the earth where the sun's radiation is perpendicular and diminishes to zero at the outer edge of the illuminated hemisphere. Its onset usually occurs within a minute, and is simultaneous throughout the hemisphere affected. Its various effects begin simultaneously, and last from about ten minutes




Fig. 10—The 55-day recurrence tendency, shown by smoothed average of disturbance intensity for all periods.

to several hours, the occurrences of greater intensity in general producing effects of longer duration. The effects include the sudden blotting out of high-frequency radio sky-wave transmission, sudden changes in low-frequency atmospheric, sudden changes in terrestrial magnetic intensities, and sudden changes in earth currents. The effects are markedly different from other types of changes in these quantities. They are more intense where it is noon than where it is other times of day, and are more intense in equatorial regions than in higher latitudes. The radio effects are very large, indicating that the ionosphere changes producing them are intense ones.

Seat of the Disturbances Deduced from Radio Effects. The various characteristics of the effects summarized in the preceding paragraph

and detailed earlier in the paper indicate them to be due to an ionosphere phenomenon; and the nature of that phenomenon is more particularly elucidated by a consideration of the radio effects.

Long-distance radio transmission takes place by means of so-called sky waves which are reflected back to earth from the ionosphere or the ionized upper portion of the atmosphere. The ionization is stratified in the daytime into a number of layers, of which three principal layers are well recognized: the E layer, F_1 layer, and F_2 layer. The E and F_1 layers are respectively about 120 and 220 kilometers above the earth's surface, and the F_2 layer is at a height varying from about 250 to 400 kilometers at different times. The maximum ionization density is progressively greater from the E to the F_2 layer. The presence of ionized particles of air makes the layers reflect radio waves which reach them. For a given maximum ionization density and angle of incidence, all radio waves up to a certain frequency are reflected and waves of higher frequency pass through to higher layers. For example, at a given time and distance, all radio frequencies up to 9000 kilocycles might be reflected by the E layer, those from 9000 to 30,000 kilocycles be reflected from the F_2 layer, and no frequencies above 30,000 kilocycles be reflected at all (i.e., no frequencies above this limit could be received over the distance considered).

An increase in the maximum ionization density of a layer raises the upper limit of frequency of radio waves which it can reflect. During a number of the sudden ionosphere disturbances measurements or recordings were in progress to determine this upper limit of frequency for the several layers, E, F_1 , and F_2 . In no case was an appreciable change observed during or just after the disturbance. (It is possible to speak of radio observations being in progress during a fade-out because there were usually some frequencies, distances, or locations for which radio transmission continued while for others the radio transmission was annihilated. See Section III.) It may be concluded that the sudden ionosphere disturbances do not change the maximum ionization density of the E, F_1 , or F_2 layers, either not at all or very slightly.

On the other hand, ionosphere studies have amply proved that an increase in the ionization density of a region *through* which radio waves pass on the way to being reflected by a higher layer causes an increase in absorption of the radio waves' energy and results in a diminution of the received wave intensity. This is exactly what happens, and indeed to a striking degree, during one of the sudden disturbances. On some occasions an increase of virtual height of one of the ionosphere layers has been observed. (See Fig. 6.)

It may, therefore, be concluded that these sudden disturbances

involve a sudden great increase of ionization in some region through which radio waves pass on the way to being reflected by a higher region. Since the fade-out occurs in radio waves reflected by the E as well as the higher layers, the absorbing medium must be below the E layer.

The seat of the sudden large increase of ionization is thus below the E layer; i.e., lower than 120 kilometers above the earth's surface. The E layer is thus not the lowest part of the ionosphere. This is in harmony with some other facts which have been discovered recently. It is now known that waves of broadcast and lower frequencies are propagated in the daytime at certain seasons by reflection from a layer lower than the E layer. This was discovered by Smith and Kirby,⁴ by observation of the changes in the characteristics of received waves near sunset and sunrise, showing a change from E layer at night to a lower layer in the daytime and back to the E layer at night.

This low layer may perhaps be called the D layer, but not enough is yet known about it to be sure that this designation is appropriate. There may be several layers acting, whose combined effect we observe, or one or another of them may predominate at different times. Or the effective layer may more or less merge into the E layer. With our present limited knowledge it is perhaps as well to think tentatively of a single low layer or region in which low-frequency transmission takes place, and in which the sudden ionosphere disturbances occur.

For low frequencies (below about 1500 kilocycles), a sudden ionosphere disturbance does not produce as complete a fade-out as at higher frequencies, because radio waves tend to be reflected by, instead of passing through, the layer in which the sudden increase of ionization occurs. Indeed, the sudden increase of ionization may even tend to increase rather than decrease the very low-frequency radio wave intensity; this is in harmony with the results of R. Bureau on low-frequency atmospherics (30 to 40 kilocycles).

For frequencies above about 1500 kilocycles, the ionization of the low layer is ordinarily not great enough to reflect the waves. They pass through and are reflected from the E or higher layers where the ionization density is greater. When the sudden increase of ionization in the low layer occurs, however, the ionization suddenly becomes great enough to produce large absorption of the radio wave energy and a fade-out occurs. There is less interchange of energy between the ions and the radio waves, the higher the frequency, and therefore for very high frequencies the fade-out effects are less pronounced; this is in accordance with experience, as described in Section III and illustrated in Figs.

⁴ "Critical frequencies of low ionosphere layers," *Phys. Rev.*, vol. 51, p. 890; May 15, (1937).

2 to 8. It is also clear from this conception why the effects on a given frequency for normal-incidence transmission are the same as the effects on a much higher frequency for grazing incidence transmission: the waves at grazing incidence travel a much longer path through the abnormally ionized layer and thus experience an added amount of energy interchange with the ions, thus compensating for their higher frequency.

The source of the sudden ionization changes must be outside the earth, and therefore has to come through the E, F₁, and F₂ layers. It must have a character, therefore, distinctly different from the source of ionization of those layers. It produces its effect at a level where the air density is great enough to insure numerous collisions of moving ions and hence rapid absorption of the radio wave energy. The radiation producing this effect is therefore of a type which can penetrate the better known higher layers and produce ionization where the mean free path is shorter than at the higher levels. The effect must be produced by a very sudden burst of very penetrating radiation, which reaches and ionizes a level of the atmosphere where the air density is great enough to insure rapid recombination of the ions as well as rapid absorption of the energy of radio waves reaching such region. This explains the great reduction of the radio wave intensity and the short duration of the effect, as well as the suddenness of the drop of radio intensity.

The recombination proceeds so fast that the ionization and the ionizing energy are very nearly in equilibrium at all times. As the ionizing radiation from the sun dies out, in accordance with the disappearance of the solar eruption, the intense ionization in the lower ionosphere wanes, and the highest radio frequencies affected are soon freed of its effects. As the ionization diminishes, lower and lower frequencies recover from the effects. The duration of a fade-out at a given frequency is thus dependent not only on the intensity of the burst of ionizing energy but also on the duration of the solar eruption.

Magnetic Effects. The occurrence of the sudden ionization being thus inferred and explained from the radio effects, it is clear why simultaneous changes are sometimes observed in terrestrial magnetism and earth currents. Both of the latter phenomena are due in part to the motion or drift of ions in the earth's atmosphere, constituting in the aggregate vast currents whose associated magnetic field constitutes a portion of the earth's magnetism and whose fluctuations account for the variations in terrestrial magnetism and earth currents. When a sudden ionosphere disturbance of the type here considered takes place, the sudden increase in ionization permits a simultaneous sudden change in net

current flowing and thus perturbations in terrestrial magnetism and earth currents. It is to be noted that such perturbations do not depend entirely on the amount of the ionization, as do the radio effects, but involve also drift or motion of the ions. The radio effects are therefore not always accompanied by magnetic and earth-current perturbations. Whether the latter become observable or not depends on the complicated circumstances of the earth's magnetism at various places and times. When observed, they share the characteristics of the radio effects and the acting cause in the ionosphere; i.e., simultaneity throughout the portion of the earth affected, absence in the dark hemisphere, suddenness, and maximum intensity where the sun's radiation is perpendicular.

As previously stated, this type of perturbation of terrestrial magnetism and earth currents is strikingly different from the perturbations associated with "magnetic storms." Radio effects have shown that during magnetic storms the ionization density of the highest layer of the ionosphere (F_2 layer) is reduced and the ionization is diffused rather than sharply stratified. These effects thus prove that at least part of the phenomena of magnetic storms have their seat in the F_2 layer.⁵

It has here been shown, on the other hand, that the sudden ionosphere disturbances have their seat below the E layer, and the phenomena causing the terrestrial-magnetic and earth-current perturbations associated therewith must therefore also have their seat below the E layer.

Thus the two kinds of magnetic phenomena arise in entirely different portions of the ionosphere, in entirely different ways, and are probably due to two different kinds of ionizing agent. We thus have a new tool for analysis of the characteristics of terrestrial magnetism and for determination of their causes. There has hitherto been little known as to the locations of the vast ionosphere current systems which cause the fluctuations of terrestrial magnetism. The new possibility of localizing the levels in which different types of perturbations originate will aid in deciding between rival theories of terrestrial magnetism and should do much to bring to light the hitherto unknown mechanisms of terrestrial magnetic variations.

Solar Source. The sun is in an extremely turbulent state, and on it

⁵ S. S. Kirby, T. R. Gilliland, E. B. Judson, and N. Smith, "The ionosphere, sunspots, and magnetic storms," *Phys. Rev.* vol. 48, p. 849, (1935).

S. S. Kirby, T. R. Gilliland, N. Smith, and S. E. Reymer, "The ionosphere, solar eclipse, and magnetic storm," *Phys. Rev.* vol. 50, p. 258, (1936).

S. S. Kirby, N. Smith, T. R. Gilliland, and S. E. Reymer, "The ionosphere and magnetic storms," *Phys. Rev.* vol. 51, (1937).

occur frequent eruptions from which are emitted radiations having a great range of wave lengths. There is no reason to doubt that some of the radiations from some of these eruptions are the sudden bursts which cause the sudden disturbances of the ionosphere of this planet. This is strongly indicated by the numerous observations of such eruptions and ionosphere disturbances coinciding in time.

The lack of occurrence of an ionosphere disturbance during every visible solar eruption does not at all vitiate the idea of a causal relation, because many different kinds of radiation are emitted in solar eruptions and visible radiation is not the kind which affects the ionosphere. The existence of visible solar effects during the solar cataclysms which cause the ionosphere disturbances is fortuitous. The simultaneous occurrence of an ionosphere disturbance and the flare of light which makes the solar eruption visible indicates that the radiation causing the ionosphere disturbance travels to earth with the velocity of light. As shown above, the radiation which causes the sudden large increase of ionization of a low region of the ionosphere is of a very penetrating type; it is therefore electromagnetic radiation of frequency far above visible light.

This doubtless gives the explanation why not all visible solar eruptions cause ionosphere disturbances. Evidently some eruptions emit the particular types of radiation which penetrates to the region below the E layer and ionizes it, and some do not.

The ionosphere disturbances and their associated effects are the only known means of detecting the causative solar radiation, because this radiation cannot penetrate the relatively dense lower atmosphere and reach the earth's surface and thus can not be directly detected by any instrumental means. We have thus come into possession of a means of studying a new class of invisible solar radiation, not hitherto accessible to detection or measurement.

The results of this research prove conclusively that ultraviolet radiation from the sun can cause terrestrial magnetic fluctuations. E. O. Hulburt has advocated similar ideas in numerous papers during the past ten years.

Ionosphere phenomena should be of very great value in increasing our knowledge of the sun. The ionization phenomena of the F_2 layer are decidedly different from those of the E layer, and there may thus be differences in the causative radiations for the two layers. Certain effects in the F_2 layer, associated with magnetic storms, may be due to a different type of radiation. As we have seen, the radiation causing the sudden ionosphere disturbances is of still different character. All of these classes of radiation can be studied only by their ionosphere ef-

fects, as they do not penetrate down to the earth's surface. Ionosphere phenomena, as detected by radio, terrestrial-magnetic, and earth-current effects thus become the unique means by which we can study various classes of radiation from the sun.

The physical nature of the sun is extremely interesting, and presents many mysteries. One of the chief mysteries is the eruptions. Little is known about the precise relation of the eruptions to sunspots or about the cause of either. The sun is a rotating sphere of very hot gas, and a sunspot is a vortex resulting from a great cataclysmic change in a portion of the sun. A sunspot lasts from a few days to a few months. The sudden eruptions, usually lasting only a few minutes, commonly occur during the early stages of a neighboring sunspot group; they may be connected with the process which gives birth to sunspots. This process is thought by astronomers to be the sudden formation of vast quantities of helium from hydrogen by the combination of four hydrogen atoms to form one of helium, with great energy liberation. Determination of the wave lengths of the radiation accompanying sudden pulses which occur during this process should aid in further identifying its nature and the obscure cause within the sun. Such determination is among the possibilities of future study of the sudden ionosphere disturbances. The duration of some of the phenomena during eruptions may also be learned through this study.

Another aspect of the sudden ionosphere disturbances which is worthy of study in connection with solar phenomena is the time grouping of the disturbances. As shown in Fig. 9, the major disturbances showed a very marked 55-day recurrence tendency from November, 1934, to May, 1936; then in May and June, 1936, there was an extraordinary outburst of them, after which there were relatively few of them for several months.

A study of the solar circumstances of the eruptions accompanying such disturbances, and the possible future determination of the wave lengths of the solar radiation associated with them, may eventually elucidate the nature of the eruptive processes within the sun and the causes of sunspots.

VII. ACKNOWLEDGMENT

The work here reported has been in large measure a world-wide co-operative study. Many individuals and organizations have sent me reports of their observations of various aspects of the sudden disturbances of the ionosphere as they occurred.

The most consistent source of data has been the continuous records of field intensity of high-frequency stations, and the records of iono-

sphere phenomena, made by my colleagues in the National Bureau of Standards, Messrs. S. S. Kirby, N. Smith, T. R. Gilliland, and S. E. Reymer.

Dr. R. Jouaust of the Laboratoire Central de Radio-electricite, France, and the author have regularly interchanged data during this study. Dr. Jouaust has compiled and distributed comprehensive bulletins of data on the radio fade-outs, principally as observed in Europe. These were forwarded from the French National Committee to the other national committees of the International Scientific Radio Union, and this service is being continued.

The Carnegie Institution of Washington has collaborated in the supplying of solar and terrestrial magnetic data. In particular, Dr. R. S. Richardson, of the Mt. Wilson Observatory, California, has cooperated with the author through the supplying of information monthly on solar eruptions.

The Coast and Geodetic Survey has assisted by supplying copies of its daily magnetograms made at its terrestrial magnetic observatory at Cheltenham, Maryland.

Regular reports on radio fade-outs as observed during the handling of radio communication traffic have been furnished by:

H. H. Beverage, Chief Research Engineer, R.C.A. Communications, Inc.

H. Pratt, Chief Engineer, Mackay Radio and Telegraph Company.

L. Espenschied, Bell Telephone Laboratories, Inc.

N. Koomans, Chief, Staatsberdreijf der P.T.T., Holland.

T. Nakagami, Chief Engineer, Kokusai-Denwa Kaisha Ltd., Japan.

Reports have been furnished on particular radio fade-outs and related phenomena by many others, including:

Chief Signal Officer, War Dept., U.S.A.

Naval Communication Service, U.S.A.

Aeronautical Radio Inc., U.S.A.

British Broadcasting Corporation, England.

W. Calloway, Office of Posts and Telegraphs, Kuala Lumpur, Malaya.

J. H. McMullin, Commissioner of Police, British Col., Canada.

C. P. Edwards, Department of Transport, Ottawa, Canada.

Reports on numerous radio fade-outs have been supplied by many radio amateurs, forwarded through the American Radio Relay League. Of these, the reports of Mr. F. D. Jenkins, of Atlanta, Ga., have been particularly helpful.

Bibliography

- J. H. Dellinger, "A new cosmic phenomenon," *Science*, vol. 82, 351; October 11, (1935).
- J. H. Dellinger, "A new radio transmission phenomenon," *Phys. Rev.*, vol. 48, p. 705; October 15, (1935).
- J. H. Dellinger, "Confirmation of cosmic phenomenon," *Science*, vol. 82, p. 548; December 6, (1935).
- J. H. Dellinger, "New radio transmission phenomenon," *QST*, vol. 19, p. 21 of December, (1935).
- J. H. Dellinger, "A new solar radio disturbance," *Electronics*, vol. 9, p. 25; January, (1936).
- R. S. Richardson, "The hydrogen outburst on the sun and radio fading," *Science*, vol. 83, 6 Supp., January 10, (1936).
- J. H. Dellinger, "New cosmic phenomenon," *QST*, vol. 20, p. 8 of January, (1936).
- R. S. Richardson, "Sunspot activity and radio transmission fade-outs," *Trans. Amer. Geophys. Union*, Part I, p. 172, (1936).
- J. H. Dellinger, "High-frequency radio fade-outs continue," *QST*, vol. 20, p. 37 of June, (1936).
- R. S. Richardson, "The bright hydrogen eruption and radio fade-out of April 8, 1936," *Ter. Mag. and Atmos. Elec.*, vol. 41, p. 197; June, (1936).
- O. W. Torreson, W. E. Scott, H. E. Stanton, "A conspicuous solar eruption on April 8, 1936, and simultaneous disturbances on magnetic, ionospheric, and earth-current records at Huancayo magnetic observatory," *Ter. Mag. and Atmos. Elec.*, vol. 41, p. 199; June, (1936).
- G. Leithäuser, "On abnormal upper atmospheric ionization on February 14, 1936," *Funktech. Monats.*, vol. 2, p. 241; July, (1936).
- D. Arakawa, "Abnormal attenuation in short radio wave propagation," *Report of Radio Research in Japan*, vol. 6, p. 31, (1936).
- Ohno, Nakagami, and Miya, "On the fall of short-wave intensity of short duration," (In Japanese), *J.I.E.E.* (Japan), p. 938; August, (1936).
- A. M. Braaten, "Fade-out observations at Riverhead, N. Y.," *T. and R. Bull.*, vol. 12, p. 111; September, (1936).
- M. Waldmeier, "The great solar eruption of August 28, 1936," *Naturwiss.*, vol. 24, p. 638; October 2, (1936).
- R. S. Richardson, "The bright eruption and radio fade-out of August 25, 1936," *Pub. Astr. Soc. Pacific*, vol. 48, p. 278; October, (1936).
- "The ionosphere; the Dellinger wipe-out," *T. and R. Bull.*, vol. 12, p. 214; November, (1936).
- R. Bureau and J. Maire, "Ionospheric anomalies of sudden onset," *Compt. Rend.*, vol. 203, p. 1275; December 7, (1936).
- H. W. Newton, "Radio fadings and bright solar eruptions," *Nature*, vol. 138, p. 1017; December 12, (1936).
- J. H. Dellinger, "Direct effects of particular solar eruptions on terrestrial phenomena," *Phys. Rev.*, vol. 50, p. 1189; December 15, (1936).
- R. Jouaust, R. Bureau, and L. Eble, "The probable causes of sudden fade-outs of short radio waves and their relation to magnetic phenomena," *Compt. Rend.* vol. 203, p. 1534; December 28, (1936).
- J. A. Fleming, "Notes on radio fade-outs of August 25, 1936," *Ter. Mag. and Atmos. Elec.*, vol. 41, p. 404; December, (1936).
- O. W. Torreson, W. E. Scott, F. T. Davies, and H. E. Stanton, "A solar eruption on November 6, 1936, and disturbances in earth's magnetism, earth-currents, and the ionospheric regions," *Ter. Mag. and Atmos. Elec.*, vol. 41, p. 409; December, (1936).
- D. Arakawa, "Abnormal attenuation in short radio wave propagation," (Second Report), *Report of Radio Research in Japan*, vol. 6, p. 169 (1936).
- "Solar eruptions and radio fade-outs," *Nature*, vol. 139, p. 61; January 9, (1937).
- R. Bureau, "Abnormalities of the ionosphere and bright solar eruptions," *Nature*, vol. 139, p. 110; January 16, (1937).

J. H. Dellinger, "Radio fade-outs through 1936," *QST*, vol. 21, p. 35 of February, (1937).

A. G. McNish, "Magnetic effects associated with bright solar eruptions and radio fade-outs," *Nature*, vol. 139, p. 244; February 6, (1937).

J. H. Dellinger, "Sudden ionospheric disturbances," *Ter. Mag. and Atmos. Elec.*, vol. 42, p. 49; March, (1937).

F. T. Davies, O. W. Torreson, W. E. Scott, and H. E. Stanton "A solar eruption of November 27, 1936, and simultaneous disturbances in earth's magnetism, earth-currents, and the ionospheric regions," *Ter. Mag. and Atmos. Elec.*, vol. 42, p. 93; March, (1937).

H. A. G. Hess, "Observations on the Dellinger-effect on Nov. 6, 1936," *Funktech. Monats.*, vol. 3, p. 74; March, (1937).



FIELD STRENGTH OBSERVATIONS OF TRANSATLANTIC SIGNALS, 40 TO 45 MEGACYCLES*

BY

H. O. PETERSON AND D. R. GODDARD
(R.C.A. Communications, Inc., Riverhead, L.I., N. Y.)

Summary—The results of daily observations at Riverhead, L.I., N. Y., since the middle of January, 1937, are reported. Some of the schedules of London and Berlin television transmissions are reported as being heard and measurements of field strengths are summarized. The vertical angle of arrival was measured, and by means of a reversible directive antenna it was determined that the signal at times arrives from a direction other than that of the great-circle path through London and Riverhead.

THIS paper will report briefly on the results of a series of observations started at Riverhead, L. I., N. Y., January 11, 1937, on the frequencies of the television transmitters at Alexandra Palace, London, and which later also included the frequencies of the television transmitters at Berlin.

London was understood to have a sound channel on 41.5 megacycles with a power rating of 3 kilowatts and a vision channel on 45 megacycles with a rating of 5 kilowatts. The Berlin transmissions consisted of a sound channel on 42.5 megacycles and a vision channel on 44.3 megacycles. The transmitting antennas were vertically polarized. The distances involved were 3400 miles for London and 3900 miles for Berlin.

Most of the observations took place between 1000 and 1100 E.S.T. Observations were, however, also made at other hours between 600 and 1700 E.S.T. The observations were at first made at the Frequency Measuring Laboratory of the Riverhead Station. They were later extended to another site where special antennas could be erected.

To facilitate the design of an antenna some measurements of the vertical angle of arrival were made. For these measurements, three horizontal dipoles were erected at 16.7 feet, 27.3 feet and 50 feet above ground. Fig. 1 shows how these antennas were arranged. By comparing the strengths of the signals picked up on each of these dipoles the vertical arrival angle was determined, according to the method described by Friis, Feldman, and Sharpless.¹ In order not to introduce errors due

* Decimal classification: R270. Original manuscript received by the Institute, May 19, 1937. Presented before joint U.R.S.I.-I.R.E. meeting, Washington, D. C., April 30, 1937.

¹ H. T. Friis, C. B. Feldman, and W. M. Sharpless, "The determination of the direction of arrival of short radio waves," Proc. I.R.E., vol. 22, pp. 47-78; January, (1934).

to transmission line losses and standing wave patterns the transmission lines from the dipoles were made of equal lengths. A receiver was mounted in the survey car shown, which could be parked near the antennas. The three transmission lines passed to the receiver through a plug and jack arrangement providing rapid change from one antenna to another.

A number of measurements made showed that the vertical arrival



Fig. 1—Three horizontal dipoles and survey car containing receiver used for vertical arrival angle measurements.

angle of the signals heard was close to 7.5 degrees. A horizontal rhombic antenna was then constructed so as to have its maximum lobe towards England at this angle. Its effective height was about eight meters.

As the observations made at the Frequency Measuring Laboratory indicated that possibly the signal was arriving along paths other than the shorter arc of the great circle from England to Riverhead it was decided to arrange the rhombic antenna in such a fashion that its direction of reception could be reversed. This was done by installing at each end of the antenna remotely controlled double-pole double-throw switches. From the blades of these switches transmission lines of equal




Fig. 2—41.5-megacycle horizontal rhombic antenna fitted with remotely controlled switches to reverse directivity.




Fig. 3—Ultra-high-frequency receiver and signal generator used for field strength measurements.

length were run to another remotely controlled double-pole double-throw switch and from the blades of this latter switch a transmission line was run to a receiver. Fig. 2 shows a diagram of the antenna and the way in which these switches were connected. The control circuits of the switches were connected so that by operating a toggle switch at the receiver it was possible to connect the receiver to either end of the antenna and simultaneously connect a damping network to the other end. This made it possible to "listen" in either a northeasterly or southwesterly direction. It was found that the damping network re-




Fig. 4—London television. Plot of single day's observation of the two transmitters at Alexandra Palace showing maximum and minimum values for each.

duced the back-end signal sensitivity about 28 decibels. Fig. 3 shows the receiver and measuring equipment used.

The measurements were made by dividing the observations into five-minute periods and alternately measuring the 41.5- and 45-megacycle emissions. During each period maximum and minimum signal strengths were recorded.

Fig. 4 shows the results of one day's measurements. The solid lines indicate the maximum and minimum values obtained on the London 45-megacycle channel. The broken lines indicate the maximum and minimum values obtained from the 41.5-megacycle channel. It shows the maximum signal received at the terminals of the receiver to have reached a peak value of about 700 microvolts on the 45-megacycle channel. It is also evident that there is a fairly constant ratio of fading of about 25 to 30 decibels on this channel. This phenomenon was ob-

served on several occasions but was not evident on the 41.5-megacycle signal.

Fig. 5 gives a summary of all daily observations made on 41.5 and 45 megacycles between 1000 and 1100, E.S.T. The solid lines represent the daily ranges of the 41.5-megacycle field strength and the dotted lines represent the same for the 45-megacycle channel. Dates on which no observations were made are indicated by "X". It will be noted that the signals were first heard January 21. Conditions for this form of propagation seemed to be at their best during February, falling off




Fig. 5—Daily maximum and minimum field strengths. "X's" indicate no observation made. "O's" indicate signal unheard.

badly in March. Whilst the data have not been plotted for the Berlin signals, these were also heard on a number of occasions in February.

Since a possible explanation for long-distance propagation at these frequencies is that perhaps they are reflected by the F_2 layer, an examination of the F_2 critical frequencies for vertical incidence is of interest. Fig. 6 shows a plot of monthly averages of the F_2 critical frequency for noon, Eastern Standard Time, as measured at Washington, D. C., by the National Bureau of Standards² over a period of years. It will be noted that the tendency has been toward higher values of F_2 critical frequency. It seems this tendency is in phase with the increase of

² T. R. Gilliland, S. S. Kirby, N. Smith, and S. E. Reymer, "Averages of critical frequencies and virtual heights of the ionosphere, observed by the National Bureau of Standards, Washington, D. C., 1934-1936," *Terr. Mag. and Atmos. Elec.*, vol. 41, pp. 379-392; December, (1936).

sunspot numbers on the present eleven-year cycle of solar disturbances, which is due to reach a maximum about 1939.

Fig. 7 shows F_2 critical frequencies as measured at Washington, D. C. by the Bureau of Standards,³ each Wednesday between the hours of 1000 and 1600 E.S.T. plotted along the data relative to conditions observed on the 41.5-megacycles and 45-megacycle channels on the same days. It is noted that the correlation is not perfect. Perhaps better correlation could be had if data were used for critical frequency measurements made more nearly on the path of propagation. Such data however, were not available at the time.




Fig. 6—Monthly averages of F_2 critical frequency, noon, E.S.T., at Washington, D. C.

The type of fading observed on the 41.5- and 45-megacycle channels differed greatly. Usually the 41.5-megacycle channel faded rapidly and deeply while the 45-megacycle channel was quite steady for several minutes at a time and would then slowly fade to a new signal level or pass through a shallow dip. The maximum field strength observed on the 45-megacycle channel was about thirty-seven decibels above one microvolt per meter.

Normally the schedule of operation of the English transmitters was from 9:45 A.M. to 11:00 A.M. and again from 4:00 to 5:00 P.M., Eastern Standard Time. The 4:00 to 5:00 P.M. schedule so far has not definitely been heard at Riverhead.

For the week of February 8 the 41.5-megacycle transmitter was kept in operation until noon, Eastern Standard Time, but no definite improvement in field strength was observed during the additional hour. On March 31 the 41.5-megacycle transmitter was operated continu-

³ The critical frequency data for January, February, and March of 1937 were kindly furnished by Dr. J. H. Dellinger of the Bureau of Standards.

ously from 6:30 A.M. until 1:00 P.M., Eastern Standard Time, but during this run the signal was unheard at Riverhead.

Observations were made simultaneously at LeRoy, Indiana, from March 3 to March 31 inclusive. The 41.5-megacycle channel was heard on four occasions at LeRoy. On these four occasions, the signal was also heard at Riverhead, the field strength being somewhat higher at River-




Fig. 7—Average F₂ critical frequency 10:00 A.M. to 4:00 P.M., E.S.T., each Wednesday at Washington, D. C., plotted with field strength ranges on same days. "X's" indicate no observation made. "0's" indicate signal unheard.

head. Apparently conditions favorable to transmission affect large areas at the same time.

The measurements made at the Frequency Measuring Laboratory consisted in observing both the 41.5- and 45-megacycle signals on various antennas. There were available several short-wave fishbone antennas directed toward Europe, South America, the west coast, etc. All of these were tried and it was frequently noted that when the signal was weak, best reception could be obtained by using an antenna directed toward the west coast. On several occasions the signal was inaudible on antennas directed toward Europe but of reasonable strength on the west coast antenna. However, during periods of strong signal the European antennas gave the best results. In general the reversible rhombic antenna gave similar results except that at no time did this

antenna show an improved signal from the southwesterly direction. Usually during periods of weak signal the normal direction gave from six to twelve decibels better signal than the reverse direction. However, on two occasions for a period of several minutes each, the signals from both directions were of equal strength.

A possible explanation for the failure of the reversible rhombic antenna to show a good signal from the reverse direction is that the signal may have been coming to Riverhead over some path other than the great-circle one. If this had been the case the rhombic antenna, being rather sharply directive, would show a good back-end response from the southwest only, whereas the Frequency Measuring Laboratory reported best reception either from the northeast or west.

Towards the end of the observations the front-to-back ratio arrangement was dismantled and the remotely controlled antenna switches were arranged to transfer the receiver to either the rhombic antenna directed toward England or a sloping wire antenna designed to receive vertically polarized waves arriving at a vertical angle of $7\frac{1}{2}$ degrees also directed toward England. The few times that it was possible to compare this new antenna with the rhombic indicated no instances of better results with the vertically polarized receiving antenna. The fact of the polarization of the received signal being independent of the polarization of the transmitting antenna supports the conclusion that propagation was by refraction phenomena in the ionosphere much the same as in the case of frequencies on the order of ten to twenty megacycles.

Some additional vertical arrival angle measurements were made in the 29-megacycle amateur band. Table I shows a table of the amateurs

TABLE I
LAYER HEIGHT DETERMINATIONS AT RIVERHEAD, L. I., N. Y.
29-MEGACYCLE AMATEURS

Call	Location	Distance km	Arrival Angle Degrees	Layer Height km
W5FHJ	Ruleville, Miss.	1800	17.2	360
	Dallas, Tex.	2340	8.9	282
W9YUD	Fremont, Neb.	2040	14.1	378
W9DHO	Wisner, Neb.	2090	13.7	358
W5CZZ	Terrill, Tex.	2280	11.7	357
W5EYV	Refugio, Tex.	2600	9.0	357
W9JWI	Independence, Mo.	1960	17.2	402
W6LUL	Los Angeles, Calif.	4050	11.6	302
W9GND	Grand Falls, N.D.	2070	12.6	351
W9DHQ	Wishek, N.D.	2200	9.5	290
W5FNH	Kerrville, Tex.	2720	8.1	353
W5CZZ	Terrill, Tex.	2280	10.6	352
	Kansas City, Mo.	1950	16.2	378
W7CKZ	Aberdeen, Wash.	4050	12.4	318
W9LKD	Wichita, Kan.	2180	10.9	352

Mean Layer Height—346 km.

Layer height and vertical arrival angle determinations made with setup shown in Fig. 3.

observed on March 4, 1937. The vertical arrival angle together with the distance between Riverhead and the transmitter location allows a figure for the reflecting layer height to be computed if an assumption is made as to the number of reflections. In the calculations made to determine the column on the right a single reflection was assumed in all but two cases, in which two reflections were assumed. The average apparent layer height derived by this method on these assumptions was 346 kilometers. The average minimum F_2 layer height as measured by the Bureau of Standards at Washington, D.C., on March 3 during approximately the same time of day was 240 kilometers. This large difference may be due to lack of knowledge of the region of the F_2 layer causing these frequencies to reflect. Repeated determinations on the London signal gave about 340 kilometers as the F_2 layer height.

ACKNOWLEDGMENT

In concluding, the authors wish to express their appreciation for the special schedules of transmission arranged by the British Broadcasting Company and for the ionosphere data supplied by the National Bureau of Standards.³



A TRANSFORMATION FOR CALCULATING THE CONSTANTS OF VACUUM TUBES WITH CYLINDRICAL ELEMENTS*

BY

W. VAN B. ROBERTS

(Radio Corporation of America, New York City)

Summary—By the method of conjugate functions formulas are derived for the amplification constant of a relatively long tube structure comprising a small cylinder concentric with the axis of the structure, a number of wires parallel to the axis and located on a circle concentric with and outside the first cylinder, and a second cylinder also concentric with the axis and surrounding the wires. Several cases are considered, according to which of these elements are taken as cathode, anode, and control electrode. The calculation of tube capacitances by means of the same transformation is illustrated and the basis for setting up transformations for other cylindrical structures is indicated.

THERE are shown in Fig. 1 n points equally spaced on a circle of radius a drawn about the origin of the complex plane. The positions of these points are $ae^{j(2\pi/n)}$, $ae^{j(4\pi/n)}$, . . . , $ae^{j(n2\pi/n)}$. Let us consider the function

$$f(z) = -q \log z + \log(z - ae^{j(2\pi/n)}) + \log(z - ae^{j(4\pi/n)}) + \dots + \log(z - ae^{j(n2\pi/n)}). \quad (1)$$

Since z is a complex quantity, $f(z)$ consists of a real part and an imaginary part so we may set $f(z) = U + jV$. Replacing z by $\rho e^{j\theta}$, (1) becomes

$$e^{U+jV} = \rho^{-q} e^{-jq\theta} \rho^n e^{jn\theta} \prod_{t=1}^{t=n} \left(1 - \frac{a}{\rho} e^{j(2\pi t/n) - j\theta} \right). \quad (2)$$

As shown in the Appendix (2) may be reduced to

$$e^{U+jV} = \rho^{n-q} \left[e^{j(n-q)\theta} - \left(\frac{a}{\rho} \right)^n e^{-jq\theta} \right], \quad (3)$$

whence,

$$e^U \cos V = \rho^{n-q} \left[\cos(n-q)\theta - \left(\frac{a}{\rho} \right)^n \cos q\theta \right] \quad (4)$$

$$e^U \sin V = \rho^{n-q} \left[\sin(n-q)\theta + \left(\frac{a}{\rho} \right)^n \sin q\theta \right]. \quad (5)$$

Squaring (4) and (5) and adding we obtain

$$e^{2U} = \rho^{2(n-q)} \left[1 - 2 \left(\frac{a}{\rho} \right)^n \cos n\theta + \left(\frac{a}{\rho} \right)^{2n} \right]. \quad (6)$$

* Decimal classification: R131. Original manuscript received by the Institute, October 2, 1936; revised manuscript received by the Institute, June 16, 1937.

Dividing (5) by (4) we have

$$\tan V = \frac{\sin (n - q)\theta + \left(\frac{a}{\rho}\right)^n \sin q\theta}{\cos (n - q)\theta - \left(\frac{a}{\rho}\right)^n \cos q\theta} \quad (7)$$

It is a fundamental property of the method of conjugate functions¹ that if U is held constant in (6) the equation defines an equipotential surface in two dimensions (that is, the cross section of a long equipotential surface extending perpendicular to the plane of the complex plane) whose potential may be taken numerically equal to U . By choosing successively different values of U we obtain the equations of the entire family of equipotentials corresponding to the transformation (1). Fig. 2 shows, qualitatively only, the result of plotting (6) for three different values of U .




Fig. 1.

In similar fashion (7) gives the field of electric force. That is, for every value of V , (7) defines a line of force.

It may be seen from the symmetry of Figs. 1 and 2 about the directions $\theta=0$ and $\theta=\pi/n$ that the electric force along these lines is the negative rate of change of U with respect to ρ . Setting $\theta=0$ in (6) we find

$$\frac{dU}{d\rho} = \mp \frac{(n - q)\rho^n + qa^n}{\rho^{q+1}e^v} \quad (8)$$

where the minus sign is used when $\rho < a$ and the plus sign when $\rho > a$ and along the line $\theta = \pi/n$

$$\frac{dU}{d\rho} = \frac{(n - q)\rho^n - qa^n}{\rho^{q+1}e^v} \quad (9)$$

From these equations it is evident that if we wish the electric force to vanish at a desired distance, say ρ_1 along the line $\theta=0$ we must

¹ J. H. Jeans, "Mathematical Theory of Electricity and Magnetism," p. 261.

choose the heretofore undetermined quantity q of the equations to satisfy

$$q = \frac{n\rho_1^n}{\rho_1^n - a^n} \quad (10)$$

Similarly for the force to vanish at the point ρ_1 along the line $\theta = \pi/n$ we must have

$$q = \frac{n\rho_1^n}{\rho_1^n + a^n} \quad (11)$$

Equations (6), (10), and (11) are all that is needed to proceed with the calculation of the amplification constant of the vacuum tube structure whose electrode shapes conform sufficiently closely to equipotentials defined by (6). Let us define the amplification constant, μ , of a vacuum tube as the ratio of plate voltage to grid voltage when emission is just cut off from all parts of the cathode. When the voltages are in this ratio the electric field at the surface of the cathode is zero at the point on the cathode from which emission first starts as the plate voltage is raised. This seems a more useful definition than the ratio of voltages that just begins to cut off emission from any part of the cathode.




Fig. 2.

Case I—Inner electrode acting as cathode, outer electrode as plate.

It is obvious that emission will start first at the point where the cathode is cut by the line $\theta = \pi/n$ or by the line $\theta = 3\pi/n$, etc. To reduce the field to zero at these points we must have, by (11),

$$q = \frac{nc^n}{c^n + a^n} \quad (12)$$

where c is the distance from the origin to the cathode along the line $\theta = \pi/n$. Putting this value of q into (6) we have

$$e^v = \left| \rho^{na^n/(c^n+a^n)} \left[1 \mp \left(\frac{a}{\rho} \right)^n \right] \right| \quad (13)$$

where the minus sign is used for points along $\theta=0$ and the plus sign is used for points along $\theta=\pi/n$.

Using the plus sign and putting $\rho=c$ in (13) we have

$$\text{cathode potential} = \log \left| c^{na^n/(c^n+a^n)} \left[1 + \left(\frac{a}{c} \right)^n \right] \right|. \quad (14)$$

Using the minus sign and taking the distance to the nearest part of the grid wire as $(a-r)$ we have

$$\text{grid potential} = \log \left| (a-r)^{na^n/(c^n+a^n)} \left[\left(\frac{a}{a-r} \right)^n - 1 \right] \right|. \quad (15)$$

Using the plus sign and letting s be the distance to the anode along $\theta=\pi/n$ we have

$$\text{anode potential} = \log \left| s^{na^n/(c^n+a^n)} \left[1 + \left(\frac{a}{s} \right)^n \right] \right|. \quad (16)$$

From (14), (15), and (16) the ratio of potential difference between cathode and anode to the potential difference between grid and cathode which, in accordance with the definition adopted is the amplification constant, is

$$\mu = \frac{\frac{na^n}{c^n+a^n} \log \frac{c}{s} + \log \left[1 + \left(\frac{a}{c} \right)^n \right] - \log \left[1 + \left(\frac{a}{s} \right)^n \right]}{\frac{na^n}{c^n+a^n} \log \frac{a-r}{c} + \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right] - \log \left[1 + \left(\frac{a}{c} \right)^n \right]}. \quad (17)$$

In ordinary structures where r/a , $(c/a)^n$, and $(a/s)^n$ are each small compared to unity, the above expression becomes approximately

$$\mu = n \frac{\log \frac{s}{a}}{\frac{nr}{a} - \log \frac{nr}{a}}. \quad (18)$$

By repeating the process of calculating the amplification but starting by making the electric force vanish at the point where the cathode is cut by the line $\theta=0$, which is equivalent to adopting the alternative definition of μ mentioned above, it will be found that the resulting expression differs from (17) only by a change of the sign of the quantity c^n in the first term of both numerator and denominator. Since this quantity was neglected in obtaining the approximate formula (18) however,

it is seen that the approximate formula is the same regardless of which definition was chosen for μ .

Case II—Outer surface used as cathode and inner surface as anode.

The electric field is made zero where the cathode is cut by the line $\theta = \pi/n$ by giving q the value determined by (11) with ρ_1 taken as s . Using this value of q in (6) we have

$$e^{\sigma} = \left| \rho^{na^n/(s^n+a^n)} \left[1 \mp \left(\frac{a}{\rho} \right)^n \right] \right| \quad (19)$$

the signs being as described in Case I. Using (19) to obtain the potentials of the three electrodes we arrive at the formula

$$\mu = \frac{\frac{na^n}{s^n+a^n} \log \frac{s}{c} + \log \left[1 + \left(\frac{a}{s} \right)^n \right] - \log \left[1 + \left(\frac{a}{c} \right)^n \right]}{\frac{na^n}{s^n+a^n} \log \frac{a-r}{s} + \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right] - \log \left[1 + \left(\frac{a}{s} \right)^n \right]} \quad (20)$$

which becomes approximately

$$\mu = \frac{n \log \frac{c}{a}}{\log \frac{nr}{a}} \quad (21)$$

if r/a and $(c/a)^n$ are small compared to unity and $(s/a)^n$ is large compared to n .

Case III—Inner surface the anode, outer surface the grid.

In this case we make the field vanish at the point on the cathode nearest to the anode. By (10) this requires

$$q = \frac{n(a-r)^n}{(a-r)^n - a^n} \quad (22)$$

or, if we assume $r/a \ll 1$ to simplify matters,

$$n - q = a/r. \quad (23)$$

Combining (23) with (6) we have

$$e^{\sigma} = \left| \rho^{a/r} \left[1 \mp \left(\frac{a}{\rho} \right)^n \right] \right| \quad (24)$$

with the same convention as to signs as before. Proceeding as before,

$$\mu = \frac{\frac{a}{r} \log \frac{a-r}{c} + \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right] - \log \left[1 + \left(\frac{a}{c} \right)^n \right]}{\frac{a}{r} \log \frac{s}{a-r} + \log \left[1 + \left(\frac{a}{s} \right)^n \right] - \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right]} \quad (25)$$

or, if r/a , $(a/s)^n$, and $(c/a)^n$ are all small compared to unity, we have approximately

$$\mu = \frac{\left(\frac{a}{r} - n \right) \log \frac{a}{c} + \left(\log \frac{nr}{a} - 1 \right)}{\frac{a}{r} \log \frac{s}{a} - \left(\log \frac{nr}{a} - 1 \right)} \quad (26)$$

Case IV—Inner surface the grid, outer surface the anode.

Call the distance to the point on the cathode nearest to the anode $a+R$ and making the field vanish at this point we have $n-q = -a/R$ approximately, so that

$$e^v = \left| \rho^{-a/R} \left[1 \mp \left(\frac{a}{\rho} \right)^n \right] \right| \quad (27)$$

whence in the same manner as in previous cases we obtain

$$\mu = \frac{-\frac{a}{R} \log \frac{a+R}{s} + \log \left[1 - \left(\frac{a}{a+R} \right)^n \right] - \log \left[1 + \left(\frac{a}{s} \right)^n \right]}{-\frac{a}{R} \log \frac{c}{a+R} + \log \left[1 + \left(\frac{a}{c} \right)^n \right] - \log \left[1 - \left(\frac{a}{a+R} \right)^n \right]} \quad (28)$$

or, if R/a , $(c/a)^n$, and $(a/s)^n$ are all small compared with unity,

$$\mu = \frac{\frac{a}{R} \log \frac{s}{a} + \left(\log \frac{nR}{a} - 1 \right)}{\left(\frac{a}{R} + n \right) \log \frac{a}{c} - \left(\log \frac{nR}{a} - 1 \right)} \quad (29)$$

It must be emphasized that these formulas for μ are not so much to be considered as approximate formulas for tube structures having circular electrodes as they are exact formulas (except for the approximate value taken for q in Cases III and IV) for structures having shapes defined by (6). These shapes are sufficiently similar to ordinary tube structures in many cases however to make the formulas applicable. For example, in Case I, by using (13) it can be shown that the anode is almost exactly circular if $(1/n)(a/s)^n$ is negligible in compari-

son with unity. However when we calculate the distance to the cathode along the line $\theta=0$ we find it less than c in the ratio $n/(n+1)$. Thus the cathode surface is slightly "corrugated" no matter how small it is.

This corrugated shape is shown in Fig. 3 which is a plot of three equipotential surfaces calculated from (6) to illustrate Case 1, together with the assumption of particular values as follows: $c=1$, $a=e$ (the base of natural logarithms), and $n=20$. The curves are drawn for the condition of complete cutoff, that is, by using (12). The solid curve is the cathode, the dotted curve is a surface whose potential is very




Fig. 3

nearly the same as that of the cathode, and the dashed line curve is a surface differing in potential from the cathode by ten times as much as the dotted curve differs. The line $\theta=0$ is the direction toward one grid wire, and the line $\theta=\pi/n$ (in this case nine degrees) is the direction halfway between grid wires where emission is just cut off.

Similarly in Case III the cathode wires, no matter how small r is taken, are found to be considerably flattened on the grid side as well as squeezed out along the circle on which the wires are located. This squeezing out should by its shielding effect make the expression of (25) and (26) a trifle less than the amplification constant of a tube having circular wires of radius r . Thus it would be advisable to plot enough of (6) to determine in any particular case in which any doubt exists, whether the surfaces defined by the equation are reasonably similar to the electrodes of the tube being investigated.

While the foregoing formulas have been derived for wires parallel to the axis, it has been generally assumed by various writers and borne out by experiment that formulas for such an arrangement apply almost equally well to the more common structure having a spiral of wire of equal spacing between two cylinders, at least in cases where the wire spacing is small compared to the distance to the other elements.

CALCULATION OF INTERELECTRODE CAPACITANCES

The conjugate function method is commonly used for the calculation of capacitances. In the present case let us calculate the grid-cathode and the plate-cathode capacitances per unit length of a struc-

ture such as Fig. 2 when the inner surface is taken as the cathode and the outer surface as the anode. By definition the grid-cathode capacitance C_{gc} is the charge on the cathode divided by the difference of potential between grid and cathode when the plate potential is made the same as that of the cathode so that all the lines of force leaving the cathode must terminate on the grid. Substituting the known co-ordinates of cathode and plate into (6) and equating the resulting potentials we obtain an equation determining q

$$c^{n-q} \left[1 + \left(\frac{a}{c} \right)^n \right] = s^{n-q} \left[1 + \left(\frac{a}{s} \right)^n \right] \tag{30}$$

whence,

$$q = n - \frac{\log \left[1 + \left(\frac{a}{c} \right)^n \right] - \log \left[1 + \left(\frac{a}{s} \right)^n \right]}{\log \frac{s}{c}} \tag{31}$$

Now it is a basic property of the method of conjugate functions that if U is taken as the potential, the total charge on a conductor occupying an equipotential surface is $1/4\pi$ times the total change in the value of V that occurs in traveling around the conductor. Let us suppose for the moment that the cathode is very small so that a/c is very great. Then (7) becomes approximately $V = -q\theta$ and the total change in V that occurs in going around the cathode is $-q2\pi$ whence the charge on the cathode is numerically equal to $q/2$. Although the cathode was assumed very small to simplify the calculation of charge, the same result would necessarily have been reached with any larger cathode as all the lines of force coming out of a small cathode must also pass through the successive surrounding equipotentials.

Putting the value of q given by (31) into (6) and using the known co-ordinates of the cathode and the nearest point on the grid we may write the cathode and grid potentials. The required capacitance is then $q/2$ divided by the difference of these potentials, or

$$C_{gc} = \frac{1}{2} \left| \frac{n \log \frac{s}{c} - \log \left[1 + \left(\frac{a}{c} \right)^n \right] + \log \left[1 + \left(\frac{a}{s} \right)^n \right]}{\left\{ \log \left[1 + \left(\frac{a}{c} \right)^n \right] - \log \left[1 + \left(\frac{a}{s} \right)^n \right] \right\} \log \frac{a-r}{c} + \left\{ \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right] - \log \left[1 + \left(\frac{a}{c} \right)^n \right] \right\} \log \frac{s}{c}} \right| \tag{32}$$

In similar fashion, by choosing q to make the cathode and grid potentials equal and dividing $q/2$ by the resulting difference of potential between cathode and plate we have the cathode-plate capacitance

$$C_{cp} = \frac{1}{2} \left| \frac{n \log \frac{a-r}{c} - \log \left[1 + \left(\frac{a}{c} \right)^n \right] + \log \left[\left(\frac{a}{a-r} \right)^n - 1 \right]}{\text{(Same denominator as in (32))}} \right|. \quad (33)$$

At this point it is of interest to compare the ratio C_{gc}/C_{cp} with the value of μ calculated in Case I above since this capacitance ratio has been stated by von Laue² to be the amplification constant of a tube. It is easily seen that this ratio differs from (17) only by the absence in the ratio of the quantity c^n appearing in the first term of both numerator and denominator of (17). Since we already noted that the sign of this quantity was reversed if we altered our definition of the amplification constant it appears that the capacitance ratio gives a value of μ intermediate to the values calculated according to the two definitions considered. In some cases the discrepancy may be important, for example if the cathode consists of broad flat ribbons between plane grid and plate electrodes one would expect a very great difference between the grid bias at which emission from the grid side of the ribbon is cut off and the bias at which complete cutoff occurs.

In conclusion, a word of explanation seems desirable to indicate how the transformation (1) was arrived at, especially since the reasoning involved is applicable to other cases than the one here treated. First of all it is well known that the potential due to a line charge involves the amount of charge per unit length and the logarithm of the distance from the line, and that in the immediate vicinity of a finite magnitude of charge the equipotentials are approximately circular cylinders around it. Thus to represent the n wires it was natural to try writing the sum of the logarithms of the differences between the point z and the locations of the wires, and to add $\log(z)$ to take care of the inner surface. The coefficient $-q$ was included to represent an undetermined charge of opposite sign from the charges on the wires. It thus appears that any arrangement of cylinders that are small in comparison with their distances apart will be given by the transformation $f(z) = A \log(z-a) + B \log(z-b) + C \log(z-c)$, etc., where A, B, C , etc., are proportional to the charges at the points represented by the complex quantities a, b, c , etc., which points are the locations of the centers of the desired small cylinders. The values of the charges may be deter-

² *Ann. der Phys.*, vol. 59, (1919).

SIMPLE METHOD FOR OBSERVING CURRENT AMPLITUDE AND PHASE RELATIONS IN ANTENNA ARRAYS*

By

JOHN F. MORRISON

(Bell Telephone Laboratories, Inc., New York City)

Summary—The paper describes a simple apparatus arrangement for observing the relative amplitudes and phases of the currents in the elements of a multi-element radiating system. The process of adjusting the array is greatly facilitated, much less time and skill being required than when each step in the process is checked by field intensity measurements. Using the method described, these measurements need only be used as a final verification of the adjustment. Field experience with a commercial application is described.

The arrangement is also suitable for use by operating personnel in making routine checks to verify the maintenance of the desired amplitude and phase relations or to indicate the direction and magnitude of changes if they have occurred.

INTRODUCTION

TO obtain a desired distribution of the radiated field about an array of antenna elements, the design engineer must specify, in addition to the spacing and arrangement of the elements, definite relations as to the amplitude and phase of the currents in the elements. With these relations established the field intensity pattern may be computed by a vector summation of the fields contributed by each element of the array.¹ The field contributed by each element is directly proportional to the amplitude of the element current and the relative phases of the fields are directly related to the phase of the corresponding element currents.

Heretofore, field intensity measurements offered the only evidence of the phase relations obtained in practice. This has been accomplished by measuring the field intensity at many points about an array and plotting the data thus collected to obtain the field intensity distribution pattern. The phase relations of the element currents have then been estimated from the shape of the measured pattern.

The device described by this paper permits a more direct observation of the relative phases of the currents in the antenna elements. Furthermore, it may be located at a convenient place in the transmitter building thereby greatly facilitating the "tuning-up" operation and providing a rapid means for periodic checks upon the array performance.

* Decimal classification: R242. Original manuscript received by the Institute, July 1, 1937. Presented before Silver Anniversary Convention, New York City, May 10, 1937.

¹ Ronald M. Foster, *Bell Sys. Tech. Jour.*, vol. 5, pp. 292-307; April, (1926).

ELEMENT INTERACTION AND ITS EFFECT UPON THE ADJUSTMENT OF AN ARRAY

The interaction between the elements of an antenna array is briefly discussed here in order to point out certain complexities in the adjustment of an array. The subject of element interaction has been treated




Fig. 1—Vector diagram of current relations in an array of two identical elements spaced one-quarter wave length.

by other authors^{2,3} and reference may be made to those publications for a mathematical treatment of the problem. However, for this purpose the interaction effects can be clearly illustrated by a vector representation of the currents in the elements. For simplicity of illustration a first approximation of the effects which occur in an array of

² P. S. Carter, "Circuit relations in radiating systems and applications to antenna problems," Proc. I.R.E., vol. 20, pp. 1004-1041; June, (1932).

³ E. J. Sterba, "Theoretical and practical aspects of directional transmitting systems," Proc. I.R.E., vol. 19, pp. 1184-1215; July, (1931).

two identical elements spaced one-fourth wave length is shown in Fig. 1. Successive approximations converge rapidly from the first so that the first approximation is sufficiently close for illustration.

It has been assumed that the pattern to be produced by this array calls for a current amplitude relation of 2:1 and the current in element 1 to lead the current in element 2 by 90 degrees. I_1 and I_2 represent, respectively, the current components produced in elements 1 and 2 by an applied generator voltage. If there were no interaction between the elements, I_1 and I_2 would be the actual element currents; i.e., they represent the current which would flow if the transmission lines feeding the elements were terminated in resistances not mutually coupled. However, when these same currents are allowed to flow in the mutually related elements they will each induce a voltage in the adjacent element causing the currents I_{i_1} and I_{i_2} to flow. The amplitudes of I_{i_1} and I_{i_2} are each proportional to the current in the adjacent element and their phase relation depends upon the element spacing as well as the phase of the adjacent element current. I_{E_1} and I_{E_2} are the vector resultant of the currents produced by the generator and induced voltages and represent closely the actual element currents.

When computing the field intensity pattern about an array of two identical elements each excited with currents that differ in amplitude, the large current can be assigned to either element and the computed pattern will have the same shape. Accordingly in the example considered I_{E_1}/I_{E_2} could equal either 2 or 0.5 without changing the pattern. It is, however, clearly shown by the first two sets of vector diagrams that the interaction between the elements is quite different for the two cases. For this reason, the choice as to which element carries the larger current should be dictated solely by the design of the element coupling apparatus.

It will be seen from the third set of vector diagrams that in order to obtain the desired element current relations, $I_{E_1}/I_{E_2}=2$, I_{E_1} leads I_{E_2} 90 degrees, the currents produced by the generator voltage must bear approximately the following relation: $I_1/I_2=0.69$, I_1 leads I_2 66 degrees.

In the adjustment of an array it is desirable to make the necessary corrections in the phases of the applied voltages by adjustments in the apparatus used for coupling between the elements and the transmission lines, thereby minimizing or avoiding the occurrence of standing waves on the transmission lines. These phase correcting adjustments can also be made to a degree in the line branching and phase shifting networks, provided that no excess voltages develop because of standing waves on the transmission lines. At high frequencies a standing wave condition

may also increase the losses in the transmission lines to an objectionable amount.

The fourth set of vector diagrams represents the case where the two elements are to be excited in phase and unity current ratio to effect maximum signal broadside to the array. It will be seen that only in this special case do the resultant element currents bear the same relative relation to each other as the currents resulting from the applied generator voltages. This accounts for the comparative simplicity of adjustment afforded by the use of broadside arrays.




FIG. 2—Impedance interaction between quarter-wave-length elements.

By the use of the superposition theorem the interaction effects between the elements of an array can, for convenience, be considered from the viewpoint of impedance relations. Fig. 2 shows the resistance and reactance introduced at the base of a vertical quarter-wave-length element, erected perpendicular to a perfect ground, by an adjacent vertical quarter-wave-length element excited with currents of the same magnitude and phase. The spacing of the elements expressed in wave lengths is the abscissa of this figure. If the currents in the adjacent element are not of the same phase or amplitude, the base impedance of each element may be computed from the formula which is also shown on Fig. 2. R_t in the formula is obtained from the curve for the element spacing under consideration. If more than two elements are to be considered, the effects of each may be computed separately from the formula, giving due regard to the spacing, current amplitude, and phase relations in each case. These effects may then be added to obtain the total effect.

Fig. 3 shows similar information for vertical half-wave-length elements. The values shown apply to the current loop which is not at the base of the antenna in this case. A knowledge of the element characteristic impedance,⁴ which depends largely upon the conductor diameter, is necessary before the interaction effects at the base of a half-wave-length element can be estimated.




Fig. 3—Impedance interaction between half-wave-length elements.

From an inspection of these curves and the accompanying formula, it will be seen that the impedance of the elements may assume almost any value, depending upon the several factors: element spacing, element height, current amplitude, and phase relations. The resistance component of the impedance of one or more of the elements may in some cases become negative, or in other words, the power flow may be toward, rather than from, the generator. An actual observation of this condition will be discussed later in the paper.

Since an array is excited by one generator at a common connection point in the system, it is not possible to measure the impedance at the driving point of each element with any present standard means for impedance measurement. The insertion of an impedance measuring instrument would upset the performance of the whole system and alter the impedance at all points in the system. The impedance being unknown, the current at the driving point of each element cannot be used for power determination, but the relative values of the currents

⁴ J. F. Morrison and P. H. Smith, "The shunt-excited antenna," PROC. I.R.E., vol. 25, pp. 673-696; June, (1937).

as measured at the several points in the system are useful as a check upon the constancy of an array adjustment.

In actual practice, where the conditions of ideal element configuration and perfect ground are not fully realized, the rigorous treatment of the interaction problem illustrated in Figs. 2 and 3 serves only as an approximation of the actual conditions. Therefore, it has been necessary for the engineer to adjust an array by a series of approximations and each time measuring the field intensity pattern to check his results. This approach to the problem is not only laborious but may require considerable time.




Fig. 4—Current amplitude and phase measuring circuit.

A METHOD OF OBSERVING CURRENT AMPLITUDE AND PHASE RELATIONS

Another and more straightforward approach to the problem of antenna array adjustment is to provide a simple means whereby the amplitude and phase relations of the element currents can be quickly and accurately observed at the transmitter location. This may be done by the method illustrated in Fig. 4.

There is placed on each shunt-excited element⁴ at the height A above ground a rigid single turn loop which may be constructed of angle iron. The dimension A is chosen so that the loop is placed just above the connecting point of the inclined conductor of the antenna element. The dimensions of the loops as well as their location on the elements must be the same at each element of a particular array. The top of the loop is directly connected to the tower, while the bottom is insulated from the tower and connected to the center conductor of a concentric type transmission line.

Transmission lines having essentially identical characteristics are run from the loop on each element to a common convenient point, such as in the transmitter building. It is important that each line be terminated by an impedance which is equal to its characteristic impedance, Z_0 . Furthermore, the lines must be made the same length, or in cases where this is not practicable, the shorter ones may be built out to the same equivalent length by artificial lines.

This arrangement of measuring loops and transmission lines makes available at a convenient location samples of the currents in each element. Symmetry of measuring loops and transmission lines is essential if the amplitude and phase relationships between current samples are to be the same as the corresponding relationships between the currents in the radiating elements but in practice it is not difficult to establish this symmetry with the required accuracy.

The amplitudes of the sample currents are read on the milliammeters M_1 and M_2 (Fig. 4) which are connected in series with the line terminating impedances.

The phase relation of the sample currents is determined as follows: The voltage developed across the terminating impedance of one transmission line is applied to the input of a continuously variable calibrated phase shifting network. The voltage at the output of the phase shifting network is amplified by a radio-frequency amplifier which compensates for the losses through the network. The voltage developed across the terminating impedance R_6 of the amplifier is applied to input No. 1 of the vacuum tube voltmeter. The voltage applied at the input of the phase shifter is at the same time applied to input No. 2 of the vacuum tube voltmeter when the switch, D_1 , is in the CALIBRATE position. The continuously variable phase shifter is then adjusted until a null is observed on the vacuum tube voltmeter which indicates that the voltage at the input of the phase shifter is in phase with the voltage at the output of the amplifier. In other words, the phase shift through the combined phase shifter and amplifier is zero.

A mechanical clutch arranged between the shaft of the variable phase shifter and the calibrated dial is then released in order to permit rotation of the dial without disturbing the phase shifter adjustment. The dial is rotated until the zero marking on it coincides with the dial indicator and the clutch is then re-engaged.

By operating switch D_1 , input No. 2 of the vacuum tube voltmeter is disconnected from the phase shifter and connected to the terminating impedance of a transmission line fed by another element of the array. The phase shifter is again adjusted until a null is observed

on the vacuum tube voltmeter and the phase relation of the currents in the two elements is then read directly on the phase shifter dial.

If the array consists of more than two elements, the phase relation of the current in each element can be observed by switching the vacuum tube voltmeter input No. 2 to the several transmission line terminating impedances, each time adjusting the phase shifter for a null indication on the vacuum tube voltmeter.

While this method of observing current amplitude and phase relations is relatively simple and straightforward, it is apparent that care must be exercised in the design and installation of the apparatus in order to obtain reasonably accurate results. In the first place, the measuring loops and transmission lines must be electrically identical. The terminating resistors of these lines should have as nearly as possible zero phase angle and be capable of maintaining their resistance value for an indefinite period, while dissipating approximately one watt of radio-frequency energy. The variable phase shifter must have practically constant loss with phase variation. Furthermore, it must be capable of maintaining its calibration under slight changes in circuit characteristics or permit of easy calibration in the field.

A CONTINUOUSLY VARIABLE PHASE SHIFTER

A continuously variable phase shifter which makes use of variable condensers⁵ in place of the usual rotating magnetic field and pickup coil was found more suitable for the purpose.

A circuit diagram of this phase shifter is also shown on Fig. 4. The resistor R_1 and condenser C_5 are connected in series and are related by the expression:

$$R_1 = \left| \frac{1}{\omega C_5} \right| = |Z_0|.$$

The transformers T_1 and T_2 are alike and their primaries are connected across the resistor R_1 and condenser C_5 , respectively. The center of each transformer secondary is connected to ground.

The purpose of this part of the circuit is to produce at the points a , b , c , and d four potentials of equal amplitude but unlike phase. If well-designed transformers are used the relative phases of the potentials at a , b , c , and d are respectively 0, 180, 90, and 270 degrees.

The four variable condensers have a maximum capacitance small compared to C_5 so that they have a negligible effect upon the potentials at a , b , c , and d . The rotors of these condensers are connected together both mechanically and electrically.

⁵ L. A. Meacham, Patent No. 2,004,613, June 11, 1935.

If we represent the variable condensers by generalized impedances such as $C_1=Z_1$, $C_2=Z_2$, $C_3=Z_3$, $C_4=Z_4$ and the resistance $R_5=Z_5$ the equations for this generalized circuit may be written as follows:

$$i_1 = \frac{e' - e}{Z_1} = Y_1(e' - e)$$

$$i_2 = \frac{-e' - e}{Z_2} = Y_2(-e' - e)$$

$$i_3 = \frac{je' - e}{Z_3} = Y_3(je' - e)$$

$$i_4 = \frac{-je' - e}{Z_4} = Y_4(-je' - e)$$

$$i_1 + i_2 + i_3 + i_4 = i_5 \frac{e}{Z_5} = Y_5 e.$$

Therefore,

$$Y_1(e' - e) + Y_2(-e' - e) + Y_3(je' - e) + Y_4(-je' - e) = Y_5 e.$$

This expression solved for e , gives

$$e = \frac{e'(Y_1 - Y_2) + je'(Y_3 - Y_4)}{\Sigma Y_n} \quad (1)$$

It is desired that the phase of e be advanced with respect to e' uniformly as the condenser shaft is rotated, the amplitude of e remaining constant.

This may be accomplished by letting

$$Y_1 = A + B \sin \theta$$

$$Y_2 = A - B \sin \theta$$

$$Y_3 = A + B \cos \theta$$

$$Y_4 = A - B \cos \theta$$

and $Y_5 = K$, a constant.

These values substituted in (1) give

$$e = e'(\sin \theta + j \cos \theta) \frac{(2B)}{(4A + K)} \quad (2)$$

Since the absolute value of $(\sin \theta + j \cos \theta)$ is unity, the amplitude of e is constant, and is given by

$$|e| = e' \frac{(2B)}{(4A + K)}$$

The phase relation between e and e' is expressed by the term $(\sin \theta + j \cos \theta)$.

Since $Y = 1/Z = 2\pi fc$ the requirements on the variation of the admittances are met with variable condensers having characteristics as follows:

$$\begin{aligned} C_1 &= a + b \sin (\theta + 0^\circ), \\ C_2 &= a + b \sin (\theta + 180^\circ), \\ C_3 &= a + b \sin (\theta + 90^\circ), \\ C_4 &= a + b \sin (\theta + 270^\circ), \end{aligned}$$

when θ represents the angular position of the rotor shaft.

It follows that these four condensers are similar and their rotors may be mounted on a common shaft.

The nature or magnitude of the impedance Z_5 does not affect the constancy of the output or the linearity of the phase shift with respect to the angular position of the rotor, if this output impedance is constant. This follows from (2) in which $1/Z_5 = K$. If this output impedance should for any reason change in nature or magnitude because of changes in vacuum tubes or circuit characteristics, the effects upon phase shift are automatically corrected by the zero calibration adjustment of the phase indicator as explained in a foregoing paragraph.

The operation of the phase shifter is illustrated pictorially in Fig. 5. The four quadrature potentials are shown vectorially and designated e' , $-e'$, je' , $-je'$. The stator plates of the condensers are shown in the same relative position as the vector potentials applied to them. These stator plates are repeatedly drawn to show the respective location of the two rotors, which are connected by a common shaft, for five settings of the calibrated dial. The curves of Fig. 5 show the variation of capacitance with change in angular position of the rotor for the four condensers I, II, III, and IV. It will be noted that the resultant vector, shown at the bottom of the figure rotates in the same direction as the rotor plates of the condensers. It will also be noted that a clockwise rotation of the rotor plates rotates the resultant vector in the same direction, or vice versa for a counterclockwise rotation of the plates.

This feature is particularly valuable for the following reasons: If we have say two vector potentials V_1 and V_2 and assume that V_1 leads V_2 by 30 degrees; then if V_2 is applied to the input of the phase shifter and V_1 to the voltmeter input No. 2, a null will be observed on the voltmeter when the calibrated dial is rotated 30 degrees in a counterclockwise direction. If, on the other hand, we apply V_1 to the input of the phase shifter and V_2 to the voltmeter input No. 2 a null will be observed on the voltmeter when the dial is rotated 30 degrees in a clock-

wise direction. Therefore, we not only have an indication of relative phase but also the quadrature relations of the vector potentials. This provides for the determination of the lead or lag relations of the element currents.

The experimental model of the complete apparatus was tested by laboratory instruments on a frequency of 780 kilocycles and the results




Fig. 5—Pictorial illustration of phase-shifter operation.

are shown on Fig. 6. The ordinates of this figure represent the phase relations of two known voltages and the abscissas are the dial readings of the phase indicator when these voltages of known phase relation were applied to the indicator. Later developments have shown that the slight departure from linearity can be reduced in future design.

The photograph, Fig. 7, is a front view of an experimental model of the current amplitude and phase indicating equipment. The two meters which may be seen on the left side of the equipment indicate the current amplitude relations. The switch located between these meters, is designated as D_1 in Fig. 4. The switching of the phase indicator

between the calibrate and test positions is accomplished by operation of this switch. The meter located on the right side of the equipment is connected in the vacuum tube voltmeter circuit and the null indications are observed on this meter. When pressed, the push button located immediately underneath this meter, greatly increases the sensitivity of the meter. This feature prevents damage to the meter which might be caused by excessive voltages during the initial adjustments of the phase shifter. The calibrated phase indicator dial is viewed through the window at the top center of the panel and it is rotated by the lower left




Fig. 6—Calibration curve of phase indicator.

knob which is a vernier control. The mechanical clutch referred to in a foregoing paragraph is located in the center of the panel. The remaining controls located along the bottom of the panel are amplifier gain control, meter balancing potentiometer, and alternating-current power switch.

The photograph, Fig. 8, is a rear view of the equipment. The apparatus on the left is power apparatus which supplies all necessary voltages for the operation of the amplifier and voltmeter. The special variable condenser may be seen at the center of the unit as well as the

radio-frequency transformers and amplifier tube shields. Two concentric transmission line jacks are located at the extreme right. These jacks are especially designed for use with concentric transmission lines. Ceramic insulation and German silver contacts are used in their construction.




Fig. 7—Front view of current amplitude and phase indicating apparatus.




Fig. 8—Rear view of current amplitude and phase indicating apparatus.

A PRACTICAL APPLICATION OF THE CURRENT AMPLITUDE AND PHASE INDICATING EQUIPMENT

This apparatus was first used in November, 1936, in connection with the adjustment of the two-element directive antenna array of the Yankee Network station WEAN at Providence, R.I.

The antenna array at that station was designed by Paul deMars, consulting engineer for the Yankee Network. It consists of two quarter-wave-length shunt-excited elements spaced one eighth of a wave length apart. The desired pattern called for a 2.12:1 amplitude ratio of the element currents and a phase difference of 150 degrees. From the information shown on Figs. 2 and 3 it was estimated that the impedance of two base-insulated elements under the same conditions of spacing, current amplitude, and phase relations would be as follows:

- Element No. 1 $-22.5 + j56$
- Element No. 2 $23.6 + j14.4$

The negative resistance of element No. 1 indicates that the power flow is from the element toward the generator. From these impedance




Fig. 9—Measured and computed field intensity pattern of the two-element antenna array at station WEAN.

relations it was estimated that the power from a 1000-watt transmitter would be distributed in the following manner: 1270 watts would flow toward element 2 and 270 watts would flow from element 1 toward the transmitter, the difference of the two powers being equal to 1000 watts.

Since the elements in the WEAN array are the shunt-excited type the impedance at the base of the inclined conductor of these elements depends largely upon the tap position and dimensions of the inclined conductor. Therefore, the means for tuning this array consisted in providing for adjusting the position of the connection of the inclined conductors to the radiating elements, for adjusting the reactance at the base of the inclined conductor, and for adjusting the phase shifting

and line branching networks which control the amplitude and phase relations of the currents fed to the individual radiating elements.

The current amplitude and phase indicating equipment proved to be a most valuable tool during the adjustment of the WEAN array. It provided at all times during the tuning adjustments an indication




Fig. 10—The two-element antenna array at station WEAN.

of the element current relations. When the desired current amplitude and phase relations were obtained, as observed by this device, there remained only two things to be done. First, to establish by measurement that there were no excessive voltages present on the transmission lines or at the coupling equipment. This may be done by measuring with a suitable high impedance voltmeter⁶ the standing wave on the

⁶ E. J. Sterba and C. B. Feldman, "Transmission lines for short-wave radio systems," *Proc. I.R.E.*, vol. 20, pp. 1163-1202; July, (1932).

transmission lines. Second, to make field intensity measurements to determine the element efficiency and the pattern produced by the array. The measured pattern is shown by the solid curve on Fig. 9. The dotted curve of this figure is the pattern estimated by deMars in the preliminary computations of the expected performance of the array.




Fig. 11—Angle-iron loop on an element of the WEAN antenna array used in connection with the current sampling circuit.

The efficiency of the individual elements was found to be slightly greater than originally anticipated which accounts for the somewhat greater measured field in the front and back directions from the array. Because of this greater element efficiency it was necessary to change slightly the current ratio from the value first specified in order to reduce the field in the directions of stations CKSO and WTAR to the values allotted by the Federal Communications Commission. The solid curve


shown in this figure is an average of well over 100 field measurements collected by the technical staff of the Yankee Network.

Fig. 10 is a photograph of the WEAN two-element, shunt-excited array.

Fig. 11 is a close-up photograph of the measuring loop used to obtain the sampling current from one of the array elements.

ACKNOWLEDGMENT

The author is indebted to his colleagues Messrs. R. H. Lindsay and W. L. Tierney for their encouragement during the development work and to the members of technical staff of the Yankee Network for their assistance in the collection of the data.



RADIATION FROM RHOMBIC ANTENNAS*

BY
DONALD FOSTER
(Boonton, New Jersey)

Summary—A direct theoretical determination of the transmitting properties of the horizontal rhombic antenna and of the closely related inverted V structure has been made. Expressions are given for the intensity of the radiation, the polarization, the radiation resistance, and the gain.

The intrinsic simplicity of the radiation distribution functions is revealed by graphical representation. Stereographic representation also supplements the analysis and provides clear insight into the effects available through variations of design, and enables the essential features of a specific design to be obtained for all directions with a very small amount of labor.

Methods of diminishing the relative intensity of radiation from subordinate lobes are considered.

I. GENERAL

THE inverted V and the horizontal rhombus as receiving antennas have been discussed by Bruce.¹ The horizontal rhombic receiving antenna was recently treated in more detail by Bruce, Beck, and Lowry.² In order to obtain a formula for the current in the receiver in terms of the direction of arrival of the incoming wave, the authors assumed a polarization that is independent of the orientation of the ray with respect to the antenna.

Their equation is limited to the case of waves polarized with the electric vector normal to the plane of incidence. But the antenna is also sensitive to waves polarized parallel to the plane of incidence and in general such parallel components exist both when receiving and when transmitting. Because of this fact the directional properties in transmitting, and the receiving properties in the general case, cannot be obtained from their formula.

When the antenna is used for transmitting, the polarization of the radiation depends on the direction in which it is emitted. Consequently the directional properties of the antenna as a radiator cannot be inferred from the properties of the same antenna as a receiver of waves of fixed polarization, as may be done in the case of certain other antennas. Direct attack on the radiation problem is therefore necessary. The equations so obtained will yield not only the directional pattern but

* Decimal classification: R120. Original manuscript received by the Institute, June 18, 1937. Presented before joint I.R.E.-U.R.S.I. meeting, Washington, D. C., April 30, 1937.

¹ E. Bruce, Proc. I.R.E., vol. 19, pp. 1406-1433; August, (1931).

² E. Bruce, A. C. Beck, and L. R. Lowry, Proc. I.R.E., vol. 23, pp. 24-46; January, (1935).

also expressions for the radiation resistance, the gain, and the polarization. By means of the reciprocity theorem the generalized receiving properties may be deduced.

In order to calculate the electromotive and magnetomotive intensities of the wave, we start with an expression for the simultaneous complex magnetic vector potential in the form

$$\bar{A} = \frac{e^{-i\beta r}}{4\pi r} \int I(s, t) e^{i\beta r' \cos \psi} d\bar{s} \equiv \frac{e^{-i\beta r}}{4\pi r} \bar{F} \quad (1)$$

where r is the distance from the origin (assumed large compared with the wave length and the dimensions of the antenna), β is 2π divided by the wave length, r' is the distance between the origin and the element of antenna $d\bar{s}$, and ψ is the angle between the radius to this element and the direction of the ray. The complex current, I , is a function of distance s along the antenna. This expression for \bar{A} is derived by transforming the well-known element of retarded vector potential³

$$d\bar{A}_{\text{ret}} = \frac{I\left(s, t - \frac{r}{c}\right) d\bar{s}}{4\pi r} \quad (2)$$

into the simultaneous form referred to a common origin, and then integrating over the extent of the antenna. The expression, (1), for \bar{A} consists of two factors, one of which depends only on the distance and the other only on the orientation of the ray. The latter factor is a characteristic of the antenna which we call the radiation vector \bar{F} .

At a sufficient distance from the antenna, the spherical components of the complex electromotive and magnetomotive intensities of the radiation are given by

$$E_{\theta} = -120\pi i\beta A_{\theta}; \quad E_{\phi} = -120\pi i\beta A_{\phi}; \quad E_r = 0. \quad (3)$$

$$H_{\theta} = i\beta A_{\phi}; \quad H_{\phi} = -i\beta A_{\theta}; \quad H_r = 0. \quad (4)$$

The time average of the rate of flow of energy per unit area normal to the ray is equal to one half the real part of the complex Poynting vector. Thus⁴

$$\bar{Q} = \text{real part of } \frac{1}{2} \bar{E} \times \bar{H}^*. \quad (5)$$

This is a vector in the radial direction whose magnitude is

$$Q = \text{real part of } \frac{1}{2} (E_{\theta} H_{\phi}^* - E_{\phi} H_{\theta}^*) \quad (6)$$

³ The practical system of units is used throughout.

⁴ \bar{H}^* means the conjugate of \bar{H} .

which after substituting the values of the intensities in terms of the vector potential becomes⁵

$$Q = \frac{15\pi}{\lambda^2 \gamma^2} (F_\theta F_\theta^* + F_\phi F_\phi^*) \quad (7)$$

where $(F_\theta F_\theta^* + F_\phi F_\phi^*) \equiv K^2$ is a factor in the intensity that depends on the direction and not on the distance from the source.

II. CALCULATION OF THE RADIATION FUNCTIONS

The cartesian co-ordinates are chosen with the origin at the apex at which the power enters the antenna from the generator. The op-




Fig. 1—The rhombic antenna, or the inverted V antenna and its image.

posite apex, where the terminating impedance is located, lies on the Z axis; and the plane of the antenna coincides with the plane $X=0$. The angle between the principal axis and an arm of the antenna is called A . The length of a side of the rhombus is designed by a . Various sets of co-ordinate angles expressing direction relative to the rectangular frame will be used, the choice depending on whether we are considering a horizontal rhombic antenna or an inverted V antenna.

With the proper terminating impedances, and assuming uniformly distributed inductance and capacitance the current in the right-hand branch is⁶

⁵ This expression for the average Poynting flux in terms of the complex vector potential is due to S. A. Schelkunoff, (private communication).

⁶ This assumed current distribution is of course not strictly true, owing to mutual coupling and radiation. Nevertheless it appears to be justified as a first approximation by the agreement between the calculated positions of null points and those found experimentally by Bruce. The analysis would be greatly lengthened by a refinement in the description of the current distribution.

$$i = I_0 e^{-i2\pi(s-ct)/\lambda} = I e^{-i\beta s}; \quad [I \equiv I_0 e^{i\omega t}] \quad (8)$$

where s is the distance from 0 along the antenna, (Fig. 1). In the left-hand branch the current is the same function of s measured away from 0 along that side, if the positive direction for current is reckoned one way, say counterclockwise, around the rhombus. In sections III and IV it is convenient to express the current in terms of the distance s' measured from $0'$. Thus,

$$i = I e^{-i\beta s} = I e^{-i\beta(2a-s')} = I e^{-i2a\beta} \cdot e^{i\beta s'}. \quad (9)$$

The relations between the components of current in the various branches (when s and t are constant) are

$$I_{y_1} = I_{y_2}; \quad I_{y_3} = I_{y_4}; \quad I_{z_1} = -I_{z_2}; \quad I_{z_3} = -I_{z_4} \quad (10)$$

and the components are given by

$$I_{y_1} = I \sin A \cdot e^{-i\beta s}; \quad I_{y_2} = -I \sin A \cdot e^{-i2a\beta} \cdot e^{i\beta s'} \quad (11)$$

$$I_{z_1} = I \cos A \cdot e^{-i\beta s}; \quad I_{z_3} = I \cos A \cdot e^{-i2a\beta} \cdot e^{i\beta s'}. \quad (12)$$

The radiation vectors of Sections I and II will be calculated with respect to 0 as origin, and Sections III and IV will be calculated with respect to $0'$. Then all will be referred to 0, and the resultant will be found.

The radiation vectors for the four sections are

$$\begin{aligned} \bar{F}_1 &= \int_0^a \bar{I}_1 e^{-i\beta s} \cdot e^{i\beta s \cos \psi_1} ds \\ &= \bar{I}_1 \frac{e^{i(a\beta/2)(\cos \psi_1 - 1)}}{\beta (\cos \psi_1 - 1)} \cdot \sin \frac{a\beta}{2} (\cos \psi_1 - 1) \end{aligned} \quad (13)$$

$$\begin{aligned} \bar{F}_2 &= \int_0^a \bar{I}_2 e^{-i\beta s} \cdot e^{i\beta s \cos \psi_2} ds \\ &= \bar{I}_2 \frac{e^{i(a\beta/2)(\cos \psi_2 - 1)}}{\beta (\cos \psi_2 - 1)} \cdot \sin \frac{a\beta}{2} (\cos \psi_2 - 1) \end{aligned} \quad (14)$$

$$\begin{aligned} \bar{F}_3' &= \int_0^a \bar{I}_3 e^{-i2a\beta} \cdot e^{i\beta s'} \cdot e^{i\beta s' \cos (\pi - \psi_2)} ds' \\ &= \bar{I}_3 \frac{e^{i(a\beta/2)(1 - \cos \psi_2) - i2a\beta}}{\beta (1 - \cos \psi_2)} \sin \frac{a\beta}{2} (1 - \cos \psi_2) \end{aligned} \quad (15)$$

$$\begin{aligned}\bar{F}_4' &= \int_0^a \bar{I}_4 e^{-i2a\beta} \cdot e^{i\beta s'} \cdot e^{i\beta s' \cos(\pi-\psi_1)} ds' \\ &= \bar{I}_4 \frac{e^{i(a\beta/2)(1-\cos\psi_1)-i2a\beta}}{\frac{\beta}{2}(1-\cos\psi_1)} \sin \frac{a\beta}{2} (1-\cos\psi_1).\end{aligned}\quad (16)$$

The primed vectors \bar{F}_3' , \bar{F}_4' are referred to O' as origin. The vector currents \bar{I}_1 , \bar{I}_2 , etc., have the magnitude I and the directions of the s or s' appropriate to the section.

Transformation from O' to O as origin is effected by means of the relations

$$\bar{F}_3 = \bar{F}_3' e^{i\beta(2a \cos A) \cos \theta}; \quad \bar{F}_4 = \bar{F}_4' e^{i\beta(2a \cos A) \cos \theta}, \quad (17)$$

the angle θ being the polar distance of the direction of radiation with respect to the Z axis. The corresponding longitude, ϕ , will be measured in the clockwise direction around the positive Z axis with the positive X axis as the initial line.

Relative to O the components of F are

$$F_{y_1} = I \sin A \cdot \frac{e^{-i(a\beta/2)(1-\cos\psi_1)}}{\frac{\beta}{2}(1-\cos\psi_1)} \sin \frac{a\beta}{2} (1-\cos\psi_1) \quad (18)$$

$$F_{y_2} = I \sin A \cdot \frac{e^{-i(a\beta/2)(1-\cos\psi_2)}}{\frac{\beta}{2}(1-\cos\psi_2)} \sin \frac{a\beta}{2} (1-\cos\psi_2) \quad (19)$$

$$F_{y_3} = -I \sin A \cdot e^{i2a\beta(\cos A \cos \theta - 1)} \frac{e^{i(a\beta/2)(1-\cos\psi_2)}}{\frac{\beta}{2}(1-\cos\psi_2)} \sin \frac{a\beta}{2} (1-\cos\psi_2) \quad (20)$$

$$F_{y_4} = -I \sin A \cdot e^{i2a\beta(\cos A \cos \theta - 1)} \frac{e^{i(a\beta/2)(1-\cos\psi_1)}}{\frac{\beta}{2}(1-\cos\psi_1)} \sin \frac{a\beta}{2} (1-\cos\psi_1) \quad (21)$$

$$F_{z_1} = I \cos A \cdot \frac{e^{-i(a\beta/2)(1-\cos\psi_1)}}{\frac{\beta}{2}(1-\cos\psi_1)} \sin \frac{a\beta}{2} (1-\cos\psi_1) \quad (22)$$

$$F_{z_2} = -I \cos A \cdot \frac{e^{-i(a\beta/2)(1-\cos\psi_2)}}{\frac{\beta}{2}(1-\cos\psi_2)} \sin \frac{a\beta}{2} (1-\cos\psi_2) \quad (23)$$

$$F_{z_3} = I \cos A \cdot \frac{e^{i(a\beta/2)(1-\cos\psi_2)}}{\frac{\beta}{2}(1-\cos\psi_2)} \cdot \sin \frac{a\beta}{2} (1-\cos\psi_2) \quad (24)$$

$$F_{z_4} = -I \cos A \cdot \frac{e^{i(a\beta/2)(1-\cos\psi_1)}}{\frac{\beta}{2}(1-\cos\psi_1)} \cdot \sin \frac{a\beta}{2} (1-\cos\psi_1). \quad (25)$$

Adding the components, 1 to 4,

$$F_y = I \sin A \left[\frac{\sin \frac{a\beta}{2} (1-\cos\psi_1)}{\frac{\beta}{2} (1-\cos\psi_1)} \left(e^{-i(a\beta/2)(1-\cos\psi_1)} - e^{i(a\beta/2)(1-\cos\psi_1)+i2a\beta(\cos A \cos\theta-1)} \right) + \frac{\sin \frac{a\beta}{2} (1-\cos\psi_2)}{\frac{\beta}{2} (1-\cos\psi_2)} \left(e^{-i(a\beta/2)(1-\cos\psi_2)} - e^{i(a\beta/2)(1-\cos\psi_2)+i2a\beta(\cos A \cos\theta-1)} \right) \right]. \quad (26)$$

By means of the relation

$$2 \cos A \cos \theta = \cos \psi_1 + \cos \psi_2 \quad (27)$$

the expression for F_y may be transformed into

$$F_y = 2i e^{i(a\beta/2)(\cos\psi_1+\cos\psi_2-2)} I \sin A \cdot \sin \frac{a\beta}{2} (1-\cos\psi_1) \cdot \sin \frac{a\beta}{2} (1-\cos\psi_2) \cdot \left(\frac{1}{\frac{\beta}{2}(1-\cos\psi_1)} + \frac{1}{\frac{\beta}{2}(1-\cos\psi_2)} \right). \quad (28)$$

Similarly,

$$F_z = 2ie^{i(a\beta/2)(\cos \psi_1 + \cos \psi_2 - 2)} I \cos A \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_1) \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_2) \cdot \left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} - \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \quad (29)$$

The spherical components of F are

$$\begin{aligned} F_\theta &= F_y \cos \theta \sin \phi - F_z \sin \theta \\ &= 2ie^{i(a\beta/2)(\cos \psi_1 + \cos \psi_2 - 2)} I \cos A \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_1) \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_2) \\ &\quad \cdot \left[\left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} + \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \sin A \cos \theta \sin \phi \right. \\ &\quad \left. - \left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} - \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \cos A \sin \theta \right] \quad (30) \end{aligned}$$

$$\begin{aligned} F_\phi &= F_y \cos \phi = 2ie^{i(a\beta/2)(\cos \psi_1 + \cos \psi_2 - 2)} I \sin \frac{a\beta}{2} (1 - \cos \psi_1) \\ &\quad \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_2) \cdot \left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} \right. \\ &\quad \left. + \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \sin A \cos \phi. \quad (31) \end{aligned}$$

The radiation function is

$$\begin{aligned} K^2 &= F_\theta F_\theta^* + F_\phi F_\phi^* = 4I_0^2 \sin^2 \frac{a\beta}{2} (1 - \cos \psi_1) \cdot \sin^2 \frac{a\beta}{2} (1 - \cos \psi_2) \\ &\quad \cdot \left[\left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} + \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \sin A \cos \theta \sin \phi \right. \\ &\quad \left. - \left(\frac{1}{\frac{\beta}{2} (1 - \cos \psi_1)} - \frac{1}{\frac{\beta}{2} (1 - \cos \psi_2)} \right) \cos A \sin \theta \right]^2 \end{aligned}$$

$$\begin{aligned}
 & + \left(\frac{1}{\frac{\beta}{2}(1 - \cos \psi_1)} + \frac{1}{\frac{\beta}{2}(1 - \cos \psi_2)} \right)^2 \sin^2 A \cos^2 \phi \\
 = 16 & \frac{I_0^2 \sin^2 \frac{a\beta}{2}(1 - \cos \psi_1) \cdot \sin^2 \frac{a\beta}{2}(1 - \cos \psi_2)}{\beta^2 (1 - \cos \psi_1)^2 (1 - \cos \psi_2)^2} \\
 & \cdot \left[\left((2 - \cos \psi_1 - \cos \psi_2) \sin A \cos \theta \sin \phi \right. \right. \\
 & \quad \left. \left. - (\cos \psi_1 - \cos \psi_2) \cos A \sin \theta \right)^2 \right. \\
 & \quad \left. + (2 - \cos \psi_1 - \cos \psi_2)^2 \sin^2 A \cos^2 \phi \right].
 \end{aligned} \tag{32}$$

Using the relations

$$\begin{aligned}
 \cos \psi_1 &= \cos A \cos \theta + \sin A \sin \theta \sin \phi \\
 \cos \psi_2 &= \cos A \cos \theta - \sin A \sin \theta \sin \phi \\
 \cos \psi_1 + \cos \psi_2 &= 2 \cos A \cos \theta \\
 \cos \psi_1 - \cos \psi_2 &= 2 \sin A \sin \theta \sin \phi
 \end{aligned} \tag{33}$$

the factor in square brackets becomes

$$\begin{aligned}
 & \left[\left((2 - 2 \cos A \cos \theta) \sin A \cos \theta \sin \phi - 2 \sin A \sin^2 \theta \sin \phi \cos A \right)^2 \right. \\
 & \quad \left. + (2 - 2 \cos A \cos \theta)^2 \sin^2 A \cos^2 \phi \right] \\
 & = 4 \sin^2 A \left[(1 - \cos \psi_1)(1 - \cos \psi_2) \right].
 \end{aligned} \tag{34}$$

Hence,

$$K^2 = 64 \frac{I_0^2 \sin^2 A \sin^2 \frac{a\beta}{2}(1 - \cos \psi_1) \cdot \sin^2 \frac{a\beta}{2}(1 - \cos \psi_2)}{\beta^2 (1 - \cos \psi_1)(1 - \cos \psi_2)} \tag{35}$$

or,

$$K^2 = 16 \frac{I_0^2 \sin^2 A}{\beta^2} \frac{(1 - \cos a\beta(1 - \cos \psi_1))(1 - \cos a\beta(1 - \cos \psi_2))}{(1 - \cos \psi_1)(1 - \cos \psi_2)} \tag{36}$$

This function applies to an isolated antenna. When the effect of the earth is considered, the function is unchanged if it is regarded as representing an inverted V antenna and its image. In this case the Y axis will be the vertical direction. The appropriate zenith distance and azimuth θ'' , ϕ'' are related to ψ_1, ψ_2 by the equations

$$\begin{aligned} \cos \psi_1 &= \cos A \sin \theta'' \cos \phi'' + \sin A \cos \theta'' \\ \cos \psi_2 &= \cos A \sin \theta'' \cos \phi'' - \sin A \cos \theta'' \end{aligned} \tag{37}$$

where the Z axis is the initial line for ϕ'' .

In the case of the horizontal rhombic antenna the radiation vector of the image antenna referred to 0 is

$$\bar{F}_i = -\bar{F}e^{i2\beta H \cos(\pi-\theta')} \tag{38}$$

where H is the height of the antenna above the ground and θ' is the zenith distance of the direction of radiation. The total radiation vector is

$$F_2 = F_i + F = F(1 - e^{-i2\beta H \cos \theta'}). \tag{39}$$

Hence,

$$\begin{aligned} K_2^2 &= (F_\theta F_\theta^* + F_\phi F_\phi^*)(1 - e^{i2\beta H \cos \theta'})(1 - e^{-i2\beta H \cos \theta'}) \\ &= K^2(2 - 2 \cos(2\beta H \cos \theta')) = 4 \sin^2(\beta H \cos \theta') \cdot K^2 \end{aligned} \tag{40}$$

If ϕ' is the azimuth corresponding to θ' and is measured from the principal axis of the antenna as initial line

$$\begin{aligned} \cos \psi_1 &= \sin \theta' \cdot \cos(\phi' - A) \\ \cos \psi_2 &= \sin \theta' \cdot \cos(\phi' + A) \end{aligned} \tag{41}$$

and the complete radiation function for the horizontal rhombic antenna may be written

$$\begin{aligned} K_2^2 &= 64 \frac{I_0^2 \sin^2 A}{\beta^2} \sin^2(\beta H \cos \theta') \\ &\frac{[1 - \cos a\beta(1 - \sin \theta' \cdot \cos(\phi' - A))][1 - \cos a\beta(1 - \sin \theta' \cdot \cos(\phi' + A))]}{(1 - \sin \theta' \cdot \cos(\phi' - A))(1 - \sin \theta' \cdot \cos(\phi' + A))} \end{aligned} \tag{42}$$

or,

$$\begin{aligned} K_2^2 &= 256 \frac{I_0^2 \sin^2 A}{\beta^2} \sin^2(\beta H \cos \theta') \\ &\frac{\sin^2 \frac{a\beta}{2} (1 - \sin \theta' \cdot \cos(\phi' - A)) \cdot \sin^2 \frac{a\beta}{2} (1 - \sin \theta' \cdot \cos(\phi' + A))}{(1 - \sin \theta' \cdot \cos(\phi' - A))(1 - \sin \theta' \cdot \cos(\phi' + A))} \end{aligned} \tag{43}$$

III. PROPERTIES OF THE RADIATION FUNCTIONS

The radiation functions of the inverted V antenna and of the closely related horizontal rhombic antenna depend on the size and shape of the structure, the wave length, and the direction, as well as the current. The radiation function of the horizontal rhombic antenna depends also on the height. Let the dependence of these two functions on the several variables be indicated by

$$K^2 = f(I_0, \lambda, a, A, \theta', \phi') \quad (44)$$

$$K_2^2 = g(H, \lambda, \theta') \cdot K^2. \quad (45)$$

The outstanding features of the radiation functions are revealed by discussing their maxima and minima. Consider first the radiation function of the isolated rhombus in empty space or an inverted V above a perfect ground. The same function also appears as a factor in the radiation function of the horizontal rhombic antenna.

The directional maxima of any antenna of fixed size and shape are given by

$$f'_{\theta'} = 0; \quad f'_{\phi'} = 0; \quad [I_0, \lambda, a, A \text{ constant}]. \quad (46)$$

If, on the other hand, we desire to find the design which will provide the highest intensity in a chosen direction, the conditions are

$$f'_a = 0; \quad f'_A = 0; \quad [I_0, \lambda, \theta', \phi' \text{ constant}]. \quad (47)$$

We shall require also to find the optimum value of A consistent with (46) for a certain azimuth and altitude. In this case we have

$$f'_A = 0; \quad [I_0, \lambda, \theta', \phi', \text{ constant}] \quad (48)$$

and,

$$[a = \text{function of } A, \text{ through (46)}].$$

Equation (35) may be written

$$K^2 = 16 I_0^2 a^2 \sin^2 A \frac{\sin^2 u}{u} \frac{\sin^2 v}{v}; \quad \begin{aligned} u &\equiv \pi \frac{a}{\lambda} (1 - \cos \psi_1) \\ v &\equiv \pi \frac{a}{\lambda} (1 - \cos \psi_2) \end{aligned} \quad (49)$$

and $\cos \psi_1, \cos \psi_2$ may be expressed in terms of any convenient orthogonal co-ordinates such as θ', ϕ' when required. Collected, these relations are

$$\begin{aligned} \cos \psi_1 &= \sin \theta' \cos (\phi' - A) = \cos A \cos \theta + \sin A \sin \theta \sin \phi \\ &= \cos A \sin \theta'' \cos \phi'' + \sin A \cos \theta'' \end{aligned} \quad (50)$$

$$\begin{aligned} \cos \psi_2 &= \sin \theta' \cos (\phi' + A) = \cos A \cos \theta - \sin A \sin \theta \sin \phi \\ &= \cos A \sin \theta'' \cos \phi'' - \sin A \cos \theta''. \end{aligned} \quad (51)$$

Differentiating (49) partially with respect to θ' and ϕ' , and equating the derivatives to zero

$$f_{\theta'}' = f_u' u_{\theta'}' + f_v' v_{\theta'}' = 0 \tag{52}$$

$$f_{\phi'}' = f_u' u_{\phi'}' + f_v' v_{\phi'}' = 0. \tag{53}$$

The roots of these two simultaneous equations, when $J(u, v)/(\theta', \phi') \neq 0$, are given by

$$f_u' = 16 I_0^2 a^2 \sin^2 A \frac{\sin^2 v}{v} \sin u \cos u \cdot (2u - \tan u) = 0 \tag{54}$$

$$f_v' = 16 I_0^2 a^2 \sin^2 A \frac{\sin^2 u}{u} \sin v \cos v \cdot (2v - \tan v) = 0. \tag{55}$$




Fig. 2—Graph of the factor $\sin^2 x/x$.

The Jacobian $J(u, v)/(\theta', \phi') = -(\pi a/\lambda)^2 \frac{1}{2} \sin 2\theta' \sin 2A$ vanishes when $\theta' = 0$ and $\theta' = \pi/2$. The critical directions are given by

$$\sin u = 0 \tag{56}$$

$$\sin v = 0 \tag{57}$$

$$2u - \tan u = 0; \quad 2v - \tan v = 0. \tag{58}$$

The last pair of equations generally correspond to maxima. The radiation function vanishes when either (56) or (57) is satisfied. (If ψ_1 and ψ_2 had been taken as independent variables, the same equations for the critical directions would have been obtained, subject to $J(u, v)/(\psi_1, \psi_2) \neq 0$; and this Jacobian vanishes only for $\psi_1 = 0, \pi$; $\psi_2 = 0, \pi$.) The roots of (58) are

$$\begin{aligned} u &= [0], & 0.3710\pi, & 1.466\pi, & 2.480\pi, & 3.486\pi, & \text{etc.} \\ v &= [0], & 0.3710\pi, & 1.466\pi, & 2.480\pi, & 3.486\pi, & \text{etc.} \end{aligned} \tag{59}$$

The pair of roots $u = 0, v = 0$ are directions of no radiation. The other roots, by pairs, correspond to a diminishing series of maxima, the greatest of which is at $u = v = 0.3710\pi$, the next at u (or v) = 0.371π and v (or u) = 1.466π , and so on. (Fig. 2.)

In terms of ψ_1 and ψ_2 , the maxima of K^2 are determined by the intersections of the two sets of cones

$$\begin{aligned} \cos \psi_1 &= 1 - \frac{\lambda}{a} 0.3710, 1 - \frac{\lambda}{a} 1.466, 1 - \frac{\lambda}{a} 2.480, 1 - \frac{\lambda}{a} 3.486, \text{etc.} \\ \cos \psi_2 &= 1 - \frac{\lambda}{a} 0.3710, 1 - \frac{\lambda}{a} 1.466, 1 - \frac{\lambda}{a} 2.480, 1 - \frac{\lambda}{a} 3.486, \text{etc.}, \end{aligned} \quad (60)$$

and the minima (zeros) occur when *either* of the following conditions is satisfied:

$$\begin{aligned} \cos \psi_1 &= 1, \quad 1 - \frac{\lambda}{a}, \quad 1 - \frac{2\lambda}{a}, \quad 1 - \frac{3\lambda}{a}, \quad \dots, \quad 1 - \frac{N\lambda}{a} \\ \cos \psi_2 &= 1, \quad 1 - \frac{\lambda}{a}, \quad 1 - \frac{2\lambda}{a}, \quad 1 - \frac{3\lambda}{a}, \quad \dots, \quad 1 - \frac{N\lambda}{a} \end{aligned} \quad (61)$$

where N is the integral part of $2a/\lambda$. For example, if $a=4.6\lambda$, $N=9$, and there are ten values of ψ_1 , and ten of ψ_2 , between 0 and π (including zero) for which K^2 vanishes. And there are nine critical values of ψ_1 and nine of ψ_2 which combine in pairs to determine directions of maximum radiation. The number of such directions is $2N^2$ minus twice the number of pairs (ψ_1, ψ_2) which satisfy either of the following conditions: $\psi_1 + \psi_2 < 2A$; $|\psi_2 - \psi_1| > A$. The first maximum to disappear when $\psi_1 + \psi_2 < 2A$ is the principal one: $\psi_1 = \psi_2 = \cos^{-1}(1 - 0.371 \lambda/a)$. The limiting condition for existence of the principal maximum is $\cos A = 1 - 0.371 \lambda/a$. In that case a single principal maximum is directed along the principal axis of the antenna. The smallest number of maxima is obtained when a/λ is small enough (or A small enough) so that $|\psi_2 - \psi_1| > A$ for all ψ 's except the pairs of type $\psi_1 = \psi_2$ which determine $2N$ maxima, all in the meridian plane. These considerations suggest one way to suppress the most important subordinate maxima. This will be discussed later when the stereographic representation of the functions is given.

In general the maxima occur in quadruplets. For every maximum at (ψ_1^m, ψ_2^n) there is an equal maximum at (ψ_1^n, ψ_2^m) , where the superscripts indicate the values of ψ_1, ψ_2 determined by the m th and n th roots of (58). However, if $m=n$, there are only two directions and they lie in the plane $\psi_1 = \psi_2$. The principal maximum is of this class. The radiation function is symmetrical with respect to the plane of the antenna and also with respect to the perpendicular plane through the principal axis (meridian plane) as may be seen also from the fact that the function is unchanged when θ' is changed to $\pi - \theta'$, or ϕ' is changed to $-\phi'$.

The radiation function of the horizontal rhombic antenna is that of the inverted V antenna multiplied by a factor that measures the effect of interference between the direct and the reflected radiation. That factor, $4 \sin^2 (\pi(2H \cos \theta'/\lambda))$ oscillates between four and zero as the zenith distance goes from zero to $\pi/2$. The factor vanishes when

$$\cos \theta' = 0, \quad \frac{1}{2} \frac{\lambda}{H}, \quad \frac{\lambda}{H}, \quad \frac{3}{2} \frac{\lambda}{H}, \dots, \quad \frac{N'\lambda}{2H}; \tag{62}$$

where N' is the integral part of $\frac{2H}{\lambda}$

and is equal to four when

$$\cos \theta' = \frac{1}{4} \frac{\lambda}{H}, \quad \frac{3}{4} \frac{\lambda}{H}, \quad \frac{5}{4} \frac{\lambda}{H}, \dots, \quad \frac{(2N'' + 1) \lambda}{4H}; \tag{63}$$

where N'' is the integral part of $\left(\frac{2H}{\lambda} - \frac{1}{2}\right)$.

From (60), (61), (62), and (63) it will be seen that the directions for vanishing and maxima of one factor of K_2^2 depend only on the ratio λ/a , while the corresponding directions for the other factor depend only on λ/H . The effect of the factor, $4 \sin^2 (\pi(2H \cos \theta'/\lambda))$, on the other factor, K^2 , depends on the relation between λ/a and λ/H .

In order that interference with the reflected wave may have the most favorable effect in the direction of the principal maximum of K^2 the following relations must be satisfied simultaneously

$$(\cos \psi_1 = \cos \psi_2) \equiv \sin \theta' \cos A = 1 - \frac{\lambda}{a} 0.371 \tag{64}$$

$$\cos \theta' = \frac{2N'' + 1}{4} \frac{\lambda}{H}; \quad N'' = 0, 1, 2, \text{ etc.}$$

Eliminating θ' ,

$$\left(\frac{1 - \frac{\lambda}{a} 0.371}{\cos A}\right)^2 + \left(\frac{2N'' + 1}{4} \frac{\lambda}{H}\right)^2 = 1 \tag{65}$$

Ordinarily it will be required that (65) be satisfied. But it may also be desirable simultaneously to require that some subordinate maximum of K^2 , say the first, be suppressed as much as possible by interference. The first subordinate maxima of K^2 are in the directions (ψ_1, ψ_2) , (ψ_2, ψ_1) given by,

$$\cos \psi_{1,(2)} = 1 - \frac{\lambda}{a} 0.3710 \equiv P; \quad (66)$$

$$\cos \psi_{2,(1)} = 1 - \frac{\lambda}{a} 1.466 \equiv Q. \quad (67)$$

Solving (66) and (67) for θ' , ϕ'

$$\tan \phi_{12}' = \cot A \cdot \frac{P - Q}{P + Q}; \quad \sin \theta_{12}' = \sqrt{1 + \tan^2 \phi_{12}'} \cdot \sec A \cdot \frac{P + Q}{2} \quad (68)$$

$$\therefore \sin \theta_{12}' = \sqrt{1 + \cot^2 A \cdot \left(\frac{P - Q}{P + Q}\right)^2} \cdot \sec A \cdot \frac{P + Q}{2}.$$

Suppression of this radiation is obtained when

$$\cos \theta_{12}' = \frac{N'\lambda}{2H} [N' = 1, 2, \text{etc.}]. \quad (69)$$

Eliminating θ_{12}' between (68) and (69), the height is given by

$$1 - \left(\frac{N'\lambda}{2H}\right)^2 = \left(1 + \cot^2 A \cdot \left(\frac{P - Q}{P + Q}\right)^2\right) \sec^2 A \cdot \left(\frac{P + Q}{2}\right)^2. \quad (70)$$

Complete suppression of the first subordinate maxima together with maximum reinforcement of the principal maximum is possible when (70) and (65) can both be satisfied; i.e., when

$$\left(\frac{4}{2N'' + 1}\right)^2 (1 - P^2 \sec^2 A) \quad (71)$$

$$= \frac{4}{N^2} \left[1 - \left(1 + \cot^2 A \cdot \left(\frac{P - Q}{P + Q}\right)^2\right) \sec^2 A \left(\frac{P + Q}{2}\right)^2\right].$$

Consider next the design of the antenna which will emit the greatest intensity in a chosen direction, for a given current. Equating to zero the partial derivatives of K^2 with respect to a and A ,

$$f_a' = 64 I_0^2 a \sin^2 A \frac{\sin u}{u} \frac{\sin v}{v} (v \sin u \cos v + u \cos u \sin v) = 0 \quad (72)$$

$$f_A' = 16 I_0^2 a^2 \frac{\sin u}{u} \frac{\sin v}{v}$$

$$\left[\pi \frac{a}{\lambda} \sin \theta' \sin^2 A \left(\frac{\sin u (2v \cos v - \sin v)}{v} \sin(\phi' + A) \right. \right. \quad (73)$$

$$\left. \left. - \frac{\sin v (2u \cos u - \sin u)}{u} \sin(\phi' - A) \right) \right. \\ \left. + 2 \sin u \sin v \sin A \cos A \right] = 0.$$

A common solution is $\cos u = 0$, $\cos v = 0$. Or

$$\begin{aligned} u &= (2R + 1) \frac{\pi}{2}; & R &= 0, 1, 2, \text{ etc.} \\ v &= (2S + 1) \frac{\pi}{2}; & S &= 0, 1, 2, \text{ etc.} \end{aligned} \quad (74)$$

These equations require that

$$\frac{a}{\lambda} = \frac{2R + 1}{2(1 - \cos \psi_1)} = \frac{(2S + 1)}{2(1 - \cos \psi_2)}. \quad (75)$$

When these relations are put in (35), we obtain the set of maximum values of K^2 with respect to a and A :

$$K_{\max}^2 = \frac{4I_0^2 \lambda^2 \sin^2 A}{\pi^2} \frac{\sin^2 (2R + 1) \frac{\pi}{2} \cdot \sin^2 (2S + 1) \frac{\pi}{2}}{\sin^2 \frac{1}{2}\psi_1 \sin^2 \frac{1}{2}\psi_2}. \quad (76)$$

Since ψ_1, ψ_2 are fixed, these maxima are all of the same magnitude. The one of most interest, however, from the standpoint of economy is the one for which a/λ is least. This means that either R or S is equal to zero. If one of them, say R , vanishes

$$\frac{a}{\lambda} = \frac{1}{4 \sin^2 \frac{1}{2}\psi_1} = \frac{2S + 1}{4 \sin^2 \frac{1}{2}\psi_2}. \quad (77)$$

This is only satisfied by certain pairs of values of ψ_1 and ψ_2 ; and if $S \neq 0$ the directions are far removed from the principal directional maximum, which ordinarily is undesirable from the point of view of gain. The antenna will therefore be oriented best with respect to the chosen direction when $R=0$ and $S=0$, and this requires also that the direction be in the meridian plane $\psi_1 = \psi_2$.

The requirements are thus reduced to $u = \pi/2$, $v = \pi/2$, which require that

$$\phi' = 0; \quad a = \frac{\lambda}{2(1 - \sin \theta' \cos A)}. \quad (78)$$

The directional maximum is not pointed in the chosen direction; but it is as near as we can get it, if we insist that the intensity be as great as possible in the chosen direction.

The corresponding optimum value of A is obtained by putting $u = v = \pi/2$ in $f_A' = 0$. We obtain thus a relation between A and θ'

$$\cos A - \sin \theta' = 0. \quad (79)$$

When this relation is satisfied, the relation (65) between λ/a and λ/H for maximum reinforcement of the principal directional maximum by ground reflection becomes

$$\left(\frac{2N'' + 1}{4}\right)^2 \cdot \frac{\lambda^2}{H^2} = \frac{\lambda}{a} 0.371. \quad (80)$$

The design at which we have just arrived has the disadvantage that the direction of greatest intensity does not coincide with the chosen direction of transmission. From the standpoint of gain, the most desirable design would be that which would aim the principal directional maximum in the direction in which the signal is to be transmitted. In the latter case we have found

$$u = v = 0.371\pi \quad (81)$$

while for the design which gives greatest intensity in a given direction

$$u = v = 0.5\pi. \quad (82)$$

Comparing intensities in the same direction we find

$$K^2_{u=v=0.5\pi} : K^2_{u=v=0.371\pi} :: 1 : \sin^4 0.371\pi = \text{antilog}_{10} 0.14672. \quad (83)$$

The loss in signal intensity due to using the smaller properly aimed antenna is only 1.5 decibels.

The angle A which will result in the greatest intensity in the direction of the principal directional maximum for a chosen altitude is obtained by putting $u = v = 0.371\pi$ in K^2 before differentiating (since the condition makes a a function of A). We obtain the same result as before (cf. (79))

$$\cos A = \sin \theta' = 0. \quad (84)$$

(This result is obtained whenever $u = v =$ any constant.)

So far we have discussed mainly the isolated rhombic or inverted V antenna. Turning now to consideration of the corresponding properties of the horizontal rhombic antenna, we have for the critical direction

$$gf'_{\theta'} + fg_{\theta'} = 0 \quad (85)$$

$$gf_{\theta'} = 0 \quad (86)$$

and the largest maxima will occur when $f_{\theta'} = 0$, $f_{\phi'} = 0$, $g_{\theta'} = 0$; which are the same conditions that we have considered, together with the additional condition $g_{\theta'} = 0$.

Also, for the design which gives maximum intensity in a given direction we have

$$gf'_a = 0; \quad gf'_A = 0; \quad (87)$$

the solutions of which are the same as for the isolated antenna. The optimum value for A when the principal maximum is aimed in a chosen direction will also be the same as before, because g is not a function of a or A . Thus the properties of the horizontal antenna are very simply related to those of the isolated antenna.

It is sometimes desirable to have the variation of the direction of the principal maximum with wave length as small as possible. The rate of change of zenith distance with wave length is

$$\frac{d\theta'}{d\lambda} = - \frac{0.371}{\sqrt{\cos^2 A - \cos^2 \psi}}; \text{ where} \quad (88)$$

$$\cos \psi = \sin \theta' \cos A = 1 - \frac{\lambda}{a} 0.371.$$

The most unfavorable condition is when $\cos A = \cos \psi$, or $\theta' = \pi/2$. In order for the principal maximum to exist, $\cos A$ must be equal to or greater than $\cos \psi$. The rate of change therefore approaches its least value when A approaches zero and ψ approaches $\pi/2$. It will be noted that the azimuthal angle covered by the major lobe is $2[\cos^{-1}(1 - 0.371\lambda/a) - A]$, and the vertical angle extends from $\theta' = \pi/2$ to $\theta' = \arcsin(1 - \lambda/a)/\cos A$, unless extinguished sooner by interference, in which case it extends only to $\theta' = \arccos \lambda/2H$.

IV. STEREOGRAPHIC REPRESENTATION OF THE RADIATION PATTERN

The properties of rhombic antennas and the effects due to variation of design and frequency will be illuminated by the use of a simple graphical representation of the directions of the zeros and maxima of the radiation function. The facts are most clearly shown when the radiation function of the isolated antenna and the ground interference factor are treated separately.

If the directions of zeros and maxima of K^2 are plotted on a spherical blackboard with the rhombus at the center, they consist of a coaxial system of small circles, of alternating maxima and zeros defined by (60) and (61), around one arm of the antenna as axis, and an identical system of circles around the other arm of the antenna. The angle between the axes of the circles is the angle $2A$ of the rhombus. The heights of the two sets of zones marked out by the null circles are all equal. Consequently all zones subtend the same solid angle at the center. This pattern on the sphere is ideally suited to representation on the plane by means of the stereographic projection. The calculations required for the plotting are thereby made extremely simple and brief.

The stereographic projection is commonly used in cartography

and crystallography; but since it is not well known to engineers, a short account of its properties and the way it is used will be given.

When the sphere is projected on the plane of one of its circles, this plane is called the primitive plane, and the circle is called the primitive circle. In the stereographic projection, the center of projection is taken at a pole of the primitive. The projection of any point of the sphere is found by drawing a straight line from the given point to the center of projection. The intersection of this line with the primitive plane is the required point. Ordinarily the primitive circle is a great circle. The




Fig. 3—Stereographic projection for the direct radiation factor.

most important properties of this projection are: (1) the projection of a circle is a circle; (2) angles on the sphere are unchanged in the projection.

Consideration of methods of construction may be limited to two special cases which include all that will be encountered here. Case (1): The plane of the given circle is perpendicular to the primitive plane. Case (2): The plane of the given circle is parallel to the primitive plane.

In connection with Figs. (3) and (4), it should be remarked that in the practical construction a single plane is used to represent both the primitive plane and the plane at right angles to it through the axes of the given circle and the primitive circle. In Case (1) the given circle and the primitive circle are at right angles where they intersect. As the angle of intersection is unchanged in the projection, the center of the

required circle is found by drawing the tangents MC and NC . Alternatively the lines of projection PN , PM may be drawn to intersect the line of measures in A and B . The center is then obtained by bisecting AB . The construction in the other case is apparent from the figures.




Fig. 4—Stereographic projection for the ground reflection factor.

Fortunately the forms of (60), (61), (62), and (63) are such as to make possible the complete and accurate stereographic mapping of the antenna characteristics with almost no computation, and without the use of tables. Referring to Fig. 3(b), if the sphere is of unit radius, the distance ST is equal to $(1 - \cos \psi)$. If, therefore, a series of points, T , are plotted along the line of measures, OS , such that $ST = \lambda/a$, $2\lambda/a$, $3\lambda/a$, etc., the corresponding points, N , will determine a series of angles ψ , which satisfy (61). Similarly the set of ψ 's which satisfy (60) are determined by plotting the points, T , for which $ST = r_1\lambda/a$, $r_2\lambda/a$, etc.,

where r is the coefficient of π in the roots of $\tan x = 2x$. Again in Fig. 4(b), if a series of points R are plotted along OQ in equal steps of length $\lambda/4H$ measured from 0, the θ 's so determined by erecting the perpendicular RB satisfy (62) and (63), the nulls alternating with the maxima at equal intervals of $\cos \theta'$.

As an illustration, let us construct part of the stereographic radiation pattern of an antenna for which $\lambda/a = 0.5$; $\lambda/H = 1$. (Fig. 5). The unprimed T 's are plotted along the horizontal diameter at intervals of 0.5×5 centimeters (5 centimeters being the radius of the primitive circle). These points locate the null circles, of which only the first, corresponding to T_1 , is shown. The primed T 's, which locate the maxi-




Fig. 5—Graphical construction of a distribution pattern.

imum circles, are plotted at distances from S equal to $0.371 \times 0.5 \times 5$ centimeters, $1.466 \times 0.5 \times 5$ centimeters, etc. For the higher orders it will be seen that they fall almost exactly between the null T 's. To locate the ground reflection interference circles the vertical diameter PQ is divided into equal segments of length $\frac{1}{4} \times 5$ centimeters beginning at 0. The primed R 's refer to maxima and the unprimed letters to zeros. Only the first null circle inside the horizon is drawn. The altitude of this circle above the horizon is equal to the angle SOA . The diagram is completed by drawing an identical system of circles whose centers lie on another axis making an angle with the other equal to the angle $2A$ of the rhombus.

Fig. 6 shows one half of the pattern of an antenna for which $a = 3.25\lambda$. It will be observed that as the length of the antenna is increased or the frequency is increased the number of zones into which the sphere is divided is increased and the radius of the principal maximum circle (on the right in the figure) diminishes. The altitude of the principal maximum attainable by varying the angle of the antenna is




Fig. 6—A portion of a distribution pattern.




Fig. 7—Complete stereographic pattern for a horizontal rhombus.

limited to the radius of this circle. If this figure is copied on tracing cloth and placed directly over the original at various angles the effects

on the complete pattern of varying the antenna angle are easily seen.

A complete pattern for a horizontal antenna is shown in Fig. 7. This design is one which gives the strongest signal which can be emitted at an altitude of 17.5 degrees. Disregarding ground interference, the intensities of the six largest maxima are proportional to the areas of the shaded circles. Note, however, that in this case the (1, 3) pair of lobes fall so close to the zeroth ground interference null that they will be considerably attenuated while the (1, 1) and (1, 2) lobes are close to the first ground interference maximum and are reinforced accordingly. The dots in the figure locate the peaks of the minor lobes. The relatively large minor peaks (1, 4) and (1, 5) are missing.

The relative magnitudes of the directional maxima of K^2 are independent of the design of the antenna. The maximum values of $(\sin^2 x)/x$ are

n	1	2	3	4	5	6	7	8	9	10	11
$\frac{\sin^2 x}{x}$	0.7246	0.2147	0.1278	0.0911	0.0708	0.0579	0.0490	0.0425	0.0375	0.0335	0.0303.

Beyond the fifth these numbers are given to this degree of accuracy by $1/x$. The intensities of the maxima in the meridian plane are proportional to the squares of these numbers; the others are measured by products. For example, the peak corresponding to the first maximum of $(\sin^2 u)/u$ and the second maximum of $(\sin^2 v)/v$, indicated by the symbol (1, 2), is proportional to the product, 0.7246×0.2147 . The relative magnitudes of the directional maxima are shown in the following table in which m indicates the order of a maximum of $(\sin^2 u)/u$ and n the order of a maximum of $(\sin^2 v)/v$.

n	1	2	3	4	5	6	7	8	9	10	11
m											
1	0.52506										
2	0.15554	0.04308									
3	0.09264	0.02744	0.01635								
4	0.06604	0.01956	0.01165	0.008306							
5	0.05132	0.01520	0.009055	0.006455	0.005016						
6	0.04197	0.01243	0.007406	0.005279	0.004103	0.003355					
7	0.03550	0.01052	0.006264	0.004465	0.003470	0.002838	0.002401				
8	0.03077	0.009114	0.005429	0.003870	0.003007	0.002459	0.002080	0.001803			
9	0.02714	0.008041	0.004789	0.003414	0.002653	0.002170	0.001835	0.001591	0.001403		
10	0.02429	0.007195	0.004286	0.003055	0.002374	0.001942	0.001642	0.001423	0.001256	0.001124	
11	0.02198	0.006511	0.003878	0.002764	0.002148	0.001757	0.001486	0.001288	0.001136	0.001017	0.0009199

As the order is increased these maxima occur at values of u or v nearer and nearer to an integral number of $\pi/2$'s. Even the fifth root of $\tan u = 2u$ occurs at a value of u only two degrees less than $9/2\pi$.

It is easy to see that the gain increases when the ratio a/λ is increased. But at the same time the solid angle covered by the principal beam is diminished, the beam is depressed, and greater height is required. The solid angle may become so small that the resulting increase

in fading will annul the advantage in gain. Therefore it is desirable to increase the gain by means which will not affect the solid angle or the altitude of the principal beam. A design in which the gain is increased by suppressing subordinate maxima is shown in Fig. 8. The (1, 3) pair of peaks are made to vanish by depressing them to the horizon. The height is adjusted so that the first ground interference null passes through the (1, 2) pair of maxima and the first interference maximum goes through the (1, 1) maximum. This particular example of a design which gives high gain with a fairly broad principal beam does not




Fig. 8—A design in which several large subordinate maxima have been suppressed.

satisfy the condition $A = \pi/2 - \theta'_{(1,1)}$ demanded by the requirement of highest intensity for a given current. But a design which effects a reduction of the radiation resistance permits the use of a larger antenna current without increasing the expenditure of power.

It may be shown that the necessary relation between λ/a and the zenith distance of the principal lobe when a certain subordinate maximum (1, n) is on the horizon is

$$\begin{aligned}
 & \left[2 \left(1 - r_1 \frac{\lambda}{a} \right)^3 - \sin^2 \theta'_{(1,1)} \left(2 - \frac{\lambda}{a} (r_1 + r_n) \right) \right]^2 \cdot \sin^2 \theta'_{(1,1)} \\
 & = 4 \left(1 - r_1 \frac{\lambda}{a} \right) \left(\sin^2 \theta'_{(1,1)} \right. \\
 & \quad \left. - \left(1 - r_1 \frac{\lambda}{a} \right)^2 \right) \left(1 - \left(1 - r_1 \frac{\lambda}{a} \right)^2 \right).
 \end{aligned}
 \tag{89}$$

Then only those peaks $(1, m)$ can exist for which $m < n$. When we say that a peak vanishes by interference, we do not mean to imply that the entire corresponding lobe is wiped out, but only a major portion of it.

V. STATES OF POLARIZATION AND APPLICABILITY OF THE RECIPROCATION THEOREM

Because of the symmetry of the radiation function, one may expect to find that the electromotive intensity is either parallel or perpendicular to the plane of the rhombus and the meridian plane for directions of radiation which lie in these planes, but not elsewhere. If a formula giving the directional properties of the antenna in reception is obtained on the assumption of a certain polarization of the received wave, it must not be supposed that the directional properties in transmission can be inferred from such a formula on the basis of the reciprocity theorem except in that range of direction for which the assumption regarding polarization is satisfied in transmission. For this reason the reception formula due to Bruce, Beck, and Lowry will not yield the directional properties of a transmitting antenna. If reciprocity exists at all, it will be confined to certain limited ranges of direction, which depend on the state of polarization of the transmitted ray. This we now proceed to investigate.

The components of the complex electromotive intensity of the transmitted wave are expressible in the forms

$$E_{\theta'} = -120 \pi i \beta A_{\theta'} \quad (90)$$

$$E_{\phi'} = -120 \pi i \beta A_{\phi'} \quad (91)$$

where $A_{\phi'}$ and $A_{\theta'}$ are the components of the complex magnetic vector potential. Hence, from the definition of the radiation vector, we have

$$E_{\theta'} = -120 \pi i \beta \frac{e^{-i\beta r}}{4\pi r} F_{\theta'} \quad (92)$$

$$E_{\phi'} = -120 \pi i \beta \frac{e^{-i\beta r}}{4\pi r} F_{\phi'} \quad (93)$$

The spherical components of the radiation vector in terms of the rectangular components are given by

$$F_{\theta'} = -F_x \sin \theta' + F_y \cos \theta' \sin \phi' + F_z \cos \theta' \cos \phi' \quad (94)$$

$$F_{\phi'} = F_y \cos \phi' - F_z \sin \phi'. \quad (95)$$

Substituting the values of F_y and F_z , we find

$$\begin{aligned}
 F_{\theta'} &= I \cos \theta' \cdot 2ie^{i(a\beta/2)(\cos \psi_1 + \cos \psi_2 - 2)} \\
 &\quad \frac{\sin \frac{a\beta}{2} (1 - \cos \psi_1) \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_2)}{(1 - \cos \psi_1)(1 - \cos \psi_2)} \\
 &\quad \times \frac{2}{\beta} \left[\left(2 - (\cos \psi_1 + \cos \psi_2) \right) \sin A \sin \phi' \right. \\
 &\quad \left. + (\cos \psi_1 - \cos \psi_2) \cos A \cos \phi' \right] \quad (96)
 \end{aligned}$$

$$\begin{aligned}
 F_{\phi'} &= I 2ie^{i(a\beta/2)(\cos \psi_1 + \cos \psi_2 - 2)} \\
 &\quad \frac{\sin \frac{a\beta}{2} (1 - \cos \psi_1) \cdot \sin \frac{a\beta}{2} (1 - \cos \psi_2)}{(1 - \cos \psi_1)(1 - \cos \psi_2)} \\
 &\quad \times \frac{2}{\beta} \left[\left(2 - (\cos \psi_1 + \cos \psi_2) \right) \sin A \cos \phi' \right. \\
 &\quad \left. - (\cos \psi_1 - \cos \psi_2) \cos A \sin \phi' \right]. \quad (97)
 \end{aligned}$$

(Note that $(\cos \psi_1 - \cos \psi_2) = 2 \sin \theta' \sin \phi' \sin A$;

$$(\cos \psi_1 + \cos \psi_2) = 2 \sin \theta' \cos \phi' \cos A).$$

We see that $F_{\theta'}$ vanishes and $F_{\phi'}$ remains finite when $\phi' = 0$ or $\theta' = \pi/2$. In other words, the electric vector is parallel to the plane of the antenna only for radiation directed in the meridian plane or the plane of the antenna.

By means of these equations the direction of the electric vector may be calculated for any direction of the ray. The most important direction is that of the principal maximum; and it is shown that for this ray the electric vector is horizontal for a horizontal rhombus and vertical for an inverted V antenna.

The formula for the complex current in the receiver given by Bruce, Beck, and Lowry, when translated into the symbols used in this paper, is

$$\begin{aligned}
 I_r &= i \frac{\epsilon \lambda}{4\pi Z_0} \left[\frac{\sin(\phi' + A)}{1 - \cos(\phi' + A) \cdot \sin \theta'} - \frac{\sin(\phi' - A)}{1 - \cos(\phi' - A) \cdot \sin \theta'} \right] \\
 &\quad \times \left[1 - e^{-i a \beta (1 - \cos(\phi' - A) \cdot \sin \theta')} \right] \left[1 - e^{-i a \beta (1 - \cos(\phi' + A) \cdot \sin \theta')} \right] \\
 &\quad \times \left[1 + e^{-i 2 \beta H \cos \theta'} \right] \quad (98)
 \end{aligned}$$

when the ground is perfect. The square of the modulus of the current is

$$|I_r|^2 = \frac{\epsilon^2 \lambda^2}{16\pi^2 Z_0^2} \left[\frac{\sin(\phi' + A)}{1 - \sin \theta' \cdot \cos(\phi' + A)} - \frac{\sin(\phi' - A)}{1 - \sin \theta' \cdot \cos(\phi' - A)} \right]^2 \quad (99)$$

$$\cdot 4 \sin^2 \frac{a\beta}{2} (1 - \sin \theta' \cdot \cos(\phi' - A)) \cdot 4 \sin^2 \frac{a\beta}{2} (1 - \sin \theta \cdot \cos(\phi' + A))$$

$$\cdot 4 \sin^2 (\beta H \cos \theta').$$

Comparing this with the corresponding function for radiation we see that they differ as functions of direction only in that

$$\left[\frac{\sin(\phi' + A)}{(1 - \cos \psi_2)} - \frac{\sin(\phi' - A)}{(1 - \cos \psi_1)} \right]^2$$

appears as a factor in $|I_r|^2$ instead of the factor

$$\frac{1}{(1 - \cos \psi_1)(1 - \cos \psi_2)} \equiv \frac{1}{(\cos \phi' - \sin \theta' \cos A)^2 + \sin^2 \phi' \cos^2 \theta'}$$

of K_2^2 . After some reduction we find that

$$\left[\frac{\sin(\phi' + A)}{1 - \cos \psi_2} - \frac{\sin(\phi' - A)}{1 - \cos \psi_1} \right]^2 \quad (100)$$

$$= 4 \sin^2 A \cdot \left[\frac{\cos \phi' - \sin \theta' \cos A}{(\cos \phi' - \sin \theta' \cos A)^2 + \sin^2 \phi' \cos^2 \theta'} \right]^2.$$

The two factors are seen to be identical only when $\phi' = 0$ or $\theta' = \pi/2$, a result which we have already predicted from the restrictions on the validity of the reciprocity theorem and the fact that the receiving equation is based on an electric vector which is normal to the plane of incidence.

It cannot be maintained that this receiving formula will be correct for a receiving antenna when it is receiving radiation directly from any of the lobes of a rhombic transmitting antenna other than those in its meridian plane. While the receiving antenna will not respond to a vertical component of E , it will respond to the horizontal component of $E_{\theta'}$ (as well as to $E_{\phi'}$, which is wholly horizontal). The component $E_{\phi'}$ is in the plane of the wave front; but the horizontal component of $E_{\theta'}$ is in the plane of incidence.

VI. NOTE ON THE RADIATION RESISTANCE AND THE GAIN

The radiation resistance is given by

$$R = \frac{30\pi}{I_0^2\lambda^2} \int K^2 d\Omega \quad (101)$$

for the inverted V, and by

$$R = \frac{30\pi}{I_0^2\lambda^2} \int K_2^2 d\Omega \quad (102)$$

for the horizontal rhombic antenna. The differential, $d\Omega$, signifies an element of solid angle; and the integration is to be carried out over all directions.

The absolute gain in decibels is

$$10 \log_{10} 4\pi \frac{K_{\max}^2}{\int K^2 d\Omega} \quad (103)$$

where K_{\max}^2 indicates the value of K^2 (or K_2^2) evaluated at the principal maximum. Difficulty of performing the indicated integrations has prevented general calculation of the radiation resistance and gain. The calculation can be performed for any particular case by mechanical integration.



CHARACTERISTICS OF THE IONOSPHERE AT WASHINGTON, D. C., AUGUST, 1937*

By

T. R. GILLILAND, S. S. KIRBY, N. SMITH, AND S. E. REYMER
 (National Bureau of Standards, Washington, D. C.)

FIG. 1 shows the critical frequency and virtual height data for August, 1937. The characteristics of the ionosphere showed the effects of the seasonal advance toward winter in that the daytime values of f_{F_2} were greater, the rise of f_{F_2} at sunrise was more rapid, and




FIG. 1. Virtual heights and critical frequencies of the E, F_1 , F_2 , and F layers of the ionosphere for August, 1937. The solid line graphs represent averages for the quiet days. The graphs for August 2, 4, and 22 represent conditions for days of ionosphere storms.

the f_{F_1} on quiet days was more poorly defined than during July. The f_{F_1} was so poorly defined on quiet days during August that the values could not be accurately determined and for this reason they are not

* Decimal classification: R113.61. Original manuscript by the Institute, September 9, 1937. Publication approved by the Director of the National Bureau of Standards of the U. S. Department of Commerce.

shown in the figure. The critical frequencies for the undisturbed days in August, 1937, exceeded those for August, 1936, by approximately the following amounts: noon f_E —250 kc, noon f_{F_2} —1100 kc, midnight f_F —1100 kc.

Out of 366 hours of observations from 0000 to 1100, E.S.T., strong sporadic E reflections up to 4400 kilocycles or higher were present seven per cent of the time and up to 6200 kilocycles or higher 2.5 per cent of the time. Out of 353 hours of observations from 1200 to 2300, E.S.T., strong sporadic E reflections up to 4400 kilocycles or higher were present fourteen per cent of the time and up to 6200 kilocycles or higher six per cent of the time. Around sunset on a few days, especially August 18, strong sporadic E reflections up to 11,000 kilocycles were present.

TABLE I
IONOSPHERE STORMS

Date 0000-2400, E.S.T.	h_F before sunrise km	Max. $f_{F_2}^x$ during day (near sunset) kc	Min. f_{F_2} during day (before sunrise) kc	Magnetic Character ¹	
				0000-1200 G.M.T.	1200-2400 G.M.T.
Aug. 22	415	6400	2800	1.7	1.1
Aug. 2	420	6400	3350	1.4	0.7
Aug. 4	352	8300	5000	1.0	0.4
Aug. 28	313	8700	4750	0.2	0.4
Aug. 29	315	9200	5300	0.3	0.0
Aug. 23†	333	near normal	4400	0.4	0.1
Aug. 3†	329	normal	5000	0.4	0.6
Average of undisturbed days	298	9870	6070	0.14	0.2

¹ American character figure. Average of seven observatories, two of which are operated by Carnegie Institution of Washington and five of which are operated by the United States Coast and Geodetic Survey.

† The ionosphere storms of August 2-3 and 22-23 ended shortly after sunrise on August 3 and 23, respectively.

Ionosphere disturbances associated with magnetic storms will hereafter be called ionosphere storms. In Table I ionosphere storms are listed approximately in the order of their severity together with other related data.

Out of 182 hours of night measurements of f_F^x between 0000 and 0500, E.S.T., twenty-four values were more than twenty per cent below the undisturbed average. All of these occurred on the ionosphere storm days of August 2, 3, 4, 22, 23, and 28. During this same period forty values of f_F^x were more than ten per cent below the undisturbed average for August. All but seven of these occurred on the dates listed in Table I. Of these night measurements no values were over twenty per cent above, two values were over fifteen per cent above, and twelve values over ten per cent above the undisturbed average.

Out of sixty-eight hours of observations between 0600 and 2200, E.S.T., on Wednesdays nine values were over twenty per cent below and fourteen values over fifteen per cent below the undisturbed average. All of these occurred on the ionosphere storm day of August 4. Between

these hours on the quiet days of August 11, 18, and 25 all values were within ± 10 per cent of the undisturbed average.

Emissions from station W8XAL, 6060 kilocycles, 650 kilometers, were propagated regularly by the F layer at night except for short periods between midnight and 0600, E.S.T., on the ionosphere storm days of August 2, 3, and 4. The ionosphere storm day of August 22 was Sunday and the W8XAL transmissions did not begin until 0800, E.S.T., which was too late to indicate an early morning failure of F layer transmissions. During August E layer transmission began on the average at 0628 and ended at 1821, E.S.T.

Transmissions from W1XK, 9570 kilocycles, 600 kilometers, during August were undergoing a transition from summer to winter type propagation. For ten days of the summer type, normal E layer transmission began on the average at 0828 and ended on the average at 1443, E.S.T. On five of these days F layer transmission was observed to begin at an average of 1752, E.S.T. On eleven winter type days F layer transmission began on the average at 0640, E.S.T. The average ending time of F layer transmission on twenty-two days was 2104, E.S.T. These transmissions were not received by F layer on August 2, 4, 21, 22, 27, and 28. Sporadic E transmissions obscured the beginning and ending of normal E and F layer transmission on several occasions.

Transmissions from DJB, Berlin, 15,200 kilocycles, 6700 kilometers, were propagated regularly by the F layer on ionospherically quiet nights. These transmissions were made regularly from 1700 to 2300, E.S.T., or 2300 to 0500, Berlin time. They failed completely on the nights of August 3-4, 22-23, 27-28, failed during the later hours of transmission on the nights of August 1-2, 19-20, and 28-29, and were very poor on the night of August 4-5. These periods of poor propagation were, except for August 19-20, all times of ionosphere storms.

Sudden disturbances of the ionosphere were not as numerous during August, 1937, as during July. They were marked by the following radio fade-outs, observed at Washington:²

TABLE II

Date	Beginning of fade-out	Beginning of recovery	Recovery complete	Location of transmitter	Minimum intensity
Aug. 1	1740	—	1756	Ohio, D.C.	0.2
Aug. 1	1820	—	2005	Ohio, Mass.	0.5
Aug. 6	2152	2201	2209	Ohio	0.01
Aug. 7	1400	1432	1540	Ohio, Mass., D.C.	0.02
Aug. 10	1420	—	1530	Ohio	0.5
Aug. 11	1905	1915	1922	Ohio	0.05
Aug. 14	1816	1829	1838	Ohio	0.0
Aug. 18	1727	1735	1800	Ohio, Mass.	0.0
Aug. 27	2047	—	2140	Ohio, D.C.	0.01
Aug. 28	1924	2006	2050	Ohio, Mass., D.C.	0.0

² All times G.M.T. Minimum intensities given in terms of transmissions from W8XAL, frequency 6060 kilocycles, distance 650 kilometers.

CONTRIBUTORS TO THIS ISSUE

Dellinger, J. H.: Born July 3, 1886, at Cleveland, Ohio. Educated at Western Reserve University, 1903-1907; received A.B. degree, George Washington University, 1908; Ph.D. degree, Princeton University, 1913; D.Sc. degree, George Washington University, 1932. Joined staff of National Bureau of Standards as physicist, 1907; chief engineer, Federal Radio Commission, 1928-1929; chief of radio section, research division, aeronautics branch, Department of Commerce, 1926-1934; chief of radio section, National Bureau of Standards, 1919 to date. United States representative at numerous international radio and electrical conferences, 1921 to date. Vice president, Institute of Radio Engineers, 1924; president, 1925. Fellow, Institute of Radio Engineers, 1923.

Foster, Donald: Born March 19, 1900, at West Torbrook, Nova Scotia, Canada. Assistant in chemistry, Acadia University, 1918-1919; topographer and assistant geologist, Geological Survey of Canada, 1918-1920; assistant in chemistry, Acadia University, 1918-1919; assistant in physics, Yale University, 1920-1921; teacher of physics and mathematics in preparatory schools, New Haven, Connecticut, 1921-1924; Loomis Fellow, Yale University, 1921-1924; received Ph.D. degree, Yale University, 1924. Optical engineer, research and development department, Eastman Kodak Company, 1924-1925; research department, Bell Telephone Laboratories, Inc., 1925-1936; physicist, Westinghouse Electric and Manufacturing Company, 1936 to date. Nonmember, Institute of Radio Engineers.

Goddard, DeWitt R.: Born November 30, 1904, at New York, New York. Received B.S. degree in electrical engineering, Worcester Poly-Technic Institute, 1929. Communication receiver research and development, RCA Communications, Inc., 1929 to date. Associate member, Institute of Radio Engineers, 1931.

Morrison, John F.: See PROCEEDINGS for June, 1937.

***Norton, K. A.:** Born February 27, 1907, at Rockwell City, Iowa. Received B.S. degree, University of Chicago, 1928. Inspection development laboratory Western Electric Company, 1929. Columbia University, 1930-1931. Radio Section, Bureau of Standards, July, 1929, to September, 1930, and June, 1931, to December, 1934. Federal Communications Commission, December, 1934, to date. Associate member, Institute of Radio Engineers, 1929.


Peterson, Harold O.: Born November 3, 1899, at Blair, Nebraska. Received B.S. degree in electrical engineering, University of Nebraska, 1921. Testman, General Electric Company, 1921-1922. Engaged in development of radio communications equipment, Radio Corporation of America, 1922-1929; in charge, radio communication receiver development laboratory, RCA Communications, Inc., 1929 to date. Associate member, Institute of Radio Engineers, 1922; Member, 1931.

* Paper published in September, 1937, issue of the PROCEEDINGS

Roberts, W. van B.: Born 1893. Received B.S. degree, Princeton University, 1915; E.E. degree, 1917; Ph.D. degree, 1924. Student engineer, Western Electric Company, summer, 1916; head of radio and signaling department, School of Military Aeronautics, U. S. Signal Corps, 1917; technical officer of sound ranging, Section 1, Engineer Corps, A.E.F., 1918; instructor in physics and communication theory, school of electrical engineering, Princeton University, 1919-1923. Radio Corporation of America, 1924 to date. Associate member, Institute of Radio Engineers, 1922; Fellow, 1929.

Samuel, Arthur L.: Born December 5, 1901, at Emporia, Kansas. Received B.A. degree, College of Emporia, 1923; received S.B. and S.M. degrees, Massachusetts Institute of Technology, 1926. General Electric Company (intermittently), 1923-1927; instructor, electrical engineering department, Massachusetts Institute of Technology, 1926-1928; technical staff, Bell Telephone Laboratories, Inc., 1928 to date. Member, American Physical Society and American Institute of Electrical Engineers. Associate member, Institute of Radio Engineers, 1924.





IT BELONGS TO MAIN STREET

— and to every other street in this country. Everybody uses the telephone. Over 300,000 people operate the business. And more than twice that number own it.

The interests of all are the same. Good telephone service — good wages — and a fair return to the owners.

BELL TELEPHONE SYSTEM




When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.



INSULATED RESISTORS

Cut Costs



TYPE MW INSULATED
POWER WIRE WOUNDS

TYPE BW LOW RANGE
INSULATED WIRE WOUNDS

TYPE BY INSULATED
METALLIZED RESISTORS

BETTER
ENGINEERING
DESIGNS

FEWER SERVICE
CALLS

QUICKER
ASSEMBLY
...Less Testing

FEWER STOCK
SIZES REQUIRED
...LESS "PAPER"
WORK

FEWER REJECTS
AT END OF
ASSEMBLY
LINE

INTERNATIONAL RESISTANCE COMPANY

401 NORTH BROAD STREET, PHILADELPHIA, PA.

Factories or Licensees in Canada, England, France, Germany, Italy, Denmark and Australia


MAKERS OF RESISTANCE UNITS OF MORE TYPES, IN MORE SHAPES, FOR MORE APPLICATIONS THAN ANY OTHER MANUFACTURER IN THE WORLD

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

NOW

....Light Up Your Panels....


with **TRIPL**
FRONT ILLUMINATION



Model 426 Without Front Illumination

A new highly attractive four-inch square modernistic design featuring extra long scale length.

Front illumination available in 3" and larger cases. Stocked in all popular ranges.



- Perfect Distribution of Light—No Glare
- Does Not Affect Operation of Instrument
- Bulb Can Be Replaced Without Opening Sealed Instrument
- Heat of Lamp Kept Out of Instrument—Permits Use of Regular Metal Dial
- Low Cost

Model 426, Showing Front Illumination Attachment

This is an exclusive Triplet development. Fits on front of case and is entirely external to instrument itself. Front illumination also available in other models.

Rear illumination with lamp inside the case, also can be supplied, preferably in the smaller size cases.

NOTE LIGHTING ATTACHMENT IS ENTIRELY EXTERNAL

Triplet instruments are noted for:

Highest Quality

1. Bar-Bridge Construction
2. Magnet pole pieces are continuous . . . gauged to precision accuracy.
3. Fewer magnetic parts . . . greater initial and lasting accuracy.
4. Fully aged to relieve strains and unnecessary adjustments.
5. Unsurpassed for ruggedness and wearing qualities.

Low Cost

1. Recognized in industry for simplified construction.
2. Produced on quantity production basis.
3. Manufactured by highly skilled workers.

Triplet manufactures a complete line of electrical measuring instruments embracing round, square, rectangular; molded and metal cases and twin meters for radio, electrical and general industrial applications.

If you have an Electrical Instrument Problem write to Triplet




The Triplet Electrical Instrument Co.
2110 Harmon Ave., Buffon, Ohio

..... Please send me more information on
 Model 426: I am also interested
 in
 Name
 Address
 City State

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

For LABORATORY or INDUSTRIAL USE



INDUCTANCE COMPARATORS

Types T.F.332 and T.F.354

These instruments have been designed for quick and accurate comparison of self inductances at a definite frequency. They incorporate an equal ratio bridge with differential inductometer, oscillator and visual detector with provision for connecting the standard and test coils.

T.F.332

Range 1—5,000 microhenries
Frequency 100 kilocycles
Differential Inductometer 40 microhenries
Accuracy $\pm 1\% \pm 0.2$ microhenry

T.F.354

Range 100 microhenries—50 millihenries
Frequency 10 kilocycles
Differential Inductometer 400 microhenries
Accuracy $\pm 1\% \pm 1$ microhenry

Comparators are also available for Impedance and Capacity tests.


May we send you further details and prices?

MARCONI-EKCO INSTRUMENTS LTD.

Electra House, Victoria Embankment, London W.C. 2

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

**Just try to find a program
you can't pick-up better with
the "8-Ball" or the "Salt-Shaker"**



BETWEEN them, these two famous Western Electric mikes meet every broadcasting need. Both can be used for non-directional pickups—both can be transformed quickly for directional work by simply putting on their acoustic baffles.

The "8-Ball," which jumped into immediate popularity two years ago, is still being bought in bunches. And orders for

the newer "Salt-Shaker" keep pouring in from broadcasters—and from Public Address operators who find it ideal for their work, too.

At the low prices, you can't afford anything less than the true Western Electric quality these two mikes will give you!

For details: Graybar Electric Co., Graybar Building, New York.



Western Electric

Distributed by GRAYBAR Electric Co. In Canada: Northern Electric Co., Ltd.

RADIO TELEPHONE BROADCASTING EQUIPMENT

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

MEASURE DISTORTION ... FIDELITY

THIS FAST ... EASY WAY !


Now you can make measurements faster, easier and more accurately! New RCA measuring equipment makes it possible.

This equipment consists of the two instruments shown on this page. With it, complete operating characteristics of amplifiers or transmitters can be accurately determined. Direct measurements of distortion percentage, noise level and frequency characteristics of equipment at frequencies in audible range can also


be made swiftly and easily. Routine fidelity checks are made in short order. Broadcast stations can maintain consistent high fidelity performance.

Proof of the quality and usefulness RCA has built into this equipment is shown by these fine features: AC operated...small, compact...rack or cabinet mounting...covers entire audio frequency band...easy adjustment, direct indication, calculations and critical adjustments unnecessary. Full technical data on request.

RCA type 68A Beat Frequency Oscillator. Specifications: Frequency Response: Is flat within plus or minus 1 db. over the range between 20 and 17,000 cycles. Instrument may be operated down to 5 cycles per second with good wave form. Output power: Maximum 120 mw. Output Impedances: 5,000, 500 and 250 ohms. Distortion: Total arithmetic sum below 100 cycles, 0.3%—Above 100 cycles, 0.2% at 12½ mw. output. Hum (zero level output): Minus 60 db. Power supply: 110-120 volts. 25-60 cycles, 70 watts.



RCA type 69A Noise and Distortion Meter. Specifications: Frequency Range for Distortion Measurements: 50 to 7,000 cycles. Distortion Measurement Range: Full scale, 1% to 100%. Minimum reading .3 of 1%. Minimum Hum Measurements: 88 db. below a 12.5 mw. level on a 500 ohm line or below 100% modulation. Includes R.F. rectifier for transmitter measurements. Audio Input Impedance: 20,000 ohms bridging input balanced to ground and 250,000 ohms unbalanced to ground.



Broadcast Equipment

RCA Mfg. Co., Inc., Camden, N. J. • A Service of the Radio Corporation of America

New York: 1270 Sixth Ave.

Chicago: 589 E. Illinois St.

Atlanta: 490 Peachtree St., N. E.

Dallas: 2211 Commerce St.

San Francisco: 170 Ninth St.

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

The AEROVOX

RESEARCH WORKER

APRIL, 1937

L. 9, NO. 4

Inverse Feedback, Its Benefits and Its Limitations

By the Engineering Department

Engineering for James
Stabilized Feed
S. Black. S
subject are
sign by


part of
and need
are hereby
permission to
in whole or
with proper
to the Aerovox
eration, the con-
of this issue of
Aerovox Research
Worker.

rent, i. passing
result is that
condenser C2
e with the ve
The phas
vector dia

the
current
phase
stand
gh
se

path for the diode
It should not comp
a choke is placed in
path is completed thro
C3 and the primary of the
to B plus.

Automatic volume co
voltages are taken from
B. These can be obtai
of the position of Switc
a.v.c. systems can be emp
ping R1 but care must be
unbalance the circuit for
placed in parallel with at
tor. R2 will have to be c
ordingly.



Taking the audio voltage from the
same tube has the advantage of
what S



TIMELY

In addition to condensers and essential resistors, AEROVOX provides vital data. Each month the RESEARCH WORKER brings you the latest technical data from engineering dept. and lab. Practical. Unbiased. Indispensable. Thousands read it.




If you are not now reading the RESEARCH WORKER each month, write for sample copy TODAY.



70 Washington St. Brooklyn, N. Y.

WHERE THERE MUST BE NO FAILURES



CORNELL - DUBILIER CAPACITORS

Here She Comes . . . 726 . . .

Mike Callahan's "Baby" out of Chicago

In dispatch to-ers along the run, messages tick over the wires day and night to keep the nation's trains on split-second schedule . . . protect the lives of sleeping passengers and safeguard the food you'll have tomorrow.


There Must Be No Failures

Instrumental in transmitting these messages, by telephone and telegraph, by radio and interlocking sound system, CORNELL-DUBILIER capacitors have met the test of a lifetime! In all the long, thundering years of railroading, C-D capacitors have established a record for on-the-job dependability and proven performance. That is why purchasing agents for the nation's railroads continue to specify C-D capacitors. One more reason why engineers on every continent today are standardizing on C-D.

Complete listing of all C-D capacitors in catalog number one hundred and fifty, free on request.

WORLD'S LARGEST AND OLDEST EXCLUSIVE
MANUFACTURERS OF CAPACITORS

Cornell-Dubilier Electric Corporation
1000 Hamilton Boulevard S. Plainfield, N.J.



CORNELL - DUBILIER ELECTRIC CORP.

South Plainfield, New Jersey



The Institute of Radio Engineers

Incorporated

330 West 42nd Street, New York, N.Y.

APPLICATION FOR ASSOCIATE MEMBERSHIP

(Application forms or other grades of membership are obtainable from the Institute)

To the Board of Directors

Gentlemen:

I hereby make application for Associate membership in the Institute of Radio Engineers on the basis of my training and professional experience given herewith, and refer to the members named below who are personally familiar with my work.

I certify that the statements made in the record of my training and professional experience are correct, and agree if elected, that I will be governed by the constitution of the Institute as long as I continue a member. Furthermore I agree to promote the objects of the Institute so far as shall be in my power, and if my membership shall be discontinued will return my membership badge.

.....
(Sign with pen)

.....
(Address for mail)

.....
(Date)

.....
(City and State)

Sponsors:

(Signature of references not required here)

Mr. Mr.

Address Address

City and State City and State

Mr.

Address

City and State

The following extracts from the Constitution govern applications for admission to the Institute in the Associate grade:

ARTICLE II—MEMBERSHIP

Sec. 1: The membership of the Institute shall consist of: * * * (c) Associates, who shall be entitled to all the rights and privileges of the Institute except the right to hold any elective office specified in Article V. * * *

Sec. 4. An Associate shall be not less than twenty-one years of age and shall be a person who is interested in and connected with the study or application of radio science or the radio arts.

ARTICLE III—ADMISSION AND EXPULSIONS


Sec. 2: * * * Applicants shall give references to members of the Institute as follows: * * * for the grade of Associate, to three Fellows, Members, or Associates; * * * Each application for admission * * * shall embody a full record of the general technical education of the applicant and of his professional career.

ARTICLE IV—ENTRANCE FEE AND DUES

Sec. 1: * * * Entrance fee for the Associate grade of membership is \$3.00 and annual dues are \$6.00.

ENTRANCE FEE SHOULD ACCOMPANY APPLICATION

MR.
Engineer



WE CAN FILL YOUR ORDER FROM A
Blueprint!

If you are stuck with a "tough one" . . . some particular piece of radio equipment you need, and can't get anywhere, it's dollars to doughnuts **WHOLESALE RADIO SERVICE** has it. But if it isn't in stock, we'll build it for you, exactly to specifications. *Wholesale can do it* - we're doing it every day for radio engineers from Siam to Seattle. Maybe that explains why Wholesale has complete stocks today of over 50,000 radio items, why this is the "Largest Radio Supply House in the World."

Perhaps you have a problem right now holding up your progress . . . some midget part, some special equipment, or the whole thing may still be in the drawing board stage. Then consult **WHOLESALE RADIO SERVICE**.

Our staff of trained technicians *know their blueprints*. They are highly experienced men, carefully trained to interpret the requirements of engineers. Use their services. There is no obligation on your part.

We suggest you send today for the 1938 Wholesale Catalog. It will make your next problem a whole lot simpler, because this catalog is the most complete radio reference book you have ever seen. It's **FREE**. Mail the coupon today!



YOURS FOR THE ASKING
MAIL COUPON NOW
FOR Free CATALOG

PASTE COUPON ON PENNY POST CARD
WHOLESALE RADIO SERVICE CO., Inc.
100 Sixth Avenue, New York, N. Y.
Rush FREE 1938 Catalog No. 69-13K7

NAME.....

ADDRESS.....

CITY..... STATE.....

WHOLESALE RADIO SERVICE CO. INC.
NEW YORK, N. Y. CHICAGO, ILL. ATLANTA, GA.
100 SIXTH AVENUE 901 W. JACKSON BLVD. 430 W. PEACHTREE ST., N. W.
BOSTON, MASS. BRONX, N. Y. NEWARK, N. J. JAMAICA, L. I.
170 FEDERAL STREET 542 E. FORDHAM RD. 219 CENTRAL AVENUE 90-08 166th STREET

INDEX TO ADVERTISEMENTS

A	
Aerovox Corporation	XVII
American Telephone & Telegraph Co. XI	
C	
Central Radio Laboratories	XXIV
Cornell-Dubilier Electric Corp.	XVII
E	
Eric Resistor Corporation	XXIII
G	
General Radio Company	Cover IV
I	
International Resistance Company ..	XII
Isolantite, Inc.	Cover III
M	
Marconi-Ekco Instruments Ltd.	XIV
R	
RCA Manufacturing Company, Inc. XVI	
T	
Triplett Electrical Instrument Co. .	XIII
W	
Western Electric Co.	XV
Wholesale Radio Service Co.	XXI

ENGINEER WANTED

MECHANICAL DESIGNER required by leading British radio manufacturers to take responsibility for the development of mechanical features. Long experience of mass production in senior position (not necessarily radio experience) essential. Reply to Box No. 180, c/o The Institute of Radio Engineers, 330 West 42nd Street, New York, N.Y., U.S.A.

ENGINEERING POSITIONS

Advertisements on this page are accepted from organizations interested in employing Institute members. Information on rates, preparation of material, and closing dates will be mailed on request.

THE INSTITUTE OF RADIO ENGINEERS

330 West 42nd Street
NEW YORK, N.Y.

ENGINEERING DIRECTORY

QUARTZ CRYSTALS

for Standard or Special
Radio Frequency Applications

Write for Catalog

BLILEY ELECTRIC CO.

230 Union Station Bldg.
BRIDGEMAN, PENNA.

Cathode Ray Tubes
and Associated
Equipment For All
Purposes

*Write for Complete
Technical Data*

**ALLEN B. DUMONT
LABORATORIES**
UPPER MONTCLAIR, N.J.

PRACTICAL RADIO ENGINEERING

One year Residence Course
Advanced Home Study Course
Combined Home Study-Residence
Course

Write for details

**Capitol Radio Engineering
Institute**
Washington, D.C.

"Q" - Measurements


We specialize in equipment for
the radio frequency measurement
of "Q" (X/R) of coils, condensers
and other radio components.

Write for Circular

BOONTON RADIO CORPORATION
BOONTON, NEW JERSEY



When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

with **PATENTED**
ERIE *insulated* **RESISTOR**
CONSTRUCTION



GREATER

MECHANICAL STRENGTH



Recent tests conducted by our engineering department show that $\frac{1}{4}$ watt ERIE Insulated Resistors can withstand an average pull of 32 pounds before failure occurs. Because of the rigid construction of ERIE Insulated Resistors, fracture occurs in the tinned-copper lead wires without damaging or open-circuiting the interior of the unit. This type of wire is used because of its superior electrical properties and the ease with which it can be soldered.

Similar tests run under identical conditions on six competitive makes of $\frac{1}{4}$ watt insulated units showed wide variations in mechanical strength. The average pull at which failure occurred in these units is indicated by the arrows on the testing machine illustrated at the left.

Patented construction of ERIE Insulated Resistors gives you this extra margin of safety against open-circuiting during or after installation in the chassis.

**CARBON RESISTORS
 AND SUPPRESSORS**

**ERIE RESISTOR
 CORPORATION**


**AUTOMATIC INJECTION
 MOLDING**

TORONTO ERIE, PENNSYLVANIA LONDON

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.




"Centralab is the difference between a satisfied customer and a dissatisfied one."



says

George Rohr.



THE SMOOTH CENTRALAB CONTROL

offers maximum resistor length for case diameter . . . close uniformity between resistors . . . accurate tapers . . . uniform current distribution . . . better power dissipation and longer life.

Mr. George Rohr of 67 Thorne St., Jersey City, N.J. hands us the above bouquet along with some other very flattering statements in a recent letter!

Thanks, Mr. Rohr . . . thousands of other servicemen feel the same way about Centralab.

In fact, set manufacturers and experimenters as well as service men have for years shown their preference for Centralab . . . and they have said it with generous orders. We suggest, you too, specify **CENTRALAB**.

CENTRALAB Div. Globe-Union Mfg. Co. Milwaukee, Wis.


Centralab

Canterbury Rd., Kilburn
London, N.W. 6, England

118 Ave., Ledru-Rollin
Paris

When writing to advertisers mention of the PROCEEDINGS will be mutually helpful.

LINKING THE SHIP AND THE SHORE



ON ocean liners, thousands of miles from land, passengers maintain constant contact with friends and business associates through ship-to-shore radio. And when danger from the sea threatens liner or freighter, the piercing note of a ship's distress signal brings swift aid from Coast Guard Station or nearby steamers. In normal routine or moment of peril, radio keeps ship and shore safely linked by its invisible waves. Only the finest quality of equipment can maintain that link—and Isolantite* ceramic insulators are an important part of this equipment.

On ship and ashore, Isolantite insulators insure maximum operating efficiency of both trans-

mitter and receiver. Isolantite Coaxial transmission lines reduce interference between sending and receiving equipment. Antenna systems insulated with Isolantite decrease the hazards of salt spray, ice and wind.


Consult Isolantite engineers on insulator design problems. Their judgment is the result of long experience in the manufacture and application of ceramic insulation.

** Registered Trade-name for the products of Isolantite Inc.*

ISOLANTITE INC.

CERAMIC INSULATORS

Factory: Belleville, N. J. • Sales Office: 232 Broadway, New York, N. Y.



THIS bridge is suited to measurements of inductance up to 1,000 h. It is particularly useful for the accurate determination of

- Inductance of small coils of very low Q
- Resistance of inductors
- Ratio of a-c to d-c resistance
- Mutual inductance

It is direct reading from 1 μ h to 1 h between 60 cycles and 10,000 cycles. Its accuracy varies between 0.2 and 0.4%.

TYPE 667-A Inductance Bridge\$325.00

Write for Bulletin 175-R for complete data

GENERAL RADIO COMPANY

300 STATE STREET, CAMBRIDGE, MASSACHUSETTS

New York

Los Angeles

San Francisco