APRIL 1992

MICROSOFT FIXES AND REFINES WINDOWS Page 34

BYTE

A McGRAW-HILL PUBLICATION

Pournelle's Picks & Pans Page 83

Four-Part How-to Series

Put Multimedia to Work

NEC PowerMate Breaks Graphics Speed Record

8 Tools for LAN Backup

Compaq's Clock-Doubled Deskpro

02662 04 0 440235 0

$3.50 U.S.A./$4.50 IN CANADA
0360-5280

World Radio History

Special

All kinds of new things are cookin' for you at Gateway 2000.

We have a brand-new application software buffet. When you buy a Gateway 2000 system, you get to choose one free software package from a smorgasbord of offerings.

There's a new fax/modem card on the menu, too. It's the Gateway TelePath – a 14,400 bps modem with 9,600 bps fax capability. The card comes with WinFax Pro™ and Crosstalk® for Windows, plus a free CompuServe Basic Services trial membership, all for $195.



If you're hungry for an ultra high-performance system at a great price, take a look at our new 50MHz 486DX2 computers. Both ISA and EISA models are based on the Intel486™ DX2 dual speed processor. With a system clock frequency of 25MHz, the internal core of this CPU executes at 50MHz for a 35% increase in performance compared to a 33MHz 486DX system.

NEW

Of course we're still serving your old favorites – the hottest PCs at the best prices on the market.

Browse through our other ad in *BYTE* for all the details about what's new from Gateway 2000. When you get the scoop, the decision to buy a Gateway will be easy as pie.

GATEWAY2000

"You've got a friend in the business."

8 0 0 - 5 2 3 - 2 0 0 0

610 Gateway Drive • P.O. Box 2000 • N. Sioux City, SD 57049-2000 • 605-232-2000 • Fax 605-232-2023

©1992 Gateway 2000, Inc. All other brand and product names are trademarks or registered trademarks of their respective companies.

World Radio History

Special

Gateway 2000 – Now Serving PCs With Free Application Software!

World Radio History

World Radio History

Special

Where Can You Get The Best Byte For Your Buck?

World Radio History

While our competitors talk about getting here.



World Radio History

At SunSoft, we're there.

Introducing Solaris.®

Why wait for some yet-to-be-delivered UNIX® knock-off where networking is an afterthought? New Technology is shipping today. It has a name: Solaris. The industry's only shrink-wrapped distributed computing solution.

The Solaris CD will put distributed computing on the world's most popular RISC and CISC platforms.

The Killer Environment

The 1980s was the decade of the killer application. The 1990s is the decade of the killer environment. Solaris. Based on SunOS, the most widely used 32-bit operating system, it will incorporate UNIX SVR4 and add symmetric multiprocessing and multithreading to turbo-charge mission critical applications. And with Solaris ONC™, the network is the computer. More than one million users have experienced the power of connecting to any computer—IBM, Apple, DEC, HP.

But Solaris doesn't stop there. It integrates the robust OpenWindows™ development platform. Empowering developers to create tomorrow's distributed applications today. Allowing applications to interoperate—whether they are in the office next door or across the continent. Our present is their future. And our future is yours today. Solaris integrates an extraordinarily powerful framework for tomorrow's technologies that we call Project DOE—Distributed Objects Everywhere. A path that painlessly brings you to the future of computing. With Solaris, objects are closer than they appear.

So easy, it can't be UNIX.

Solaris: 32-bit. Virtual memory. Multitasking. Multivendor connectivity. Application interoperability. Adding this year SVR4, symmetric multiprocessing, multithreading and distributed objects. Imagine this power uniting the world's most popular SPARC and 80x86 computers in 1992. Imagine being able to access it—simply.

Imagine no more. Solaris puts all network resources at your fingertips graphically through the 3D OPEN LOOK® desktop metaphor. Magnified Help—on-line context-sensitive hypertext documentation— acts as your personal tutor. And Solaris adds DeskSet™, a suite of 15 workgroup productivity applications including Multimedia Mail with integrated voice and video capabilities and Workgroup Calendar which links groups and schedules across the world.

What's more, Solaris has all your favorite applications. Lotus 1-2-3, Ashton-Tate dBase, WordPerfect. More compatible solutions than any other 32-bit environment. More than 3600 in all.

Solaris combines 3D OPEN LOOK with your favorite applications.

To get there, start here.

A lot of companies talk about making distributed computing reality. Still more only dream about it. But at SunSoft, we've made it happen. So if you want to hear where distributed computing is going in the 90s, talk to some other manufacturers. But if you want to see where it is, call us. 1-800-227-9227

Because we're there.

SunSoft
A Sun Microsystems, Inc Business

Circle 174 on Inquiry Card.

World Radio History

BYTE

April 1992 *Volume 17, Number 4*

COVER STORY

FEATURE

Practical Desktop Video, PART 1

PAGE 106

NEWS

23 MICROBYTES
Next steps into the Intel-based world, and a powerful start-up called Rambus says "Thanks, but no thanks" for those old memories.

34 FIRST IMPRESSIONS
Windows 3.1 Is Ready to Roll
Microsoft's new release is finally ready for prime time.

◁38
Have Docking Station, Will Travel
A new Safari notebook hits the road.

41
New from Compaq: Deskpro 50M
A speedy graphics workstation from Compaq.

42 New Hard Drives Keep Your Data Safe
A new generation of hard drives are fast and ultra-reliable.

51 Cameo Personal Video System, Model 2001,
it stars on the Mac

486DX-50 Cache, a complete 50-MHz PC for $3749

Boxer Text Editing System 3.20,
a flexible shareware editor

PGC CASE Graphics 1.0,
CASE for the inquisitive

58 WHAT'S NEW
The Mpression Notebook Presentation System; the Silentwriter Model 95; Project Manager; and more.

FEATURES

106 Practical Desktop Video, Part 1
The BYTE Multimedia Lab's series on desktop video production begins with a look at video formats.

119 Windows Goes Real Time
The iRMX for Windows operating system provides the best of both worlds on a single PC.

STATE OF THE ART

134 AN INTERFACE FOR ALL SENSES
Overview: Kinder, Gentler Computing
Natural I/O technologies provide computers with the ultimate in user-friendly interfaces.

151 The Power of Speech
Automatic speech recognition is going to radically alter how you interact with computers.

165 Even As We Speak
Speech synthesis is a practical and valuable computer-output format.

175 The Ultimate User Interface
Information systems create environments in which we work. New research aims to allow better design of these information systems.

187 Resource Guide: Natural I/O



COVER PHOTOGRAPHY MARK ROCKWOOD © 1992

World Radio History

HOT NEW ZEOS '386

PC Magazine calls it "the ultimate-power desktop PC." What will you call your new *ZEOS '486 Editors' Choice* system? Probably the hottest computer you've ever owned! No matter how much power you're looking for, ZEOS has it for you.

ANNOUNCING THREE HOT NEW PROCESSOR OPTIONS: '486SX-25, '486DX2-50 AND '486DX-50!

Go ahead and Pick your Power! ZEOS gives you all the options. You can start out by taking a look at the de facto desktop power standard, the 386DX-33. Our '386-33 workhorse is a great entry point for true desktop power computing. But if it's a '486 you're after, hang on to your hat!

Upgradable.

Because you're off to a fast start with a 486SX-20 or our brand-new 486SX-25. The 486SX is like a 486DX without the built-in math co-processor. It's the easiest way to own the '486. And for full blown 486*DX* power, why not opt for your own *Editors' Choice* system!

It's the ZEOS *Editors' Choice* 486DX-33. Quite simply, there is nothing else like it. Go with the ZEOS '486 if you want the type of quality, performance and value that makes an *Editors' Choice* machine. And if it's *50MHz* you've been dreaming about, dream no more.

Because right here, right now, ZEOS gives you the option of '486 50MHz power! We're talking power unlike anything you've seen before. Take either the ZEOS 486DX2-50 or the 486DX-50. Absolutely unbelievable *performance!* And the price? That's what you really won't believe; only a couple hundred dollars more than the ZEOS 486-33. *Amazing.*

AND THAT'S JUST FOR STARTERS.

Because ZEOS combines the high speed upgradable processor of your choice with some of the fastest DRAM made. Both

World Radio History

REVIEWS

192 SOLUTIONS FOCUS
New LAN Backup Tools
The BYTE Lab looks at eight tape backup systems that promise to make your network safe and sound.

212 Rough Gems: First Pen Systems Show Promise, Lack Refinement
The first pen-input systems will need to overcome some technical hurdles.

226 BYTE Lab Product Report: Art for Business's Sake
One of these packages is sure to make it easier for you to create good-looking pictures, charts, and graphs.

259 LAN Manager 2.1 Opens the Gates
Microsoft's latest showcases TCP/IP, remote access, Mac services, and NetWare connectivity.

262 New MultiSyncs Prove That Flatter Is Better
NEC updates the MultiSyncs with four new monitors.

267 Video Goes Digital with Fluency
Developers get a head start with this digital-video bundle for PCs.

269 Local Bus Fuels PowerMate's Graphics Response
NEC's local-bus design delivers outstanding graphics performance.

272 REVIEWER'S NOTEBOOK
A superfast super server and wireless print sharing.



HANDS ON

279 SOME ASSEMBLY REQUIRED
Mac Programming Revealed
The Mac *is* easy to program, within limits.

291 UNDER THE HOOD
Wireless Networking
New technologies and standards portend the era of mobile computing.

295 SOFTWARE CORNER
Batch-File Toolkit
Better automation for DOS and Unix, and a way to hunt down Mac viruses.

297 BEYOND DOS
Inside 386 Enhanced Mode
by Martin Heller
Under the covers of Windows 386 enhanced mode.

299 ASK BYTE
Getting *less* from VGA, Windows batch-file botches, high-resolution graphics for BASIC, and other topics.



BYTE (ISSN 0360-5280/92) is published monthly with an additional issue in October by McGraw-Hill, Inc. U.S. subscriber rate $29.95 per year. In Canada and Mexico: $34.95 per year. European surface mail subscriptions $50; airmail $70. Non-European subscriptions: $50 surface mail or $75 airmail. All foreign subscriptions are payable in U.S. funds that can be drawn on a U.S. bank. Single copies $3.50 in the U.S., $4.50 in Canada. Executive, Editorial, Circulation, and Advertising Offices: One Phoenix Mill Lane, Peterborough, NH 03458. Second-class postage paid at Peterborough, NH, and additional mailing offices. Postage paid at Winnipeg, Manitoba. Registration number 9321. Printed in the United States of America. **Postmaster:** Send address changes, USPS Form 3579, and fulfillment questions to BYTE Subscriptions, P.O. Box 552, Hightstown, NJ 08520.

COVER CORNER PHOTOGRAPHY: MEL LINDSTROM © 1992

OPINIONS

83 USER'S COLUMN
User's Choice Awards
by Jerry Pournelle
Jerry issues his annual User's Choice Awards.

99 ROUNDTABLE
The Future of Pen Computing, Part 2
Pen-software and systems developers discuss the limits of handwriting recognition, display technology, and other issues.

366 PRINT QUEUE
Ways to Keep It Lucid
Designing better documents, Windows programming, and object-oriented technology explained.

368 STOP BIT
Hidden Persuaders
The computer you use determines how you work—and how you think.

10 EDITORIAL
Pen-Input Systems

14 LETTERS
Kudos for classic languages, and questions about OS/2.

READER SERVICE
364 Editorial Index by Company
361 Alphabetical Index to Advertisers
362 Index to Advertisers by Product Category
Inquiry Reply Cards: **359**

PROGRAM LISTINGS
From BIX: Join "listings/frombyte92"
From Demolink: See ad on page **365**
On disk: See ad on page **271**

INSIDE BYTE

ABOUT THE COVER
This month's cover was created by photographer Mark Rockwood in collaboration with ImageSet Design (Portland, ME). Three separate photos, a video camera, and a monitor and keyboard were scanned, color-corrected, and manipulated using state-of-the-art hardware and software from Scitex, Adobe, and Quark. Film was generated with an Agfa Selectset 5000 Imagesetter.

This "Ultimate-Power Desktop PC" was chosen Editors' Choice.

Here's why.

MAGAZINE EDITORS' CHOICE 2-11-92

World Radio History

AND '486 SYSTEMS!

ZEOS. Nine times Editors' Choice. Your Best Choice as Well!

are mounted on your ZEOS system board, one of the most advanced in the industry. And that's where your new system really begins to shine.

Because to this we add an *incredibly fast* IDE hard drive and genuine Teac® floppy drives. We have located the ports for these drives right on the motherboard along with your serial, parallel and game ports. The result? Two slots are saved giving your new ZEOS system a total of *eight*. All this while others

Low Cost.

are trying to get you to accept fewer slots. It's part of your ZEOS expansion advantage. The slots to expand, how about the room?

This is where ZEOS has performed something akin to magic. We call it our SpaceSaver case. Complete with *seven* drive bays (six with the DX-50), this incredible case is actually smaller than many cases offering only five drive bays. Plus, we've also added a *second whisper quiet cooling fan*. Why? Because the cooler a system runs the longer it will last. Now that's ZEOS Value.

Your new ZEOS system is absolutely loaded with features. Like our 300 watt power supply with *built-in surge suppression*. And, every ZEOS system is UL® listed.

And don't forget you're also receiving 24 Hour a Day Toll Free Technical Support, our 30 day Absolute Satisfaction Money Back Guarantee, Express Parts Replacement and more.

So go ahead. Pick your Power, your Package, and your Price and give us a call. Your friendly, expert ZEOS Systems Consultant is ready to answer any questions you may have. *Call Now Toll Free 800-423-5891.*

ZEOS SYSTEMS— A FEW EXPERT OPINIONS:

PC Magazine, **"Out of 104 machines from 58 companies...For Overall Excellence we selected ZEOS International..."**

InfoWorld, **"We find the ZEOS '386 an excellent value. Speed: Excellent. Compatibility: Excellent. Value: Excellent."**

Government Computer News, **"Arguably the fastest MS-DOS and OS/2 micro in the world."**

PC Magazine, Editor's Choice, **"The ZEOS blows away every other computer...a smart choice."**

ZEOS SYSTEMS. A SMART CHOICE INDEED!

ORDER NOW TOLL FREE 800-423-5891

TAKE YOUR PICK!

Choose From 4 Great Money Saving Packages.

Or Specify Your Own Custom Configuration!

ZEOS COMPLETE SYSTEM PACKAGE #1
- The Processor and Speed of your choice plus future upgradabilty!
- 1MB of High Speed RAM, expandable to a system total of 32MB right on the motherboard.
- 42MB High Speed IDE hard drive with its own cache.
- 1.2MB or 1.44MB Teac® floppy drive.
- ZEOS 14" flat screen Hi-Res amber monitor with Tilt/Swivel Base.
- Shadow RAM and EMS support.
- ZEOS/RS 101-key SpaceSaver keyboard.
- Two Serial, one Parallel & one Game Port built right onto the motherboard.
- 7-16, 1-8 bit expansion slots. 80387 math coprocessor support for '386 systems.
- Rugged ZEOS SpaceSaver case with twin cooling fans for added reliability and product life.
- Seven drive bays and our custom 300 watt power supply with built-in surge suppressor!
- Includes ZEOS 24 Hour a Day Toll Free Technical Support and Customer Satisfaction Package.

INCREDIBLE ZEOS PACKAGE #3
Add even more memory, a larger drive. And more Savings!
- 4 full Megabytes of Ultra High Speed RAM.
- Our fast 130MB IDE hard drive with built-in cache.
- Teac® 1.2MB & 1.44MB FDD's!
- Diamond SpeedStar Hi-Color VGA card/1MB RAM (32,000+ colors) plus WinRIX drawing software!
- ZEOS 14" High Res 1024 x 768 Non-interlaced VGA Color Monitor w/ Tilt & Swivel.
- Lotus 1-2-3 for Windows, Ami Pro 2.0 with Adobe Type Manager, Microsoft Windows, DOS 5.0 *plus* a Microsoft Mouse!

PACKAGES 2, 3 & 4 INCLUDE LOTUS BUNDLE!

	Pkg. #1	Pkg. #2	Pkg. #3	Pkg. #4
386-33	$1395	$1895	$2395	$2895
486-SX20	$1595	$2095	$2595	$3095
486SX-25	$1695	$2195	$2695	$3195
486DX-33	$1795	$2295	$2795	$3295
486DX2-50	$1995	$2495	$2995	$3495
486DX-50	$2195	$2695	$3195	$3695

Add $200 to any price for a 128K cache. 486DX-50 SpaceSaver case has 6 bays.

THE ULTIMATE ZEOS PACKAGE #4
Now, Memory goes to 8MB and the drive to 210MB. *PC Magazine Editors' Choice* as a 486DX-33 Vertical!
- 8 full Megabytes of High Speed RAM.
- Your screaming 210MB IDE hard drive with its own built-in cache.
- Teac® 1.2 & 1.44MB FDD's!
- Diamond Speedstar Hi-Color VGA card/1MB RAM (32,000+ colors) plus WinRIX drawing software!
- ZEOS 14" 1024 x 768 Non-interlaced VGA Color Monitor w/ Tilt & Swivel.
- Lotus 1-2-3 for Windows, Ami Pro 2.0 with Adobe Type Manager, Microsoft Windows, DOS 5.0, Microsoft Mouse!

INCREDIBLE ZEOS PACKAGE #2
We take Package #1 and upgrade your ZEOS Modular System to include:
- 2 full Megabytes of Rip-roaring RAM.
- Our incredible 107MB IDE hard drive with its own built in cache.
- Both the Teac® 1.2MB & 1.44MB floppy drives!
- Diamond SpeedStar Hi-Color VGA card/1MB RAM & Sierra DAC plus WinRIX drawing software!
- ZEOS 14" Hi Res VGA Mono Monitor with Tilt & Swivel Base.
- Lotus 1-2-3 for Windows, Ami Pro 2.0, *plus* Microsoft Windows and DOS 5.0, *plus* a genuine Microsoft Mouse!

Lotus Software Bundle!

For a limited time only, order any ZEOS Windows system (like packages 2, 3 and 4 above) and we will also include Lotus 1-2-3 for Windows and Ami Pro 2.0— at no additional charge!

ORDER NOW TOLL FREE
800-423-5891

FAX Orders: 612-633-1325
Gov't & Educ: 800-245-2449
Outside US and Canada: 612-633-6131
MasterCard, VISA, Am Exp, Discover, Z-Card, COD and leasing programs.
GSA #GSA00K91AGS5176
Open 24 Hours a Day, 365 Days a Year!

ZEOS INTERNATIONAL LTD

Purchase orders subject to approval. All prices and specifications are subject to change without notice. Please call to confirm pricing, specification and warranty details. Lotus 1-2-3 and Ami Pro are trademarks of Lotus Development Corporation; Microsoft and Windows are trademarks of Microsoft Corporation. Z-Card, SpaceSaver and ZEOS are trademarks of ZEOS International Ltd., 530 5th Avenue, N.W., St. Paul, MN 55112 USA © 1992.

Circle 141 on Inquiry Card.

World Radio History

INSIDE BYTE

BYTE Topic Index and Author Guide

This index helps you find articles that contain information on each of the listed topics. (The topic list changes each month.) Combined with the table of contents (page 4) and the Editorial Index by Company (page 364), you can identify articles by type, subject, title, author, or product discussed.

APPLICATIONS 58
BACKUP 192
CASE 54
DAT 197
DESKTOP 51
FAX 58
486 51, 83
FREEWARE/SHAREWARE 52, 295
GRAPHICS 41
GUIS 34, 368
HANDWRITING 134, 212
HARD DRIVES 42
INPUT 151
INTERFACE 272
IRMX 119
LAPTOPS/NOTEBOOKS/PORTABLES 38, 212
MACINTOSH 51
MEMORY 23
MODEMS 58
MONITORS 262
MOTHERBOARDS 58
MULTIMEDIA 34, 51, 106, 267
MULTISCANNING 262
MUSIC 137
NATURAL I/O 134
NETWORKS 58, 192, 259, 291
NEXT 23
OS/2 259
PAINT 226
PATTERN RECOGNITION 151
PCMCIA 99, 212
PEN PC 99, 212
PRESENTATION GRAPHICS 106, 226
PRINTERS 58
PRINT SERVER 58
PROGRAMMING 58, 279, 295, 297, 366, 368
PROJECTION PANEL 58
PUBLISHING 366
REAL TIME 119
RISC 23
SCSI 42
SERVER 259
SPEECH 134, 151, 165, 187
SUPER VGA 262
386/386SX 269, 299
TRACKERS 148
UTILITIES 192, 272
VIDEO 51, 106, 267, 269
VIRTUAL REALITY 175
VOICE 187
WINDOWS 34, 119, 297
WIRELESS 291
WORKSTATIONS 41

AUTHORS

Alford, Roger C. 197
Allen, Dennis 10
Andrews, D. L. 23
Apiki, Steve 269
Baran, Nicholas 23, 99, 212, 291
Barker, D. 226
Bhasker, Narjala 119
Brain, Marshall 368
Bricklin, Dan 99
Caudill, Maureen 134
Cook, Rick 23
Côté, Raymond GA 52, 54, 226
Dao, Jeff 99
Das, Subrata 151
Diehl, Stanford 192
Edwards, David L. 226
Eglowstein, Howard 192
Gerber, Rick 119
Heller, Martin 297
Holloway, Richard 180
Jacobson, Bob 175
Joch, Alan 262
Katz, Neil 99
Kenner, Hugh 366
Kurzweil, Raymond C. 156
Lazzaro, Joseph J. 165
Liffick, Steve 99
Linderholm, Owen 23
Loeb, Larry 23
Machover, Tod 137
Malloy, Rich 38, 41
Marcus, Beth 148
Mentley, David 99
Miastkowski, Stan 42, 52
Nadas, Arthur 151
Nance, Barry 295
Pournelle, Jerry 83
Rajamani, Krishnan 119
Sheldon, Kenneth M. 23, 51
Smith, Ben 23, 295
Snyder, Steve 119
Swartz, Carol J. 58
Thompson, Tom 226, 279, 295
Udell, Jon 34, 259
Ullman, Ellen 23
Verhaeghe, Bart 158
Waterfield, Amanda L. 58
Wszola, Stan 226
Yager, Tom 35, 106, 192, 267
Zimmerman, Jan 168

BYTE

EDITOR IN CHIEF
Dennis Allen

PUBLISHER
Ronald W. Evans

EXECUTIVE EDITORS
New York: Rich Malloy
Peterborough: Michael Nadeau

MANAGING EDITOR
Anne Fischer Lent

ASSISTANT MANAGING EDITOR
Lauren A. Stickler

NEWS
New York:
News Editor: Andrew Reinhardt
Peterborough:
Sr. Ed., New Products: Stan Miastkowski
News Editors, What's New: Martha Hicks, Carol Swartz, Amanda Waterfield
Microbytes: D. L. Andrews
San Francisco/West Coast:
Bureau Chief: Kenneth M. Sheldon
Sr. News Editor: Owen Linderholm
Editorial Assistant: Barbara J. Caravello
UK/Europe: *Bureau Chief:* Andrew Redfern

BYTE LAB
Senior Editor & Director. Alan Joch
Technical Director: Rick Grehan
Technical Editors:
Stephen Apiki: *systems, networking*
D. Barker: *applications software*
Rich Friedman: *graphics software, add ins, peripherals*
Tom Yager: *multimedia, Unix, operating systems, software development*
Testing Editors/Engineers: Raymond GA Côté, Stanford Diehl, Howard Eglowstein, Stanley Wszola
Lab Assistant: Selinda Chiquoine

STATE OF THE ART/FEATURES
Senior Editor: John W. Donovan
Technical Editors: Janet J. Barron, Robert M. Ryan, Ben Smith

SENIOR TECHNICAL EDITORS
At Large: Tom Thompson, Jon Udell
Columns: Rob Mitchell
Special Projects: Gene Smarte

ASSOCIATE TECHNICAL EDITORS
Ellen Bingham, Susan Colwell, Jeff Edmonds, Tom Kevan, Cathy Kingery, Margaret A. Richard, Warren Williamson

SENIOR CONTRIBUTING EDITOR
Jerry Pournelle

CONTRIBUTING EDITORS
Hugh Kenner, Barry Nance

CONSULTING EDITORS
Roger C. Alford, Jonathan Amsterdam, Nicholas Baran, Don Crabb, David Fiedler, Laurence H. Loeb, Trevor Marshall, Mark J. Minasi, Dick Pountain, Wayne Rash Jr., Phillip Robinson, Jane Morrill Tazelaar, Ellen Ullman, Peter Wayner

EDITORIAL ASSISTANTS
Office Manager: Peggy Dunham
Assistants: Linda C. Ryan, June Sheldon

DESIGN
Director: Nancy Rice
Associate Director: Joseph A. Gallagher
Designer: Jan Muller
Assistant Designer: Rebecca Magill

PRODUCTION AND FINANCE
Director: Claudia Flowers

PRODUCTION
Director: David M. Cohen
Production Manager: David R. Anderson
Senior Editorial Production Coordinator: Virginia Reardon
Editorial Production Coordinator: Barbara Busenbark
Systems Manager: Sherry Fiske
Applications Manager: Donna Sweeney
Typesetter: Christa Patterson
Creative Services Mgr: Susan Kingsbury
Production Artist: Lillian J. Wise
Advertising Services Manager: Linda Fluhr
Senior Advertising Services Representative: Lyda Clark
Advertising Services Representatives. Dale J. Christensen, Karen Cilley, Rod Holden
Advertising Services Assistant. Roxanne Hollenbeck
Quality Control Manager: Wai-Chiu Li
Operations Assistant. Christine Tourgee

FINANCE
Business Manager: Kenneth A. King
Assistants: Marilyn Parker, Diane Henry, JoAnn Walter, Jeanne Gatcombe, Jaime Huber, Agnes Perry

MARKETING AND PLANNING
Director. L. Bradley Browne
Administrative Assistant. Carol Cochran
Marketing Communications Manager. Pamela Petrakos
Public Relations Mgr: Dawn Matthews
Asst. Promotion Manager. Lisa Jo Steiner
Marketing Art Dir.: Stephanie Warnesky
Associate Art Director: Sharon Price
Market Research Manager. Julie Perron
Copyrights Manager: Faith Kluntz
Reader Service: Cynthia Sands
Marketing Assistant: Carol Sanchioni

CIRCULATION
Director: Glyn Standen
Subscriptions Manager. Paul Ruess
Assistant Manager. Pam Wilder
Subscriptions Assistant: Holly Zilling
Newsstand Manager: Vicki Weston
Assistant Manager: Karen Desroches
Back Issues: Louise Menegus
Direct Accounts Coordinator: Ellen Dunbar

Publisher's Assistant: Donna Nordlund

ADVERTISING SALES
National Sales Manager: Jennifer L. Bartel (214) 701-8496

NEW ENGLAND
Daniel D. Savage (617) 860-6344

EAST COAST
Kim Norris (212) 512-2645
Ariane Casey (212) 512-2388

SOUTHEAST
John Schilin (404) 843-4782

MIDWEST
Kurt Kelley (312) 616-3328

SOUTHWEST, ROCKY MOUNTAIN
Jennifer Walker (214) 701-8496

SOUTH PACIFIC
Beth Dudas (714) 753-8140
Alan El Faye (213) 480-5243

NORTH PACIFIC
Bill McAfee (408) 879-0381
Roy J. Kops (415) 954-9728
Leslie Hupp (415) 954-9705

INSIDE ADVERTISING SALES
Director: Liz Coyman (603) 924-2518
Assts.: Susan Monkton, Vivian Bernier

NATIONAL ADVERTISING SALES
Mary Ann Goulding (603) 924-2664
Patricia Payne (603) 924-2654
Jon Sawyer (603) 924-2665
Barry Echavarria (603) 924-2574

THE BUYER'S MART (1x2)
Joseph Mabe (603) 924-2656

HARDWARE/SOFTWARE SHOWCASE
Ellen Perham (603) 924-2598
Mark Stone (603) 924-2695

REGIONAL ADVERTISING SECTIONS
Brian Higgins (603) 924-2651
Barry Echavarria (603) 924-2574
Larry Levine (603) 924-2637

BYTE DECK
Ed Ware (603) 924-2596

EURO-DECK
James Bail (603) 924-2533

INTERNATIONAL ADVERTISING SALES STAFF
See listing on page 363.

PERSONNEL
Human Resources Admin.: Patricia Burke
Assistant. Fran Wozniak
Receptionist. Beverly Goss

HOW TO CONTACT THE EDITORS

We welcome your questions, comments, complaints, kudos, and submissions.
MAIN OFFICE: One Phoenix Mill Lane, Peterborough, NH 03458, (603) 924-9281.
WEST COAST: 425 Battery St., San Francisco, CA 94111, (415) 954-9718; 15635 Alton Pkwy., Suite 290, Irvine, CA 92718, (714) 753-8140.
NEW YORK: 1221 Avenue of the Americas, New York, NY 10020, (212) 512-3175
UK/EUROPE: Wimbledon Bridge House, One Hartfield Rd., Wimbledon, London SW19 3RU, England, 011-44-81-543-1234.
ELECTRONIC MAIL: On BIX, send to "editors." All BYTE editors and columnists also have individual mailboxes on BIX for easy access.
MCI: 250-0135 BYTE Magazine. Many editors also have individual MCI addresses in their own name.
OTHERS: Many editors also are reachable through uunet, AppleLink, CompuServe, and numerous other services.
U.S. fax: Editorial: (603) 924-2550
Advertising: (603) 924-7507
U.K. fax: 011-44-81-540-3833

SUBMISSIONS
Authors: We welcome article proposals and submissions. Unacceptable manuscripts will be returned if accompanied by sufficient return postage. Not responsible for lost manuscripts or photos.
Vendors: We welcome news of your new products; please call the News department or the BYTE Lab at the earliest possible date. We cannot be responsible for unsolicited product samples.

SUBSCRIPTION CUSTOMER SERVICE

Inside U.S. (800) 232-BYTE; outside U.S. (609) 426-7676. For a new subscription—(800) 257-9402 U.S. only, or write to BYTE Subscription Dept., P.O. Box 555, Hightstown, NJ 08520. Subscriptions are $29.95 for one year, $54.95 for two years, and $74.95 for three years in the U.S. and its possessions. In Canada and Mexico, $34.95 for one year, $64.95 for two years, $87.95 for three years. In Europe, £29 (U.S. $50) for fast surface delivery, £41 (U.S. $70) for air delivery. Non-European countries U.S. $50 for surface mail, or U.S. $75 for air mail. Single copy price is $3.50 in the U.S. and its possessions, $4.50 in Canada. Foreign subscriptions and sales should be remitted in U.S. funds drawn on a U.S. bank. Please allow six to eight weeks for delivery of first issue.

PHOTOCOPY PERMISSION:
Where necessary, permission is granted by the copyright owner for those registered with the Copyright Clearance Center (CCC), 27 Congress St., Salem, MA 01970, to photocopy any article herein for personal or internal reference use only for the flat fee of $1.50 per copy of the article or any part thereof. Correspondence and payment should be sent directly to the CCC, 27 Congress St., Salem, MA 01970. Specify ISSN 0360-5280/92, $1.50. Copying done for other than personal or internal reference use without the permission of McGraw-Hill, Inc., is prohibited. Requests for special permission or bulk orders should be addressed to the publisher. BYTE is available in microform from University Microfilms International, 300 North Zeeb Rd., Dept. PR, Ann Arbor, MI 48106, or 18 Bedford Row, Dept. PR, London WC1R 4EJ, U.K.

Copyright © 1992 by McGraw-Hill, Inc. All rights reserved. BYTE and BYTE are registered trademarks of McGraw-Hill, Inc. Trademark registered in the United States Patent and Trademark Office.

Member
Audit Bureau of Circulation

BIX BYTE INFORMATION EXCHANGE

DIRECTOR
Stephen M. Laliberte

MANAGING EDITOR
Tony Lockwood

DEMOLINK
BYTE program listings are available at (617) 861-9767 (set modem at 8-1-N, 2400 or 1200 bps). Enter Demolink.

MICROBYTES DAILY
Coordinator: D. L. Andrews, *Peterborough*
Rich Malloy, *New York*
Nicholas Baran, *Sandpoint, ID*
Laurence H. Loeb, *Wallingford, CT*
Rick Cook, *Phoenix, AZ*
Stephen Banker, *Washington, DC*
David Reed, *Lexington, KY*
Andrew Reinhardt, *New York*

EXCHANGE EDITORS
Amiga Exchange: Joanne Dow
Entertainment and Leisure Exchange: Rich Taylor
IBM Exchange: Barry Nance
Macintosh Exchange: Laurence H. Loeb
Programmers Exchange: Bill Nicholls
Professionals Exchange: David Reed
Tojerry Exchange: Jerry Pournelle
Writers Exchange: Wayne Rash Jr.

BIX, the "BYTE Information Exchange," (operated by General Videotext Corporation), is a worldwide, low-cost, on-line information service featuring industry news, downloadable software, powerful electronic mail, previews of upcoming BYTE articles, the full text of published issues of BYTE, and source and/or executable code for BYTE benchmarks and noncommercial software mentioned in feature articles. BIX also offers unmatched "conferences" on virtually every computer-related topic imaginable, where you can share information with thousands of other computer pros. To subscribe via modem, set your communications software to full duplex, 7 bits, even parity, 1 stop bit, and then call 800-225-4129; in MA, call (617) 861-9767. International, call NU1310690157800. Then hit the Enter/Return key and enter "BIX" when asked to log in; then enter "BIX.VILLE" when asked for a name. For current fees and more information, call (800) 227-2983 or (617) 354-4137 on voice phone.

OFFICERS OF MCGRAW-HILL, INC.:
Founder: James H. McGraw (1860–1948).
Chairman, President and Chief Executive Officer: Joseph L. Dionne, *Executive Vice President, General Counsel and Secretary:* Robert N. Landes, *Executive Vice President:* Walter D. Serwatka, *Senior Vice President, Treasury Operations:* Frank D. Penglase, *Executive Vice President and Chief Financial Officer:* Robert J. Bahash, *Executive Vice President, Administration:* Thomas J. Sullivan, *Senior Vice President, Corporate Affairs, and Executive Assistant to the Chairman:* Mary A. Cooper, *Senior Vice President, Editorial:* Ralph R. Schulz.

World Radio History

WordPerfect users prefer Microsoft Word for Windows.

NSTL TEST RESULTS, DECEMBER 1991

	Word for Windows	WordPerfect for Windows
Preferred to use	79%	21%
Easier to learn	71%	21%
Easier to use	83%	13%
Would purchase	79%	21%



In a recent test conducted by the National Software Testing Labs, nearly 8 out of 10 users of WordPerfect® for DOS preferred Microsoft® Word for Windows™ 2.0. They not only discovered how fast Microsoft Word lets them accomplish everyday tasks, but they also discovered that Word is an easier upgrade to learn and use than WordPerfect for Windows. To take advantage of our $129 upgrade offer,* simply call (800) 323-3577, Dept. Y69. We'll also send you the files you need to test Word yourself. If you're not satisfied, we'll refund your purchase in full.**

Microsoft®

*Offer good for current licensees of WordPerfect, MultiMate,® WordStar,® MS® Word for MS-DOS® and DisplayWrite.® Please allow 2-4 weeks for delivery upon receipt of order by Microsoft. Offer expires 6/30/92. Limit one per customer. Reseller prices may vary. Call for system requirements. **If you're not satisfied with Word for any reason, return the product to Microsoft within 90 days with proof of purchase for a full refund. Offer good only in the 50 United States. To receive only the NSTL test results: In the United States, call (800) 323-3577, Dept. Y69. For information only: In Canada, call (800) 563-9048; outside the U.S. and Canada, call (206) 936-8661. © 1992 Microsoft Corporation. All rights reserved. Printed in the USA. Microsoft, MS, and MS-DOS are registered trademarks and Windows is a trademark of Microsoft Corporation. WordPerfect is a registered trademark of WordPerfect Corp. NSTL is a trademark of the National Software Testing Laboratories, Inc.

World Radio History

All the benefits of a laser printer

DESKTOP CONVENIENCE

RELIABILITY

LOW COST

SHARP, HIGH QUALITY OUTPUT

FAST PRINTING SPEED

PLAIN PAPER

A size

At last. A personal output device that combines the best features of a desktop laser printer with the ability to produce large C-size drawings. It's called ProTracer — a monochrome ink jet printer/plotter designed for the personal use of PC CAD professionals.

MEDIA FLEXIBILITY

ProTracer is a desktop printer/plotter that lets you produce A, B, as well as large C-size output. It prints sharp, precise lines on a variety of media including plain and bond paper, plotter paper, and vellum.

SPEED

ProTracer is fast and quiet because it uses the latest inkjet technology and an Intel i960 processor. Just compare it to any other large format plotter and you'll see. A complex C-size drawing often takes over half an hour on a pen plotter, while ProTracer completes the same drawing in only five minutes!

HIGH QUALITY OUTPUT

ProTracer achieves its high quality output by utilizing a 64 nozzle printhead to deliver crisp lines and bold, high contrast blacks. Its 360 dpi resolution assures sharp lines needed for everything from the most complex engineering drawings to sophisticated text and graphics used in letters and reports.

VERSATILE AND EXPANDABLE

Unlike other large format devices, ProTracer isn't limited to plotting. Instead, it can produce high quality finished output for a variety of

Pacific Data Products, Inc., 9125 Rehco Road, San Diego, CA 92121. ProTracer is a trademark of Pacific Data Products, Inc. PostScript is a registered trademark of Adobe Systems, Inc. All other trade names referenced are the trademarks or registered trademarks of the respective manufacturer. Nozzle image courtesy of AutoDesk Inc. Tiger rendering, artist unknown; picture part of public domain. ProTracer uses the latest in high technology innovation including PeerlessPage™, the advanced Imaging Operating System from Peerless. EUROPEAN OFFICES: Geneva Tel (41) 22 41 26 50, Fax (41) 22 41 06 82, France Tel (33) 1 39 23 20 00, Fax (33) 1 39 63 31 20, U.K. Tel (44) 442 231414, Fax (44) 442 23 65 40

World Radio History

On a much larger scale.

C size

applications including word processing, spreadsheets, and desktop publishing. Start with the ProTracer base unit that incorporates resident IBM ProPrinter and Epson LQ-1050 emulations, as well as an ADI plotter driver for AutoCAD users. Then, depending on your needs, choose from a variety of easily installable upgrades and accessories including HP-GL and PostScript® language emulations, and memory.

Optional Printer Accessories	
HP-GL emulation card	$399
PostScript language emulation card	$499
2 MB memory upgrade	$299
8 MB memory upgrade	$899
Sheet feeder I (100 sheet)	$149
Sheet feeder II * (100 sheet)	$129
PacificTalk (AppleTalk interface module)	$199

*Sheet feeder I is required for use

FIRST RATE CUSTOMER SERVICE

At Pacific Data Products, we're well known for our devotion to customer service. We offer a ***60-day money back guarantee of satisfaction,*** one year and optional extended warranties, and free lifetime technical support. Should you require a replacement unit while under warranty, one will be rushed to you the next day to minimize your downtime.

If you'd like to expand your personal printing and plotting capabilities, call Pacific Data Products at (619) 597-4619, Fax (619) 552-0889.

PACIFIC DATA PRODUCTS

© 1992 Pacific Data Products, Inc.

World Radio History

EDITORIAL

DENNIS ALLEN

PEN-INPUT SYSTEMS

Most of the excitement about pen-based computers is unwarranted. Industry gurus have been cheerleading for pen technology for well over a year, and even we carried a cover story last November on the Momenta, which promised to replace the traditional notebook computer. Yet those who are building these machines have not been deluged with orders. The reason is that pen-based systems are too expensive, don't deliver all the functionality needed, and require too much training.

Despite all the hoopla about pen-input systems, is the world ready for them?

Two paradigms get most of the attention for pen computing. In one, a pen-based system might replace the notebook computer. That is the approach taken by Momenta. The trouble is that a notebook computer is a moving target. Currently, notebook makers are transforming their products into do-everything, portable replacements for desktop systems with color, lots of power, and lots of memory and disk space.

And as if to prove once and for all that a notebook can replace a desktop system, some makers are building desktop "docking stations" to contain the components and add-in cards that don't happen to fit into the notebook itself. Then there's the whole issue of color. How can a notebook replace a desktop system if it doesn't offer high-quality color at a reasonable price? Add to all that the complexity of a pen interface and handwriting recognition, and you have a complicated piece of machinery that even NASA can't afford to build.

The other paradigm is pen computing as an adjunct to existing computers. Consider a small, highly portable computer that literally replaces a pocket-size paper notebook. The idea is that instead of writing notes on paper to later transcribe into your computer, you would simply "write" those notes on the pocket-size pen computer and later transfer that information to your desktop system.

That makes a lot of sense, but there's still one problem: The technology just isn't there yet. Building a pen system to fit into a coat pocket is not too difficult, but packing in enough power to do handwriting recognition—and remain reasonably fast—is a major hurdle for manufacturers to overcome. There's no easy way to pack, say, an alkaline-battery-powered 486 CPU with lots of memory and storage and a pen screen into a 10-ounce package that fits in your coat pocket.

Even if the engineers could, I'm not sure that you'd want to take the time to train it. Handwriting-recognition technology just isn't good enough to deal with everyone's handwriting style, so you have to teach the system how *you* write each letter of the alphabet. Even after training, most pen systems expect you to change the way you write to improve the odds of recognition.

Maybe that wouldn't be so bad if the odds weren't stacked against you. The fact is that most systems ask you to rewrite many characters so that they can be recognized. Isn't this the reason that voice recognition never caught on? If you ever sat in front of a microphone saying "Enter" over and over again instead of just hitting the Enter key, you know what I mean.

This may all sound as though I don't like the idea of pen computing, but that's not true. What I want to see is a pen-based system that truly makes sense. It wouldn't have to fit into my coat pocket, but it would have to be light—under 2 pounds. It would also have to come in a form with which I'm used to working—roughly the dimensions of a sheet of paper and no thicker than a pad of paper. I don't want to give up anything I can do on paper.

My ideal pen-based system would also run all day before recharging if it used rechargeable batteries, or several weeks before replacing the batteries if it used alkaline batteries. It would also have the power and performance to recognize my scribbly, inconsistent handwriting with perfection, and it would do it so fast that I'd not be particularly aware that it was happening.

Most important of all, it would be connected to my desktop system and my office network, so that I could access any information I need when I need it. It could use a wireless LAN when I'm in a conference room at my office building or a cellular connection when I'm away. And, finally, my system would cost only about $2000.

Unfortunately, my ideal system isn't available, and the current offerings don't even come close. When it does become available, you'll probably find it on the cover of BYTE. So the real question is whether pen computing is ready for the world. Except for a few special applications, such as electronic forms, the answer is no, not today.

—Dennis Allen
Editor in Chief
(BIX name "dallen")

World Radio History

Introducing Quattro Pro 4.0 The only DOS spreadsheet with pushbutton power!

Borland does it again— Sorry, Lotus!

No other DOS spreadsheet gets your work done faster than Borland's new Quattro® Pro 4.0 with pushbutton power!

Quattro Pro beats 1-2-3 . . . again!

New	Quattro Pro 4.0	Lotus 1-2-3 R 2.3	Lotus 1-2-3 R 3.1+
Most Powerful	**Yes**		
Intelligent Graphs	Yes	No	No
Novell Network optimized	Yes	No	No
Multiple sheets	Yes	No	Yes
Multi-variable solver	Yes	No	*
Easiest to Use	**Yes**		
SpeedBar	Yes	No	No
Print-To-Fit	Yes	*	*
Read Lotus 1-2-3 files, styles & macros	Yes	Yes	Yes
Best Performance	**Yes**		
All features in 640K	Yes	?	No
Price	**$495**	**$495**	**$595**

? Yes, but almost no room remains for data.
*Yes, but requires attaching an add-in.

NEW SpeedBar

Quattro Pro's customizable, built-in SpeedBar™ is a row of clearly labeled buttons that use simple English commands to give you instant mouse-click access to your frequently used features and macros. Plus you get immediate access to a host of new features.

NEW Intelligent Graphs

Intelligent Graphs let you perform extended analysis with your graphs without changing your data. And Quattro Pro's Optimizer™ allows you to solve complex problems using multiple variables.

The best spreadsheet on networks

Only Quattro Pro 4.0 gives you superior Novell NetWare support, including automatic logon, drive mapping and a new Print Queue Manager.

The most feature-packed DOS spreadsheet ever!

And in addition to Quattro Pro 4.0's dramatic new advances, you get the features that have made it the #1-rated spreadsheet in the world. Features such as WYSIWYG, Print-To-Fit™ spreadsheet output, superb 1-2-3® compatibility (you can even read Allways, Impress and WYSIWYG files) and more.

NEW Novell Support

Top-rated spreadsheet Top-rated company

Quattro Pro has won more awards for technical excellence and customer satisfaction than any other DOS spreadsheet. And J.D. Power and Associates ranked Borland "best application software in customer satisfaction in Small to Medium-sized and Large Businesses."[1]

Now you know why more than one million people have upgraded to the power of today's spreadsheet. Quattro Pro.

Attention 1-2-3 users!
Step up now!
Special Upgrade offer
See your dealer today or call now, 1-800-331-0877, Dept.5605

BORLAND
Software Craftmanship

[1]1991 J.D. Power and Associates® Computer End User Satisfaction Study: Phases I and III: Small to Medium-sized Businesses (responses from 1,784 business sites with 1 to 499 employees) and Large Businesses (responses from 1,094 business sites with 500 or more employees).

Copyright © 1992 Borland International, Inc. All rights reserved. Pricing is in U.S. dollars. Offer good in U.S. and Canada only. Dealer prices may vary. BI 1471

Circle 49 on Inquiry Card (RESELLERS: 50).

World Radio History

IN A CATEGORY OBSE AND LIGHTER, COMPAQ W ANOTHER ADJE

Make it smaller. Make it lighter. Make it lighter. Make it smaller.

These must be the mandates emblazoned upon every R&D document handed to the engineers of today's crop of notebook computers.

Admirable goals to be sure. Goals that the engineers at Compaq, however, believe fall well short of making the most of portable computing.

Accurate to within minutes, the COMPAQ Power Smart Pack battery gauge clearly displays remaining battery life at the touch of a button.

Which explains why the latest 386SL notebook technology from the labs in Houston — the new COMPAQ LTE Lite/25 and LTE Lite/20 PCs — are not only the lightest (a scant 6 lbs.) and the smallest (only 8.5"x11"x1.75") notebook PCs that we've ever built. They're also the smartest.

The COMPAQ Hibernation feature saves all open files to the hard drive and turns the unit off, either upon request or as an automatic feature. Power up the COMPAQ LTE Lite later and you're back exactly where you left off.



THE BRAINS BEHIND THE OPERATION.

When it came time to design a new notebook, we started (logically enough) with the battery.

The new COMPAQ Power Smart Pack battery in our new notebooks delivers up to 4.5 hours of computing, a full hour longer than most.

A microprocessor inside the battery itself monitors current usage levels and continually calculates the available power remaining.

It can even instruct the notebook to save all open files to the hard drive should the battery power run too low.

And the energy-saving features in our newest notebooks go far beyond the presence of an Intel 386SL chip.

To make the most of the smarter battery, the new COMPAQ LTE Lite also comes with user-adjustable power-drain settings, and three different sleep modes — System Idle, System Standby, and Hibernation.

A MOST MODERN MODEM.

Our optional 9600-bps modem for the COMPAQ LTE Lite PCs would make even Alexander Graham B. proud.

The COMPAQ Enhanced 9600-bps Internal Modem is compatible with the broad base of today's communications protocols.



Just slip the COMPAQ LTE Lite into the COMPAQ Desktop Expansion Base and you're instantly connected. Expansion slots, external ports, and mass storage bays give you immediate access to monitors, networks, hard drives, tape drives, CD-ROM and more. And all the while, built-in security features ensure a safe harbor for your notebook.

In modem talk, that means true V.32 9600-bps data transmission and V.42bis compression for up to 38.4 kbps throughput, as well as full support for Hayes AutoSync.

This little marvel negotiates the fastest transmission throughput that the other end of the line can muster, whether it's sending or receiving.

It even drops to a low power-drain standby state and monitors incoming signals if you're waiting for a call to come in.

Or for that matter, another modem to catch up.

NOT ONLY SMART, BUT BRIGHT.

The new, efficient COMPAQ Maxlight VGA display makes for a much brighter screen than our previous notebooks, and does it without sacrificing battery life.

Sharper graphics and text in up

COMPAQ LTE Lite/25 only. © 1992 Compaq Computer Corporation. All rights reserved. COMPAQ, LTE Registered U.S. Patent and Trademark Office. Maxlight and Power Smart are trademarks of Compaq Computer Corporation. Trademarks and trade names shown are those of the respective companies. The Intel Inside Logo is a trademark of Intel Corporation.

World Radio History

SSED WITH SMALLER OULD LIKE TO SUGGEST CTIVE: SMARTER.

to 64 shades of gray complement an enhanced video subsystem that's so fast it virtually eliminates "submarining," better known as "where did that #%$**# cursor go?"

A NOTEBOOK THAT'S USELESS IN THE WRONG HANDS.

At Compaq, we realize that data security is every bit as important as hardware security.

At the hardware level, DriveLock locks the hard drive, preventing access to data even if the drive is removed.

One-touch QuickLock and QuickBlank functions

Isolated inverted "T" cursor controls are in a familiar position so you don't have to teach your fingers new tricks.

allow you to quickly (surprise) disable the keyboard or blank the screen.

And of course, our new notebooks come with a Keylock slot for an optional cable lock.

With all of the above, plus a 120-MB hard drive,* RAM expansion to 10 MB, cache memory, simultaneous display, and an auxiliary battery, to say these are the best notebooks we've ever made would be something of an understatement.

To back them with a one-year worldwide warranty and our toll-free Compaq Customer Support Center hotline would be more like it.

intel inside

So don't choose between a small notebook and a smart notebook. Choose both.

Choose the new COMPAQ LTE Lite. For information about our new notebooks or an Authorized COMPAQ Reseller near you, call Compaq in the U.S. at 1-800-231-0900, Ext. 100, or in Canada at 1-800-263-5868, Ext. 100.

COMPAQ

Actual weight: 6 lbs. Actual dimensions: 8.5"x11"x1.75". Actually, this is the best notebook we've ever built.

Circle 55 on Inquiry Card.

World Radio History

LETTERS

APL Praise

It was refreshing to read Doris Appleby's "Classic Languages, Part 4: APL" (December 1991). APL deserves much more serious attention both from expert programmers and from managers with difficult problems to resolve.

APL has been described by James Martin as the only language worthy of being called a fifth-generation language. Ironically, it is also one of the oldest languages. APL is the only fully international language, precisely because of its special character set. It is the only language that has been devised for *people* first and then converted to machine use.

Because of its power, the scope of APL is almost certainly far wider than that of any other language. This power makes it unequaled in fields, such as actuarial mathematics, statistics, and operations research modeling, where common languages are terribly cumbersome and tedious to use. This power is equally evident and just as useful in business when there is need for resolving complex questions in a hurry and for adapting to ever-changing conditions.

Georges Brigham
Wilton, CT

Great Road Maps

The article "Distributed Open Environments" (November 1991) is the best I've seen on the subject.

Soon every personal computer will be part of a global network. We need road maps, and we need to know the traffic rules, the rule makers, and the rule-making groups, as well as the products, construction/configuration/architecture, and management techniques. Articles like this are the reason I subscribe to BYTE. Don't spare the detail, and keep up the good work.

George McKee
Houston, TX

More on OS/2 2.0

Jon Udell's "OS/2 2.0: A Pilgrim's Journey" (December 1991) raises more questions than it answers.

First: Where's the software? My favorite mail-order house advertises a hundred products for Windows and not one for OS/2. Did Udell use any OS/2 applications? He doesn't mention any. He says that "potent" OS/2 software "waits in the wings," as has been said since 1987. Meanwhile, as the curtain rises on OS/2 2.0, Lotus uses a four-page color foldout inside BYTE's front cover to tell us about 1-2-3 for Windows.

Second: If OS/2 is a "better DOS than DOS," why is there a multiple boot facility? Substitute "DOS 5.0," a truly better DOS, in place of "OS/2" in one of Udell's remarks and see how it reads: "Even the most partisan DOS 5.0 users occasionally need to boot plain old DOS 3.3." Udell goes on to call the multiple boot facility "one of OS/2 2.0's nicest features." If you found that DOS 5.0 users always keep DOS 3.3 ready on their disks as well, would you accept that as anyone's idea of a "better DOS than DOS"?

Third: Exactly how much does it cost a Windows user, in extra RAM and disk space, to run OS/2? Even if Windows applications run just as well, OS/2 is not "a better Windows than Windows" if it takes more resources to do the same job. Underneath a lot of techno-speak about VDM and DPMI, I think that Udell is telling us that it takes a lot more. Windows applications ran "fine" on his 12-MB Systempro but "poorly" on his 4-MB Swan. Yet 4 MB is twice what vendors ship with their "Windows-ready" PCs.

Finally: Will IBM really support OS/2 on non-IBM hardware? When Udell wrote in April 1990 ("OS/2 2.0: It's a Family Affair") that OS/2 2.0 was the system he wanted, it was backed by Microsoft. Now it's in the hands of a hardware vendor whose ads for years suggested that OS/2 required the Micro Channel to run reliably. IBM's current ads don't say that—but they say nothing at all about what machines it will run on or who will provide the software support. Udell succeeded in running OS/2 on his Swan and his Systempro, but I would like to know if this is just an experimental observation, or if IBM certifies and supports it for those platforms. How does the OS/2 list compare with Microsoft's list of nearly 200 platforms that support Windows?

Daniel P. B. Smith
Norwood, MA

"Where's the software?" Although your mail-order house may not prominently advertise the fact, OS/2 versions of many of the most important Windows (and DOS) applications exist. I run OS/2 versions of Smalltalk/V, PageMaker, Epsilon, and HyperAccess, for example, along with OS/2-only gems like the Hamilton C Shell. Of course, that's just the icing on the cake. OS/2 2.0 subsumes nearly all existing DOS and Windows programs, so the answer to your question will be "everywhere" if 2.0's Windows support turns out as well as its DOS support has.

As to multiple boot, it's just plain useful. As a developer, I'd love to be able to use a single machine to test my application under DOS 3.3, 4, and 5, as well as OS/2 1.3 and 2.0. And note that the multiboot feature isn't just a way to fall back to DOS—you can use it to toggle between OS/2 and Unix or other operating systems. Now that you mention it, yes, I think multiple boot would be a nice enhancement to DOS 5.0 as well.

How much extra RAM? As I mentioned, the Windows support in the early version of OS/2 I tested did not yet successfully exploit OS/2's memory manager. Clearly, that's critical. Windows can't be said to run well under OS/2 unless it can perform on a 4-MB machine. Will it? The jury's still out. Note, however, that OS/2 and DOS

WE WANT TO HEAR FROM YOU. *Address correspondence to Letters Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458, or send BIXmail c/o "editors." Your letter may be edited for length and clarity.*

World Radio History

Introducing Quattro Pro 4.0 The only DOS spreadsheet with pushbutton power!

Borland does it again– Sorry, Lotus!

No other DOS spreadsheet gets your work done faster than Borland's new Quattro® Pro 4.0 with pushbutton power!

Quattro Pro beats 1-2-3 . . . again!

New	Quattro Pro 4.0	Lotus 1-2-3 R 2.3	Lotus 1-2-3 R 3.1+
Most Powerful	**Yes**		
Intelligent Graphs	Yes	No	No
Novell Network optimized	Yes	No	No
Multiple sheets	Yes	No	Yes
Multi-variable solver	Yes	No	*
Easiest to Use	**Yes**		
SpeedBar	Yes	No	No
Print-To-Fit	Yes	*	*
Read Lotus 1-2-3 files, styles & macros	Yes	Yes	Yes
Best Performance	**Yes**		
All features in 640K	Yes	?	No
Price	**$495**	**$495**	**$595**

? Yes, but almost no room remains for data.
*Yes, but requires attaching an add-in.

NEW SpeedBar

Quattro Pro's customizable, built-in SpeedBar™ is a row of clearly labeled buttons that use simple English commands to give you instant mouse-click access to your frequently used features and macros. Plus you get immediate access to a host of new features.

NEW Intelligent Graphs

Intelligent Graphs let you perform extended analysis with your graphs without changing your data. And Quattro Pro's Optimizer™ allows you to solve complex problems using multiple variables.

The best spreadsheet on networks

NEW Novell Support

Only Quattro Pro 4.0 gives you superior Novell NetWare support, including automatic logon, drive mapping and a new Print Queue Manager.

The most feature-packed DOS spreadsheet ever!

And in addition to Quattro Pro 4.0's dramatic new advances, you get the features that have made it the #1-rated spreadsheet in the world. Features such as WYSIWYG, Print-To-Fit™ spreadsheet output, superb 1-2-3® compatibility (you can even read Allways, Impress and WYSIWYG files) and more.

Top-rated spreadsheet Top-rated company

Quattro Pro has won more awards for technical excellence and customer satisfaction than any other DOS spreadsheet. And J.D. Power and Associates ranked Borland "best application software in customer satisfaction in Small to Medium-sized and Large Businesses."[1]

Now you know why more than one million people have upgraded to the power of today's spreadsheet. Quattro Pro.

Attention 1-2-3 users!
Step up now!
Special Upgrade offer
See your dealer today or call now, 1-800-331-0877, Dept.5605

BORLAND
Software Craftmanship

[1]1991 J.D. Power and Associates® Computer End User Satisfaction Study: Phases I and III: Small to Medium-sized Businesses (responses from 1,784 business sites with 1 to 499 employees) and Large Businesses (responses from 1,094 business sites with 500 or more employees).

Copyright © 1992 Borland International, Inc. All rights reserved. Pricing is in U.S. dollars. Offer good in U.S. and Canada only. Dealer prices may vary. BI 1471

Circle 49 on Inquiry Card (RESELLERS: SO).

World Radio History

IN A CATEGORY OBSE AND LIGHTER, COMPAQ W ANOTHER ADJE

Make it smaller. Make it lighter. Make it lighter. Make it smaller.

These must be the mandates emblazoned upon every R&D document handed to the engineers of today's crop of notebook computers.

Admirable goals to be sure. Goals that the engineers at Compaq, however, believe fall well short of making the most of portable computing.

Accurate to within minutes, the COMPAQ Power Smart Pack battery gauge clearly displays remaining battery life at the touch of a button.

Which explains why the latest 386SL notebook technology from the labs in Houston — the new COMPAQ LTE Lite/25 and LTE Lite/20 PCs — are not only the lightest (a scant 6 lbs.) and the smallest (only 8.5"x11"x1.75") notebook PCs that we've ever built. They're also the smartest.

The COMPAQ Hibernation feature saves all open files to the hard drive and turns the unit off, either upon request or as an automatic feature. Power up the COMPAQ LTE Lite later and you're back exactly where you left off.

THE BRAINS BEHIND THE OPERATION.

When it came time to design a new notebook, we started (logically enough) with the battery.

The new COMPAQ Power Smart Pack battery in our new notebooks delivers up to 4.5 hours of computing, a full hour longer than most.

A microprocessor inside the battery itself monitors current usage levels and continually calculates the available power remaining.

It can even instruct the notebook to save all open files to the hard drive should the battery power run too low.

And the energy-saving features in our newest notebooks go far beyond the presence of an Intel 386SL chip.

To make the most of the smarter battery, the new COMPAQ LTE Lite also comes with user-adjustable power-drain settings, and three different sleep modes — System Idle, System Standby, and Hibernation.

A MOST MODERN MODEM.

Our optional 9600-bps modem for the COMPAQ LTE Lite PCs would make even Alexander Graham B. proud.

The COMPAQ Enhanced 9600-bps Internal Modem is compatible with the broad base of today's communications protocols.



Just slip the COMPAQ LTE Lite into the COMPAQ Desktop Expansion Base and you're instantly connected. Expansion slots, external ports, and mass storage bays give you immediate access to monitors, networks, hard drives, tape drives, CD-ROM and more. And all the while, built-in security features ensure a safe harbor for your notebook.

In modem talk, that means true V.32 9600-bps data transmission and V.42bis compression for up to 38.4 kbps throughput, as well as full support for Hayes AutoSync.

This little marvel negotiates the fastest transmission throughput that the other end of the line can muster, whether it's sending or receiving.

It even drops to a low power-drain standby state and monitors incoming signals if you're waiting for a call to come in.

Or for that matter, another modem to catch up.

NOT ONLY SMART, BUT BRIGHT.

The new, efficient COMPAQ Maxlight VGA display makes for a much brighter screen than our previous notebooks, and does it without sacrificing battery life.

Sharper graphics and text in up

COMPAQ LTE Lite/25 only. © 1992 Compaq Computer Corporation. All rights reserved. COMPAQ, LTE Registered U.S. Patent and Trademark Office Maxlight and Power Smart are trademarks of Compaq Computer Corporation. Trademarks and trade names shown are those of the respective companies. The Intel Inside Logo is a trademark of Intel Corporation.

World Radio History

SSED WITH SMALLER OULD LIKE TO SUGGEST CTIVE: SMARTER.

to 64 shades of gray complement an enhanced video subsystem that's so fast it virtually eliminates "submarining," better known as "where did that #%$**# cursor go?"

A NOTEBOOK THAT'S USELESS IN THE WRONG HANDS.

At Compaq, we realize that data security is every bit as important as hardware security.

At the hardware level, DriveLock locks the hard drive, preventing access to data even if the drive is removed.

One-touch QuickLock and QuickBlank functions

Isolated inverted "T" cursor controls are in a familiar position so you don't have to teach your fingers new tricks.

allow you to quickly (surprise) disable the keyboard or blank the screen.

And of course, our new notebooks come with a Keylock slot for an optional cable lock.

With all of the above, plus a 120-MB hard drive,* RAM expansion to 10 MB, cache memory, simultaneous display, and an auxiliary battery, to say these are the best notebooks we've ever made would be something of an understatement.

To back them with a one-year worldwide warranty and our toll-free Compaq Customer Support Center hotline would be more like it.

So don't choose between a small notebook and a smart notebook. Choose both.

Choose the new COMPAQ LTE Lite.

For information about our new notebooks or an Authorized COMPAQ Reseller near you, call Compaq in the U.S. at 1-800-231-0900, Ext. 100, or in Canada at 1-800-263-5868, Ext. 100.

COMPAQ

Actual weight: 6 lbs. Actual dimensions: 8.5" x 11" x 1.75". Actually, this is the best notebook we've ever built.

Circle 55 on Inquiry Card.

World Radio History

LETTERS

APL Praise

It was refreshing to read Doris Appleby's "Classic Languages, Part 4: APL" (December 1991). APL deserves much more serious attention both from expert programmers and from managers with difficult problems to resolve.

APL has been described by James Martin as the only language worthy of being called a fifth-generation language. Ironically, it is also one of the oldest languages. APL is the only fully international language, precisely because of its special character set. It is the only language that has been devised for *people* first and then converted to machine use.

Because of its power, the scope of APL is almost certainly far wider than that of any other language. This power makes it unequaled in fields, such as actuarial mathematics, statistics, and operations research modeling, where common languages are terribly cumbersome and tedious to use. This power is equally evident and just as useful in business when there is need for resolving complex questions in a hurry and for adapting to ever-changing conditions.

Georges Brigham
Wilton, CT

Great Road Maps

The article "Distributed Open Environments" (November 1991) is the best I've seen on the subject.

Soon every personal computer will be part of a global network. We need road maps, and we need to know the traffic rules, the rule makers, and the rule-making groups, as well as the products, construction/configuration/architecture, and management techniques. Articles like this are the reason I subscribe to BYTE. Don't spare the detail, and keep up the good work.

George McKee
Houston, TX

More on OS/2 2.0

Jon Udell's "OS/2 2.0: A Pilgrim's Journey" (December 1991) raises more questions than it answers.

First: Where's the software? My favorite mail-order house advertises a hundred products for Windows and not one for OS/2. Did Udell use any OS/2 applications? He doesn't mention any. He says that "potent" OS/2 software "waits in the wings," as has been said since 1987. Meanwhile, as the curtain rises on OS/2 2.0, Lotus uses a four-page color foldout inside BYTE's front cover to tell us about 1-2-3 for Windows.

Second: If OS/2 is a "better DOS than DOS," why is there a multiple boot facility? Substitute "DOS 5.0," a truly better DOS, in place of "OS/2" in one of Udell's remarks and see how it reads: "Even the most partisan DOS 5.0 users occasionally need to boot plain old DOS 3.3." Udell goes on to call the multiple boot facility "one of OS/2 2.0's nicest features." If you found that DOS 5.0 users always keep DOS 3.3 ready on their disks as well, would you accept that as anyone's idea of a "better DOS than DOS"?

Third: Exactly how much does it cost a Windows user, in extra RAM and disk space, to run OS/2? Even if Windows applications run just as well, OS/2 is not "a better Windows than Windows" if it takes more resources to do the same job. Underneath a lot of techno-speak about VDM and DPMI, I think that Udell is telling us that it takes a lot more. Windows applications ran "fine" on his 12-MB Systempro but "poorly" on his 4-MB Swan. Yet 4 MB is twice what vendors ship with their "Windows-ready" PCs.

Finally: Will IBM really support OS/2 on non-IBM hardware? When Udell wrote in April 1990 ("OS/2 2.0: It's a Family Affair") that OS/2 2.0 was the system he wanted, it was backed by Microsoft. Now it's in the hands of a hardware vendor whose ads for years suggested that OS/2 required the Micro Channel to run reliably. IBM's current ads don't say that—but they say nothing at all about what machines it will run on or who will provide the software support. Udell succeeded in running OS/2 on his Swan and his Systempro, but I would like to know if this is just an experimental observation, or if IBM certifies and supports it for those platforms. How does the OS/2 list compare with Microsoft's list of nearly 200 platforms that support Windows?

Daniel P. B. Smith
Norwood, MA

"Where's the software?" Although your mail-order house may not prominently advertise the fact, OS/2 versions of many of the most important Windows (and DOS) applications exist. I run OS/2 versions of Smalltalk/V, PageMaker, Epsilon, and HyperAccess, for example, along with OS/2-only gems like the Hamilton C Shell. Of course, that's just the icing on the cake. OS/2 2.0 subsumes nearly all existing DOS and Windows programs, so the answer to your question will be "everywhere" if 2.0's Windows support turns out as well as its DOS support has.

As to multiple boot, it's just plain useful. As a developer, I'd love to be able to use a single machine to test my application under DOS 3.3, 4, and 5, as well as OS/2 1.3 and 2.0. And note that the multiboot feature isn't just a way to fall back to DOS—you can use it to toggle between OS/2 and Unix or other operating systems. Now that you mention it, yes, I think multiple boot would be a nice enhancement to DOS 5.0 as well.

How much extra RAM? As I mentioned, the Windows support in the early version of OS/2 I tested did not yet successfully exploit OS/2's memory manager. Clearly, that's critical. Windows can't be said to run well under OS/2 unless it can perform on a 4-MB machine. Will it? The jury's still out. Note, however, that OS/2 and DOS

WE WANT TO HEAR FROM YOU. *Address correspondence to Letters Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458, or send BIXmail c/o "editors." Your letter may be edited for length and clarity.*

World Radio History



interface development & screen management in a utopian environment!

In the perfect world, you probably wouldn't choose to spend excessive time and energy (read: any) sweating the interface to satisfy the constantly changing whims of your end-users. On the other hand, the perfect world wouldn't *have* end-users.

But the real world does.

And the more difficult, picky, and fickle they get about how their screens look and function, the more likely it is you're going to want to change careers.

Vermont Views™ v3.0

Fortunately, we can end your end-user nightmares — whether you're developing for UNIX, DOS, VMS, or all three! Vermont Views takes the aggravation out of coding and recoding perfect C language interfaces. Instead, we let you create sophisticated screens *interactively*, with our program's powerful, intuitive, menu-driven Designer.

With the Designer, you can create window-based data-entry forms that have tickertape and memo fields, pushbuttons and radio buttons, scrollable form regions, choice lists, scroll bars, shadow borders, and more. Just peruse, choose, and there they are!

Changes? Easy! New details? No problem! Whole new approaches? *Go* for it!

In fact, there's almost nothing you *can't* do, because Vermont Views is backed by an incredible library of 586 tested, debugged, reliable functions. Which means that every screen you create can look and run distinctively, uniquely, and precisely the way you need it to.

Of course, the real beauty of Vermont Views may be the easy portability among DOS, UNIX, POSIX, XENIX, and VMS. That you can use it with Oracle, Informix, db_Vista, Sybase, Btrieve, C-tree — or any database that interfaces to C. Or run it on IBM, NCR, DEC, HP, AT&T, and all the others. How come? Because Vermont Views functions *independently* of operating system, database, and hardware. And we supply shrouded source, so you know you'll be able to move applications to *any* desired platform — without paying runtime fees or royalties.

Which isn't to say that Vermont Views' portable interfaces are restricted in capability. Anything but! Our DOS interfaces have *everything* that *anyone* has imagined — including full mouse support. And our terminal versions have the fastest screen updates in the business. How fast? Don't bother reaching for the Twinkies. *That's* how fast.

Now take that blinding execution speed, that fourth generation language convience, that power and flexibility, and top it all with great documentation, superb tech support, seven years of developer input... and immediately, one fundamental question leaps to mind: Why are you still letting your end-users whack your fragile head against their hard, heartless walls?

Join our thousands and thousands of happy, healthy customers. Take that big step towards developer's dreamland.



Circle 133 on Inquiry Card.

Demo paradise for yourself. Free.

Call 1-800-848-1248 US & Can.

(Please mention "Offer 279")

Vermont Creative Software

Pinnacle Meadows, Richford, VT USA 05476
(802) 848-7731, fax (802) 848-3502

©1992 Vermont Creative Software

World Radio History

The award winning T2200SX

If you need any more power than this

If your desire for power is on the scale of say, Louis XIV, consider the Toshiba T2200SX. Weighing a mere 5.5 pounds and taking up just half a briefcase, it possesses an awesome 20 MHz 386SX microprocessor and a 40, 60 or 80 MB hard drive with 2MB RAM expandable to 10 MB. And it's powerful enough to have grabbed both a PC/Computing MVP award and a PC Magazine Technical Excellence Award.

© 1992 Toshiba America Information Systems, Inc. The Intel Inside logo is a trademark of Intel Corporation. All symbols are trademarked and/or registered by their respective manufacturers.

World Radio History

The new T3300SL

maybe you should get into politics.

If your need for power is on the scale of say, Napoleon, consider the new T3300SL. It offers a 25MHz 386SL microprocessor plus 64 KB cache for blazing speed and longer battery life. Not to mention an 80 or 120MB drive and a PCMCIA-compatible slot. And like its cousin the T2200SX, it offers a Nickel Hydride battery and a carbon-fiber reinforced case. So call 1-800-457-7777. Or if you want even more power, don't forget it's an election year.

In Touch with Tomorrow
TOSHIBA

Circle 131 on Inquiry Card.

World Radio History

applications do quite well on a 4-MB machine.

And what about clone support? I don't have an official list from IBM, but an unofficial one is available on BIX (see the file CLONES.ZIP in ibm.os2/listings). Among the 386/486 systems that have successfully run both OS/2 1.x and 2.0 are those made by Northgate, Gateway, Everex, Compaq, CompuAdd, Dell, Tristar, Cheetah, Arche, Ergo, Acer, Hewlett-Packard, and Zeos. These systems sport hard disk subsystems with RLL, ESDI, and IDE interfaces (yes, SCSI support is still weak); BIOSes from AMI, Award, Compaq, and Phoenix; display adapters by Video Seven, ATI, Boca, Paradise, and Trident. Yes, high-resolution/deep-color drivers are few. But most observers have been pleasantly surprised by 2.0's promiscuity.—Jon Udell

No Longer Unthinkable

Dick Fleming's "Think About the Unthinkable" (November 1991) was right on the money. I work in an office where we are going through computer-literacy growing pains. Most of our people use computers only because they have to, and they tend to put in only the minimal amount of time to learn about them. I often get on a soap box about backing up files and documenting activities and procedures.

I would add to Fleming's list a screen dump of the system setup menus. Ours got changed by some unwitting soul, and because we didn't have a copy, we had to call the manufacturer for the hard disk data values.

Fleming says that if you take the time to think about the unthinkable, "someone may be grateful that you did." Well, if *you* have a hard disk failure and have to rebuild your system, *you* might be the one who'll appreciate the data recovery notebook that Fleming advocates.

Jerry E. Semler
Huber Heights, OH

Evaluating Standards

Eric S. Raymond's "Standards Everywhere" (January) raises some important issues associated with the increasing growth of "open" standards and economic and technical cartels. Unfortunately, some of his arguments and conclusions are poor at best.

In an attempt to describe the proliferation of standards, he cites "ACE versus SPARC versus EISA versus PS/2. X Window System versus News versus Display PostScript. And GUIs. Don't even *talk* to me about GUIs." These comparisons are incorrect because they do not represent entities of the same class: ACE is a cartel; SPARC is a RISC definition; EISA is a bus standard; and PS/2 is a brand of IBM PC. A better comparison might be ACE versus Sun (or SPARC, Inc.) versus Apple/IBM versus 88/Open. The X Window System is a drawing engine and a crude GUI even without Motif or Open Look—so he has broken his rule about not talking about GUIs. Network Extensible Windows System (News) is display PostScript; News is an example of a failed standard, as Sun is one of the last to support it.

Open standards come from various beginnings, but most are seeded by an economic need to reduce the rate of change for the item being standardized. This is an attempt to reduce software life-cycle costs. Today most new hardware systems have a half-life of 18 months, yet the government and some large businesses can't get the specifications for new software out in less than 12 months. Coupled with an economic need for 10- to 20-year life cycles (with technology infusion every so often), the computer industry is becoming very strained.

Standards slow the rate of change, allowing users to keep up to date with technology without massive costs. Major standards do tend to take longer to be approved or to change than one would like to see, but standards force industry to serve users, not sellers.

I agree with Raymond that any standard with more exceptions than rules should be shunned. I do not agree with his Rules for Standards Survival. Rule 1 states that you should wait to commit to a standard until everyone else also appears to commit. If you do that, you are likely to be left out in the cold. Rule 2 warns you not to honor a standard if it's dictated by a single entity. This is true in most cases; however, if the government is that entity, you may be right only half the time. Rule 3 states that the bigger the standard, the less its value. For an example of why this is wrong, look at Ada. It's a small standard, yet it lacks the elegance that Raymond says he values.

Larry Chandler
Eagan, MN

Humans vs. Machines

I enjoyed Ben Smith's "The Dangers of Multitasking" (December 1991). However, with the greatest respect, I suggest that he has got the hierarchy of computers and humans upside down.

To my mind, the core of human communications is the dynamic modeling of all the other participants and then the recursive modeling of oneself, and everyone else, within that model, all updated in milliseconds at critical points in a discussion. This is an exquisitely intricate affair, involving as it does the feelings and relationships of those involved, over and above the technical matters under discussion.

The issue has wider importance when viewed from a sociological point of view. Just as Smith fears, I believe that our technical tools imperil our society by trivializing our behavior.

Suffice it to say, I am impressed that these aspects of technology are getting exposure in such a technically oriented journal. Keep up the good work!

Duncan M. Butlin
Tulsa, OK

FIXES

- In the February First Impressions (pages 39 and 47), we neglected to swap three high-resolution images for low-res. We apologize to Farallon Computing, Inc., and Microsoft Corp.
- The GXtra/W SBus card from Tech-Source (February, What's New, page 54) comes with a keyboard and a mouse port, not a keyboard and a mouse. ■

World Radio History



MICROSOFT SOFTWARE DEVELOPMENT TOOLS

Graphic proof that developing Windows apps is now easier.



Use QuickCase:W to draw the graphical elements of your Windows program, from menus and dialog boxes to cursors and icons. Then, let QuickCase:W generate commented expert-level C source code for the design that you've created.



QuickC for Windows supports a wide range of breakpoint types, from breaking at a location to breaking on a Windows procedure when a message is received.

Take a look at Microsoft® QuickC® for Windows™.

It's Windows-hosted, so you can edit, compile, and debug inside a single environment. Click on the Toolbar™ to choose frequently-used functions, from changing fonts to setting breakpoints. Workspace templates let you save your screen layouts, so you can reload them quickly from another session.

Plus, a remarkable tool known as QuickCase:W lets you create every element in your user interface with a few strokes of a mouse. Then it automatically generates the C source code you need.

All of which lets you create more applications. And more kinds of applications: C programs that call Windows APIs, graphical front-end programs for FORTRAN and COBOL, and C DLLs for other programs.

We suggest a visit to your Microsoft dealer. Because with QuickC for Windows, seeing is believing.

*© 1991 Microsoft Corporation. All rights reserved. Printed in the U.S.A. Inside the 50 United States, call (800) 541-1261, Dept. V75; outside the 50 United States, call (206) 936-8661. In Canada, call (416) 568-3503. Microsoft, CodeView, MS-DOS, QuickC and the Microsoft logo are registered trademarks and Windows, and Toolbar are trademarks of Microsoft Corporation. *As used herein, "DOS" refers to MS-DOS and PC-DOS operating systems.*

Key Features

- Windows-hosted integrated development environment including an editor, compiler, and debugger.
- All you need to write a Windows-based program.
- QuickCase:W generates source code from your program design and regenerates the code if you change the design.
- Wide range of breakpoint support, including breaking at a location, breaking when an expression has changed, and breaking at a Windows procedure when a message is received.
- Complete printed and online documentation on the Windows API.
- Toolbar for quick access to frequently used editing and debugging functions.
- Save Workspace and Load Workspace for saving and restoring window positions and breakpoints.
- Syntax highlighting in editor.
- Customizable tools menu allows you to run any Windows or DOS* program from within the QuickC for Windows environment.
- QuickWin library for converting well-behaved C programs for DOS to Windows programs.
- Generates Windows Executables, Windows Dynamic Link Libraries, QuickWin Executables for the Windows environment, and MS-DOS® Executables.

PROGRAMMER'S TIPS

- *To rebuild your character-based DOS applications to run under the Windows environment, select the "QuickWin EXE" Project type in the Options menu.*
- *Use the new and improved Dialog Editor to quickly and easily design dialog boxes for your programs.*

Microsoft

World Radio History

It takes lots of screaming fans

Eleven million, to be exact. And in the math coprocessor business, that's definitely a record.

It just goes to show that Intel is the de facto standard in math coprocessors. And has been for the last ten years.

Not surprisingly, a whopping nine out of ten math coprocessors in use today carry the Intel name. And you can bet almost every one of them is sitting right next to an Intel CPU.

Get the connection? It's as perfect a match as you can get. Intel Math CoProcessors are 100% compatible with your Intel CPU, not to mention more than 2,100 software applications.

©1992 Intel Corporation. i387 is a trademark of Intel Corporation. Outside of the U.S. or Canada call 1-503-629-7354.

World Radio History

to go platinum eleven times.

It's all part of Intel's commitment to providing powerful solutions today, like the world's fastest microprocessors, plus the enhancements for even greater performance. Today and down the road.

WE MAKE COMPUTERS WORK HARDER.
Call and ask for packet BZ.
1-800-538-3373

To receive a detailed information packet about the complete family of Intel Math CoProcessors, call 1-800-538-3373.

You'll see why Intel Math CoProcessors have topped the charts for ten years running.

intel®

Circle 80 on Inquiry Card (RESELLERS: 81).

World Radio History

The Pros Rate CA-SuperCalc Higher Than Lotus 1-2-3 And Microsoft Excel.



VARBUSINESS Spreadsheet Report Card

	CA-SuperCalc	Lotus 1-2-3	Microsoft Excel
Ease of use	7.30	6.50	7.11
Memory Requirement	7.00	5.41	6.14
Ease of programming	6.48	5.86	6.26
Ability to manipulate data	7.31	6.71	7.00
Sorting capabilities	7.50	6.64	6.68
Provision for software security	6.96	5.25	5.10
Report writing capabilities	6.78	5.33	6.17
Ease of use of interface	7.45	6.19	6.77
Software integration capabilities	7.30	6.23	6.78
Ease of data retrieval	7.50	6.78	7.00
Satisfaction with product profitability	6.81	5.75	6.42
Overall quality of product	7.70	7.18	7.53
Provision for customer support	7.52	5.79	6.22
Charges for training time	6.43	5.60	5.71
Provision for technical support	7.34	5.55	5.95
Provision for marketing support	6.69	5.71	5.93
Documentation & product information	6.90	6.70	6.98
Frequency of updates & revisions	6.59	5.75	6.15
OVERALL AVERAGE	7.09	6.05	6.44

Recently, *VARBUSINESS* conducted a survey of some people who know more about spreadsheets than anyone.

The people who sell, install, and support them for a living. The survey asked hundreds of spreadsheet dealers and resellers all kinds of questions to find out what the pros rate as the best spreadsheet. And the pros told them.

CA-SuperCalc.®

In virtually every category from ease-of-use to technical support, CA-SuperCalc was rated higher than Lotus® 1-2-3® and Microsoft® Excel.

We're not surprised. While Lotus and Microsoft have been fussing over their many different spreadsheet versions, we've been stuffing one spreadsheet, CA-SuperCalc, with everything you would ever want. From spreadsheet linking to 3-D graphics and beautiful, presentation-quality output, CA-SuperCalc has it all.



And it runs on just about any PC.

But the best part is the price. At $149.00, CA-SuperCalc costs less than half the price of Lotus 1-2-3 and Excel. Heard enough? Call 1-800-CALL CAI today for the name of the nearest dealer where you can buy the best spreadsheet there is.

If you're willing to spend a couple hundred dollars less.

CA90s
CA's Computing Architecture For The 90s.

COMPUTER® ASSOCIATES
Software superior by design.

© Computer Associates International, Inc., One Computer Associates Plaza, Islandia, NY 11788-7000. All product names referenced herein are trademarks of their respective companies.
© 1991 by CMP Publications, Inc., 600 Community Drive, Manhasset, NY 11030. Reprinted from *VARBUSINESS* with permission.

Circle 58 on Inquiry Card.

World Radio History

NEWS

MICROBYTES

Next to Step into the 486 Arena

Kicking off the first NextWorld Expo in San Francisco, Steve Jobs, president and CEO of Next, confirmed the long-standing rumor that Next will supply its NextStep interface and software development environment on the Intel 486 platform. The entire operating system—the same Mach version of Unix used on the Next platform—will be ported.

Rumors circulated at the show that Jobs would announce licensing deals with Compaq and Dell, but Jobs would only say that Next is negotiating licensing agreements with several manufacturers. Nevertheless, Next demonstrated alpha versions of NextStep 3.0 running on both Dell and Compaq 486 machines during Jobs's presentation and on the show floor. Jobs emphasized that the Intel port in no way affects the company's intent to compete in the hardware marketplace.

NextStep for the 486 will be available in a shrink-wrapped version directly from Next, with an end-user version priced at $995 and a full developer's version priced at $2495. Both versions are essentially identical to their Next computer counterparts. Jobs said that a beta version of NextStep for the 486 will be ready in the second quarter of this year and that a production version will ship in the third quarter.

Jobs claimed that NextStep is catching on in corporate U.S., Japan, and Europe as the premier tool for custom software development, particularly for "in-house, mission-critical custom applications." Jobs said NextStep's object-oriented development environment, Display PostScript imaging model and graphical interface, and Mach multitasking Unix kernel are technically superior to any of the competition's.

"We're three to five years ahead of Solaris, Windows NT, and Taligent," boasted Jobs. Jobs claimed that Next is getting more opportunities to compete with Sun Microsystems for volume sales deals and is "winning 80 percent [of them]."

The problem is that NextStep's advantages are not readily apparent to end users. While software developers find NextStep attractive, they are reluctant to invest in it unless they can see a large installed base of users. Whether NextStep on the 486 can turn things around remains to be seen.

—Nicholas Baran

Quorum Converts Mac to RISC, Provides Latitude over PowerPC

Quorum Software Systems (Menlo Park, CA) is developing a software porting system that helps developers turn Mac System 7.0 programs into native implementations on SPARC, IBM RISC System/6000, and Silicon Graphics Iris Indigo RISC workstations. Quorum's Latitude system maps Mac system and user-interface calls to the native calls of the target platform. The porting system, slated for release in June, lets developers reach an unprecedented number of platforms with a single instance of source code.

Silicon Graphics and SunSoft officials expressed delight at seeing Mac applications migrating to their platforms. But Latitude provoked quite a different attitude from at least one Apple official. Roger Heinen, vice president and general manager of Apple's Macintosh Software Architecture Division, sat quietly in the audience as he watched Latitude's unveiling at the UniForum trade show and said only that he could not comment.

Quorum's product was previewed at the MacWorld Expo. At that show, Mac software was shown running blazingly fast on an Indigo workstation.

One possible reason for Heinen's muted response is that Apple may have entered into its alliance with IBM mainly in the hope of seeing the Mac integrated into the RISC world on the PowerPC. Quorum Latitude appears to do now what the PowerPC will do in 1993 or 1994.

—Ellen Ullman

NANOBYTES

Canon plans to distribute a kanji version of **NextStep 3.0** in Japan. Reports in the Japanese press also indicate that Canon will port a Japanese version of NextStep for the 486 to its 32-bit PCs. □

A major revision to the NextStep interface and development environment is scheduled to ship in June. In the networking arena, NextStep 3.0 will include built-in Novell NetWare and AppleShare protocols, which will allow seamless networking to PCs and Macs and to Unix workstations that support NetWare. Version 3.0 will include support for PostScript Level 2 and the **RenderMan 3-D** development specification. NextStep 3.0 also includes two long-awaited features: object linking and a database toolkit. □

In the keynote speech of January's Usenix conference, **Mitch Kapor**, founder of Lotus Development and more recently the chairman

of On Technology, discussed the commercial access and use of the **Internet** network, which is dedicated to research and educational use. The Internet is becoming increasingly commercial, raising the same types of questions first asked about TV during its infancy, such as who is going to own it and who is going to control it. Before TV became popular, everyone thought that it would be the uplifting factor that would raise our culture from ignorance and apathy. Of course, that's not quite what happened. Kapor pleaded with his listeners not to let the Internet end up like the "vast wasteland of TV." □

World Radio History

Now you can and not get

Introducing new RISC System/6000 POWERstations

If you're interested in open systems but don't want to suffer the slings and arrows of outrageous prices, IBM is about to hit you where you live. The RISC System/6000™ POWERstation 220 gives you more wallop for your money, while delivering a hefty 25.9 SPECmarks.™ That's compared to the SUN IPC's™ 13.4 SPECmarks and the DEC5000's™ 17.8.

Model	Entry Grayscale Workstation**	Entry 8-bit Color Workstation†
IBM 220W	$7,185	$9,995
HP 705/710	$8,415	$14,065

Scientists see stars. CASE users can start with a grayscale workstation with a paging disk for just $7,185. If it's CAD clout you're after, you can get a workstation specially outfitted for mechanical design—with 2D color graphics and 400MB of fixed disk storage—for only $9,995. All models in the POWERstation 220 series come with two expansion

*In Canada, call 1 800 465-1234. **16MB, Paging Disk, Display, Operating System, Graphical User Interface. †16MB, 400MB Disk, Display, Operating System, Graphical User Interface. IBM is a registered trademark and RISC System/6000 is a trademark of International Business Machines Corporation. SPECmark is a geometric mean of the ten SPECmark tests and is a trademark of Standard Performance Evaluation Corporation. All SPECmark figures listed are as published by their respective manufacturers. All prices listed are MSRP. Remarketer prices may vary. IPC is a trademark of Sun Microsystems, Inc. DEC5000 is a trademark of Digital Equipment Corporation. UNIX is a registered trademark of UNIX Systems Laboratories. HAGAR THE HORRIBLE Character(s) © 1992 King Features Syndicate, Inc. © 1992 IBM Corp.

World Radio History

get more clout, clobbered.

and POWERservers that pack more punch for less.

slots and upgradable components. And industry-standard memory upgrades and add-ons for both are affordable, so growing won't be a pain.

Striking a blow for business. The POWERserver 220 is great for commercial UNIX® solutions, too. You can configure it as a commercial server, to give your business the speed, muscle and openness of UNIX, for only $9,715. And the POWERserver 220 is as expandable as all our other models.

IBM is in your corner. Nobody else delivers the knockout support of IBM. An IBM customer engineer can install your machines, configure your network and integrate all your systems, whether they're made by IBM or not. And IBM Credit Corporation has flexible financing packages to meet your needs. Get hit with the details. Call your IBM marketing representative or Business Partner. For literature, call 1 800 IBM-6676, ext. 769*

And, for those who decide to shop for UNIX solutions elsewhere, a word of advice. Duck.

The RISC System/6000
For the Power Seeker.

IBM

World Radio History

NEWS

MICROBYTES

Rambus's New Memory Architecture Could Put More Video PCs on Desktops

Rambus, a start-up company backed by three venture-capital firms and stocked with a stable of technical engineers, has developed a DRAM architecture and chip-to-chip data transfer technology that could solve the classic memory bottleneck problem. Geoff Tate, president and CEO of the Mountain View, California, company, said that the Rambus interface standard can be directly implemented on CMOS DRAMs, memory controllers, processors, graphics/video chips, and other components.

Tate said that Rambus's solution will deliver a tenfold increase in component throughput. A single Rambus DRAM (RDRAM) delivers up to "500 million bytes per second on a standard PC over a narrow, high-speed bus," he said. The company expects to capture more than 50 percent of the DRAM market by 1997. Tate adds that the company's solution uses fewer ICs and a modular system.

The problem Rambus addresses is well known to systems designers: The data transfer rate of memory ICs lags behind a processor's ability to handle data. Although DRAM densities have increased, DRAM performance has improved only marginally. Because of this, systems designers have resorted to complex workarounds of the bottleneck by using multilevel memory hierarchies, with Level 2 static RAM (SRAM) caches and cache controllers. And as display resolutions increase and customers clamor for true color, costs are driven up due to the memory needed to supply pixels at a high rate for a flicker-free display. Animation graphics and video also require high data transfer rates to display images in real time. All these requirements have resulted in complex architectures that use specialized multiport DRAMs or video RAMs (VRAMs) to maintain the high data transfer rates.

Rambus replaces all these subsystems with a solution made up of masters, slaves, and a narrow, high-speed bus. Rambus engineers have developed a bus that's 1 byte (9 bits) wide and capable of transferring data at 500 MBps by using both edges of a 250-MHz clock. Masters and slaves connect to the printed-circuit board via a simple 32-pin interface. Small signal swings replace conventional, noisy TTL signals and operate in a controlled-impedance transmission-line environment, the company says.

Rambus says that its design will eliminate the need for Level 2 SRAM caches, cache controllers, and today's VRAM. Toshiba, Fujitsu, and NEC have already agreed to become Rambus interface licensees.

Tate predicts that RDRAMs will enable designers to jump from 8-bit VGA 256-color palettes to low-cost 24-bit true-color graphics. But he admits that there are still barriers to the Rambus vision. "You're not going to do animated graphics on today's monochrome displays." Nevertheless, Rambus may provide a solution that will accelerate the progression toward true video PCs.

—D. L. Andrews

BSDI: Unixlike and Free of AT&T

To a cheering audience of 1000 Usenix conference attendees, former SunSoft employee Rob Kolstad announced his new company, BSDI (Falls Church, VA), and its new product, a Berkeley Unix–compatible operating system for 386 and 486 PCs. The Unixlike software, called BSD/386, is 100 percent free of AT&T code and licenses, which means it costs less: Including the kernel and full source code, it sells for $995. A binary-only (i.e., non-source code) version should be available in the third quarter of this year for $500.

BSD/386 is a complete operating system that is compatible with BSD 4.3 with BSD 4.2 networking. It includes TCP/IP, X Window System 11.5, Posix functions, ANSI C, C++, `troff`, Tex, and a reimplementation of Sun's Network File System. It supports more than a dozen popular Super VGA cards, most mice, and SCSI, IDE, and ESDI controllers. To use it, you'll need a 386 or higher PC with 4 MB of RAM and a 100-MB hard drive. By the third quarter, BSD/386 will be able to run all SCO Unix applications without a hitch, BSDI says.

The product is the result of years of effort by the Unix community to create a widely available, AT&T-code-free Unix workalike. The crowd responded to Kolstad's presentation with great enthusiasm, applauding and cheering each member of his team.

—Ben Smith

NANOBYTES

It wasn't quite the same as Dire Straits front man Mark Knopfler singing about moving refrigerators and color TVs, but as BSDI program manager **Rob Kolstad** explained all the various licensing options of his company's Unixlike BSD/386 software, he said with his usual wit, "I'm Crazy Rob. I've gotta move these kernels." □

At Buscon/92-West in Long Beach, California, IBM showed a technology demonstration of streaming data approaching a **160-MBps data transfer peak**. The demonstration used a modified RISC System/6000 deskside unit and a bus-master adapter card on the Micro Channel bus, both developed specifically for the demonstration. □

At UniForum, DEC announced version 1.0 of **DEC OSF/1**, what the company calls the "first production version" of the Open Software Foundation operating system. Users can't install this system, which is a developer's version, scheduled to ship last month. The end-user platform will be version 2.0, due in the second half of the year. □

At the recent National Association of Music Merchants International Music Market show, Passport Designs (Half Moon Bay, CA) announced a preliminary version of Producer, which the company calls "integrated digital audio and MIDI soundtrack software." The software, the first version of which will run on the Mac, will integrate computer animation, graphics, titling, laser discs, video, CD-ROM, MIDI, samplers, sound cards, and soundtrack software. The company also plans a Windows version. Passport says that the main use of Producer is as a media integration tool, accepting inputs from many sources and letting you build a final product. □

World Radio History

Delivering the Power: WATCOM C9.0/386



- **The Widest Range of 32-bit Intel x86 Platforms**
  32-bit DOS, 32-bit Windows, OS/2 2.0, AutoCAD ADS
- **The Industry's Leading Code Optimizer**
  Advanced global optimizer with new 486 optimizations
- **The Most Comprehensive Toolset**
  Debugger, profiler, protected-mode compiler and linker, 32-bit DOS extender with royalty-free run-time, licensed components from Microsoft SDK, and more
- **The Best Value in 32-Bit Tools: $895***

Unleash 32-bit Power!

WATCOM C9.0/386 lets you exploit the two key 32-bit performance benefits. The 32-bit flat memory model simplifies memory management and lets applications address beyond the 640K limit. Powerful 32-bit instruction processing delivers a significant speed advantage: typically at least a 2x speedup.

You Get:

- **100% ANSI and SAA compatible:** C9.0/386 passes all Plum Hall Validation Suite tests
- **Extensive Microsoft compatibility** simplifies porting of 16-bit code
- **Royalty-free** run-time for 32-bit DOS, Windows and OS/2 apps
- **Comprehensive toolset** includes debugger, linker, profiler and more
- **DOS extender** support for Rational, Phar Lap and Ergo
- **Run-time compatible with WATCOM FORTRAN 77/386**

32-bit DOS support includes the DOS/4GW 32-bit DOS extender by Rational Systems with royalty-free runtime license

- Virtual Memory support up to 32Mb

32-bit Windows support enables development and debugging of true 32-bit GUI applications and DLL's.

- Includes licensed Microsoft SDK components

32-bit OS/2 2.0 support includes development for multiple target environments including OS/2 2.0, 32-bit DOS and 32-bit Windows

- Access to full OS/2 2.0 API including Presentation Manager
- Integrated with IBM Workframe/2 Environment

AutoCAD ADS and **ADI** Development: Everything you need to develop and debug ADS and ADI applications for AutoCAD Release 11

Novell's *Network C for NLM's SDK* includes C/386

The Industry's Choice.

Autodesk, *Robert Wenig, Manager, AutoCAD for Windows:* "At Autodesk, we're using WATCOM C/386 in the development of strategic new products since it gives us a competitive edge through early access to new technologies. We also highly recommend WATCOM C/386 to third party AutoCAD add-on (ADS and ADI) developers."

Fox Software, *David Fulton, President:* "FoxPro 2.0 itself is written in WATCOM C, and takes advantage of its many superior features. Optimizing for either speed or compactness is not uncommon, but to accomplish both was quite remarkable."

GO, *Robert Carr, Vice President of Software:* "After looking at the 32-bit Intel 80x86 tools available in the industry, WATCOM C was the best choice. Key factors in our decision were performance, functionality, reliability and technical support."

IBM, *John Soyring, Director of OS/2 Software Developer Programs:* "IBM and WATCOM are working together closely to integrate these compilers with the OS/2 2.0 Programmer's Workbench."

Lotus, *David Reed, Chief Scientist and Vice President, Pen-Based Applications:* "In new product development we're working with WATCOM C because of superior code optimization, responsive support, and timely delivery of technologies important to us like p-code and support for GO Corp's. PenPoint."

Novell, *Nancy Woodward, V.P. and G.M., Development Products:* "We searched the industry for the best 386 C compiler technology to incorporate with our developer toolkits. Our choice was WATCOM."

Microsoft Windows · PC Magazine Editors' Choice · Info World Best in Its Class · Computer Language Productivity Award 1990 · Computer Language Product Excellence Award 1990 COLA

WATCOM **1-800-265-4555**

The Leader in 32-bit Development Tools

415 Phillip Street, Waterloo, Ontario, Canada. Telephone: (519) 886-3700, Fax: (519) 747-4971. * Price does not include freight and taxes where applicable. Authorized dealers may sell for less. WATCOM C and Lightning Device are trademarks of WATCOM Systems Inc. DOS/4G and DOS/16M are trademarks of Rational Systems Inc. Other trademarks are the properties of their respective owners Copyright 1992 WATCOM Products Inc.

Circle 135 on Inquiry Card.

World Radio History

NEWS

MICROBYTES

Spreadsheet Could Boost PenPoint

At-Hand, a spreadsheet developed for Go Corp.'s PenPoint operating system for pen-based computers, could be the first application to validate the PenPoint platform. Developed under the direction of Dan Bricklin, vice president of development for Slate (Scottsdale, AZ), the program fully exploits the advantages of pen computing.

Bricklin gave this reporter a preview of At-Hand running on a prototype pen-based machine from Samsung. Instead of using a traditional spreadsheet's edit line to enter labels and values, you just write directly into cells using the stylus. At-Hand offers a 256- by 8192-cell grid, immediate access to 90 built-in functions, and 15 types of charts and graphs. Bricklin described the language as "BASIC-like...but it knows about spreadsheet primitives such as cells and ranges."

At-Hand reads and writes WK1 (Lotus 1-2-3) and XLS (Excel) files. In a typical scenario, Bricklin says, users will transfer files to and from their pen and desktop systems. When At-Hand files are sent to the desktop, the program provides a choice of export formats. Of course, it supports PenPoint's standard gestures and connectivity and recognizes handwriting, with optional deferred recognition. It also incorporates an extensible graphics language that lets corporate developers improve the spreadsheet's graphing capability by creating specialized graph types.

The software uses 1.5 MB of hard disk space and requires only about 500 KB of RAM to run. Although it is scheduled to ship in the second quarter of this year at a list price of $295, At-Hand product manager Lisa Underkoffler cautions that the schedule is dependent on Go's releasing PenPoint.

—D. L. Andrews

RFI Problems Plague Pen Systems

Massive increases in RFI from pen-based computers are causing the FCC to rethink its testing procedures; it has already delayed the release of at least one pen-based system. The RFI problem doesn't pose a health threat to users, but it does mean that some of the eagerly awaited pen-based designs will be later to market than expected because of redesigns.

The problem is that when you place your hand close to the screen of an operating pen-based computer, the RFI the computer produces increases enormously. Since all pen-based systems involve writing on the screen with a stylus, that increase occurs with normal use of the system.

Charles N. Cobbs, chief of the FCC's equipment and authorization branch (Columbia, MD), says that the emissions increase can be as much as 15 dB. "This is not like tripping over a curb, it's like falling over a cliff," Cobbs says. "We couldn't let that go."

Essentially, the human body serves as an antenna to radiate additional energy from the computer. The radiation is not dangerous to people, but it is enough to interfere with electronic equipment.

The problem was unexpected because the FCC's current test standards don't allow for a user's effect on the system RFI. As a result, the manufacturers weren't looking for those effects in their designs. The first company to get caught with this problem was NCR and its 3125 pen system.

—Rick Cook

Apple and Sharp May Be Paired Up in the Consumer Market

Now that Apple chairman and CEO John Sculley has said that Apple will enter the consumer electronics market, observers have wondered what products the company will offer. Sculley told attendees at the semiannual Consumer Electronics Show that Apple will enter the "digital consumer information products sector of the consumer electronics industry" and reiterated Apple's interest in the technology of Personal Digital Assistants.

Sculley also said that Apple has worked this year to establish relationships with several leading consumer-electronics companies. Sony may be the company that comes to mind as first choice for a partnership, but sources say that Apple will work with Sharp on CD-based devices, which may already be built. Longtime Apple partner Frogdesign may also have had a hand in the devices' design.

—Larry Loeb

NANOBYTES

When you see this man's face, think of QuickTime. In his keynote address at the MacWorld Expo show,

Apple chairman and CEO **John Sculley** said that what people would remember the most about his time at Apple is QuickTime—even more than the Macintosh. □

It's also now clear that Apple thinks QuickTime will influence platforms other than the Mac. At the show, Apple announced plans to bring the benefits of QuickTime to other computing environments such as DOS, Silicon Graphics, DEC, and Cray Research. To further extend the adoption of Apple's Movie file format, **Corel Systems** is developing a file format translator to be shipped with the QuickTime Starter Kit, a product for those who want to explore the capabilities of QuickTime. The Corel utility will allow the conversion of popular DOS and Windows format presentations, graphics, and animation files into QuickTime movies. Apple wants QuickTime to be the cross-platform method for personal computers to handle multimedia. □

At NetWorld, CE Software announced QuickMail for MHS (Message Handling Services), which the company says will provide Novell network users with "similar functionality and flexibility" to the QuickMail product for the Mac. Previous versions of QuickMail supported Macs and PCs, but they required both a Mac server and an AppleShare network. The planned new version will provide **native NetWare MHS** support for the Macintosh. □

Apple is reportedly working on new technology that lets people control off-the-shelf Macs using ordinary spoken language. The technology may be used in future consumer products. □

World Radio History

NEC introduces a 486 series that has a built-in survival instinct.

World Radio History

NEC's new PowerMate Express Series. A lesson in survival and security.

Next time you need a mission-critical PC or network server, here's something you might want to think about: NEC is one of a handful of companies that have received the Deming Award, the highest honor bestowed in the quality assurance field, on five separate occasions.

Imagine a line of affordable 486 PCs and towers that is completely modular and upgradable.

Now imagine how secure you'd feel in your decision to purchase such a system. A system that would not only meet your needs today, but also adapt to changing technologies.

We adapt to your environment.

With NEC's new PowerMate® Express™ Series, you get total subsystem modularity and scalability, including CPU, memory, video, disk subsystems, and EISA option slots at no extra cost. All working in balance with each other. And flexible enough for your particular needs.



An easy-open chassis design, featuring thumb screws and snap-in device rails, gives you convenient access to all internal subsystems. Standard SIMM sockets—16 of them—provide for easy, inexpensive memory expansion.



You can add an MIS-preferred EISA SCSI host adaptor. And choose from three video options—Base VGA, 1024 VGA, even BITBLT EVGA for graphics-intensive applications.

In short, you can configure your system exactly the way you want it.

128-bit memory path gives us quicker reflexes.

Instead of the traditional 32-bit memory path, our PCs have one that's four times as wide, guaranteeing you 0-wait state performance even at faster processor speeds. Giving you the ability to handle data-intensive applications or networking demands with ease.

Our best feature hasn't been invented yet.

Perhaps the best feature of the PowerMate Express Series is its ability to reduce the possibility of your system becoming obsolete soon after you buy it.

C&C Computers and Communications

Novell Labs Tested & Approved

*Manufacturer's suggested retail price. PowerMate is a registered trademark and Express is a trademark of NEC Technologies, Inc. Intel is a registered trademark of Intel Corp. All other trademarks are the property of their respective owners. ©1992 NEC Technologies, Inc.

World Radio History

Our CPU scalability starts at 486SX/20 for only $2,999* and goes up through 486SX/25, 486/33, and beyond.

All at affordable prices.

What's more, our modular systems are ready for the next generation of Intel® microprocessors, and adaptable to new developments in video and memory technologies.

We can take the heat.

We've given each of our PCs generous power supplies to handle even the most power-hungry components. As well as a three- or four-fan array, to enable your system to keep cool—and keep working—under any amount of pressure.

Proof that a well-balanced system is a weapon.

Scalability. And balance. In the end, that's what distinguishes our 486 computers from others in their class.

Just look at a side-by-side comparison of our features versus COMPAQ's and AST's.

We think it's further proof that investing in a PowerMate Express Series PC or tower could very well be one of the best decisions you'll ever make.

A decision that will help you survive in today's business environment. And tomorrow's.

Desktops:	NEC PowerMate® Express Desktops	COMPAQ Deskpro/M Series	AST Premium II Series	Advantage
Towers:	PowerMate Express Towers	Systempro/LT Series	Premium SE & 33 Series	Advantage
1. # SIMM sockets standard	16	4	4	NEC
	16	4	4	NEC
2. Maximum RAM capacity	64	64	80	AST
	112	64	80	NEC
3. Internal hard-drive storage capacity	2.7GB	1GB	420MB	NEC
	4GB	4GB	2.4GB	Tie
4. Power supply	285W	240W	167W	NEC
	388W	355W	300W	NEC
5. Internal fans	3	1	1	NEC
	4	2	2	NEC
6. Snap-in device rails	Yes	No	No	NEC
	Yes	No	No	NEC

Data based on manufacturer-supplied specifications

For more information, call 1-800 NEC-INFO (in Canada, 1-800-343-4418), or NEC FastFacts at 1-800-366-0476, #XPRESS (977377), for immediate literature.

Because ↑ is the way you want to go. NEC

Circle 96 on Inquiry Card.

World Radio History

NEWS

MICROBYTES

Microsoft and Intel Team Up on Portable Power

Until computer hardware gets less energy-hungry, the only way to cut power use in portable machines will be through better software tricks. Microsoft and Intel have now created a suite of technologies, called the Portable Computing Initiative, that are intended to do just that. By matching operating-system features with the special hardware of portables, the two companies aim to improve the efficiency of mobile computing.

The Portable Computing Initiative encompasses several efforts, including putting system software in ROM instead of on disk, developing drivers for PCMCIA solid-state storage cards, and building a simple data transfer utility into DOS.

The most innovative development is called Advanced Power Management (APM), which gives applications the ability to tell the hardware when it doesn't need certain system resources, such as I/O ports; this will let programs help the system save energy. Most power management today is performed only at the system level, without regard to program state.

According to Microsoft, Windows and many applications are idle 50 percent to 75 percent of the time, waiting for user input or other system events. By providing an application programming interface (API) through which compliant programs can write to the system BIOS and say that they are idle, you can cut power usage by as much as 25 percent, Microsoft says. Not only can the system be intelligently shut down, but it can also select peripherals or add-ins. The APM scheme is defined independently of the CPU, chip set, and operating system.

Why use an API instead of building these features directly into the operating system? Unlike in the Mac world, where virtually all software interacts with the system through defined system calls, many DOS programs bypass the operating system and interact directly with firmware.

—Owen Linderholm

Headland's Cache Enhancement Chip Set Optimizes the 486

Headland Technology (Fremont, CA) has introduced a chip set with cache-enhancement features that optimizes the performance of the 486 processor's internal cache. The company says that the benefit of the HTK340 chip set is that the processor never has to wait for write operations, resulting in improved system performance.

As Headland describes it, the significant performance determinate, on the system level, of the 486 is efficiency in memory write operations. Headland says its advanced features eliminate the write bottleneck by integrating a four-level-deep write buffer with out-of-order operations and byte gathering. The company tries to eliminate the DRAM write bottleneck by assembling 8- and 16-bit writes and writing them as 32-bit writes, and by allowing out-of-order operations while maintaining the integrity of the data.

Headland claims a twofold to fourfold improvement in DRAM write operation efficiency. Like the first member of this family, the HTK320 386DX chip set, the HTK340 is a two-chip set that includes an ISA bus controller chip and a memory controller unit. A Headland product line manager admitted that the improvement offered by the chip set isn't all that evident with low-level benchmarks. It shows up more on "complex, real-world" benchmarks.

The chip set supports frequencies of up to 33 MHz. It will cost $45 each in quantities of 1000.

—Ken Sheldon

C&T Quits Multiprocessor Business

Chips & Technologies is pulling out of the multiprocessing chip-set business. Saying the market is too small, the company has announced that it will try to sell off its M/PAX architecture and technology, which can tie together as many as six 386 or 486 processors in a LAN server. C&T was the only company left trying to make money as a merchant supplier of multiprocessing chip sets. Most multiprocessing servers, such as the Systempro from Compaq, use proprietary designs. ■

—Rick Cook

NANOBYTES

To reduce use of the power-hungry hard drive, Microsoft has developed a ROM-based version of DOS 5.0, and it's now shipping. The company also says it has created scalable versions of DOS 5.0 that take up less RAM in exchange for reduced functionality. One tiny 4-KB version of COMMAND.COM lets a system run DOS programs but not perform any other functions. This will be especially useful for palmtops with limited memory and that only need to launch programs. □

Slate vice president Dan Bricklin predicts that in two years some pen-based computers will retail for under $1000. The same systems today can cost as much as $5000, if you can find one. Bricklin said that pen-based systems running PenPoint are currently **"scarcer than hens' teeth."** After a pause, he added, "Actually, there are a lot more hens' teeth in the world." □

Specular International (Amherst, MA) is working on a tool for reducing the time required for rendering graphics images. A new program called **BackBurner** lets you render a single image on multiple Macs by dispersing rendering tasks over Ethernet or AppleTalk networks and relegating the most intensive rendering duties to the fastest available machines. BackBurner must be used with Infini-D, Specular's 3-D rendering, modeling, and animation software. Pricing has not been determined. □

The great baseball player Satchel Paige once said, "Don't look back—something may be gaining on you." Intel must feel that way sometimes about AMD. **AMD** is developing a 486 and a 33-MHz version of the Am386SX, which will be manufactured with an advanced 0.7-micron CMOS process that allows low power operation. ■

World Radio History

The Borland *Visions* Video Series

Now the easiest way to learn software!

NEW!

Borland makes learning fun

Now there's a faster, easier and more entertaining way to gain proficiency in today's top software and advanced technology. In a matter of hours, you can master all the concepts presented. You're taught exactly what you want to learn. And it's all self-paced, so you can learn when and where it's convenient for you.

David Intersimone, Borland's language ambassador, makes learning software fun!

Learn from the experts

Taught by internationally recognized experts, each videotape training course provides a thorough and fun way to learn, using easy-to-understand examples presented in clear, everyday language. Lively presentation is further enhanced by state-of-the-art production techniques and exciting animation graphics. Easy-to-follow workbooks written by recognized authorities solidify the concepts. And, in many cases, free sample source code is included so you can get off to a fast start by simply plugging it into your application.

> "Borland clearly invested a lot of care in this project, and the result is an excellent example of what a multimedia course can achieve when done right."
> Craig Menefee
> writing about *World of C++* in *Computer Shopper*, Feb. 1992

Ideal for everyone who uses a PC

Programmers, developers, MIS, department managers—nearly anyone who uses a PC can benefit from the Borland *Visions* Video Series. Every videotape is a complete, step-by-step tutorial. So whether it's understanding what Object-Oriented Programming is all about or learning how to best manage corporate data, Borland has a video for you. Most of all, it's fun. Order today!

Every video training package under $100!

World of ObjectVision

Learn to create your own Windows applications *without programming*. With ObjectVision® it's easy, and this clear videotape with sample applications makes it even easier. Now everyone from non-programmers just getting started . . . to developers looking for faster application prototyping can create their own Windows applications in no time. Hosted by John Mandell. Sample ObjectVision applications included. 85 minutes.

$39.95

Free compiler included!

Learn Programming Today with Turbo Pascal

Did you ever wish you had the power to program your own computer and write your own programs? Easy videotape instructions, workbook and sample programs will teach you how to write programs in record time. Perfect for the beginning programmer. Hosted by Zack Urlocker. Workbook written by Keith Weiskamp. 90 minutes.

$69.95

World of Database Management

Now more than ever, information is power. Learn the latest concepts in database management software, including object-oriented technology and Windows database technology. If you want to manage corporate information in the most efficient and profitable way, this videotape is a must-see. Hosted by Philippe Kahn. 29 minutes.

$19.95

World of Objects

Philippe Kahn and his special guests take you on a guided tour of the basic concepts behind Object-Oriented Programming. A fact-filled overview full of fun and insight for everyone. 20 minutes.

$19.95

Make the Move from C to C++!

The Award-winning *World of C++*

World of C++ is the easy way for the experienced C programmer to step up to C++ and the power of Object-Oriented Programming. With 21 lively video lessons, David Intersimone gives you a solid understanding of how C++ works, and how you can use it to streamline your programs and speed through development cycles. Comes complete with videotape, workbook and sample source code. Workbook written by Bruce Eckel. 120 minutes.

only $99.95

"The combination [of video, workbook and source code] . . . is the best introduction I've ever seen to any complex language."
Jerry Pournell, *BYTE*, December 1991

World of ObjectWindows for Turbo Pascal

The ObjectWindows™ application framework provides easy-to-add-on Windows user interfaces for Turbo Pascal® This complete training package will show you how to get the most out of this cutting-edge technology in the shortest amount of time. Hosted by David Intersimone. Workbook written by Tom Swan. Sample source code included. 120 minutes.

$99.95

World of ObjectWindows for C++

Now C++ programmers can skip the tedious chore of writing Windows user interfaces—with just a few lines of code you can add the robust ObjectWindows application framework to your application. Two videotapes, workbook and source code make it easy to get up to speed fast in Windows. Hosted by David Intersimone. Workbook written by Tom Swan. 120 minutes.

$99.95

Now, with an order over $30, you get *World of Objects* or *World of Database Management* absolutely FREE!

GET A FREE VIDEO

To order, and get your free video, see your dealer or call now,

1-800-331-0877, Dept. 6913

60-day, money-back guarantee

BORLAND

Software Craftsmanship

Visions VIDEO SERIES

Suggested retail prices. All prices are in U.S. dollars. Dealer prices may vary. Copyright © 1992 Borland International, Inc. All rights reserved. All Borland products are trademarks of Borland International, Inc. BI 1481

Circle 296 on Inquiry Card (RESELLERS: 297).

World Radio History

Windows 3.1 Is Ready to Roll

JON UDELL

After a long gestation period, Windows 3.1 has matured into a solid product that fixes past problems and introduces mainstream PC users to multimedia

Scalable fonts, compound documents, and multimedia support are headline attractions, but the Windows 3.1 story doesn't end there. A great many fixes and refinements—none revolutionary—conspire to make version 3.1 a faster, friendlier, and stabler system. You'll notice improvements as soon as you launch Setup. Following an optional tutorial, you can take the "express" or "custom" route. Choose the latter, and you specify the games, wallpaper, and accessories you want and skip the rest. (The multimedia subsystem is not optional, however.)

You'll notice longer lists of supported display adapters, printers, and networks. The standard display drivers now include Texas Instruments Graphics Architecture, Extended Graphics Array, 8514/A, and a generic Super VGA (800 by 600 pixels with 16 colors).

Something that most users won't see, but that I appreciate, is Setup's more intelligent handling of network installation. The new Setup /A option streamlines the process of loading a site-licensed copy of Windows onto a network drive and marking the files read-only. Tweak a few lines in a Setup file, and you can present users with shared Program Manager groups containing only the applications you want them to run, while crippling Program Manager's ability to launch unauthorized software or to create new groups and items.

Serious network administrators still have plenty of reasons to lean on advanced utilities like Windows Workstation from Automated Design Systems. But those who rightly complained about LAN installation of Windows 3.0 will find version 3.1 more cooperative.



Objects embedded in or linked to a Write document launch their creators when you double-click on them. It looks easy, but you may be surprised at what happens when you save, copy, or print the document. OLE breaks important new ground but raises thorny user-interface issues.

Printing with TrueType

TrueType isn't just an Adobe Type Manager clone. On your screen, the two technologies produce similar results—fonts that scale cleanly. But TrueType's superb printer support transcends what ATM offers. If you have a Hewlett-Packard LaserJet Series II and you don't have HP soft fonts, or don't have them installed properly, ATM can create pages that match what you see on-screen only by cranking out huge bit maps that clog your network and take forever to print. TrueType, on the other hand, conjures up the downloadable fonts on the fly. It's fast, convenient, and utterly transparent.

The same technique works with PostScript printers: TrueType can manufacture unhinted Adobe Type 1 fonts on the fly. If you inspect the PostScript code that's generated, you'll see that the driver cleverly defines only the characters actually used in the print job. You can also send bit maps, or, if you know that the printer has an Adobe font whose metrics match those of a TrueType font, you can just invoke the printer fonts directly.

Choose Your Mode

Windows 3.1 abandons the vestigial real mode. Users won't mourn its passing—version 3.0 would run on an 8086, but not happily—and programmers will breathe a collective sigh of relief. That leaves standard mode for 286 and low-end 386 machines and enhanced mode for 386/486

World Radio History

It Talks, It Sings, It's Multimedia Windows

Tom Yager

Windows 3.1 seems like much more than a point release. But one crucial piece of it—multimedia support—hit the streets several months before its commercial release. The Windows Multimedia Extensions are part of the Multimedia PC specification (see "The Multimedia PC: High-Powered Sight and Sound on Your Desk," February BYTE). With version 3.1, the software side of MPC becomes a standard part of Windows.

What the extensions buy you depends largely on your configuration. The most accessible addition is audio. If you have an audio I/O card like Creative Labs' Sound Blaster Pro, the new routines and applications in version 3.1 will let you record and play digitized sound. If your audio card supports MIDI, or you have a component MIDI device that's compatible with Roland's MPU-401, version 3.1 will let you record and play MIDI data. The Multimedia Extensions are, not surprisingly, extensible, so in addition to audio and MIDI, they support the following media types: CD audio, videodisc, video overlay, and animation. Each of these types (except animation) requires additional hardware and, in most cases, drivers supplied by vendors.

In a way, animation requires additional hardware, too: a Mac, which is now the only way to create an MPC-compatible animation. Support for full-motion (digital) video (using the "digitalvideo" media type) is expected shortly, and there are also reserved (but not supported) media types called dat, scanner, vcr, and other. I don't know what an "other" does, but the rest of the names are self-explanatory.

Some of the media types are covered by their own low-level programming calls. For some operations, such as MIDI recording, it helps to have the most direct control possible. But the heart of the multimedia programming support is the Media Control Interface. This is a well thought-out, high-level function-call interface to a command interpreter. An MCI command string includes a command, a target device, and arguments. The interpreter routes the command to the appropriate handler for the specified device.

The result is readable code and straightforward addition of new media types to existing applications. The string interface also works well with alternative Windows programming environments like ToolBook. Those of us who work in C need Microsoft's Multimedia Development Kit, which requires a CD-ROM drive and the Windows Software Development Kit.

MCI's command structure is patterned after a tape transport. Commands supported by most devices include open, play, and pause. The first two are all that's required to get most media types to play or display their output. Here is one that plays a digital audio file called WILLIAM.WAV:

```
open \sounds\william.wav
type waveaudio alias bill
play bill
```

The alias simply gives you an easier way to reference the open file. Playing a MIDI file, an animation, a track on an audio CD, or any of the other supported media types is no more difficult than this, and digital video and other future types will follow the same command format.

If you're not a programmer, the fact that MCI is so easy to write helps you as well. MPC-compatible software will become available rapidly because MCI is such a cinch to learn and use. Microsoft probably hopes you'll see all the multimedia stuff in version 3.1 and run out and buy an MPC upgrade kit. Maybe that's not such a bad idea.

Tom Yager is a BYTE technical editor and director of the Multimedia Lab. He can be contacted on BIX as "tyager."

workstations with 2 MB or more. Version 3.1 will run in standard mode in the presence of DOS 5.0's EMM386 memory manager, something that version 3.0 refused to do. But users who have favored standard mode even on high-end hardware might want to reconsider that policy in light of version 3.1's enhanced mode.

The virtual memory manager has been overhauled, and disk I/O benefits from a new 32-bit virtual device driver that works with Western Digital and compatible hard drive controllers. A performance boost, not mode-dependent, comes from the new Smartdrive. Caching both reads and writes, it keeps my disk noticeably quieter than its version 3.0 counterpart.

Keep on Keeping On

As a DOS multitasker, version 3.0's reach often exceeded its grasp—it encouraged you to try things that either wouldn't work or wouldn't work reliably. This wasn't surprising, given the sandy DOS foundation on which Windows builds its airy superstructure of virtual machines (VMs).

What has pleasantly surprised me about version 3.1 is that, although the basic architecture hasn't really changed, DOS multitasking does work a whole lot better. Preliminary CPU and screen I/O benchmarks peg version 3.1 VMs well ahead of their version 3.0 counterparts. And the VMs are much more stable. Incidentally, version 3.1 can handle 9600-bps serial communications, even in the background.

Matching some of OS/2 2.0's features, windowed VMs now provide DOS mouse support and offer a variety of alternative fonts. An .INI file remembers the size and location of windowed DOS programs.

Windows now traps the three-fingered salute. Press Ctrl-Alt-Del, and version 3.1 prompts you to continue the current DOS (or Windows) task, kill it, or actually reboot. If you pull the plug on a DOS task in this situation, Windows shuts it down without the scary termination message.

According to Microsoft, Windows does a sanity check to see if DOS seems healthy. Even so, a rogue DOS task can subtly alter low memory and bring down the whole

World Radio History

system. Does that matter? In practice, it may not. I think many users just want Windows to run their important DOS programs "well enough," and version 3.1 meets that criterion better than version 3.0 did.

If a Windows task meets with misfortune—at your hands or in the form of what used to be called an unrecoverable applications error—you're in better shape than before. Windows again performs a sanity check, this time on its own data structures, and, according to Microsoft, it can even repair damage so the system can continue safely.

Additional lines of defense include stricter parameter checking (both at run time and in the Windows header file), more informative error messages when protection faults do occur, and a postmortem utility (Dr. Watson) that records Windows' state and the user's description of the actions leading to the fault.

Given that Windows and its tasks still share one local descriptor table in version 3.1, protected mode isn't as bulletproof as in Unix or OS/2. But the pragmatic approach that Microsoft has taken—managing faults both proactively and reactively—should help matters a lot.

On the Applications Front

Most Windows 3.0 applications I tried ran happily under version 3.1, including PageMaker, CorelDraw, Picture Publisher, Persuasion, Turbo Pascal for Windows, Word for Windows, and Excel. As you'd expect, I ran into some programs that will require maintenance upgrades, including PowerBuilder, Quest, and WinSleuth Professional. In general, however, your transition shouldn't be traumatic.

Old chestnuts like File Manager, Write, and Paintbrush improve in a variety of ways. For starters, they now exploit common dialog boxes for opening and saving files, selecting fonts, and printing. Mac programmers who have used `SFGetFile` and `SFPutFile` for years will find it amusing that Windows is only just now getting into the act. Still, better later than never.

File Manager now presents directory trees in a more useful double-pane format and reads in directories much faster. While it was formerly unusable on large network drives, it has become a handy tool for browsing and disk grooming. File Manager is also the source of version 3.1's new drag-and-drop behavior. You can drag files out of File Manager's window and drop them onto Print Manager, onto iconized applications, or into open application windows. To print in this manner, the document you drop must be associated with an application that must define a print command in the new system registration database.

An even more interesting thing happens when you drop a .BMP file onto an open Write document. Windows thinks for a minute, and a Paintbrush icon appears in the file. When you double-click on it, Paintbrush launches and loads the bit map. You've just used drag-and-drop to embed a reference to one document inside another. Behind the scenes, Windows ran a tool called Packager to specify the embedded object's appearance (the Paintbrush icon) and its content (the reference to the .BMP file). Welcome to the weird, wonderful world of Object Linking and Embedding (OLE).

Everybody Say OLE

The version 3.1 accessories include OLE servers (Paintbrush and SoundEdit) and OLE clients (Write and CardFile). Other applications that formerly rolled their own OLE but can interoperate with the OLE libraries shipped with version 3.1 include Word, Excel, and Ami Pro.

The Write document in the screen contains a series of embedded and linked objects. The two Paintbrush images appear identical, but they aren't. The first, an embedded object, resides anonymously within the Write document. The second, a linked object, takes up the same amount of space in the Write document but refers to a named Paintbrush file. In both cases, double-clicking on the object launches Paintbrush. But the embedded object is accessible only via Write; the linked object can also be reached by loading its corresponding file into Paintbrush.

In addition to the drag-and-drop I've already described, you can embed an object by pulling a file directly into the client using the Insert Object command, or by copying from the server to the Clipboard and then using the client's Paste Special command. To link, you copy from the server to the Clipboard and use either Paste Special or Paste Link in the client.

This all sounds simple, and in a way it is, but it takes a surprisingly long time for all the implications to sink in. The three flavors of Paste command—Paste, Paste Special, and Paste Link—can be confusing, especially since Paste Special usually lists a variety of formats the client can use to render the embedded or linked object. Yet the results of each of these procedures can look exactly the same.

Also, those results may or may not be what you expected. When you paste a range of cells from a spreadsheet into Write, you expect to see something that looks like a spreadsheet—and you do. When you double-click on the sound object, you expect to hear something, and with a sound board installed, you do. But when you paste a range of text from Word, what appears is Word's icon, not text. Why? The OLE client library can render only metafile or bit-map data. Microsoft has defined a way for an OLE server to provide an "object handler" that renders data on its own terms—formatted text, in the case of Word.

OLE in its current form is a bold experiment. It lacks the network awareness of Apple's Publish/Subscribe, begs for a next-generation file system that is itself somehow object-oriented, and often doesn't behave the way you'd expect, but it's a good start. As programmers learn how to use the daunting OLE libraries, I think we'll see Windows software evolve in fascinating new directions. ■

Jon Udell is a BYTE senior technical editor at large. You can reach him on BIX as "judell."

THE FACTS

Windows 3.1
$149; upgrade from Windows 3.0, $49

System requirements:
Standard mode: 286 or higher with 1 MB of RAM, a mouse, and a supported monitor.
Enhanced mode: 386 or higher with 2 MB of RAM, a mouse, and a supported monitor.
Multimedia Extensions: a sound board and/or a CD-ROM drive.

Microsoft Corp.
1 Microsoft Way
Redmond, WA 98052
(800) 426-9400
(206) 882-8080
fax: (206) 883-8101
Circle 1220 on Inquiry Card.

World Radio History

Now, upgrading a computer is as simple as plugging it in.

You don't have to replace circuit boards. You don't have to spend an arm and leg for upgrade modules. All you need is two fingers. One microchip.

And an AcerPower™ 386SX or 486SX.

Because Acer has invented something no other computer in the world can give you. A breakthrough technology that makes upgrading a computer dramatically easier than ever. For a lower cost than ever. And it's available off-the-shelf from dealers everywhere.

We call it ChipUp.™

Take the AcerPower 386SX. It comes out of the box as a 386SX machine. When you're ready to upgrade, just drop in a 486 chip. That's it. The computer does the rest–upgrading itself automatically. Giving you up to five times the power. It's like buying an entirely new, state of the art computer for the price of a single chip.

So why worry that the computer you bought today will be obsolete tomorrow, when it's such a snap to prevent it?

Punch in 1-800-SEE-ACER in the U.S. and Canada and find out how a computer can save you money. Now. And in the future.

Acer, the Acer logo, AcerPower and ChipUp are registered trademarks of Acer Inc. and Acer America Corp.
Patents pending for ChipUp technology.

Circle 35 on Inquiry Card (RESELLERS: 36).

World Radio History

Have Docking Station, Will Travel

RICH MALLOY

The NCR 3170 Safari Notebook, with its FingerPoint Mouse, signals a new generation of portables

Last year, Safari Systems, an interesting joint venture of AT&T and the Japanese company Marubeni, brought out the Safari NSX/20 notebook (see "IBM and AT&T Enter the Fray of 386SX Notebook Computers," August 1991). That system went on to win a BYTE Award of Merit and quite a bit of attention. This year, Safari Systems has been folded into AT&T's recent acquisition, NCR. The company has just introduced a bold new machine, the NCR 3170 Safari Notebook, which may set the pace for many notebooks to follow.

A Designer Notebook

Like the NSX/20, this new notebook is stylish enough to feel right at home in a designer showroom. But this system wasn't meant to sit around idly. It seems to have been purposely designed for three things: to travel, to run Windows, and to communicate. Based on the early prototype that I saw, I believe it will probably excel at all three.



Photo 1: *The NCR 3170 Safari Notebook is similar in style to the award-winning Safari NSX/20 notebook.*

For traveling, the system is small and light (only 5 pounds) and features the battery-friendly 386SL processor. (You can also save power by manually setting the speed to 6 or 12 MHz.) The size of the notebook is small enough (8 by 11 by 1¼ inches) to let you fit it into a briefcase with a ream of 8½- by 11-inch paper.

To achieve the light weight, the floppy drive was put into a small external box, but it will be included in the price of the system. This arrangement lets you leave it home if you don't need it. To complement the 386SL processor, a power management system can automatically save power by cycling the system through four states: normal (25 MHz), slow (3.125 MHz), sleep (0 MHz), and suspend (the system shuts down and draws only 20 milliamperes).

Although there is no internal floppy drive, the new Safari system is one of the first to include a slot for PCMCIA cards. These cards are used mostly for adding memory or data storage, but there will soon be PCMCIA cards that function as network interface cards, 9600-bps modems, and even wireless modems.

For Windows, the system will feature 2 MB of memory (expandable to 20 MB) and a 17-millisecond 80-MB hard drive, which can hold at least a few Windows applications. A customized version of Windows 3.1 will be included with the machine, as will a power management–aware version of DOS 5.0a and an Asymetrix ToolBook TourGuide. The modifications to Windows will include such things as a large mouse pointer for easy use on a monochrome LCD screen. The 25-MHz 386SL processor with a 64-KB cache (and socket for a 387SL) ensures that the system will be powerful enough to handle almost all Windows tasks easily.

The display is a 9½-inch sidelit triple-supertwist VGA LCD using cold-cathode fluorescent tubes. The contrast is excellent, even in direct sunlight.

For communications, the NCR 3170 includes a 2400-bps modem with MNP level 5 and V.42bis error correction and compression, and 9600-bps send/receive fax capability. Other ports are standard-size connectors for one serial and one parallel device (with enhanced data-transmission

World Radio History

capabilities), a mouse or keyboard, and a VGA monitor. On the software side, the system includes a Windows software package that allows background connection with AT&T Mail and BitFax software.

The FingerPoint Mouse

Perhaps the most unusual feature of the NCR 3170 Safari Notebook is its pointing device, the FingerPoint Mouse, which sits in the lower right corner of the keyboard, where the cursor keys are usually located. In fact, the FingerPoint Mouse replaces the cursor keys, with good results.

The FingerPoint Mouse consists of three keys that are aligned horizontally. The center key is round and about the size of a penny, and it can tilt in any direction. Tilting it in any direction moves the mouse in the same direction. The two keys to either side function like the two mouse keys on a Microsoft Mouse.

What about the cursor keys? As it happens, the FingerPoint Mouse can control either the mouse pointer or the cursor. You merely press two keys simultaneously to toggle between the two functions.

How well does the FingerPoint Mouse work? There are two answers to that question. When it is used to control the cursor, the function is fairly straightforward. In fact, in some cases it is better—and definitely more intuitive—than a set of cursor keys. But in mouse mode, the answer involves some personal taste, which is usually the case when mice are involved. Based on an early prototype that I used, I found the FingerPoint Mouse good for small precise movements, such as moving columns of text in a desktop publishing program.

Opinions on the FingerPoint Mouse will vary. However, dedicated mouse users will appreciate the PS/2-style mouse port on the side of the system.

A Portable Docking Station

A docking station—a desktop device that attaches to a notebook and provides additional capabilities—is nothing new. But for its docking station, Safari has provided a novel twist: portability. This docking station is so small that even when it is mated with the notebook, the entire unit can still fit inside some briefcases.

This small size belies the capabilities inside: three bays for peripherals (e.g., a floppy drive) and two expansion-card slots (one full-length AT slot and one half-length XT slot). Depending on how many expansion cards are inserted, there is even space inside for two nickel-cadmium batteries of the same type that is used by the notebook. The total size of the unit, including notebook and docking station, is only 12 by 15 by 3 inches. The weight, loaded with peripherals and two batteries (plus one in the notebook), is 14 pounds.

Photo 2: *The docking station is almost as portable as the notebook itself. It weighs only 9 pounds with its batteries.*

Safari envisions the docking station being outfitted with a CD-ROM drive and an RF modem. In fact, an RF modem based on the ARDIS network should be available around the same time the docking station is—near the end of this month.

Multiple Communications Options

Perhaps the most useful feature of the new Safari system is its wide array of communications capabilities and options. Safari designers have obviously not been shy about exploiting the communications expertise of two of its parent companies, AT&T and NCR.

As mentioned above, the NCR 3170 comes standard with a fax/data modem (either 2400 or 9600 bps) and Windows software for accessing fax messages and AT&T Mail. Currently, there is an interesting gateway in AT&T Mail that allows you to send short messages to Telefind alphanumeric pagers. New wireless modems, such as the ones mentioned for the docking station and the PCMCIA slot, should allow two-way wireless communication fairly soon.

Two-way wireless communication is where the NCR connection should come in handy, with its ARDIS cellular network. When these modems become available, Safari owners will be able to purchase modems for either the ARDIS network or the more common voice-based cellular network.

Extras

There is a maximum contrast mode for easier viewing of text. In this mode, all text-mode colors are mapped to either black or white, without any intermediary shades of gray.

There is a CPU speed lock, which lets you bypass the power management facilities and lock in a desired CPU speed for performance-sensitive functions.

Finally, the small LCD window displaying various system-status icons can be seen if the system is open or closed. In addition, a mail icon in this display flashes when the serial port is in use and can be programmed to stay on when a mail message has been received.

Prices for the new notebook were unavailable at press time, but the price of a low-end version with an 80-MB hard drive should be around $4700.

All in all, the NCR 3170 Safari Notebook combines a considerable amount of power, usability, and impressive design in a very small package. Shoehorning Windows into a system that can be easily carried and used in a variety of different locations is no easy task. The BYTE Lab should soon follow up with a review of a shipping version of this system. But until then, this is a system that deserves a good deal of attention. ■

Rich Malloy is an executive editor for BYTE located in New York City. He can be reached on BIX as "rmalloy" and on MCI Mail at #306-6564.

THE FACTS

NCR 3170 Safari Notebook
with 2 MB of RAM, an 80-MB hard drive, and a 2400-bps modem; or with 4 MB of RAM, a 120-MB hard drive, and a V.32 modem with fax capability; prices not available at press time

NCR Corp.
1700 South Patterson Blvd.
Dayton, OH 45479
(800) 225-5627
(513) 445-5000
Circle 1233 on Inquiry Card.

World Radio History

— Full native 32-bit programming power —

C++ PLUS.

ONLY ZORTECH™ C++ OFFERS A TRUE MULTI-PLATFORM COMPILER AND MUCH MORE.

When it comes to building larger, more complex applications, C++ is the language of choice. And now with Zortech C++, Symantec presents the only C++ compiler that provides professional tools for Windows,™ DOS and OS/2 in a single, integrated package.

Zortech C++ goes well beyond the other C++ and C compilers by delivering more of the tools serious programmers demand—plus a collection of exclusive features designed to increase your productivity and reduce your development time.

All of which means you'll get your applications to market faster than ever before.

For starters, our unique WINC library automatically converts DOS command line programs to true Windows applications. And you won't need to switch development systems, because you'll have the flexibility of moving to different platforms.

The security of one compiler across multiple platforms has never been more essential. With Zortech C++, developing applications has never been easier or more efficient.

Zortech C++ even includes royalty-free 32-bit and 16-bit DOS extenders, for the cost-effective development of programs with advanced memory requirements.

And since Zortech C++ provides absolutely everything you need to edit, compile, link and debug any Windows application, you won't need to buy the Microsoft Windows SDK. We've also added a help compiler and engine, a resource compiler, Windows header files and libraries, and printed SDK documentation.

Zortech C++ dramatically cuts your multi-platform development time by supporting the complete range of PC architectures.

For unmatched performance, Zortech C++ offers globally optimizing compilers that boost program speed and significantly reduce program size. So regardless of the platform, Zortech C++ delivers performance and security where it matters...in your finished application.

In fact, as the safest choice you can make, Zortech C++ ensures total C++ and ANSI C compatibility. It's also supported by leading third-party utilities, libraries and other tools.

That's probably why more and more corporations are moving to Zortech C++ for their application development.

UPGRADE TO ZORTECH C++ FOR JUST $199.

There's never been a better time to take advantage of the world's first multiple-platform C++ compiler. Because, for just $199, users of Borland C++ and Microsoft C can now upgrade to Zortech C++ For Windows, DOS & OS/2—that's a savings of $500!*

And if your applications require even greater numerics support, pick up the Zortech C++ Science and Engineering Edition (which offers everything from the Windows, DOS and OS/2 version, along with the M++ array language extension, IEEE-754 and NCEG 91-015 numerical support, and much more).

Zortech's industrial-strength compiler breaks through the DOS 640K barrier, enabling you to develop programs of up to 16MB and beyond.

Either way, you'll get unmatched Zortech quality backed by Symantec's outstanding service and support. So visit your dealer or call us at **1-800-228-4122, Ext. 804Y** for more information about Zortech C++ and our competitive upgrade offer.

SYMANTEC.™

*Promotion ends April 30, 1992. Offer good in the US and Canada only. In Canada, call 1-800-465-2266. For more information in Europe, call 31-71-353111. In Australia, call 612-879-6577. Everywhere else, call 408-252-3570.

© 1991 Symantec Corporation. All rights reserved. Zortech is a trademark of Symantec Corporation. All other brand or product names mentioned are trademarks or registered trademarks of their respective holders.

Circle 129 on Inquiry Card.

World Radio History

New from Compaq: Deskpro 50M

Of the many changes that have occurred at Compaq recently, the most notable are several new products: a 486DX2 processor module, a 1024- by 768-pixel resolution graphics accelerator board, and a 17-inch flat-tension-mask color monitor. Combined, these products form a most impressive graphics workstation, which Compaq calls the **Deskpro 50M**.

The Deskpro 50M has 8 MB of RAM (expandable to 64 MB). You have a choice of a 19-millisecond 120-MB hard drive, a 12-ms 340-MB hard drive, or no hard drive at all. Like the other members of the Deskpro/M family, this machine has a rather standard desktop size (17 by 15 by 6 inches). However, it also features five EISA slots (one used by video), a fairly husky (240-watt) power supply, and a removable I/O board containing ROM chips and the system's CMOS battery.



486DX2 Module

The processor module in the Deskpro 50M is built around the newly announced Intel 486DX2 chip. This chip runs at 50 MHz internally, but it has a special interface that lets it appear to the external world as a 25-MHz chip, which lets designers more easily build systems around it. However, this 25-MHz operation also causes the chip to perform at slightly slower rates than you might expect based on its internal 50-MHz clock. Intel claims that instead of running at twice the speed of a 486DX/25, the DX2 will run merely 50 percent to 70 percent faster, depending on how the memory is organized.

To squeeze as much performance as possible from the new chip, Compaq has augmented the 8-KB internal cache on the 486 with a 256-KB two-way associative write-back cache. Preliminary performance numbers based on BYTE Lab benchmarks and an early prototype of the system suggest this could be one of the fastest DX2 systems on the market.

Compaq has wisely implemented the DX2 on a processor module that can be used as an upgrade processor for owners of other Deskpro/M systems or System-pro/LT file servers. Probably, though, the DX2 processor will be purchased most often as part of the Deskpro 50M.

New Graphics Controller

No matter how fast your processor is, you can get even better graphics performance with a graphics accelerator card. Thus, the Deskpro 50M comes with Compaq's new **QVision 1024/E Graphics Controller**. This EISA card features 1 MB of video RAM, which lets it support 256 colors in 1024- by 768-pixel resolution and 65,000 colors in 640- by 480-pixel resolution, as well as regular VGA.

For enhanced Windows performance, the card features a BitBlt engine and a hardware cursor. For fast AutoCAD performance, the card has a line-draw engine. The net effect of these features is very impressive performance. (An ISA version of the card has slightly slower performance.)

THE FACTS

Deskpro 50M
Model 1: 8 MB of RAM and a 3½-inch floppy drive. Model 120: 19-ms 120-MB hard drive. Model 340: 12-ms 340-MB hard drive.

QVision 1024/E Graphics Controller
1 MB of video RAM, 1024 by 768 pixels with 256 colors, VGA compatible, and an EISA bus interface.

QVision 170 Color Monitor
17-inch diagonal, flat-screen, multiscan color analog monitor, 1024 by 768 pixels.

Prices unavailable at press time.

Compaq Computer Corp.
20555 State Hwy.
Houston, TX 77070
(800) 231-0900
(713) 370-0670
Circle 1234 on Inquiry Card.

Flat-Screen Monitors

The latest rage in color monitors seems to be flat screens, and Compaq has decided to offer the flattest screens around. The company's new **QVision Color Monitors** are actually large-screen versions of Zenith Electronics' much-admired flat-tension-mask monitors.

Zenith Electronics (not to be confused with the computer manufacturer Zenith Data Systems) has been selling a 13-inch version of the monitor for years, but Compaq is the first company to offer 15- and 17-inch versions. The 17-inch screen that I saw was unique among large monitors, with a screen so flat that it seemed concave.

A New Tradition

At press time, all Compaq would say was that it would watch the market carefully and offer prices competitive with companies such as Dell and ALR, a promise it has made before and followed through on. If this new tradition holds, Compaq will soon be selling one of the most powerful and most cost-effective graphics workstations on the market.

—Rich Malloy

World Radio History

New Hard Drives Keep Your Data Safe

It's no secret that hard drives are the Achilles' heel of personal computer systems. Unlike the rest of a computer, which moves electrons from place to place, hard drives are electromechanical devices with lots of moving parts that sooner or later wear out—usually at the most inconvenient time.

That hard drives fail is a fact of life. What's an individual user to do? There *are* alternatives, and two new drives are cases in point. The Kalok **KL3100** and the Quantum **Passport XL** take very different approaches to keeping your data safe, but both do the job admirably.



Kalok

Kalok isn't the most familiar name to end users. The company has concentrated on selling its line of hard drives to system makers and dealers. But Kalok is a name you should know about.

Kalok drives are plain-looking (OK, ugly) black boxes that have a disconcerting feature of making a great deal of noise when they access and write data. But don't be fooled.

In one of my prior incarnations as a PC consultant, I computerized a small business with a half-dozen computer systems. In one of them I installed a Kalok drive. I shook my head as I heard it clunk and clank through its paces. Four years later, all the other hard drives I installed have failed. The Kalok, however, just keeps clunking along.

The major reason that Kalok drives are so reliable (and make more noise) is that they use 50 percent fewer components than typical drives from major players. Fewer parts mean fewer pieces to wear out and break down. It works.

The KL3100 is Kalok's latest, a 3½-inch 105-MB IDE drive. It has a 32-KB onboard buffer with a proprietary look-ahead caching algorithm. Couple the cache with a configuration that uses 35 sectors per track, and the result is that the KL3100 delivers more data per rotation than its competitors. I measured its throughput at about 1.8 MBps, the type of speed more commonly seen from synchronous SCSI drives. (The average seek time is 19.5 milliseconds.)

Although Kalok won't provide a suggested retail price, you should be able to buy a KL3100 for around $400. Its rated mean time between failures is an impressive 50,000 hours (over five years), about twice the MTBF for competing drives. My experience shows that figure to be conservative.

Quantum

Last year's acquisition of Plus Development by Quantum was one of those proverbial marriages made in computer heaven. Both companies are known for making high-reliability (albeit expensive) drives. The newest fruit of the merger is a unique system indeed: the Passport XL. This is a series of four removable hard drives (ranging from 50 to 240 MB) that sets new standards for performance and reliability.

Each Passport XL unit is a completely self-contained and sealed SCSI drive in a shockproof container. There are external chassis for PCs and Macs, and an internal chassis fits in a standard half-height 5¼-inch PC drive bay. (You'll also need a SCSI board for your PC.)

The interface to the chassis is a pin connector at the rear of each drive unit. But you don't just push the drive in the chassis. As soon as you start to insert the drive unit, a motor-driven mechanism grabs it and gently pulls it into the chassis. This makes for high reliability. Quantum rates the drives for an incredible 20,000 insertion/removal cycles. That's the equivalent of inserting and removing the drive five times a day for 10 years.

The drives contained in each cartridge are also unique. They have a built-in cache for an effective access time of 9 ms, and they have a sustained data transfer rate of 1.4 MBps. But it's their rated reliability that really raised my eyebrows. Quantum says that the MTBF is 250,000 hours. (That's 28 years!) It's even more impressive when you consider that these drives are designed to be removed, transported, and bounced around. Because of the rated life, Quantum is guaranteeing *forward* compatibility for the Passport XL. The company says you'll be able to use both the drives and the chassis as new generations of products are introduced.

At first blush, the Passport XL seems expensive: A 105-MB drive unit, internal chassis, and SCSI adapter list for $1207. But since it's designed to be a lifetime investment, it's an unbeatable value.

Both the Kalok and Quantum drives are indicative of a refreshing trend toward drives that truly keep your data safe. But a word to the wise: You still need to make backups. Murphy lives.

—Stan Miastkowski

THE FACTS

KL3100
(contact dealer for price)

Kalok Corp.
1289 Anvilwood Ave.
Sunnyvale, CA 94089
(408) 747-1315
fax: (408) 747-1319
Circle 1235 on Inquiry Card.

Passport XL
50 MB, $449; 105 MB, $629; 120 MB, $899; 240 MB, $1099
internal chassis, $359
external chassis, $469

Quantum Corp.
500 McCarthy Blvd.
Milpitas, CA 95035
(800) 624-5545
(408) 894-4000
fax: (408) 894-3205
Circle 1236 on Inquiry Card.

World Radio History

Gateway Cafe

Side Orders

Introducing The Gateway TelePath™

For $195, you get the Gateway TelePath – a new custom-designed V.32bis modem with 9,600 bps fax capability plus WinFax Pro,™ Crosstalk® for Windows™ and a free 30-day subscription to CompuServe® Basic Services. Anywhere else you'd pay more for the software alone!

Speed. The Gateway TelePath modem operates up to 14,400 bps. The Gateway TelePath send/receive fax runs at 9,600 bps.

Compatibility. The 14,400 bps modem is compatible with the standard AT command set and can be used with almost any compatible software. With the Gateway TelePath fax, you can send to or receive from any Group 3 or earlier fax machine using Class 1 or Class 2 commands.

- Fax mode: V.17, V.29, and V.27ter
- Data mode: (try to find one we don't support!) V.32bis, V.32, V.22bis, V.22, V.21, Bell 212A and 103, V.42 and MNP 2-4 error correction, V.42bis/MNP 5 data compression

Price. You'll find comparable fax/modem packages can cost in excess of $500 not including the software. At $195, the Gateway TelePath price is very easy to swallow.

Side Orders

New Video Options For Your PC

The 15-Inch Crystal Scan 1572FS

The new 15-inch Crystal Scan 1572FS has a flat, square, non-glare screen to reduce distortion around the corners and provide an edge-to-edge display area. We've also moved the fine tuning controls to the front of the monitor for easy access. The Crystal Scan 1572FS is an option with 386DX and 486 systems for an additional $195. Availability is limited.

The new 15-inch Crystal Scan is bigger and better than the 1024 series.

The ATI™ Graphics Accelerator

You're really cookin' when you run a Gateway 2000 system with ATI's graphics accelerator, the Graphics Ultra. ATI achieves a quantum leap in performance by using a highly optimized graphics coprocessor on the Graphics Ultra card. The 1024 x 768 mode is fully compatible with IBM® 8514/A, VGA, Super VGA and previous IBM graphics standards, which makes it easy to install applications using the standard video drivers.

The ATI Graphics Ultra video card is standard with the 486DX/33 system, optional with other DX systems. The street price of this card is over $500, but with the purchase of a Gateway 2000 system, you can upgrade to it for $150!



Figures compared on a 486DX/33 and provided by ATI Technologies Inc.

Gateway Cafe

Desserts

New On The Menu: Choose One Software Option Free With Your PC!

With the purchase of any Gateway 2000 computer system, you now receive your choice of free application software. Pick one from the seven application options in our software buffet. We'll install one software option on your hard drive, optimally configured for your system and Windows, and provide you with the master diskettes and manuals – absolutely free.

You can also buy additional software at extremely competitive prices, or choose from other popular applications not listed here. Ask your sales person for the details.

Option #1

Microsoft® Excel for Windows™ 3.0

- A powerful graphical spreadsheet program
- Includes online help for Lotus® 1-2-3® users
- *PC Magazine's* Editor's Choice

Retail value: $495. Discount value: $300+. Can be yours free with a Gateway 2000 PC!

Option #2

Microsoft Word for Windows™ 2.0



- Best selling word processor for Windows
- New version 2.0 adds spectacular refinements
- Includes online help for WordPerfect® users

Retail value: $495. Discount value: $300+. Can be yours free with a Gateway 2000 PC!

Option #3

Microsoft PowerPoint for Windows™ 2.0

- Easy-to-use desktop presentations program
- Creates high-quality overheads and 35mm slides

Retail value: $495. Discount value: $300+. Can be yours free with a Gateway 2000 PC!

Option #4

The Paradox® 3.5

- Award-winning database management program
- From Borland, the leader in database and programming software

Retail value: $695. Discount value: $500+. Can be yours free with a Gateway 2000 PC!

Option #5

The Entrepreneur Pack

Includes Microsoft's Works,™ Publisher™ and Money,™ the latest versions, and an Entertainment Pack, all for Windows, plus TurboTax for Windows® from ChipSoft

- Works integrates a word processor, spreadsheet, database and more into one easy-to-use program
- Publisher has page layout tools to create publications
- Money helps you control your finances by writing checks, setting budgets, tracking expenses
- Entertainment Pack, eight games including Tetris®
- TurboTax is an easy-to-use tax preparation program with online help for understanding IRS rules

Retail value: $607. Discount value: $400+. Can be yours free with a Gateway 2000 PC!

Peripherals are sold only with the purchase of a system. If you already own a Gateway 2000 computer, you can buy peripherals separately. Availability is limited.

World Radio History

Come On In.

Serving PCs

What comes to mind when you picture the classic 50's diner? Good food and plenty of it. Great service. And the price on the check is remarkably affordable.

When you buy a personal computer from Gateway 2000, the experience has its similarities. You get a solid quality, high-performance computer that comes fully loaded with all the

World Radio History

Gateway Cafe

Desserts

Main Course

Gateway Cafe

Main Course

Main Course

Feast Your Eyes On These Entrees – Including A New 486DX2 Special!

Option #6

The Windows Programmer Pack

Includes Microsoft's QuickC for Windows,™ Visual Basic for Windows,™ Windows Control Development Kit,™ MS Windows Help Compiler™ and MS Windows Programmer's Online Reference™

- Everything you need to create programs for Windows

You can't buy all of these tools in one package elsewhere, but this option can be yours free with a Gateway 2000 PC!

Option #7

Microsoft Project for Windows™ 3.0

- Flexible and easy project management program
- Includes interactive online tutorial
- *PC Magazine* calls it the best program in its category

Retail value: $695. Discount value: $425+. Can be yours free with a Gateway 2000 PC!

If the free software packages offered here don't suit your needs, we have others that are very competitively priced. For example, if you'd rather get Microsoft Office,™ which includes Word for Windows, Excel and PowerPoint, you can upgrade to it. Office retails for $750, with a discount value of $499. It can be yours for only $175 with a Gateway 2000 PC. Ask your sales representative for details.

This offer includes the identical applications contained in retail packages but will not include the retail box. You get a complete set of diskettes and manuals, shrink-wrapped and packaged in a Gateway 2000 box.

Gateway 2000 computer systems – the meat and potatoes of our menu – come with all the trimmings at no extra charge.

And if you're hungry for an ultra high-performance system at a great price, take a look at our new 50MHz 486DX2 computers. Both ISA and EISA models are based on the Intel486 DX2 dual speed processor. With a system clock frequency of 25MHz, the internal core of this CPU executes at 50MHz for a 35% increase in performance compared to a 33MHz 486DX system.

NEW

50MHz 486DX2 $3195

50MHz 486DX2 EISA $4095

386SX Systems

Gateway 2000's 386SX systems come in a compact, mini desktop model. To give you plenty of room for expansion in a small footprint system, we integrated the diskette drive controller, the video chip set and the I/O card on the motherboard, leaving five 16-bit slots open in the standard configuration.

The mini desktop models have a standard mouse port (PS/2® compatible), leaving two serial ports open. RAM on these systems is expandable to 16MB on the motherboard. The Western Digital® IDE hard drives feature a 32K read-look-ahead cache buffer. All mini desktop models have Quadtel® BIOS and 200 watt power supplies.

The 124-key AnyKey keyboard comes standard with all Gateway 2000 systems.

386DX Systems

The 386DX systems have a true 32-bit memory bus and more expansion capability. We start with a genuine Intel® 80386 microprocessor on a Micronics® motherboard. We add a generous portion of RAM – 4MB expandable to a system total of 64MB. Put in 64K of cache RAM on the 386DX/33 for a nice performance boost. Add IDE hard drives from Western Digital. Then give them Diamond Speedstar Plus™ 16-bit VGA graphics cards with 1MB RAM, non-interlaced 14-inch Crystal Scan 1024 x 768 color monitors, Phoenix™ BIOS, a Weitek socket on the 33 and 200 watt power supplies. That's the basic recipe for these tried-and-true, workhorse computers.



Both systems have a 32-bit slot open in the standard configuration for RAM expansion. The motherboard has a total of one 32-bit and seven 16-bit slots, with one 32-bit and five 16-bit expansion slots available in the advertised configuration. Gateway's 386DX and 486 systems come in a desktop model that is roomy and easily accessible. A floor-standing tower model is an option for an additional $100.

486DX And DX2 Systems

Gateway 2000's 486 systems run on the real McCoy – an Intel486™ processor with built-in math coprocessor and 8K instruction cache. The ISA systems have a Micronics® motherboard, while the motherboard for the EISA systems is custom-manufactured for Gateway 2000. RAM is expandable to a system total of 64MB.

New on the ISA models is the ATI® Graphics Ultra, which is the fastest video card by far in its class. The EISA models include a Diamond Speedstar Plus, which is also a high-performance video card. Both systems come with 1MB video RAM.

The ISA systems have eight 16-bit slots on the motherboard, six available in the standard configuration. The EISA machines have eight 32-bit EISA slots on the system board. You have five 32-bit EISA slots open in our standard configuration.

The ISA systems have Phoenix BIOS, while the EISA computers use Award® BIOS. All systems come with Weitek sockets and 200 watt power supplies.

INCLUDED WITH EVERY SYSTEM:

• One-year limited warranty • 30-day money-back guarantee • Lifetime toll-free technical support • Free on-site service to most locations • Free bulletin board technical support • C.O.D. terms and major credit cards honored • Net 30-day credit terms and leasing options available to qualified commercial customers

World Radio History

With The Works!

This ad was photographed at Archie's Diner in Sioux City, Iowa. Archie is behind the counter. Other characters are Gateway 2000 employees from departments throughout the company.

features you want. The service is unsurpassed anywhere. And the price you pay is also remarkably affordable.

Go ahead and browse through the Gateway Cafe menu. We serve a wide selection of the freshest items in the PC industry. You're sure to find something that will appeal to your taste and budget.

GATEWAY2000
"You've got a friend in the business."

Gateway Cafe

16MHz 386SX

- Intel® 80386SX Processor
- 2MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 40MB 17ms IDE Drive with 32K Cache
- 16-Bit VGA with 512K
- 14" Crystal Scan 1024 Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 1 PS/2 Mouse Port
- 124-Key AnyKey™ Keyboard
- Microsoft® Mouse
- MS® DOS® 5.0
- MS Windows™ 3.0
- Choice of Application Software

$1445

20MHz 386SX

- Intel 80386SX Processor
- 32K Cache RAM
- 4MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 80MB 17ms IDE Drive with 32K Cache
- 16-Bit VGA with 512K
- 14" Crystal Scan 1024 Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 1 PS/2 Mouse Port
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$1745

25MHz 386DX

- Intel 80386 Processor
- 4MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 80MB 17ms IDE Drive with 32K Cache
- 16-Bit VGA with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$1895

33MHz 386DX

- Intel 80386 Processor
- 64K Cache RAM
- 4MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 200MB 15ms IDE Drive with 64K Multi-Segmented Cache
- 16-Bit VGA with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$2395

33MHz 486DX

- Intel 80486 Processor
- 64K Cache RAM
- 8MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 200MB 15ms IDE Drive with 64K Multi-Segmented Cache
- ATI™ Ultra 8514/A Video with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$2945

50MHz 486DX2

- Intel 80486DX2 Processor
- 64K Cache RAM
- 8MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 200MB 15ms IDE* Drive with 64K Multi-Segmented Cache
- ATI Ultra 8514/A Video with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$3195

*"Enhanced IDE with RIDE (Rapid Integrated Drive Electronics) technology

33MHz 486DX EISA

- Intel 80486 Processor
- 128K Cache RAM
- 8MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 340MB 15ms SCSI Drive with 128K Multi-Segmented Cache
- 32-Bit EISA SCSI Controller
- 16-Bit VGA with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$3895

50MHz 486DX2 EISA

- Intel 80486DX2 Processor
- 128K Cache RAM
- 8MB RAM
- 1.2MB 5.25" Drive
- 1.44MB 3.5" Drive
- 340MB 15ms SCSI Drive with 128K Multi-Segmented Cache
- 32-Bit EISA SCSI Controller
- 16-Bit VGA with 1MB
- 14" Crystal Scan 1024NI Color VGA Monitor
- 1 Parallel/2 Serial Ports
- 124-Key AnyKey Keyboard
- Microsoft Mouse
- MS DOS 5.0
- MS Windows 3.0
- Choice of Application Software

$4095

BEST BUYS

- Get our 33MHz 386DX system, same configuration as listed, with a 120MB IDE hard drive instead of the 200MB drive.

$2145

- Same features as our 33MHz 486DX system except this machine has 4MB RAM instead of 8, and a 120MB IDE hard drive instead of the 200MB drive in our standard configuration.

$2495

Sales Hours: 7am-10pm Weekdays, 9am-4pm Saturdays (CST)
Service Hours: 6am-Midnight Weekdays, 9am-2pm Saturdays (CST)

All prices are subject to change. Prices do not include shipping.

GATEWAY2000
"You've got a friend in the business."

800-523-2000

610 Gateway Drive • P.O. Box 2000 • N. Sioux City, SD 57049-2000 • 605-232-2000 • Fax 605-232-2023

©1992 Gateway 2000, Inc. AnyKey and TelePath are trademarks of Gateway 2000, Inc. Intel and Intel Inside are trademarks of Intel Corporation.
All other brands and product names are trademarks or registered trademarks of their respective companies.

World Radio History

The VideoPhone Goes Home Computer

The company that provided the compression algorithm and the hardware for the AT&T VideoPhone 2500—Compression Labs—has announced a computer-based version of the same system. The **Cameo Personal Video System, Model 2001** consists of a small video camera that sits atop your Mac. The camera is connected to a *video processor module* that sits beside the system, sidecar-style. The camera passes the image to the video processor and then to an ISDN card in the computer, which transmits it over ISDN lines to another Cameo unit. When your system receives a video image, the video processor passes it to a digitizing video card, which displays it on the monitor.

Unfortunately, those images still suffer from the need to cram lots of video information through a narrow communications bandwidth. At 15 frames per second—about half of what's needed for smooth motion—and a resolution about that of a VHS movie, this is a far cry from the viewscreens on the starship *Enterprise*. (If you don't want a caller to see you, you can close the shutter over the camera.)

The software that comes with the Cameo system is easy to use, mimicking a full-featured telephone. With a click of a mouse button, you can dial, activate the video image, see your own image, mute the audio, hang up, put your party on hold, or take a snapshot of a party's image. A graphical phone directory lets you store those snapshots, so you can later call someone just by clicking on his or her image. Slider bars let you adjust the image brightness and tint, as well as the audio volume (which comes through your regular telephone).

While it's less expensive than previous commercial videophones, the Cameo system isn't cheap. You'll need a Mac IIci, IIfx, or Quadra with System 7.0, QuickTime, a RasterOps digitizing display card, an Apple ISDN card, and access to ISDN lines. If you already have the Mac and the ISDN lines, the extra pieces will cost you about $2000, not including the Cameo system itself, which costs $2095. (The Cameo cost is $1595 if you use your own video camera, which you can plug into the standard NTSC interface on the video processor.)

Given those constraints, Compression Labs is wisely aiming the Cameo system at businesses that are looking for a lower-cost alternative to the expensive teleconferencing systems they've been using. Many of those customers already have the ISDN lines installed.

For the rest of us, however, Compression Labs has plans to branch out very soon. The company says it will have an IBM PC–compatible Cameo system later this year (the video processor itself is platform independent), as well as versions that will operate over normal (i.e., analog) telephone lines (which will make them compatible with the AT&T VideoPhone). Other proposed features include a "chalkboard" that will let you transmit freehand drawings as you talk about them. Those kinds of additions could move the videophone from the realm of technological curiosity to standard consumer device.

—Kenneth M. Sheldon

THE FACTS

Cameo Personal Video System, Model 2001
including camera, $2095; without camera, $1595

Compression Labs, Inc.
2860 Junction Ave.
San Jose, CA 95134
(800) 225-5254
(408) 435-3000
fax: (408) 922-5429
Circle 1216 on Inquiry Card.

Blue Dolphin Makes a Splash

The PC price/performance race shows no signs of slowing down, and it's certainly one area where end users are benefiting. The latest conspicuous example is the **486DX-50 Cache** from the interestingly named Blue Dolphin Computers. This is one loaded, powerful, and incredibly fast system at a price that will raise some eyebrows. At $3749 complete, it is (as this was written) the most inexpensive 50-MHz system on the market.

As its name implies, the 486DX-50 Cache is built around Intel's 50-MHz 486 chip, which is finally becoming available in quantity. Besides the 486's internal 8-KB cache, the system includes a 64-KB external static RAM cache. As you'd expect, this is a screamer of a system. My preliminary BYTE Lab benchmark results showed this to be one of the fastest systems we've ever tested.

Running processor- and graphics-intensive applications at this speed is a revelation. It's especially noticeable with a GUI like Windows. There's virtually no delay in applications. One of my personal favorites for subjective performance measurement is AutoDesk's Chaos, which makes heavy use of the 486's built-in math coprocessor. Drawing a standard Mandelbrot set on the 486DX-50 Cache takes just a few seconds. (It can take minutes on slow 386 systems.)

It takes more than a fast processor to make a fast computer, and the 486DX-50 Cache is a well-integrated system. It comes standard with a Diamond Stealth video RAM graphics card with 1 MB of memory. One of the fastest VGA cards

World Radio History

THE FACTS

486DX-50 Cache
$3749

Blue Dolphin Computers, Inc.
890F Cowan Rd.
Burlingame, CA 94010
(800) 345-0633
(415) 259-9890
fax: (415) 259-9898
Circle 1217 on Inquiry Card.

available, the Diamond Stealth includes a number of software drivers, including Windows at up to 1024- by 768-pixel resolution.

The 486DX-50 Cache comes with an Optiquest-2000, a 15-inch flat-screen monitor that handles high-resolution noninterlaced Windows at a display size that makes it eminently usable. The Optiquest-2000 is a high-quality monitor at a fair price, making it a perfect match for the 486DX-50 Cache.

Other standard features include a 212-MB hard drive (either Seagate or Maxtor), a 5¼-inch 1.2-MB floppy drive, and a 3½-inch 2.88-MB floppy drive (soon to be a standard for small floppy drives). There's also 8 MB of RAM (expandable to 64 MB on the motherboard) and the usual complement of ports. Rounding things out are a Key Tronic keyboard and a Logitech mouse. DOS 5.0 and Windows 3.0 are preloaded on the system.

At BYTE, we see many "me-too" clone systems. Too many are hastily put together from substandard parts and pieces, and the companies often go out of business within months. Blue Dolphin is a refreshing exception to this trend. It's been in business for over six years.

Obviously, the Blue Dolphin 486DX-50 Cache system is also put together from standard parts and pieces. However, the company has done an enviable job of integrating high-performance and mid-priced components into an impressive system. No, it's not a big-name system from a big-name company. Some corners did have to be cut. But Blue Dolphin backs up its products with a 45-day money-back guarantee, a 45-day system replacement policy, a one-year warranty, and lifetime toll-free technical support. If you need (or want) cutting-edge PC performance at an affordable price, the 486DX-50 Cache is the system for you.

—Stan Miastkowski

Boxer: A Text Editor with Punch

One of the easiest ways to launch an argument among programmers is to emphatically state that one text editor is better than another. The **Boxer Text Editing System 3.20** from Boxer Software is a quick, powerful shareware product that deserves to receive some strong support of its own. The text editor's smoothly integrated mouse support is pleasingly comfortable and intuitive.

If you edit text files for a living, you won't find much lacking in Boxer. Although it is restricted to in-memory editing, this should be no problem for many of the programmers for whom Boxer is designed. I was able to load a 163-KB file in a 549-KB DOS session. The memory limitation



appears serious only when you attempt to edit multiple files simultaneously.

This editor has more features than I have space to describe, yet I did not experience feature overload. Each function is but a single menu or keystroke away.

Some of my favorite functions include 26 single-key macros, the ability to write all files with a single command, removing extra blanks from the end of lines, and the addition of configurable headers and footers on printouts. The ability to search and replace text across all open files is a real time-saver. You can perform searches using text only or full regular expression matching, including checks for end of line, start of line, and match only complete tokens.

Boxer provides support for special VGA video modes. In addition to the common 43- and 50-line modes, Boxer provides a

World Radio History



THE SCREAMING SPEED YOU NEED

Windows Accelerators, from $499*

Where we're going, there are no speed limits. ATI® Graphics Accelerators boost graphical applications like Windows® to escape velocity — and beyond.

PC Magazine picked our 8514•ULTRA® as their Editors' Choice among high-end graphics cards, calling it "...the fastest Windows performer." Now our new Graphics Vantage® takes its place alongside the 8514•ULTRA and the Graphics ULTRA®, as the most economical way of accelerating your PC beyond earthbound speeds.

Powered by the same Mach 8® graphics engine as the ULTRA products, the Graphics Vantage delivers resolutions from VGA® upward, and propels 800x600 and 1024x768 modes — in 256 dazzling colors — to over eleven times the speed of Super-VGA adapters. It's like transforming your 386 into a rocket-powered 486 — instantly.

Our CRYSTAL Fonts® and flicker-free refresh rates — up to 72 Hz — clarify Windows with "near laser quality" text, readable down to 5 points even on 14" monitors. We've also equipped the Graphics Vantage with a Microsoft®- compatible mouse — and a down-to-earth price that will definitely give you no cause to scream — except perhaps with amazement.

ATI Graphics Accelerators. Because in today's world, there's no such thing as "fast enough."





GRAPHICS ULTRA
One of the ATI
Graphics Accelerators™

PC MAGAZINE
EDITORS' CHOICE
June 25, 1991
ATI 8514-ULTRA

BEST OF SPRING COMDEX 1991
BYTE
GRAPHICS VANTAGE

See Us At
WINDOWS WORLD '92
April 6-9, 1992
McCormick Place • Chicago, Illinois USA
Booth W 1808

ATI TECHNOLOGIES INC.
3761 Victoria Park Avenue
Scarborough, Ontario
Canada M1W 3S2
Telephone: (416) 756-0718
User Support: (416) 756-0711
Facsimile: (416) 756-0720

Copyright © 1991 ATI Technologies. Trademarks are registered by their respective companies. *Suggested retail price, dealers may sell for less.

Circle 44 on Inquiry Card.

World Radio History

28-line mode, which is useful because the edit area is a standard 24-line screen size.

In addition to standard editor features, Boxer provides a programmer's calculator (hexadecimal, octal, binary, and decimal); the ability to add columns of numbers; an ASCII chart; a movable ruler that measures in inches, millimeters, and picas; a calendar; and a function to remove tabs from text. Because this is a programmer's editor, Boxer provides the ability to compile files and then track through any generated errors.

Both keyboard commands and printer configurations are supported through customizable option files. Command configurations are provided for popular editors (e.g., Brief, Epsilon, WordPerfect, and WordStar). Printer support files include Epson, LaserJet, and Okidata 92. You can easily configure both the keyboard command and the printer configuration files so that you can use them with packages that currently are unsupported.

Boxer does have several interface quirks that I found annoying. The first is the distinction between windows and files. Most multiple-file text editors that I've used open each file in a separate window. Boxer does not do this. Although it supports multiple windows, Boxer also lets you cycle through each file in a single window. Such a separation of files from windows can be quite disconcerting until you become used to working with a text editor that is set up this way.

Another quirk is the implementation of what is called the End-End-End behavior. Brief exhibits this behavior. Pressing the End key once moves to the end of line. Pressing twice moves to the end of screen. Pressing three times moves to the end of document. The Brief keyboard mapping that is provided almost gives this functionality. Boxer, instead of counting End (or Home) presses, checks its position before moving. Thus, pressing End when at the end of a line moves to the end of screen. This subtle difference in behavior is sufficient to cause no end of headaches.

Conclusion? Boxer is well worth a look. The beta version 3.20 I examined was reliable and responsive. Even though I have my own favorite text editor, I'm always looking for a freeware or shareware editor I can carry around with me when consulting on other people's systems. Boxer is a definite addition to my travel kit.

—Raymond GA Côté

THE FACTS

Boxer Text Editing System 3.20
$50 shareware registration fee

Boxer Software
P.O. Box 3230
Peterborough, NH 03458
(603) 924-6602
Circle 1218 on Inquiry Card.

A Touch of CASE from the Gold Coast

PGC CASE Graphics 1.0 from Pacific Gold Coast is an interesting development and design tool that's in need of improvement. This $129 package is not so much a full-fledged CASE tool as it is a diagram-drawing tool. PGC promises additional functionality (e.g., a data dictionary and diagram checking) in six planned modules. However, even a diagram-drawing tool can give the uninitiated a taste of the technology.

PGC CASE Graphics supports several standard diagraming methods: Yourdon data flow, Gane and Sarson data flow, Chen entity-relationship diagram, structure diagram, and structure chart. A special General Graph is provided, which seems to be a catchall for a collection of miscellaneous icons. The documentation claims that you can produce object-oriented programming software designs, but this appears to be limited to the ability to place circles and lines on a drawing.

The working diagram area is limited to the approximate size of a standard VGA screen and cannot be expanded. Because scrolling is not supported in the chart area, your final diagram is also limited to this size.

Diagram icons are presented in an easy-to-use tool bar. However, the tool-bar icons themselves (e.g., an *X* for delete and a camera for copy) are nonintuitive. The complete lack of on-line help definitely hinders the learning process.

One of the package's most useful features is the ability to link multiple diagrams into a hierarchical network. Instead of linking actual icons to the next diagraming level, PGC CASE Graphics links labels. Although this is a little strange in concept, it works quite well because all icons typically have labels with which they are associated.

PGC CASE Graphics does an excellent job of moving icons and connected lines about the diagram quickly and cleanly, providing real-time rubber-banding (i.e., the ability to update and reposition the connecting lines to an icon as the icon is moved). Unfortunately, the text associated with the moved lines does not change position. Thus, after moving a portion of a rather complex diagram, I was forced to move all the labels individually—a task prone to errors.

In spite of the inadequacies I found in PGC CASE Graphics, I was able to create some decent-looking data-flow diagrams and structure charts, an exercise that brought to light some features I want to see in the next release. The ability to resize icons is important, as is the ability to associate labels with lines. The additional capability to group and ungroup icons for copying and moving would also speed diagram development.

For the most part, PGC is on the right track with PGC CASE Graphics. However, I'd wait out the shakedown cruise and look for version 2.0. ■

—Raymond GA Côté

THE FACTS

PGC CASE Graphics 1.0
$129

System requirements:
A 286 or higher with 2 MB of RAM, a VGA or EGA monitor, Windows 3.0, and a Windows-compatible mouse.

Pacific Gold Coast Corp.
15 Glen St., Suite 201
Glen Cove, NY 11542
(800) 732-3002
(516) 759-3011
fax: (516) 759-3014
Circle 1219 on Inquiry Card.

World Radio History

The Quality Memory Solution

Phar Lap DOS-Extenders

When your reputation's at stake...

We know how much work you put into building your product. Why use inferior tools that often create more problems than they solve? With a Phar Lap DOS-Extender, you know you're getting industry-leading, market-tested tools that have worked reliably for thousands of developers. Other DOS extenders simply can't measure up. Let Phar Lap show you what a DOS extender should be.

Phar Lap Software: Chosen 10 to 1 over all other DOS extenders. Here's why:

	Phar Lap DOS-Extender	Vendor A	Vendor B
Maturity	Over 5 years and 1000 applications	Less than a year	Brand new
Memory Model	Safe	Dangerous	Dangerous
Compatibility	INT 15, XMS, VCPI, DPMI	XMS, DPMI	XMS, VCPI
Library Support	Extensive list of 32-bit libraries	Limited library support	Limited library support
Documentation	Extensive and detailed	Limited	Less than 50 pages

Shatter the 640K barrier and build multi-megabyte DOS applications.

No more suffering with overlays or EMS.

Other DOS extenders can let common programming errors cause system crashes.

Build multi-megabyte DOS programs with Phar Lap's DOS-Extenders!

286|DOS-Extender™ — it's never been so easy! With our 286|DOS-Extender and your Microsoft C, Borland C++ or Microsoft Fortran compiler, you've got all the tools you'll need to quickly and easily build multi-megabyte protected-mode applications — often by simply relinking without making source code changes. Now you can build protected mode applications that access up to 16 megabytes of memory on any DOS-based 80286, 386, 386SX, or i486 PC — without changing development tools! 286|DOS-Extender is also compatible with both Borland's Turbo Debugger and Microsoft's linker and CodeView debugger.

386|DOS-Extender™ — the ultimate in 32-bit power. 386|DOS-Extender turns DOS into a true 32-bit operating system with a flat, 32-bit address space. Your program can access all the memory available in the machine — up to 4 gigabytes! 386|DOS-Extender runs on any DOS-based 80386, 386SX, or i486 PC, and has been used in over 800 applications, including AutoCAD 386 and IBM's Interleaf Publisher. It is backed by a full complement of 32-bit languages, including C, C++, Fortran, Pascal, Ada and Assembler. With true 32-bit performance, you can finally build workstation-class applications for the PC.

Phar Lap Software, Inc
60 Aberdeen Avenue
Cambridge, MA 02138
617-661-1510
FAX 617-876-2972

Trademark holders: 286|DOS-Extender™, 386|DOS-Extender™ - Phar Lap Software, Inc.; Interleaf Publisher™ - Interleaf, Inc.; Windows™ - Microsoft Corp.; DESQview™ - Quarterdeck Office Systems. Registered trademark holders: Phar Lap® - Phar Lap Software, Inc.; AutoCAD® - Autodesk, Inc.; Borland®, Turbo Debugger® - Borland International, Inc.; IBM® - IBM Corporation; CodeView®, Microsoft®, MS-DOS® - Microsoft Corp.

1989 BYTE AWARD OF EXCELLENCE

1991 BYTE AWARD OF DISTINCTION

COMPUTER LANGUAGE PRODUCTIVITY AWARD 1991

Circle 105 on Inquiry Card.

World Radio History



World Radio History



through code the way you do.

IRIS INDIGO • RISC/PC



CASEVision and IRIS Indigo–
CASE like you've never seen it before.

You've known us as the company that builds hot graphics machines. Now we've taken that vision and applied it to CASE.

The result: we've created an intuitive, visual interface that reflects the way programmers think.

We've also included an entire suite of the most advanced and fastest C, C++ and FORTRAN programming, compiling, debugging and analysis tools available today – designed for large, multiple-language, and even multi-processing applications.

Put all this on any of our award-winning IRIS Indigo™ RISC/PCs, and you've got the ultimate software development platform.

Where you go with all that power is completely up to you.

See for yourself. Get our CASEVision™ and IRIS Indigo literature package and find out where to check them out in person.

Call 1 (800) 800-7441. Ext.12

BYTE 1991

IRIS Indigo delivers 30 MIPS, 4.2 MFLOPS, 26 SPECmarks, CD-quality audio, 8-24 bit color, ACE-compatibility, and comes complete with color monitor, keyboard and mouse. Copyright © 1991 Silicon Graphics, Inc. Silicon Graphics, the Silicon Graphics logo and IRIS® are registered trademarks, and CASEVision and IRIS Indigo are trademarks of Silicon Graphics, Inc. All other registered and unregistered trademarks are the sole property of their respective owners.

SiliconGraphics®
Computer Systems

World Radio History

Portable Presentations in Color

A portable desktop computer with its own color overhead projection LCD panel, the Mpression Notebook Presentation System uses standard overhead projectors to display computer text or graphics. The system consists of a 33-MHz 486 Mport 433 computer with a 120-MB IDE hard drive, plus the LCD panel.

The Mpression displays 256 colors from a palette of 187,000, automatically mapping the CRT colors. The system also automatically expands or compresses VGA modes of different resolutions to fit the 640- by 480-pixel LCD.

To install the system, you plug the cable from the LCD panel into the LCD VGA port of the Mport 433 (which has up to 32 MB of RAM), put the LCD panel on your overhead projector, and turn on the computer for simultaneous overhead and computer displays. The Mpression's 6-foot cable provides video signals and power from the Mport 433. Compatible with DOS, Unix, OS/2, PICK, and DR DOS, the system supports 410-W projectors with the light source below the LCD panel.
Price: $11,995.
Contact: Micronics Computers, Inc., 232 East Warren Ave., Fremont, CA 94539, (510) 651-2300; fax (510) 651-5612.
Circle 1271 on Inquiry Card.

An overhead presentation system, the Mpression Notebook Presentation System combines an LCD panel with its Mport notebook computer.

CPU in a Cartridge

Replaceable CPU cartridges form the basis of the PC Positive 1000 and 2000 upgradable systems. Four cartridges, ranging from a 20-MHz 386SX through a 33-MHz 486, fit either system; an internal CD-ROM is available as an option for either system.

With 4 MB of RAM (expandable to 32 MB), the PC Positive 1000 base system has a 105-MB hard drive, 5¼- and 3½-inch floppy drives, a Super VGA color monitor with a video controller, a 2400-bps modem, a Logitech mouse, and six expansion slots. DOS 5.0, Windows 3.0, Microsoft Works for Windows, and Microsoft Productivity Pack are preloaded on the hard disk. WinFax is packaged with the system.

The basic PC Positive 2000 features 8 MB of RAM (expandable to 32 MB), a 200-MB hard drive, and a 9600-/2400-bps send/receive fax/modem. Prodigy is included, in addition to the software and accessories that come with the 1000 system.
Price: Basic PC Positive 1000, $1400; basic PC Positive 2000, $1900.
Contact: Positive Corp., 9174 Deering Ave., Chatsworth, CA 91311, (818) 341-5400; fax (818) 718-2938.
Circle 1272 on Inquiry Card.

To upgrade the PC Positive 1000 and 2000 models, just change the CPU cartridge.

Desktop System Packages Power

Packaged as a complete system, the ME 486-SX/25 desktop computer includes 4 MB of RAM (expandable to 32 MB via 70-ns SIMMs), 128 KB of 25-ns write-back cache RAM (expandable to 256 KB), an 80-MB hard drive, and dual floppy drives. The system's extended VGA card displays up to 256 colors at a resolution of up to 1024 by 768 pixels on a 14-inch nonglare screen.

The ME 486-SX/25's AMI BIOS offers selectable shadowing. The system has eight 16-bit expansion slots, five drive bays, and an upgradable motherboard.
Price: $1999.
Contact: Micro Express, 1801 Carnegie Ave., Santa Ana, CA 92705, (800) 989-9900 or (714) 852-1400.
Circle 1273 on Inquiry Card.

Fast Transfer on the Local Bus

Built on the Opti Local/CPU Bus chip set, Bell's 40-MHz 386 system transfers data at the 40-MHz speed of the CPU rather than at the 8-MHz speed of the AT bus. Since the CPU has its own card, you can upgrade the system.

The system features 4 MB of RAM, 64 KB of cache memory, a 250-MB hard drive, a 1-MB local/CPU bus VGA card, and a 14-inch Super VGA monitor. Also included are one parallel and two serial ports, a mouse, DOS 5.0, Windows 3.0a, and dual floppy drives.
Price: $3495.
Contact: Bell Computer Systems, 6615 Valjean Ave., Van Nuys, CA 91406, (800) 922-1126 or (818) 909-3501.
Circle 1274 on Inquiry Card.

World Radio History

Prolific Possibilities from a Printer

The 6-ppm PostScript Level II Silentwriter Model 95 laser printer has automatic emulation switching that detects PostScript and Printer Control Language files and automatically configures the printer for the proper language. The printer also has automatic interface monitoring that switches between active ports for simultaneous connection of multiple PCs and Macs.

The Silentwriter Model 95 has 2 MB of RAM (expandable to 5 MB). Its 16.7-MHz 68000 microprocessor includes a built-in PostScript Level II interpreter that provides 35 resident scalable typefaces. Built-in trays include a 15-envelope feeder, a 250-sheet cassette that accommodates 24-pound paper and transparencies, and a multipurpose tray that handles 41-pound paper.

An optional PostScript fax/modem lets you send and receive Group 3 faxes as well as PostScript faxes from the printer.

Price: $1749; fax/modem, $599.

Contact: NEC Technologies, Inc., 1414 Massachusetts Ave., Boxborough, MA 01719, (800) 632-4636 or (508) 264-8000; fax (508) 264-8673.

Circle 1275 on Inquiry Card.

Mac and DOS compatible, the Silentwriter Model 95 presents a plethora of printing possibilities.

Draw Multiple Uses from This Graphics Tablet

DrawingPad combines the capabilities of a digitizer, a graphics tablet, and a mouse. Available for the Mac and the PC, DrawingPad lets you create original graphics on your computer as well as convert any paper-based graphical image into a digital form recognized by the computer. After the image is in your machine, you can edit it as you please.

The 2-pound DrawingPad has a resolution of up to 1270 lines per inch with accuracy at ±0.025 inch. It includes 18 user-recordable macros, tablet-to-screen and proportional mapping capabilities, the capability to map the active tablet area to an active window on the screen, and a feature that lets you switch between the mouse and other modes without losing your place on the tablet. You can choose your input device from a number of cordless pen and cursor options.

Price: $395.

Contact: CalComp, Inc., Digitizer Products Group, 14555 North 82nd St., Scottsdale, AZ 85260, (800) 458-5888 or (602) 948-6540; fax (602) 948-5508.

Circle 1276 on Inquiry Card.

Spill-Proof Keyboard

The Membrane Keyboard 101's washable membrane replaces the full-travel keys on a conventional keyboard, but in other respects it matches an Enhanced AT keyboard. Seven ounces of pressure is all that's needed to activate a key, which responds with a light click to let you know your touch was recognized. Interfaces include a keyboard port for an AT or PS/2 computer, an RS-232 serial port, a parallel port, and a universal terminal interface. The scan code serial and parallel versions are fully programmable.

Price: Basic keyboard, $300; universal terminal version, $350.

Contact: Genovation, Inc., 17741 Mitchell N, Irvine, CA 92714, (714) 833-3355; fax (714) 833-0322.

Circle 1277 on Inquiry Card.

Video Editor for Windows

The Editizer video editor from Technical Aesthetics Operations features true A/B roll and SMPTE time-code editing in Windows, as well as integrated tape logging and edit-decision list management support. The combination hardware/software editor encompasses an interface box and software that uses more than 10 independent pop-up windows, including three VCR windows, the Controller window, a Tape Logger window, and an Edit Decision window.

The object-oriented design of the Editizer gives you powerful and sensible access to your data. To change any time code, you click on the time-code number on the screen for a dialog box that lets you set a new number.

You can use the Editizer with your PC to log videotapes and edit, rearrange, and record productions using existing decks. You can connect multiple video decks to any PC that supports Windows and export the Editizer edit-decision list into an industry-standard CMX file to be used by a commercial postproduction firm. Interfaces include RS-232, RS-422, Panasonic AG-1960, and Sony Control-L.

Price: $1995.

Contact: Technical Aesthetics Operations, Inc., 501 West Fifth St., Rolla, MO 65401, (800) 264-1121 or (314) 364-4925; fax (314) 364-5631.

Circle 1278 on Inquiry Card.

The Editizer, a Windows-based video editor, supports the full life cycle of a video production.

World Radio History

Upgradable Power from Predator

The Predator motherboard is 10 products in one. With a change of the CPU and setup jumpers, the board can be a 25-, 33-, or 40-MHz 386; a 20- or 25-MHz 486SX; a 20- or 25-MHz 487SX; or a 25-, 33-, or 50-MHz 486.

The 8½- by 13-inch Predator features selectable bus speeds and cache memory that is field upgradable from 64 KB to 128 and 256 KB. Able to support multiple operating systems running concurrently, the board is compatible with DOS, OS/2, Unix, and NetWare. Standard interfaces include two serial ports, a mouse port, a bidirectional parallel port, a dual-floppy controller, and an AT interface for IDE hard drives.

Predator's flash memory BIOS is upgradable via a floppy disk. The board, which ships with no system memory, supports up to 16 SIMMs, allowing system memory of up to 64 MB.
Price: With 64 KB of cache memory, $450.
Contact: Deico Electronics, Inc., 2800 Bayview Dr., Fremont, CA 94538, (510) 651-7800; fax (510) 651-6109.
Circle 1279 on Inquiry Card.

Cross-Platform Media Compatibility

Based on Intel's Digital Video Interactive technology and 750B video processor, the EyeQ Delivery board compresses and decompresses 30-frame-per-second full-screen video to the hard disk on your desktop computer in real time. With 2 MB of video RAM (expandable to 4 MB) and four application-specific ICs, the NuBus board supports 12- and 13-inch Mac displays and multisync displays up to 16 inches (800 by 600 pixels). The board lets you play MacDVI media files on any DVI system.

The EyeQ Delivery board has a data transfer rate of 150 KBps and includes support for NTSC and PAL video standards. Other features include QuickTime compatibility, QuickDraw graphics acceleration, high-fidelity audio, video overlay, and support for multiple compression algorithms.
Price: $2495.
Contact: New Video Corp., 220 Main St., Suite C, Venice, CA 90291, (213) 396-4000; fax (213) 396-0282.
Circle 1280 on Inquiry Card.



Deico's Predator takes on many configurations.

Six-in-One I/O Board

Integrating the functions of six boards on a single board, the Sigma Six is designed for the AT bus. The board includes 10-Mbps Ethernet connectivity, a 9600-/2400-bps send/receive fax/modem, Super VGA with 1024- by 768-pixel noninterlaced resolution and a 70-Hz refresh rate, Windows 3.0 compatibility, DOS 5.0 software in flash EPROM, IDE and floppy drive controllers, and parallel and serial ports.
Price: $695.
Contact: Advanced Micro Technology Computers, Inc., 123 University Pkwy., Pomona, CA 91768, (800) 487-4539 or (714) 598-6120.
Circle 1281 on Inquiry Card.

Micro Channel Memory Enhanced

The BocaRAM.MCA32 memory enhancement board supplies up to 32 MB of SIMM memory to IBM 32-bit Micro Channel computers, letting them run operating systems such as DOS, OS/2, Unix, Xenix, and NetWare. The memory on the board can be extended, expanded, or a combination of both. Memory configurations are directed by a menu-driven installation program; the MC32TEST utility verifies that the board is working properly. A driver for EMS 4.0 is included.

Configurations of BocaRAM range from unpopulated to 32 MB. You can upgrade board memory by adding SIMMs.
Price: $295 to $3295.
Contact: Boca Research, Inc., 6413 Congress Ave., Boca Raton, FL 33487, (407) 997-6227.
Circle 1282 on Inquiry Card.

Display Adapter for PowerBooks

The Notebook Display Adaptor 030, an 8-bit display adapter for use with the Macintosh PowerBook 140 and 170, drives 13-inch color displays and projection devices that have up to 256 colors. With a pass-through memory port that accepts an Apple 2- or 4-MB memory upgrade, the adapter is available with or without 2 or 4 MB of RAM on-board.
Price: $795.
Contact: Envisio, Inc., 510 First Ave. N, Suite 303, Minneapolis, MN 55403, (612) 339-1008; fax (612) 339-1369.
Circle 1283 on Inquiry Card.

World Radio History

Programmer's Paradise

ALBRIDGE COMPANY

Cache 86	39
PreCursor	CALL

BKS SOFTWARE

POET	CALL

BORLAND

Borland C++	299
& Application Frameworks	479
ObjectVision 2.0	105
Paradox 3.5	525
Turbo C++	69
w/Turbo Vision	139
Turbo Debugger & Tools	105

GREENLEAF SOFTWARE

Greenleaf Comm++	289
Greenleaf Comm Library	287
Greenleaf DataWindows	315
Greenleaf Fin. Math Lib.	315
Greenleaf Fin. Math Lib++	155
Greenleaf Functions	179
Greenleaf SuperFunctions	239
Greenleaf ViewComm	319
Greenleaf ViewComm++	289

INTERSOLV

PVCS CONFIG. Builder	209
PVCS Version Mgr.	509
PVCS Professional Editor	249

SOFTWARE BLACKSMITHS

C-DOC	169

SOFTWARE QUALITY AUTO.

SQA: ROBOT	979

SOLUTION SYSTEMS

BRIEF	CALL
BRIEF & dBRIEF	CALL
CHARGE	89
C-Worthy	399
w/source	579
Sourcerer's Apprentice	455

SOUTH MOUNTAIN SOFTWARE

Breakout II	189
C Utility Library	199
Essential B-Tree	159
Essential Communications	259
Essential Graphics Chart	149
Essential Graphics GUI	105
Essential Graphics Kernel	149
TSRific	79

STINGRAY CORPORATION

123 CONNECTION	179
256-K VGA Toolkit	119
CLARINET	179
EMBARK	279
PerfectLEM	89

ImageMan™

PUTS IMAGES IN YOUR WINDOWS- ImageMan is the first and only object-oriented Windows library that puts advanced image display and print capabilities in your software. Access any type of image with the same set of standard function calls. ImageMan fully supports TIFF, PCX, GIF, EPS, WMF and BMP formats. Use ImageMan with any language that supports calling DLLs:: C, C++, Turbo Pascal for Windows, Visual Basic, Smalltalk/V, Actor and many more. Royalt Free.

List: $395 **Ours: $350**

FAX*cetera* #3612-0001

Embark Professional Standard Edition

Installation software that is revolutionary in its approach to creating software installations. An integrated environment is provided to design, simulate, estimate disks, include custom help and create disks. File compression, splitting, selection, target directories, autoexec.bat/config.sys modification and much more done by selection options. "Scriptless programming" feature allows full customizing, all without any programming. Fully NetWare aware.

List: $299 **Ours: $279**

FAX*cetera* #1000-7201

SUN COUNTRY SOFTWARE

SHOWCATImage Catalog	179
SHOWCASE Image Database	535
SUNSCAN Digital Scanware	269
SUNSHOW	
Advanced Image Toolkit	219
"C" Language Image Lib.	219
Database Professional	89
Image Converter	225

SYMANTEC

Just Write	179
Norton AntiVirus	99
Norton Backup	99
Norton Commander	99
Norton Desktop f/Windows	109
Norton Editor	85
Norton Utilities 6.0	129
On Target	279
Q&A	265
Time Line 5.0	475
Zortech C++ Dev. Edition	445
Zortech C++ S&E Edition	659

BORLAND

Turbo Pascal 6.0	105
Turbo Pascal Pro 6.0	209
Turbo Pascal for Windows	175
World of C++ Video	95

CASEWORKS

CASE:W Knowledgebase	349
CASE:W Corporate Edition	899
CASE:PM for C or C++	1895
CASE:PM for COBOL	2395

COPIA INTERNATIONAL

AccSys for C/dBASE	349
FaxFacts	CALL

DIGITALK

Smalltalk/V	99
Smalltalk/V 286	169
Smalltalk/V PM	395
Smalltalk/V Windows	395

DISK SOFTWARE

TGL 20/3D	239
TGL Professional	389
TGL/Utilities	159

DOLPHIN SOFTWARE

Dolphin C Toolkit	119
Dolphin Encrypt	139

FAIRCOM

c-tree Plus	489
Faircom SQL Server	409
Faircom Toolbox	899
r-tree	239

GIMPEL SOFTWARE

PC-Lint	105
C-terp	229

MEDIA CYBERNETICS

Dr. HALO IV Compet. Upgrade	49
Dr.HALO IV Imaging Pak	105
HALO Desktop Imager	105
HALO F/X	219
HALO Image File Format Lib	189
HALO Professional	279

MICROSOFT

MS BASIC Prof. Devel. Sys.	349
MS C/C++ 7.0	299
MS C/C++ Comp. Upgrade	134
MS COBOL	629
MS FORTRAN	349
MS Macro Assembler	105
MS Office for Windows	499
MS OS/2	
Present. Mgr. Softset	105
MS Pascal	209
MS QuickBASIC	69
MS QuickC for Windows	139
MS Visual Basic	139

MORTICE KERN SYSTEMS

MKS LEX & YACC	197
MKS Programming Platform	539
MKS RCS	149
MKS Toolkit	199

PERISCOPE

Periscope Debuggers	CALL

PHAR LAP

PharLap 386 DOS Extender	435
PharLap 386 VMM	259
PharLap 286 DOS Extender	435

SEQUITER SOFTWARE

CodeBase 4.5	265
Code Base ++	265

WATCOM

WATCOM C9.0	429
WATCOM C9.0/386	629
WATCOM FORTRAN 77 8.5	449
WATCOM FORTRAN 77/386	629
WATFOR-77 3.1	335

WHITEWATER GROUP

Actor 4.0	219
Actor Professional	445
ObjectGraphics	CALL
WINTRIEVE	339
WRT	CALL

SourceSafe

SourceSafe is the project-oriented version control system. It organizes source code into logical project groups that you define. VCS features include complete "reverse-delta" histories, including project snapshots and commentary; maintenance of parallel variations of projects; and coordination of multiple developers. Other features include unequalled ease-of-use and online help.

List: $245 **Ours: $209**

FAX*cetera* #1000-7301

CALL FAX*cetera*™

(908-) 389-8173

for additional information on the best selling products!

MICROSOFT C/C++ 7.0 IS HERE!

Programmer's Paradise has special bundle offers available on products from Island Graphics, Greenleaf Software, CASEWORKS, Sequiter Software, PocketSoft, Mortice Kern Systems, Zinc Software, Rogue Wave & Liant Software when purchasing MS C/C++ or the competitive upgrade.

CALL TODAY FOR DETAILS.

CORPORATE (CORSOFT): 800 422-6507

Circle 88 on Inquiry Card.

Paradise

800-445-7899

CORPORATE (CORSOFT): 800 422-6507

World Radio History

NEWS

WHAT'S NEW • OTHER HARDWARE

A Case for the Mac PowerBook

Magenta Seven's MagentaCase padded carrying case for the Macintosh PowerBook is made of resilient Du Pont 1000-denier Cordura nylon and closed-cell foam to protect the notebook during travel. Pockets and pouches carry all accessories, such as the power pack and as many as five batteries. The case is designed so that you can use the PowerBook without removing it, easing the problems of computing while on a plane or in a car.

Magenta Seven automatically enters owners into a lost-and-found registry. Each MagentaCase is uniquely coded, so if it is lost or stolen and then recovered, the company can identify the owner. Owners may elect to register their PowerBooks with the company.

Price: $119.95.
Contact: Magenta Seven, Inc., 5109 Holly Ridge Dr., Suite 209, Raleigh, NC 27612, (919) 787-2787; fax (919) 787-1277.
Circle 1284 on Inquiry Card.

FDDI Tester

A hand-held, battery-powered Fiber Distributed Data Interface tester, the Model LCT 100 Link Confidence Tester can test FDDI links and stations to test networks and troubleshoot network problems. The LCT 100 tests protocols and optical performance, and you can use it to verify that your cable's performance is adequate for FDDI. The unit tests connection management and link confidence, as well as link error rate.

The MagentaCase comes in a variety of colors.

Price: $5900.
Contact: Fotec, Inc., 529 Main St., Box 246, Boston, MA 02129, (800) 537-8254 or (617) 241-7810; fax (617) 241-8616.
Circle 1285 on Inquiry Card.

Give Intelligence to Your PC

The Intelligent Power Module automatically powers off your PC when your system finishes its unattended jobs. Activated by receiving on/off signals from your PC via a signal cable connected to the PC's parallel or serial port, the module sits in-line between a wall outlet and a power strip.

The Intelligent Power Module works by responding to the power-off command you've put at the end of the BAT file you use to run unattended operations. When the job is complete, your PC sends the signal to the module to shut down the system. The unit ships with software commands on a floppy disk and a signal cable to attach to your PC.

Price: $59.
Contact: Server Technology, Inc., 2332-B Walsh Ave., Santa Clara, CA 95051, (800) 835-1515 or (408) 988-0142; fax (408) 988-0992.
Circle 1286 on Inquiry Card.

External Blocking of ELF Radiation

ELF ProTech, an externally mounted, extremely low frequency magnetic field suppressor for video display terminals, reduces your VDT's ELF magnetic field to significantly less than the 2.5-milligauss guidelines prescribed by MPR II, according to NoRad. The shielding device is made of a highly specialized alloy, modified by NoRad to attract and absorb magnetic fields radiating from the monitor.

You can use ELF ProTech to retrofit an existing monitor without using special tools. When installed on the sides and top of the monitor housing, the device is transparent to the VDT's performance and does not impair image quality while it reduces ELF magnetic field strength from the front, back, sides, and top of the monitor.

Price: $49 to $99, depending on number of panels required.
Contact: NoRad Corp., 1549 11th St., Santa Monica, CA 90401, (310) 395-0800; fax (310) 458-6397.
Circle 1287 on Inquiry Card.

Standby Computing Power

Available in 250-VA and 450-VA models, the Patriot standby power system is rated UL 1449 for its full-time lightning and surge protection. Patriot protects against high-voltage conditions by switching the load from line to inverter. The system provides full-time EMI/RFI protection via its advanced multistage filter for 33 dB of common-mode and 47 dB of normal-mode noise isolation. Two audible alarms and a triple-mode status indicator light to warn of overloads or a low battery are included.

The Patriot 250 VA supports small stand-alone computers, including the Mac SE/30. It can support a PS/2 Model 30 with a VGA monitor for 22 minutes.

The Patriot 450 VA has an interface port that lets it trigger a safe, orderly shutdown and includes CheckUPS software and automatic shutdown kits for operating systems such as DOS, OS/2, AS/400, NetWare, LAN Manager, LANtastic, and Unix/Xenix. The Patriot 450 can support a PS/2 Model 55 for 18 minutes or a Sun-3/60 system for 12 minutes.

Price: Patriot 250 VA, $169; Patriot 450 VA, $279.
Contact: Best Power Technology, Inc., P.O. Box 280, Necedah, WI 54646, (800) 356-5794; fax (608) 565-2929.
Circle 1288 on Inquiry Card.

World Radio History

Data Compression of course, but

Which One?

Why not go with the real-time data compression software being used by more PC users worldwide!

Just install SuperStor 2.0 and you instantly increase your disk capacity by 2-3 times! Then use your computer the way you normally do, no extra commands or keystrokes are required.

SuperStor 2.0 provides up to 25% greater compression than before! It's the fastest, most advanced product of its kind, with many unique features that make it more powerful, easier to use, and far more flexible than the competition. Just look at the chart to review SuperStor's numerous features–many of which are not offered by other compression products.

SuperStor 2.0 is not only the most powerful, it's the most user friendly, too! Clear, colorful graphic displays make installing and using SuperStor simple. And, SuperStor 2.0 runs with all popular operating systems and application programs.

So when choosing data compression, SuperStor is the one!

For more information, please call 1-800-732-3133.

Not all data compression products are created equal!	*SuperStor New Version 2.0*	Stacker 2.0
Compresses hard drives, RAM, floppy, and other removable media by an average ratio of 2:1, doubling your disk capacity!	YES	YES
Real-time on the fly data compression doesn't slow down your PC!	YES	YES
Universal Data Exchange allows compressed floppies or removable drives to be read and saved by any PC!	YES	NO
Fully integrated menu-driven software program offers ease of installation and operation!	YES	NO
Advanced Compression Utility Tool Kit scans, checks, and repairs compressed data!	YES	NO
Advanced Disk Optimization Utility defragments or consolidates compressed data for optimal disk performance!	YES	NO
Highest compression ratio of any data compression software (up to 25% greater with version 2.0!).	YES	NO
Automatically updates CONFIG.SYS on physical partition to further enhance transparent operation!	YES	NO
Dynamically adjusts drive capacity to fit more data on compressed disks with less effort!	YES	NO
Performance enhancing Disk Cache results in faster system performance!	YES	YES
Device driver easily loads high, maximizing conventional memory for RAM-intensive applications!	YES	YES

addstor

3905 Bohannon Drive
Menlo Park, CA 94025
Tel: 800-732-3133 ▪ Fax: 415-688-0466

AddStor and SuperStor are trademarks of AddStor, Inc. Copyright © AddStor, Inc. 1991. All rights reserved. Stacker is a trademark of Stac Electronics.

Circle 170 on Inquiry Card.

World Radio History

IF IT HAS ADOBE* SCALABLE FONTS, COLOR, AND QUIET TECHNOLOGY,

IT CAN ONLY BE FROM PANASONIC.

The KX-P2124, a 24-pin with ATM and color option.*

World Radio History



A few dot-matrix printers offer you scalable fonts.

A few, color. But no other printer offers you scalable fonts...color...and Panasonic® Quiet Technology.

Put our KX-P2124 and 2123 to work and you'll get the flexibility of Adobe Type Manager® and scalable fonts...you'll add drama to your documents with our optional color kit...and you'll hear very little, indeed.

Put any of our other Quiet Technology printers to work and you can accomplish whatever your needs.

From our 2123, a budget-minded 24-pin with Adobe Type Manager* and optional color...to our 2624 wide-carriage business printer with ATM*,...to our 9-pin 2180 with 6 near letter quality fonts and optional color.

All with the kind of features that made Panasonic printers the leaders of the industry. Such as multiple paper paths, EZ™ Set control panels, and a two-year limited warranty on parts and labor†.

The Panasonic 2000 Series Quiet Technology Printers.

Call us for more information: 1-800-742-8086. Or visit your Panasonic dealer.

†See your dealer for warranty details.
*ATM and Adobe Type Manager are registered trademarks of Adobe.
Available on selected printers only.

Panasonic
Office Automation

ONCE YOU'VE TRIED OUR QUIET TECHNOLOGY PRINTERS, YOU'LL NEVER SETTLE FOR ANYTHING LESS.

The KX-P2123, a 24-pin with ATM and color option.*

The KX-P2180, a 9-pin with color option. ATM not available.*

The KX-P2624, a 24-pin with ATM. Color option not available.*

PQ9-BY

Circle 99 on Inquiry Card.

World Radio History

Phone and Fax While on the Move

FaxPak, an integrated cellular phone and fax machine, uses a cellular transceiver from Motorola, ensuring reliable performance in remote areas, according to the company. With a five-page document feeder and 98-foot rolls of paper, the FaxPak provides easy faxing while you're traveling.

Compatible with standard office fax machines, the 1-ppm FaxPak FP-100B can be powered three ways: via its internal rechargeable batteries, a cigarette lighter adapter, or an AC 110-V adapter. The sealed lead-acid batteries recharge whenever the unit is connected to an external power source, permitting you to use it while the batteries are charging.

Price: $2295.

Contact: Infinidisc Corp., 7 Littleton Rd., Westford, MA 01886, (508) 692-0898.

Circle 1289 on Inquiry Card.

Pocket a Parallel Port Print Server

You can install the Pocket Print Server ESI-2828A for 10Base-T networks on the parallel port of any printer, which lets the printer attach anywhere on the network. Supporting NetWare 2.15 or higher and NetWare 386, the Pocket Print Server's parallel interface transfers data into the printer in large blocks at speeds of up to 60 KBps.

Price: $495.

Contact: Extended Systems, 6123 North Meeker Ave., Boise, ID 83704, (208) 322-7575; fax (208) 377-1906.

Circle 1290 on Inquiry Card.

The FaxPak integrated solution to the portable office gives you first-rate communications in the field.

Fax from Your Desktop

The 2400 ETC-Fax internal modem supports V.42 error correction and V.42bis and MNP level 5 data compression. Able to send and receive faxes at 9600 bps, the fax modem is compatible with Group 3 and EIA Class 1 fax machines. The modem includes Multiple Interrupt Selection, which lets it coexist with other add-ins, such as network cards, memory boards, and mouse controllers. The modem also features the capability to schedule fax transmissions during off-peak hours, broadcast faxes to multiple destinations, and create custom cover pages.

Price: $249.

Contact: ATI Technologies, Inc., 3761 Victoria Park Ave., Scarborough, Ontario, Canada M1W 3S2, (416) 756-0718; fax (416) 756-0720.

Circle 1291 on Inquiry Card.

Miniature MAU

Patton Electronics' Model 2100 MiniMAU 10Base-T transceiver/multistation access unit lets you use your Ethernet attachment unit interface ports to communicate over twisted-pair cable. The 2- by 1.68- by 0.79-inch unit with CMOS circuitry supports cable runs of up to 300 feet without AC power or batteries. Raised LEDs are readable from most angles for easy monitoring of autopolarity, collision, jabber, link integrity, transmit, receive, and power functions.

Price: $89.

Contact: Patton Electronics Co., 7958 Cessna Ave., Gaithersburg, MD 20879, (301) 975-1000.

Circle 1292 on Inquiry Card.

Qmodem 5 Offers New Features

Version 5 of Qmodem adds a number of enhancements to the communications program. The major addition, the Off Line Mail Reader, lets you download packets of mail from an originating BBS and read them off-line at your leisure. The feature also lets you write your replies off-line and then upload them for sending.

New features in the Dialing Directory let you specify the directory entry setting, such as name of service, phone number, and baud rate, for automatic dialing of subsequent calls. Other additions to the Dialing Directory include the capability to attach notes to any dialing entry, automatically redial an unlimited number of entries, and sort your directory by an entry's name, phone number, or total number of calls.

Terminal emulations added to Qmodem include the IBM 3101, DEC VT52, and Heath Zenith 19. You also can now preconfigure the program for more than 90 commercial modems. The learn mode now lets you create automated scripts to record repetitive tasks. The scripts help you by automating common functions such as log-in sequences, transferring files, downloading messages, and sending replies.

Price: $99.

Contact: Mustang Software, Inc., P.O. Box 2264, Bakersfield, CA 93303, (805) 395-0223; fax (805) 395-0713.

Circle 1293 on Inquiry Card.

World Radio History

WHEN IT COMES TO MATH COPROCESSORS

THE CHOICE IS SIMPLE!

✓IIT

HIGH PERFORMANCE



LOW POWER CONSUMPTION



HIGHEST SPEED GRADES

VALUE

- ✓ **Guaranteed 100% Compatibility with all 286, 386 and 386SX systems**
- ✓ **Warranteed For the Lifetime of Your System**
- ✓ **Free QAPlus and POWERMETER Software**

Call now for more information
800-832-0770
408-727-1885

Test results obtained on a 20 MHz 386SX system.

The IIT logo is a trademark of Integrated Information Technology, Inc. (IIT). QAPlus and POWERMETER are trademarks of DiagSoft, Inc.
All other trademarks are of their respective companies. ©1991 IIT. All rights reserved.

™ INTEGRATED INFORMATION TECHNOLOGY • INC.

Circle 77 on Inquiry Card (RESELLERS: 78).

World Radio History

Mini Modem for Portables

The ViVa 2400 Pocket modem lets you communicate with remote computers or time-sharing systems via your portable computer. The 6½-ounce, 2400-bps unit works in full-duplex mode over a dial-up or two-wire leased telephone line.

Able to automatically dial a call and answer incoming calls over the phone line from a remote system, the ViVa 2400 Pocket can redial a busy number and dial an originate-only modem. The four LEDs include a modem-ready light that indicates when the unit is receiving power, two lights that show when a carrier is detected and when the battery is low, and a light that indicates when the unit is operating at high speed.

The modem comes with communications software, a wall-mount power pack, and a 9-V battery. Software packages supported include Smartcom II 2.1, Symphony, WordStar 2000, PC-Talk, Crosstalk, and Sidekick.
Price: $139.
Contact: Computer Peripherals, Inc., 667 Rancho Conejo Blvd., Newbury Park, CA 91320, (800) 854-7600 or (805) 499-5751; fax (805) 498-8306.
Circle 1294 on Inquiry Card.

Take Automatic Inventory of Your LAN

The LAN Directory hardware and software inventory program gathers and reports information in hundreds of categories for each workstation on your LAN. The utility automatically audits workstations and file servers for information and can inventory standalone personal computers by running the software at each machine. You can audit external devices manually and then enter the information into the software.

The custom reporting feature in LAN Directory lets you create your own reports or build on and modify the reports that are included in the utility. You can create multiple headers and footers and move text around the screen, placing the title and data areas wherever you wish. You can gather LAN workstation data automatically by adding a command to the log-in script.
Price: $495.
Contact: Frye Computer Systems, Inc., 19 Temple Place, Boston, MA 02111, (617) 451-6364; fax (617) 451-6711.
Circle 1295 on Inquiry Card.



The ViVa 2400 Pocket modem travels in your pocket for use anywhere.

A Modem for Secure Communications

The SecureModem 2032e has the double security feature of callback access control and DES data encryption. The dual feature protects dial-in networks from unauthorized access and secures sensitive data transmission against illegal tampering and monitoring.

The SecureModem 2032e has V.42 error control and MNP level 5 data compression, a combination that enables error-free encryption throughput of 19,200 bps. The desktop unit's full-screen menus are easily configured to automatically authenticate an incoming call, perform call-back or pass-through, and secure communications by scrambling data.
Price: $895.
Contact: Cettlan Corp., P.O. Box 397, Irvine, CA 92650, (714) 559-4016; fax (714) 262-0708.
Circle 1296 on Inquiry Card.

Create a Skyline View of Network Traffic

Skyline/E, a Macintosh-based network-analysis tool, provides managers of mixed-vendor, multiple-protocol networks with a history of Ethernet network traffic. Designed to provide a visual overview of network traffic, Skyline/E captures and stores data over extended periods.

The main window shows a histogram-type chart with bars that represent network use over a length of time of from 1 second to hours or days. You can assign colors and levels of use to the bars for an instant picture of traffic over a designated period.
Price: $695.
Contact: The AG Group, Inc., 2540 Camino Diablo, Suite 202, Walnut Creek, CA 94596, (510) 937-7900; fax (510) 937-2479.
Circle 1297 on Inquiry Card.

Eight-Port Hub for 10Base-T

An eight-port 10Base-T Ethernet concentrator, the 10T Hub/8 includes a BNC port for connecting to thin coaxial cable. The hub features auto-partitioning, which automatically shuts down a bad port when the hub detects jamming signals, and it has the ability to shut off Link Integrity port by port. It includes an in/out-selectable unshielded twisted-pair port that lets you connect to other hubs with UTP cabling.
Price: $399.
Contact: Asanté Technologies, Inc., 404 Tasman Dr., Sunnyvale, CA 94089, (408) 752-8388; fax (408) 734-4864.
Circle 1298 on Inquiry Card.

World Radio History

LOOK AT THE INSIDE STORY ON POWER SUPPLIES.

What power supply is inside your computer? If you are like most people, you don't know, and frankly, don't care. But, because your computer's power supply is a critical system component, what you don't know, may hurt you. An inferior power supply can cause interference, rebooting, hard drive errors, and other nasty hard-to-track problems. So why take chances? Call the power supply specialists at PC Power and Cooling today.



Turbo-Cool 300 Ordinary Power Supply

HERE ARE TEN GREAT REASONS TO SELECT THE INDUSTRY'S BEST, THE TURBO-COOL™ 300 AND TURBO-COOL™ 450.

1. 50% TO 100% MORE POWER

The more power, the better! Our high-capacity units start drive motors with ease, run cooler, last longer, and allow for future expansion.

2. BUILT-IN LINE CONDITIONING

Turbo-Cool power supplies won't skip a beat when the line voltage sags. Their wide input range (85-135V, 170-270V) and heavy-duty input components protect your PC and its data from sags, surges and spikes.



3. FCC-B AND VDE-B LINE FILTER

A dual-stage EMI filter keeps electrical noise well below agency standards.

4. INDEPENDENT REGULATION

Turbo-Cool's superior independent-regulation design keeps output voltage tolerances 20 times tighter than that of an ordinary power supply. This exceptional stability improves hard drive reliability during critical access periods.

5. ULTRA-CLEAN DC OUTPUT

A dual-stage output filter ensures that sensitive computer chips receive pure, low-ripple power.

6. PROTECTION CIRCUITRY

Our units offer the most complete protection from dangerous overvoltage, overcurrent, and short circuit conditions.

7. THERMASENSE™ COOLING FAN

The Turbo-Cool 300 features ThermaSense, our high-capacity, thermostatically-controlled, variable-speed fan. It's ideal! High-performance systems operate up to 35° cooler while standard ones run as much as 75% quieter.



8. UL/CSA/TUV APPROVALS

Our high-capacity units are safety approved by not only UL, but also by Canada's CSA and Germany's strict TUV.

9. TWO-YEAR WARRANTY

Turbo-Cools are designed and tested for MTBFs of over 100,000 hours. They come with a no-hassle 2-year warranty and a 30-day money-back guarantee.

10. GREAT VALUE

Loaded with premium features, a Turbo-Cool power supply will upgrade the performance of your PC or LAN file server at a retail cost of only 55¢ to 80¢ per watt. You'll be powered by a unit that is popular with award-winning PC manufacturers and recommended by experts such as the PC Magazine Advisor!



Turbo-Cool 450

PC POWER & COOLING, INC.

5995 Avenida Encinas, Carlsbad, CA 92008 • (619) 931-5700 • (800) 722-6555 • Fax (619) 931-6988

Circle 101 on Inquiry Card (RESELLERS: 102).

World Radio History

Introducing the be notebook co



World Radio History

st color display in a mputer. Ever.

In its review of our UltraLite® SL/25C notebook, *PC Magazine* said, "NEC is about to make the future of portable computing a whole lot brighter."

We couldn't agree more.

The best color display in a notebook. Ever.

The fact is, NEC is the first to offer an active-matrix TFT color screen in a notebook, and yet, in the words of *PC Magazine*, "its price tag rivals lower-quality passive-matrix offerings."

What's the difference between active-matrix and passive-matrix color screens? One looks vivid, sharp and bright, like your desktop monitor. The other doesn't. One can be viewed from wide angles. The other can't. One is clearly the future of notebook computing. The other isn't.

The best processing technology in a notebook. Ever.

To quote *PC Magazine* once more, our SL/25C "has more going for it than just spectacular color. It's also one of the first notebooks to use Intel's new 25-MHz 386SL chip set."

The new chip provides all the processing punch of a 386 desktop PC. Offers intelligent power management for longer battery life. And runs even the most complex applications at blazing speed. The 7.5 lb. SL/25C comes standard with 2MB of RAM (expandable to 10MB), an 80MB hard disk, internal floppy and 64KB cache. As well as MS-DOS® 5.0 and Windows™ 3.0, loaded and ready to run.

Just what exactly is active-matrix TFT display anyhow?

Active matrix TFT (thin-film transistor) display means that for each pixel on the screen, there is a tiny transistor. In the case of the SL/25C, that adds up to over 900,000 transistors covering the entire screen, forming the image. With each pixel controlled by its own transistor, the image is always in sharp focus, and far brighter than other screen designs permit. NEC has long been a world leader in display technology. And the SL/25C is one example of this.

It does everything a powerful desktop does. Except chain you to a desk.

There's a serial port, SuperVGA CRT port, PS/2® mouse port and optional internal modem. An enhanced parallel port allowing improved throughput for network connections. And an optional full-function, portable Docking Station™ unit—with two expansion slots and a 3.5" drive bay—that not only turns the SL/25C into a desktop you can take anywhere, it also gives you other options, like fully integrating sound and image to create your very own portable multimedia platform.

A powerful argument for color, right here in black and white.

It also has a brilliant VGA display. A palette of over 225,000 colors. A fast screen refresh rate (so you never lose your cursor). And a "simultaneous video" feature—so the image you see on your screen can also be viewed on an external video device, like a big-screen projector. All of which makes one thing perfectly clear: the SL/25C is truly the ultimate presentation tool.

Shown with optional Docking Station.



Call today.

For more details, call 1-800-NEC-INFO. Or call NEC FastFacts at 1-800-366-0476, #ULSL25C (8575252). In Canada, call 1-800-343-4418.

We'll give you enough information about the SL/25C to make you not want to be without it. Ever.

C&C
Computers and Communications

Because ⬆ is the way you want to go. NEC

Circle 95 on Inquiry Card.

World Radio History

UltraLite is a registered trademark of NEC Corp. Booklet Bui... 1.2.25 pm 21 NEC Living Freelance.eps. PC is a registered trademark of IBM Corp. MS-DOS is a registered trademark and Windows is a trademark of Microsoft Corp. Intel and 386SL are trademarks of Intel Corp. © 1992 NEC Technologies, Inc.

Multiplatform Applications with Objects

WinTran uses a system of named visual objects, such as text, lists, images, or tables, rather than windows, to develop multiplatform GUI applications. The WinTran application code is written in standard programming language but is not tied to any particular windowing model. WinTran treats visual objects uniformly across GUI platforms, so you can port their associated applications across Windows, OS/2, Macintosh, OSF/Motif, and other platforms.
Price: Windows version, $495.
Contact: Guideware Corp., 2483 Old Middlefield Way, Suite 224, Mountain View, CA 94043, (415) 969-6851; fax (415) 969-3862.
Circle 1299 on Inquiry Card.



WinTran's Project Manager consolidates all the application elements and presents a visual map of the project as it develops. The Builder window on the right provides tools for building interface screens without your having to switch back and forth between programs.

Knowledge Garden Upgrades Its OOP Tool

Version 2.0 of the KnowledgePro Windows (KPWin) object-oriented programming environment features improvements to its design tools, dynamic link library (DLL) access, and Multimedia Extensions support.

The upgrade lets you use objects such as combo boxes or buttons by selecting them from a library, dropping them into a window, and applying attributes like size, color, and font. KPWin automatically generates alterable corresponding code. You can link your objects to external DLLs via one-line commands. This DLL support lets you access all the commands in the Microsoft Multimedia Developers Kit, the company reports.

Knowledge Garden also offers the KPWin SVW Video Toolkit, an add-in toolkit for controlling motion video in real time. The Video Toolkit works with New Media Graphics' Super VideoWindows overlay board.
Price: KPWin 2.0, $249; SVW Video Toolkit, $299.
Contact: Knowledge Garden, Inc., 12-8 Technology Dr., Setauket, NY 11733, (516) 246-5400; fax (516) 246-5452.
Circle 1300 on Inquiry Card.

The KnowlegePro Windows visual design tools come with source code. You can generate code interactively, amend it, and then feed it back to the design tool.

Link and Swap Memory with Blinker 2.0

Said by its developer to be the only linker offering an integrated memory-swap function, Blinker performs linking and dynamic overlaying of programs written in Microsoft C, Zortech and Borland C++, and many other languages. Blinker 2.0 can also dynamically overlay the Microsoft BASIC PDS 7.1 development system. Blinker's memory-swap capability lets you use expanded or extended memory to save an executing program and then shell out and run a second program from within the first.
Price: $299.
Contact: Blinkinc, P.O. Box 7154, Richmond, VA 23221, (804) 355-4444; fax (804) 355-1676.
Circle 1301 on Inquiry Card.

Add Neural Networking to Windows

NeuroWindows lets you incorporate neural networks into your applications. Release 2.0 adds real-time execution of supervised and unsupervised learning processes. The library lets you incorporate up to 128 neural networks within a single program. A driver that provides support for the company's NeuroBoard (a RISC-based board for speeding up network training time) is included in release 2.0.
Price: NeuroWindows, $369; NeuroBoard, $2000 to $3100, depending on configuration.
Contact: Ward Systems Group, Inc., 245 West Patrick St., Frederick, MD 21701, (301) 662-7950; fax (301) 662-5666.
Circle 1302 on Inquiry Card.

A Video Library for C and BASIC

LiveWindows lets you write your own video-based applications in C or BASIC. The LiveWindows library lets you scale captured NTSC or PAL video to any size and display it in an on-screen window. The program lets you place VGA text or graphics on your live or frozen video.

The LiveWindows library is available for a variety of languages and compilers. A motion video board and VGA card with feature connector are required.
Price: $395; $995 with video board.
Contact: Software Interphase, Inc., 82 Cucumber Hill Rd., Suite 140, Foster, RI 02825, (800) 542-2742; fax (401) 397-6814.
Circle 1303 on Inquiry Card.

World Radio History

Raima Database Engine Captures Fortune 500 With Record Speed



Accelerated Database Performance

Compared to conventional relational databases, retrieval of records can be 10—20—even 50 times faster with Raima Data Manager from Raima Corporation.

Propelling The Biggest Names In Business

Companies like General Motors, Hewlett-Packard, IBM, Eastman Kodak, Rockwell and others are using Raima Data Manager in their competitive environments. Today's most critical, most demanding applications demand the high performance of Raima Data Manager.

Powerfully Efficient Leading-Edge Technology

Raima's combined technology merges the flexibility of relational databases with the lightning speed and efficient storage of the network model. With the program written entirely in C, you can "fine-tune" the Raima Data Manager engine for optimum performance in any application.

Put Yourself In Fast Company

Give yourself the competitive edge of Raima Data Manager:

- Speed—faster access to data
- Portability—supports most environments
- Royalty-free—increase your profits
- Source code availability—total programming flexibility
- Full Raima support services—including training

Whether you're writing a stand-alone DOS application, or one for UNIX accessing thousands of records, Raima Data Manager will put your application on the fast track. Race to the phone and call for more information!

Raima Data Manager™

The High Performance DBMS

In the U.S. or Canada, call: 1-800-DB-RAIMA

In Washington state or international, call: **(206)747-5570**

Specifications Relational B-tree indexing. Network data model. Relational SQL query and report writer. Single & multi-user. Automatic recovery. Built-in referential integrity. **Supports:** VMS, QNX, ULTRIX, UNIX System V, Berkeley 4.2, AIX, SunOS, SCO, MS DOS, MS Windows, and OS/2. **Most C Compilers and LANs supported.**

Raima Corporation 3245 146th Place S.E., Bellevue, WA 98007 USA **(206)747-5570** **Fax: (206)747-1991**
International Distributors: Australia: 61 2 419 7177 **Belgium:** 32 2 734 9818 **Finland:** 358 080405350 **France:** 33 1 46 09 27 84 **Germany:** 49 7022 34077; 49 214 91051 **Italy:** 39 49 829 1285
Japan: 81 33 865 2140 **Mexico:** 52 83 49 53 00 **The Netherlands:** 31 2159 46814 **Norway:** 47 2 38 48 88 **Singapore:** 65 334 0061 **Sweden:** 46 13 111 588 **Switzerland:** 41 64 517475
Taiwan: 886 2 552 3277 **United Kingdom:** 44 992 500919
Copyright ©1992 Raima Corporation. All rights reserved. Photo: Dale LaFollette

RY42RC

NEWS

WHAT'S NEW • BUSINESS SOFTWARE

Share Windows, Mac, or GEM Scheduling Data

With version 4.0L, Artemis Schedule Publisher offers real-time calculation of schedules, resources, and costs. The project management tool runs on Windows, Macintosh, or GEM systems and lets you share files among the three environments. Schedule Publisher 4.0L uses on-screen option boxes to automatically trigger scheduling data, such as placement of resources or descriptions within the project.

Integrated with Schedule Publisher is Artemis Presents 2.0A, Lucas's graphics presentation program. Presents lets you compile reports that include text files, scanned images, and CAD drawings.

Price: Schedule Publisher, $1995; Presents, $995; both, $2495.

Contact: Lucas Management Systems, Inc., 12701 Fair Lakes Cir., Suite 350, Fairfax, VA 22033, (703) 222-1111; fax (703) 222-8203.

Circle 1304 on Inquiry Card.

Financial Finesse with Mutual Fund CD-ROM

Now you can be your own broker by using Morningstar Mutual Funds OnDisc to evaluate, compare, and track more than 2200 mutual funds. The CD-ROM package contains a database of front-load, no-load, equity, and fixed-income funds. You can use fund data in conjunction with the program's searching and graphing capabilities to select funds and plot them against each other, compare returns for funds over a period of time, and present your findings as graphs or reports. You can export fund data via PCX, WK1, and ASCII files for use in spreadsheet, word processing, presentation, or other applications.

You can measure your Mutual Funds OnDisc selections against nine benchmark indexes, including the Standard & Poor's 500. The program includes a history and complete portfolio for each fund. In many cases, Morningstar provides information acquired directly from the fund manager.

Price: Subscription with annual update, $295; with quarterly update, $495; with monthly update, $795.

Contact: Morningstar, 53 West Jackson Blvd., Chicago, IL 60604, (312) 427-1985; fax (312) 427-9215.

Circle 1305 on Inquiry Card.



Artemis Schedule Publisher's real-time calculation tools let you use a mouse to slide a particular resource and immediately see the impact of your change on other resources.

All-in-One Mac Office Software

HandiWorks combines a word processor, a spreadsheet, a basic drawing program, page layout tools, and an address database in a single Macintosh program. The package provides tools for linking textual and numerical data and updating that data within a document. You can import and export ASCII, Microsoft Word, MacWrite, and WriteNow files. HandiWorks supports a variety of graphics file formats. Using Claris's XTND filters, HandiWorks can exchange files with other word processors and spreadsheets.

Price: $175.

Contact: MacVonk•USA, 313 Iona Ave., Narberth, PA 19072, (215) 660-0606.

Circle 1306 on Inquiry Card.

Using Network H.Q., the network administrator can collect and update key workstation files such as CONFIG.SYS or WIN.INI.

Translation Program for HP 95LX

The Globalink Translation ROM cards run on Hewlett-Packard's HP 95LX portable computer and use grammatical analysis to do sentence-by-sentence translations between English and German, Spanish, or French. Each 2-MB card contains a pair of dictionaries with more than 50,000 terms.

Price: $299 per language pair; $815 for one pair and the HP 95LX.

Contact: Globalink, Inc., 9302 Lee Hwy., Fourth Floor, Fairfax, VA 22031, (800) 255-5660 or (703) 273-5600.

Circle 1307 on Inquiry Card.

Survey Your Networked Hardware

Network administrators can now use Network H.Q. over a variety of networks to track workstation configurations. Version 2.0 runs over NetWare, Microsoft LAN Manager, Banyan Vines, and Hayes Lan/Step NOS networks and identifies PC model numbers, chip-set data, and other hardware information. According to Magee Enterprises, the H.Q. utility will survey Macs connected to your network. Network H.Q. also surveys software on both the server and workstation internal drives.

Price: $395 for 100-workstation license; $595 per server with unlimited users.

Contact: Magee Enterprises, Inc., P.O. Box 1587, Norcross, CA 30071, (404) 446-6611; fax (404) 368-0719.

Circle 1308 on Inquiry Card.

World Radio History

Open new windows with TI microLaser™ printers.

And get powerful fonts and graphics, ease of use and more speed than ever.

By now you've heard how fast and easy Microsoft® Windows™ makes it to tap all that PC power you've got on your desk.

Well now there's an affordable, easy way to put that power on paper — microLaser from Texas Instruments.

Right out of the box, microLaser comes with what you need to print the dazzling pages of text and graphics you've dreamed of.

Just plug it in and go. POSTSCRIPT

That's because microLaser PS models come with PostScript® software from Adobe® and the memory it takes to use it. Plus you get your choice of either 17 or 35 scalable fonts, starting at just $1,399*.

New model. More speed. Same price.

When it comes to print speed, the new microLaser Plus zips along at 9 ppm. If you need a shared printer solution, turn to the 16 ppm microLaser XL.

If all that isn't enough, just look at what else you get with microLaser. It's the smallest printer in its class. It handles more paper and envelopes in more ways. And it supports more than 4,000 software packages, including your Windows applications.

So when you add it all up, you'll understand why the power of your ideas needs the power, convenience and economy of microLaser. Let microLaser open new windows for you.

For the name of the nearest dealer, call

1-800-527-3500.

TEXAS INSTRUMENTS

*TI suggested retail price. (Dealer prices may vary.) microLaser is a trademark of Texas Instruments Incorporated. Microsoft is a registered trademark and Windows is a trademark of Microsoft Corporation. Adobe, PostScript and the PostScript logo are registered trademarks of Adobe Systems, Inc. © 1991 TI 71860

Circle 130 on Inquiry Card.

World Radio History

See Fox *RUN*.



We've just added a new word to the database vocabulary: *RUN*.

And it can make you a master of your database management universe. Even if you've never managed a database before.



The most powerful PC DBMS available is now the easiest to use, too: FoxPro™ 2.0.

Pick *Run* from the FoxPro 2.0 main menu and you have instant access to your information. Click on *Report*, choose the name of the report you want, and it's yours. Do the same for queries, forms, labels and applications.

For answers on-the-fly, pick *RQBE* (Relational Query By Example) and get a simple interface for creating custom queries quickly and easily. Unlike other query systems, RQBE lets you browse the information or create instant databases, reports, labels, or business graphs (with optional FoxGraph or other graphic program).

Custom systems are easy, too.

You create quick reports, forms, labels and applications by clicking on the *New* button in the dialog box instead of picking a name from the list.

Then using our simple tools, you build forms containing buttons, lists, check boxes, text regions and data fields. Reports with headers, footers and

World Radio History

subtotals. And even complete applications.

All without any programming.

So while it's the most powerful DBMS you can get today, it's ideal for small businesses and large. In industry or government. For invoicing and inventory control, order entry and accounting, and all your data handling needs.

FoxPro is the state-of-the-database-art.

FoxPro 2.0 is the object-oriented, event-driven DBMS programmers have been waiting for, too.

We've added over 100 new and enhanced commands. 4GL (Fourth Generation Language) tools for creating screens, reports and menus as reusable application objects. And the ability to attach entry and exit procedures to fields, forms and windows for pre- and post-processing.

We've integrated SQL SELECT, UPDATE and CREATE TABLE into the language, with the ability to use RQBE for creating SELECT statements you just cut and paste into your application code.

We've added a project manager on top of our debugger, trace window, and editor.

We provide an Application Program Interface (API) that links to C or assembler function libraries (Library Construction Kit optional).

And we offer an optional Distribution Kit to distribute your applications royalty-free.

Today's best choice for upgrading or downsizing critical database applications.

FoxPro is devastatingly faster than competitive products (see chart† – the difference is even greater in single-user tests), and has out-queried even mainframe databases like Oracle, XBD and DB2, using our patent-pending Rushmore™ query optimization.

No one comes close to FoxPro's multi-user query response.

It's backward compatible with dBASE III+/IV and earlier versions of Fox software to protect your investments in hardware, software, training, and support.

And in the few months since its release, FoxPro 2.0 has swept the awards. Best DOS Application - *Spring COMDEX*. Technical Excellence *-PC*. Award of Excellence *-Byte*. Best DBMS *-Data Based Advisor*. And many, many others from both editors and users of FoxPro 2.0.



Applications developed today with FoxPro for DOS, unlike other databases, will be able to run under Windows and SCO/UNIX and on the Macintosh when we release our new versions of FoxPro later this year.

Get a headstart on tomorrow today.

Today, FoxPro exchanges data with FoxBASE+ on Macs and on PCs running SCO UNIX. Later this year, FoxPro will be available for Windows, UNIX, and the Mac, all with access to Netware SQL, SQL Server, and Oracle databases.

And applications written using FoxPro's 4GL tools will be platform-adaptive, so DOS or Windows applications will run on UNIX or the Macintosh, and vice-versa.

Which means you can get a headstart on your future by starting your Windows, Mac or UNIX development now with FoxPro on your current DOS PCs.

It comes with a 60-day money-back guarantee.

So pick up a copy of FoxPro 2.0 at your nearest computer or software store. Try it out for 60 days, then if you don't like it, just return it to your dealer for a full refund.

But we think you'll agree with Byte magazine in their 1/92 review of dBASE: "...FoxPro is the better product."

Call 1-800-837-FOX2 today.
(419-874-0162 from Canada)
Ask for Lit Pak BYT401

FOX SOFTWARE

†Query benchmark tests performed by Micro Endeavors, Inc. (215) 449-4680, from Data Based Advisor 8/91.

FoxPro, FoxBASE+ and FoxBASE+/Mac are trademarks of Fox Holdings Inc.; other products are not. © Fox Holdings Inc. 1992.

Animate Your Spyglass Data Models

A new scripting capability enables Spyglass Transform 2.1 for the Macintosh to create animated images from your plotted data. Scripting lets you automate Transform commands and batch-process your 2-D data files. Because the program accepts Apple events, you can run Transform commands from other applications. The template feature lets you save Transform commands performed on one data set and execute them later on another data set. According to Spyglass, the program performs five to 10 times faster than the previous version.

Transform 2.1 lets you control orientation, axis location, and labeling. You can run plot animations as PICS, HDF, or PICT sequences.
Price: $495.
Contact: Spyglass, Inc., 701 Devonshire Dr., C-17, Champaign, IL 61820, (217) 355-6000; fax (217) 355-8925.
Circle 1309 on Inquiry Card.



You can scale Spyglass Transform colors to represent actual numeric values.

Turn Your Monitor into a Meter Display

PCImeter lets you display analog data on-screen as digital and analog meters and bar graphs. You can run up to 16 meters simultaneously, and you can set high and low alarm points for each meter. If you so desire, PCImeter can be configured to trigger digital outputs as your data reaches the setpoints. You can save meters to your PCImeter application files and reconfigure them at any time.

PCImeter runs under Windows 3.0 or higher. The program acquires data for analysis via an Intelligent Instrumentation I/O board, and it can export the results to Microsoft Excel spreadsheets using Dynamic Data Exchange.
Price: $95.
Contact: Intelligent Instrumentation, 1141 West Grant Rd., MS 131, Tucson, AZ 85705, (602) 623-9801; fax (602) 623-8965.
Circle 1310 on Inquiry Card.

PCImeter, here displaying a digital meter (lower right corner), an analog meter (bottom center), and bar graphs (left and top).

Math Modeling with Expanded Graphics Tools

Matlab 4.0 merges numeric computation software with application-specific tools and graphics capabilities to provide a mathematical modeling tool with a variety of analytical functions. Enhancements to the X Window System program include sparse matrix support, support for data import and export via any arbitrary file format, and sound output.

Version 4.0 provides tools for analyzing and visualizing data, as well as optimizing engineering system designs and algorithms. You can use Matlab 4.0 to create mathematical models, solve systems of equations, and perform general computations. The program lets you create and animate 3-D graphs using rectangular, spherical, and general parametric coordinate systems.

Matlab 4.0 is available for the Sparcstation; Hewlett-Packard 900/300, 400, and 700; IBM RISC System/6000; DECstation Ultrix; and Silicon Graphics workstations.
Price: $2995.
Contact: The MathWorks, Inc., Cochituate Place, 24 Prime Park Way, Natick, MA 01760, (508) 653-1415; fax (508) 653-2997.
Circle 1311 on Inquiry Card.

Develop and Plot Systems of Equations

With VisSim for Windows, you can turn the most convoluted equation into a sensible data model. VisSim lets you build flowchart-style programs from data blocks and connect the blocks with function-performing FlexWires. Once you've developed your program (e.g., for representing the cycles of a bouncing ball or the flow of blood in the human body), VisSim plots it against a time element. Version 1.1 lets you alter your data model by using a slider control to adjust the source data.

You can save your VisSim models as screens and export them to Windows applications such as WordPerfect. The program lets you import and export ASCII data files, and you can print your models on all Windows-supported output hardware.

VisSim lets you build model programs that contain up to 16,300 data blocks. Visual Solutions also offers a personal version with a 255-block limit. The company recommends using a math coprocessor with VisSim.
Price: Professional version, $895; personal version, $190.
Contact: Visual Solutions, Inc., 487 Groton Rd., Westford, MA 01886, (508) 692-5499; fax (508) 692-3102.
Circle 1312 on Inquiry Card.

World Radio History

14,400 bps DATA
14,400 bps FAX
Voice*
Caller ID*
5 Year Warranty
$399.95

Are We Connecting Yet?

Introducing the amazing new SupraFAX-Modem™ V.32bis! On the fax side, it has 14,400 bps send and receive fax, Class 1 and 2 commands, and compatibility with the millions of Group 3 fax machines in use. On the data side, it connects at 300 to 14,400 bps and provides up to 57,600 bps throughput with V.42bis compression. (It has MNP 2–5 and 10, too.) Plus its revolutionary display gives you 25 different status reports! And for just a little more, you can easily add caller ID and voice capabilities later this year. In addition to the $399.95 stand-alone version (without software), SupraFAXModems are available in Windows™, DOS™, and Macintosh™ packages.

Supra Corporation

1-800-727-8647

9600 bps Version $299.95

7101 Supra Drive S.W., Albany, OR 97321 USA • 503-967-2410 • Fax: 503-967-2401

* Low-cost, user-installable Voice & Caller ID upgrades available Q2 '92.

All trademarks belong to their respective companies.

Circle 171 on Inquiry Card.

World Radio History

NEWS

View AutoCAD Files on Your Sparcstation

Drawing Librarian for Sun lets you view and make notes on AutoCAD, DXF, and slide files. You can access AutoCAD drawings on your Sparcstation via Sun's Open Look interface or use Drawing Librarian to convert DWG files to DXF.

Using a menu of drawing commands, Drawing Librarian lets you mark up CAD images and save the notations in a separate file. The program's functions include zoom and rotate, and you can display blocks, layers, and other AutoCAD information. Drawing Librarian supports AutoCAD versions up through release 11.
Price: $1000.
Contact: SoftSource, 301 West Holly St., Bellingham, WA 98225, (206) 676-0999; fax (206) 671-1131.
Circle 1313 on Inquiry Card.

FreeHand Upgrades for Mac and Windows

Upgrades to the Aldus FreeHand design program are available for Windows and Macintosh environments. FreeHand 3.0 for Windows lets you access tools and layers via floating palettes. You can also use the Windows upgrade to draw and edit in full-screen color preview mode. FreeHand 3.1 for the Mac offers a pressure-sensitive capability for use with freehand drawing tools. The program fully supports System 7.0 and offers new file import and export options.
Price: $595 each.
Contact: Aldus Corp., 411 First Ave. S, Seattle, WA 98104, (206) 628-2320.
Circle 1314 on Inquiry Card.

Drawing Librarian lets you view and add notes to files faster than with AutoCAD, SoftSource reports.

Graphing and Presentation Tools for Mac

Version 1.5 of DeltaGraph Professional offers System 7.0 support and more than 40 styles of business and scientific charts. DGP lets you import text and graphics data via WKS, PICT, and other filters, Publish/Subscribe, or a direct link to Microsoft Excel. Once you import your data, you can plot it as a column, pie, or other business chart or as a scientific chart (e.g., a time line, spider, or bubble). Charting options include scatter, surface, and true 3-D x, y, z surface plots.

DGP lets you create unlimited libraries in which to store custom-formatted charts, clip art, or other items. The Slide Show feature lets you present charts from the screen as printouts or as screen captures. Slide Show offers 32 slide transition effects.
Price: $295.
Contact: DeltaPoint, Inc., 2 Harris Court, Suite B-1, Monterey, CA 93940, (408) 648-4000; fax (408) 648-4020.
Circle 1315 on Inquiry Card.

SPREAD THE WORD

Please address new product information to New Products Editors, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458. Better yet, use your modem and mail new product information to the microbytes.hw or microbytes.sw conferences on BIX. Please send the product description, price, ship date, and an address and telephone number where readers can get more information.

A Multitude of Tools for AutoCAD

With version 5.0 of ASG Core, you can now apply a wide variety of tools and utilities to AutoCAD applications. The program contains a hierarchical layer manager, a scheduling manager, a cost-estimating interface, menu and text file editors, Advanced Modeling Extension menus, full metric and imperial support, compatibility with NetWare and other networks, and other features.
Price: $495.
Contact: ASG, 4000 Bridgeway, Suite 309, Sausalito, CA 94965, (415) 332-2123; fax (415) 332-2146.
Circle 1316 on Inquiry Card.

Scan Text and Graphics with OmniPage

OmniPage, for Macintosh systems, automatically separates text from graphics and lets you scan any document, regardless of the number of typefaces or columns. OmniPage's optical-character-recognition tools let you process text at rates of up to 2000 words per minute. The Verification Window lets you edit a scanned document while simultaneously viewing a bitmapped image of the original page.

Other features include the ability to recognize and correct upside-down scans, correct interpretation of similar-looking characters, and System 7.0 support.
Price: $995.
Contact: Caere Corp., 100 Cooper Court, Los Gatos, CA 95030, (408) 395-7000; fax (408) 354-2743.
Circle 1317 on Inquiry Card.

World Radio History



World Radio History

WE'LL BE THERE WHEN YOU GET THERE.

Desktop Direct from Digital™

With Desktop Direct from Digital, you're never alone on the road. A support team of 10,000 stands behind every i386™-based, 20MHz DECpc™ 320P Notebook Personal Computer. Wherever you are, we're just a free phone call away.

So whether you need help running Windows™ in a Wisconsin coffee shop or advice on connecting a modem in a midtown Manhattan hotel, give us a call. If we can't solve your problem over the telephone, we'll send you a repaired system—even on the road—within 48 hours. Even in the unlikely event that your disk drive goes down in Des Plaines or your keyboard comes loose in Kalamazoo.

Think of it as travel insurance for your notebook computer.

Circle 65 on Inquiry Card.

World Radio History

Wherever you go, you won't miss any connections with the DECpc 320P Notebook. That's because the 320P comes *standard* with a 2400 baud modem so you won't get behind in answering your MCI Mail®—or get cut off from your company database.



And at $1,995 the DECpc 320P Notebook is *priced* to go. Fast.

We put it all on the table. The 20MHz DECpc 320P Notebook Personal Computer is the most comfortable to use on the market today, while the components inside are the hottest. We started with the Intel™ 386sx™ processor and the built-in 2400 baud modem (optional data/FAX modem). Because we don't believe you should have to sacrifice power for portability.



Next, we made the standard 2MB memory expandable to 8MB—plenty of room for running multiple Windows applications. For extra oomph in spreadsheet recalcs, we made room for an optional 80387sx™ Math Coprocessor. Then we added a 40MB (optional 80MB) hard drive and a 3.5″ Floppy diskette drive for ample storage—with DOS™ 5.0 and Windows 3.0 pre-installed. We topped off the chassis with the Triple Super Twist (TST) Backlit VGA display—that puts Windows on-screen without an aggravating blur. We built an AC adapter to weigh less than a pound—so it's easy to carry around—*and* we added the Logitech™ TrackMan®Portable,for FREE.

We even included a three-hour plus battery life to keep you up and running even when you're away from it all.

So call Desktop Direct, before you go, anywhere.

DESKTOP DIRECT from DIGITAL
Taking PCs into the world ahead

Call Desktop Direct at
1-800 PC BY DEC (1-800-722-9332)
Please reference ALU when you call.
8:30 am to 8:00 pm (ET) Mon.-Fri.

digital™

Circle 65 on Inquiry Card.

World Radio History

LEADER OF

The **DEC**pc 320P Notebook

Includes:

Microprocessor:	Intel i386sx running at 20MHz
Memory:	2MB
Storage:	40MB IDE Hard Disk Drive 3.5" 1.44MB Floppy
Display:	TST Backlit VGA
Modem:	2400 bps Data
Keyboard:	84-key Keyboard
Mouse:	Logitech TrackMan Portable
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0 (factory installed)

(Carrying case included)

Special Package Price **$1,995**

FR-PCP11-AA

NEW LOW PRICE

The **DEC**pc 316sx

Includes:

Microprocessor:	Intel i386sx running at 16MHz
Memory:	1MB, 80ns Memory Kit
Storage:	52MB IDE Hard Disk Drive 3.5" 1.44MB Floppy
Resolution Mode:	1024 X 768 SVGA Adapter
Display:	14" Multi-sync VGA Color Monitor
Keyboard:	101-key Keyboard
Mouse:	Three-button Mouse
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0

Special Package Price **$1,749**

DJ-PC444-05

NEW LOW PRICE

The **DEC**station 325c

Includes:

Microprocessor:	Intel i386 running at 25MHz
Memory:	4MB, 80ns Memory Kit
Storage:	52MB IDE Hard Disk Drive 3.5" 1.44MB Floppy 1.2" dd Floppy
Resolution Mode:	1024 X 768 SVGA Adapter
Display:	14" VGA Color Monitor
Keyboard:	101-key Keyboard
Mouse:	Three-button Mouse
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0

Special Package Price **$2,179**

DJ-PC462-04

NEW LOW PRICE

Circle 65 on Inquiry Card.

World Radio History

THE PACKS.

The DECpc 320P Notebook

Includes:

Microprocessor:	Intel i386sx running at 20MHz
Memory:	2MB
Storage:	80MB IDE Hard Disk Drive 3.5" 1.44MB Floppy
Display:	TST Backlit VGA
Modem:	2400 bps Data
Keyboard:	84-key Keyboard
Mouse:	Logitech TrackMan Portable
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0 (factory installed)

(Carrying case included)

Special Package Price **$2,495**

FR-PCP11-FA

The DECstation™ 320sx

Includes:

Microprocessor:	Intel i386sx running at 20MHz
Memory:	1MB, 80ns Memory Kit
Storage:	52MB IDE Hard Disk Drive
Resolution Mode:	1024 X 768 SVGA Adapter
Display:	14" Multi-sync VGA Color Monitor
Keyboard:	101-key Keyboard
Mouse:	Three-button Mouse
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0

Special Package Price **$1,849** NEW LOW PRICE

DJ-PC443-05

The DECpc 433 Workstation

Includes:

Microprocessor:	Intel i486 running at 33MHz
Memory:	8MB, 70ns Memory Kit
Storage:	40MB IDE Hard Disk Drive 3.5" 1.44MB Floppy
Resolution Mode:	1280 X 1024 TIGA Adapter
Display:	20" Color Monitor
Keyboard:	101-key Keyboard
Mouse:	Three-button Mouse
Operating Systems:	MS-DOS 5.0 and MS-Windows 3.0

Special Package Price **$4,999** NEW LOW PRICE

Offer Good Thru 3/31/92

DJ-PCW10-02

DESKTOP DIRECT from DIGITAL

Taking PCs into the world ahead

1-800 PC BY DEC (1-800-722-9332)

Please reference ALU when you call. **Circle 65 on Inquiry Card.**

World Radio History

PUT YOUR PC TOGETHER ON PAPER.

FAX
TOLL FREE TO
1-800-524-5694

and we'll send you a special system recommendation. Or call 1-800-722-9332 and we'll recommend by phone.

OPEN For Business

DESKTOP DIRECT from DIGITAL
Taking PCs into the world ahead

digital™

i386, i386sx, i80387sx and Intel are trademarks of Intel Corporation. MCI Mail is a registered trademark of MCI Communications Corporation. Windows, and DOS are trademarks and Microsoft and MS-DOS are registered trademarks of Microsoft Corporation. Logitech is a trademark and TrackMan is a registered trademark of Logitech International S.A. Apple is a registered trademark of Apple Corporation. Compaq is a registered trademark of COMPAQ Computer Corporation. AST is a trademark of AST Researchers, Inc. Dell is a registered trademark of Dell Corporation. OS/2 and PC/AT are registered trademarks and Presentation Manager is a trademark of International Business Machines. Q&A is a registered trademark of Symantec Corporation. NetWare is a registered trademark of Novell, Inc. Banyan Vines is a registered trademark of Banyan Systems, Inc. VLSI is a registered trademark of VLSI Design Associates. TOPCAT is a registered trademark of Westinghouse Corporation.

The DIGITAL logo, DECpc, DECstation and PATHWORKS are trademarks of Digital Equipment Corporation.

Circle 65 on Inquiry Card.

Your Name _____

Title _____

Company Name _____

Address _____

City _____ State _____ Zip _____

Your Telephone No. _____ Your FAX No. _____

I'd like information on:

- ☐ DECpc i386 and i386sx based systems
- ☐ DECpc i486 and i486sx based systems
- ☐ The DECpc 320P Notebook
- ☐ The Catalog

Customization Worksheet

Your base system is a: ☐ 286 ☐ 386 ☐ 486 ☐ Other

How many applications will your PC(s) run in a typical workday? _____

What best describes the type of work the system will be used for? (Check all that apply)

☐ Word Processing	☐ Desktop Publishing	☐ Scientific Research
☐ Order-entry	☐ Education	☐ Software Development
☐ Database (filing records)	☐ Design (CAD/CAM)	☐ E-Mail
☐ Financial Calculations	☐ Engineering	☐ Other industry-specific applications (please specify)
☐ Retail Store Management	☐ Industrial Process Control	

How many people work in your group, department or small business?
☐ Less than 10 ☐ 10-20 ☐ 20-35 ☐ More

Is your operating system:
☐ DOS ☐ DOS with Windows ☐ OS/2 ☐ MAC ☐ UNIX™ ☐ Other

Which of the following graphics-oriented applications best describes your needs? (Check all that apply)

☐ Desktop Publishing	☐ Realtime Modeling	☐ AutoCad
☐ CAD/CAM	☐ Animation	☐ Business Graphics
	☐ Image Processing	

LAN Communication

How many PCs do you have installed? _____ From how many manufacturers? _____

What kinds of connections does your PC(s) require? (Check all that apply)

- ☐ Links with other PCs in the immediate surroundings
- ☐ Connection to the local area network (LAN) throughout a building
- ☐ A line to a host system in a remote location

What kind of media (cable) is used in your LANs today? _____

What is the networking software now being used in your company? _____

What kind of host system will your PC communicate with?
☐ DEC ☐ IBM ☐ Other _____

What Kind of Service Do You Really Need?

☐ On-site Hardware Support ☐ Software Support ☐ Telephone Support
☐ Training ☐ FAX Hotline

How many of your users take portables on the road? _____

Do you currently have a service contract(s) for your PCs? ☐ How many? _____

1-800 PC BY DEC (1-800-722-9332)
Please reference ALU when you call.

World Radio History



JERRY
POURNELLE

USER'S CHOICE AWARDS

It's that time again. Unlike some people, I don't give my annual awards until the end of the year, which means it is now time for the 1991 User's Choice Awards and the Chaos Manor Orchid and Onion Parade.

Two cheers for IBM for not releasing OS/2 2.0 in 1991. They advertised that it will be a better DOS than DOS and a better Windows than Windows, and no matter that it's been coming Real Soon Now for quite a while, they're not going to ship it until it works properly. I can agree with that decision.

Two cheers for Bill Gates for delaying the release of Windows 3.1 and announcing Windows NT (New Technology) years before it will ship. Meanwhile, out here in User Land, we'd just like something stable that works and won't give us unrecoverable applications errors....

Three cheers and an orchid for AMD and their 386 chip, which has sent the prices of 386 systems tumbling, and for developing a 40-MHz 386 chip. Two cheers to the Taiwanese clone makers who advertise systems as "Intel Inside" and then in small print tell us they're using AMD chips....

User's Choice

I began the annual User's Choice Awards on a whim. This was long before everyone else began giving awards. It was also during the early days in the computer industry, when there weren't many products that *deserved* awards. I conceived it as part of my job to drive the computer industry in directions I thought would be best for users. The awards, as well as the onions and orchids, were designed to further that end, and they've had some success.

The trouble is that I began with the wrong approach, because I wanted to give awards for "the best of the year." That wasn't bad in the early days, when I really could look at most of the major items in any given category, but now it's often plain ridiculous to pretend that I have looked at everything significant. Worse, though, is how do I choose when several products are more than good enough?

Sometimes, though, a product will stand out so much that there's little doubt, and I have no hesitation in calling it the top product in its field. When that happens, I'll say so. But do understand that just because some product stands out alone doesn't mean that it's "better" in some absolute sense than another wonderful product that has to share the glory with a competitor. Good enough is good enough, and that's how User's Choice Awards should be taken. By designating a product as User's Choice, I'm saying that if you need its capability, you won't be sorry you bought it.

The rules here are simple: I don't recommend anything I have not personally used long enough to have confidence in. I discuss these decisions with my BYTE editorial colleagues, and BYTE helps distribute the certificates, but the User's Choice Awards remain my sole responsibility. Blame me, not BYTE....

Upgrading Your System

The annual Orchid and Onion Parade at Chaos Manor

Probably the best upgrade you can buy for your DOS system is a caching drive controller. Caching is a means of anticipating what data your computer will want next and putting that data where the machine can find it fast. For example, all caching systems keep the disk directory and file allocation table in cache memory so that the computer doesn't have to physically access the disk to find out where to get or store a file. After that the caching programs vary, although all of them use some kind of "most used, last discarded" algorithm.

One way to get the benefit of caching is to add more memory and use one of the better software caching programs (e.g., Vcache from Golden Bow Systems or even the SMARTDRV.SYS that comes with Windows). However, those programs just add to the work load of your CPU and bus, and they tie up memory you could be using for other things.

By contrast, caching controllers have an on-board CPU, so you're doing true multiprocessing. They have algorithms at least as good as the software-only caching programs and caching memory on the controller card. The result is a dramatic improvement in performance: reads and writes go much quicker than under straight DOS or DOS with a software cache, and you still have all your expanded memory. Moreover, you can save system memory. I have not been able to see any difference

ILLUSTRATION: STEVE TURK © 1992

World Radio History

in performance with or without buffers, which wasn't true prior to my getting a caching controller.

I have used two caching controllers. The first one I got is from Distributed Processing Technology, the PM2011/90 for SCSI hard drives. (I also have their PM3011/70 for ESDI hard drives.) The other one is the HyperStore 1600 from Perceptive Solutions, Inc. They both work splendidly. I have to work hard to devise tests that will show any performance advantage to either one. One test I have is a big matrix inversion that repeatedly stores intermediate results on the hard disk. Caching controllers typically save about 50 percent of the 5 minutes the program requires when running with a noncache controller, and the difference in time for the controllers from DPT and PSI is negligible.

Both these controllers are easily installed. Each company has SCSI and ESDI controllers. PSI has configuration modules for other types of drives, so if you have such a drive, your choice is clear. Otherwise, you simply have to go on brand loyalty and price.

Moreover, both PSI and DPT controllers have modes to let you use just about any old drive you have available. PSI has a way to add on several different *kinds* of physical drives and run them all at once through add-on modules known as *media adapters*. This could be useful if you have, say, a SCSI drive and an IDE drive and want to use both in the same machine. Both PSI and DPT controllers have ways of making your machine believe you have an AT-compatible hard drive, no matter what it really is; they will also let you use the latest and greatest hard drives and software. Both companies have excellent technical support. Although it isn't needed for simple installations, it can be important as soon as things get tricky.

I've been writing about both companies for three years, and I have received no reader complaints against either. DPT is a bigger company and has been around longer. Their products cost more, and they use proprietary memory cards. PSI has been steadily gaining market share in the last two years and has been around long enough that I'm sure they'll be here for a while. PSI charges less and uses standard SIMMs for memory.

In a word, both companies are plenty good enough. I am pleased to award DPT and PSI User's Choice Awards for 1991 for their caching controllers.

Video Boards

Windows with old and slow video is nearly intolerable. If you want to switch to Windows, it's imperative that you get a fast video board. The improvements are dramatic. Our friend Steve Allen Mitchell, a Unix workstation guru, has to work with Windows off and on. He was recently introduced to a 486 with an ATI Technologies Graphics Ultra video board and said, "That's as close to a workstation as a PC is going to get."

Unfortunately, pure speed is not enough: there are boards out there that are plenty fast enough, but whose BIOS hogs memory the board doesn't really need. It's important to get a board that works properly with Windows, yet allows you to use good memory managers; and it's important to get that board from a company that understands driver software.

I have had half a dozen video-board companies recommended to me. I'm sure they're all good, but I can recommend only what I use myself. Do understand, I have tested these only under Windows, not under the X Window System or Unix.

For Windows, the two video boards and

Move to Windows, stay with the VAX.™

Considering Windows? But can't afford to lose contact with your host? KEAterm 420 is the solution: DEC VT420 terminal emulation software for Windows 3. Now, you can have the best of both worlds!

KEAterm 420 is a true Windows 3 application which provides the functionality of DEC's VT420, VT320 and VT220 terminals in a window. KEAterm 420 version 2 gives you the features that count: multiple pages, multiple sessions, file transfer, multilingual support (English, French and German), script language and DDE support as well as network connections. Using the familiar Windows interface, KEAterm makes it easy to move between servers, hosts and PC applications. With KEAterm, you can do it easier, do it faster, do it better!

To tie it all together, use KEA's network connection software: KEAlink LAT, KEAlink TCP/IP, and KEAlink IPX for concurrently connecting to your Novell network and your VAX or UNIX host. To eliminate keyboard remapping, select KEA's *PowerStation* VT layout keyboard to plug into your PC. And if you're a DOS or UNIX user, KEA Systems offers the ZSTEM family of VT graphics and text emulation software for desktops running DOS or UNIX.

For superior PC-VAX-UNIX connectivity, call today!

KEA Systems Ltd.
Orders: 1-800-663-8702
Telephone: (604) 431-0727
Fax: (604) 431-0818

KEA

See us at Windows World and Comdex Spring '92, Booth 2742

VT Emulation Under Windows

KEA Systems Ltd., 3738 North Fraser Way, Unit 101, Burnaby, BC, Canada V5J 5G1.

The KEA logo, KEAterm, KEAlink, ZSTEM and PowerStation are trademarks of KEA Systems Ltd. All other brand and product names are trademarks or registered trademarks of their respective holders. Copyright © KEA SYSTEMS LTD. 1991. All rights reserved.

Circle 83 on Inquiry Card.

World Radio History

MINUTEMAN TAKES CHARGE IN OVER 1000 JCPENNEY STORES.

Every time JCPenney sells a pair of jeans, a toaster or a bottle of perfume, MINUTEMAN takes charge. That's because more than one thousand JCPenney stores rely on MINUTEMAN UPS systems to back up power to their point-of-sale systems.

Every day your company relies on its voice and data communications equipment to stay productive. Unfortunately, the electricity that powers these vital systems is not reliable.

Blackouts, brownouts, spikes, surges and even lightning strikes are common in most business environments. And the high cost of losing vital information and productivity due to power outages and surges calls for preventive measures.

Power requirements can be confusing. And your company has unique needs that often require custom solutions.

MINUTEMAN offers the most comprehensive line of UPS systems available, protecting all your business equipment from stand-alone workstations to the largest of the IBM AS/400s.

MINUTEMAN products are *sold and serviced worldwide*. Call on our skilled professionals to help you determine your exact power protection needs.

MINUTEMAN PRODUCTS

- On-line and standby UPS
- Shutdown software for every available operating system
- 300VA to 10KVA
- Power boost design on the new MINUTEMAN Power Master 600
- Automatic voltage regulators
- International models

Call our toll-free POWER HOTLINE now for your free Power Protection Guide.

(800) 238-7272

MINUTEMAN®
UNINTERRUPTIBLE POWER SUPPLIES



Dick Patefield, Senior Project Manager for Store Systems Support, JCPenney

Recently JCPenney Co., Inc. changed its operations from the old POS systems to the new PC-based technology, relying on PC platforms for point-of-sale and in-store support. And they back each one up with help from MINUTEMAN.

"There was a violent surge in one of our stores," says Patefield. *"If we didn't have the MINUTEMAN unit, it probably would have seriously damaged all of our point-of-sale equipment.*

"The key was the switch-over time from AC to battery," says Patefield. *"It really has the best continuity of the UPS systems we evaluated. Also, the price was very favorable. When you're installing them in as many locations as we are, the pricing was very attractive."*

SEE US AT
COMDEX CHICAGO
BOOTH #113

FOR LAN TESTED AND APPROVED Novell Compatible



© 1992 Para Systems, Inc., 1455 LeMay Drive, Carrollton, Texas 75007 (214) 446-7363 (214) 446-9011 fax

Circle 100 on Inquiry Card.

World Radio History

video software that I currently recommend are from ATI and Sota Technology. Both boards are easy to install, the physical board and software drivers. The documents are complete and easily understood, and technical support is good. I'm pleased to give the ATI Graphics Ultra and the Sota Lightning VGA my 1991 User's Choice Awards.

Printers

For many years, we have had one of the very first Hewlett-Packard LaserJet printers ever made. It was eventually refurbished as a LaserJet Plus and became The Printer That Would Not Die. Over the years, I came to dislike certain features, particularly the fact that it stacked the paper face-up, meaning that a book came out with its pages in the wrong order. It was also difficult to insert letterhead. It wasn't particularly fast, although compared to the Diablo daisy-wheel printer it replaced, it certainly was.

All that was mere grousing, though; that printer was wonderful. It worked year after year—never in the shop, never out of service, always there when I needed it. I turned out thousands of letters and a dozen or more books on that printer.

It still works and is in use at a church school. But this year I replaced it with a LaserJet III, and once again I'm in love. If you need a real workhorse printer, one good enough for most office work, the LaserJet III is more than just good enough; it's outstanding. It's easily installed. There are dozens of fonts for it (it uses all the font cartridges from my old LaserJet I), and nearly every software package provides drivers for it. It's fast, it's designed so that it's easy to insert letterhead or print envelopes, and it's very reliable.

I have no hesitation in giving the LaserJet III a User's Choice Award as the most useful printer of 1991.

The LaserJet III does have resolution limits, although they aren't severe. As I detailed in a previous column, Jim Baen was able to do the final typesetting of *Go Tell the Spartans* by Pournelle and Stirling using the Baskerville typeface, Ventura Publisher, and a LaserJet III to produce masters that were then photoreduced to make the printing plates. However, that book was an all-text paperback printed on typical paperback paper; this process would not have been good enough to do the typeset masters of a larger-format book on slick paper.

For that kind of resolution, I recommend the LaserMaster TrueTech 1000. This produces 1000-dot-per-inch resolution output with well-shaped letters. The LaserMaster algorithms for increasing printer resolution appear to be better than HP's trick for accomplishing that. Indeed, I see no reason why LaserMaster output couldn't be used to master any book I have, regardless of size, typeface, and paper stock. Let me hasten to add that I don't pretend to be the final authority on typesetting, and if you're contemplating doing high-resolution print masters, you probably want to spend some time researching the situation.

I do know that the LaserMaster TrueTech 1000 produces aesthetically pleasing copy. Moreover, unlike the phototypesetter it can often replace, the LaserMaster doesn't require nasty chemicals, and, also unlike most phototypesetters, it's extremely reliable. If you need high resolution, you'll be happy with the LaserMaster TrueTech 1000. It gets a User's Choice Award in the Very High Resolution Printer category.

The CEO wants to know when it will be finished.



The staff wants to know when they can start.



As a project manager, you've seen it all before. Everyone who needs to know, all too often, needs to know something different. Which is why there's new Microsoft® Project version 3.0 for Windows.™

It not only makes it easy to present things the way *they* want, but also lets you plan things the way *you* want.

Now you can enter and view data in a variety of ways – Gantts, tables, graphs, forms and more. Microsoft Project also has a customizable Toolbar,™ giving you access

©1992 Microsoft Corporation. All rights reserved. Printed in the USA. Offer good only in the 50 United States. To order a Working Model for $9.95 or for more information: In the United States, call (800) 541-1261, Dept. X.

World Radio History

File Conversions

There's always a need to convert files from one format to another. It's especially true when changing over to Windows, but since I use Q&A Write, hardly a week goes by when I don't get a file in a format different from that of my word processor. When that happens, I rely on Word for Word from Mastersoft to convert the file, and that usually works.

I say *usually* for accuracy; I'm not trying to be hard on Word for Word. The problem is that there are a lot of file formats out there, and some of them use some obscure tricks. It would be surprising if everything worked the first time every time. I've used a lot of file-conversion programs, and the one that has worked consistently best has been Word for Word; moreover, they keep updating it, and each revision is an improvement.

I'm not 100 percent satisfied with the program: I wish there were better "intelligent ASCII" conversions for use on files pulled off-line, and once in a while I get some odd glitches when converting to Q&A Write format. But it's still the best conversion program I know, plenty good enough to win a User's Choice Award.

Windows vs. Desqview

I can't decide. I have used Desqview for years, and I'm comfortable with it. Desqview with a 386 machine is so superior to DOS that until Windows 3.0, I couldn't imagine using anything else—and it's indispensable for 286 systems. It's true that you have to fuss a bit with Desqview, but even that's much simpler now that Quarterdeck has revamped the installation program. Desqview works and works well, and I'm used to it, so I can jump from word processor to notebook to telephone book to diary to communications program simply and easily, and I generally have no problems at all.

Alas, it's not *fun*, while Windows is. I confess it: I like being able to customize my start-up screen. I like wallpaper, and flying toasters are fun, and so is having a Gary Larson Far Side cartoon come up with my calendar page on start-up. I like having silly little customized icons. I can even offer the intellectual defense that seeing all those icons on my computer desktop reminds me that they're there, just as having books all around me in my office reminds me of things I read long ago. Then, too, there really are some Windows programs that are so good that it may be worth buying Windows to be able to run them. I'll get to those in a minute. The point is, there's a lot to like about Windows.

Alas, there are a couple of things to hate, too. The one I hate most is that Windows is far more likely to crash than Desqview, and when it does, it's likely to crash utterly and completely, requiring a hardware reset and certainly losing any unsaved work.

In fairness, I have to say that I never install and try a new application in either Windows or Desqview without saving everything first, so the amount of work I have actually lost due to Windows crashes is small to nonexistent. Also, the time lost to having to go through hardware reset is probably made up by the fact that it's generally faster and easier to install a DOS program under Windows than to get it right on Desqview. I also have to say that Desqview used to crash fairly often, and I stuck with it, and I'm not sorry.

The programs that crash Windows have generally been games. Some of them, like Strategic Studies Group's Warlords, will run under Desqview but crash Windows.

continued

The controller wants to know how much it will cost.

We want to know what you're waiting for.





to the functions you use most with a click of the mouse. While PlanningWizards give you online assistance to help develop plans.

What's more, new Microsoft Project has WYSIWYG and Multi-Page Print Preview, so plan on visiting the printer less.

For your upgrade or the name of a reseller, call (800) 541-1261, Dept. X13. You'll satisfy a lot more people. Including yourself.

Microsoft

For information only: In Canada, call (800) 563-9048; outside the United States and Canada, call (206) 936-8661. Microsoft is a registered trademark and Windows and Toolbar are trademarks of Microsoft Corporation.

World Radio History

Circle 126 on Inquiry Card.

BACK BY POPULAR DEMAND!

HARD DRIVE MANAGEMENT MADE EASY

SpeedStor for DOS
Hard Drive Installation, Management And Diagnostic Software

- Install and partition hard drives in minutes
- Maximize speed, capacity and efficiency with advanced utilities
- Comprehensive diagnostics not found in DOS

NEW v6.0 FEATURES!
- DOS 5.0-compatible
- Supports 8-, 16- and 32-bit controllers
- Works with memory managers

$99.95* SRP $29.95* Upgrade
*Plus tax, postage and handling

To order, call
800-967-4246 Ext. 2

OVER 700,000 INSTALLED

STORAGE DIMENSIONS
The Industry Leader In Storage Solutions

UPGRADE $29.95*

But I have to confess that I seldom play games under either Windows or Desqview, so the problem would seem more theoretical than real—but the theoretical problem is that if that game will crash Windows, what else will? And once in a while I get some very mysterious glitches, but I'm pretty sure they're specific to the Windows 3.1 update and will be fixed before you read this.

Alex points out that you can run Windows under Desqview; that way, you run all the DOS applications as Desqview applications and all the Windows applications in Windows. What you get that way is standard-mode Windows, but the practical effect of what enhanced mode really does is memory-address checking, and the combination of QEMM and Desqview does that better and faster anyway. Even so, it feels like a kludge, and I'd rather not have to run two different environments, particularly when I'm testing new software.

The gripping hand, as Moties are wont to say, is that if Windows hasn't quite become good enough, it won't be long before it gets there. While I will keep Desqview and use it when necessary, I expect the switch to Windows to be done by the end of this year. Therefore, the User's Choice Award for Operating Environment of the Year goes to Microsoft Windows.

Memory Management

I like Windows, and clearly I recommend that if you don't change to Windows, you should run Desqview. Either way, you'll need a memory manager; fortunately, the same one works for both. It used to be that QEMM and Windows had some problems, but no longer. Now they work together just fine. Moreover, installing QEMM-386 6.02 is a snap, and so is optimizing for either Windows or Desqview. As an example, we are looking at a Tandy 4033LX multimedia machine. It comes nicely integrated with Windows and CD-ROM and DOS extensions; the only problem is that as it comes, it has DOS windows of 530 KB. We installed QEMM and let the Optimize program do its thing; we now have 630-KB DOS windows on that machine.

I've looked at a lot of memory managers this year, and I have no trouble at all choosing Quarterdeck's QEMM-386 6.02 as the User's Choice for Best Memory Manager of 1991.

Windows 3 Secrets

If you use Windows, run, do not walk, to your nearest bookstore and get Brian Livingston's *Windows 3 Secrets*. Read the first four chapters, and I guarantee that you'll then know more about Windows than almost anyone you know. This book explains in clear language just what Windows is doing, what it's trying to do, and what its programmers thought they were trying to do.

It explains undocumented features. It interprets the Windows error messages, including those that imply precisely the opposite of what they seem to be saying. It explains what standard mode is, and why you probably want to use it even though you have a 386 system. It tells you how to make Windows save your desktop without exiting and restarting (i.e., open a DOS application and attempt to leave Windows with the "save on exit" switch on; Program Manager will inform you that there are open applications, but before it finds that out, it has saved the current desktop). It tells you what the "About Program Manager" display in "Help" means (and it's nothing to do with help at all).

Finally, the book comes with two disks of shareware Windows programs that will make your life a lot easier.

I don't care how many Windows books you already have; get this one. If you have this one, it's not likely you'll need any other. *Windows 3 Secrets* hands down wins the User's Choice Award for the Best Windows Book of 1991.

Ascend

The Franklin Time Management System is one of the best known of the paper and notebook time management systems. It's usually presented in a 4-hour seminar that teaches and motivates you to use the tools. Of course, some people find all that unpleasant and aren't interested in time management systems and tools. I've even heard a few call the system inflexible. I don't see it that way. I find the Franklin system a useful way to organize my work and set priorities on what I want to accomplish.

Ascend is a Windows implementation of the Franklin system. It comes with forms and notebooks to hold the calendars and schedules that the program generates, a software implementation of the Franklin system, and tapes and workbooks that present the Franklin seminar about as you'd get it if you attended in person. The result is that you have everything you need to change your life.

Now, if you don't need to have your life changed, this program isn't going to do much for you. Some people are well organized and don't need any help. Others are hopelessly disorganized, and it's possible that this won't help them because they like being the way they are. For the rest of us, the Franklin system offers some hope.

Franklin is a bit different from its rival

World Radio History

GATEBUSTERS!

$2,899 486-33 ISA*

$3,499 486-33 EISA**

- 32-Bit Intel 80486/33 MHz CPU
- Burst Mode Support
- **Zero-Wait 64KB (Exp. to 256KB) High Speed Cache***
- **Zero-Wait 128KB High Speed Cache****
- 4MB Zero-Wait State 32-bit memory on the World's Best Motherboard made by AMI (Expands to 32MB*/96MB**)
- 8 Expansion Slots 16-bit*/7-EISA and 1-32/8 bit**
- **SONY 1304 HG 14" SVGA Monitor (1024 × 768 Non-Interlaced)**
- Orchid ProDesigner II VGA Card with 1MB RAM
- 207MB 15ms Maxtor IDE Hard Drive
- Teac 1.2 AND 1.44 Floppy Drives
- 2 Serial/1 Parallel Ports I/O*
- 2 Serial/2 Parallel Ports I/O**
- PC Power & Cooling 300 Watt Power Supply
- Vertical Case: 6 Bays/Security Lock/LED
  (Also shown is our optional deluxe case 450 W PS)
- **Keytronics 101-key Enhanced Keyboard**
- **AMI BIOS/CMOS Set-up/Diagnostics/Clock/Calendar**
- 3-Ring Cloth Binder for Manual and Software
- 10-year Lithium Battery/ TOUCHE Tool
- 800 number for Lifetime Technical Support
- TRW On-Site Service Available to Most Locations
- Federal Express Replacement of Defective Components
- FCC B Certification

Made in the USA

$1,899 386-33 MHz COMPLETE SYSTEM
Upgradable to 486

386 20SX Starting at $799

COLORADO 120MB Tape Back-Up Option $249
BOCA 2400 Baud Internal Modem Option $69

TOUCHE
A PC PROS Company
8205 South Cass Avenue Darien, Illinois 60559
708/810-1010 Fax 708/810-9490

VISA DISCOVER FEDERAL EXPRESS

THE TOUCHE COMMITMENT TO QUALITY AND VALUE KEEPS GROWING!

OUTSTANDING. That is the word PC Magazine used to describe our system! We're very proud of our 486-33 review and we encourage you to read it.

One example: Of 30 systems reviewed, TOUCHE **ranked #1 in the small-record DOS access file** test and #2 in the large DOS access file test for speed! To achieve this feat we relied on Maxtor and Ultrastor, two fantastic product partners.

Maxtor and Ultrastor are just two companies on a long list of companies we obtain high-quality components from to custom-build high-quality systems. AMI–SONY–Intel–Teac–Orchid–Keytronics–Micropolis–CYRIX–SIEMENS–PC Power & Cooling–BOCA are all names you'll easily recognize. You'll never see us offer components from **Fui-Manchui** or other tongue-twisting companies you've never heard of before.

WYSIWYG is a term used in desktop publishing. **What You See Is What You Get** is also a standard we use in building our systems. That means you get exactly what you expect when you receive your order from us. No hidden surprises or cut corners that many of our competitors try to sneak by with cheap or low quality components.

The use of AMI motherboards **guarantees** full DOS-UNIX-OS2 compatibility. We custom-build every system and offer special prices on enhancement items to upgrade your system like CD ROM's, digitizers, laser printers, scanners, 20" monitors, and hundreds of other products.

Our parent company, PC PROS, was founded in 1982. *Before you buy any system, ask all the hard questions and compare.* Who makes the motherboard? This is one of the most important questions to ask since this is the heart and soul of any computer. We use more AMI motherboards than anyone in the world. **Don't be fooled by claims of an AMI BIOS equaling an AMI motherboard.** Insist you receive a system with the best motherboard money can buy . . . an AMI.

Whether you're government, FORTUNE, major institution or just need a machine or two for your home or office, we offer the absolute best quality and service anywhere!

WHO YA GONNA CALL?

708/810-1010

Circle 145 on Inquiry Card.

World Radio History

Day-Timer, because the essence of the Franklin system has to do with setting priorities and goals. But the schedules and calendars that Franklin generates are fairly similar to those in a Day-Timer. I used to carry a Day-Timer everywhere I went, but I found that I wasn't able to coordinate between information gathered on the road and the home-base calendar. Ascend uses the computer to do much of that coordinating for you.

If you've been hoping to find something that would let your computer help organize your life, this program may be it. In any event, it gets a User's Choice Award for Windows Applications Software.

The Far Side

The Far Side Computer Calendar won't change your life. It's just a good Windows-based calendar program. On the other hand, it's fun, with a different Larson Far Side cartoon every day and some animations done by Larson himself.

It has the standard features of a calendar, with schedules and alarms and suchlike, and it will print them out in reasonable formats. But you wouldn't buy it for that since there are shareware programs that do as well. The Far Side Computer Calendar gets an orchid because it's *fun*.

Database Applications

For ordinary flat-file database applications, we use Q&A. There's a new version, 4.0, that fixes most of the annoyances of earlier versions and makes several improvements, including adding mouse support. Do understand, the problems we've had with Q&A have been minor annoyances, not major aggravations. Q&A remains the easiest database to learn and use that we know. A technoklutz can sit down in front of a Q&A screen and be building database forms within an hour; within a week, he or she will be able to do Christmas cards and print the labels, handle inventories, log in receivables, and generate reports.

Q&A Write is similarly easy to learn as a word processor, and it's powerful enough for anything I need: I write all my books and columns with it. Indeed, I recently installed Microsoft Word for Windows, and while it's elegant and has many features Q&A Write will never have, it didn't take long before I installed a Q&A Write icon and brought that up in Windows. I suppose someday I'll learn Word for Windows, but what's the hurry?

Flat-file databases may not be enough. You may need a really powerful full relational database. Most people don't. One of these days when I don't have to cover a zillion awards, I'll devote a chunk of the column to examining when and why

BY HAND. OR BY NOON.



Flow Charting™ 3

Now, even complex flowcharts that once took days to perfect can be presentation-perfect—in no time!

Quick to master and a snap to use, Patton & Patton's flowcharting software is the standard of both large and small businesses around the world—and is available through all major software dealers.

See your dealer today! Or, for a "live," interactive demo disk, call:
800-525-0082, ext.1116.
International: 408-778-6557, ext.1116.

PATTON & PATTON
Software Corporation
Excellence in charting the flow of ideas!

Works on IBM & 100% compatible PC's, supports CGA/EGA/VGA and over 150 dot matrix and laser printers, with multiple print densities and 10 font sizes. **Creates multi-page charts, portrait or landscape, on most standard paper sizes.** Mouse or keyboard controlled.

IBM is a registered trademark of International Business Machines Corporation.

Circle 22 on Inquiry Card.

World Radio History

New QEMM-386 v6.

There's no better way to manage your memory.

> "It's nothing less than a dream come true"
> —Steve Gibson InfoWorld 8/26/91

Suddenly PC users have a lot of memory managers to choose from. Seems that everyone has figured out what users have been telling us for years: they need every last 'K' of available memory between 640K and 1 megabyte—especially if they're running on a network. Or using TSRs.

Our new QEMM-386 version 6 is the best way to get the most out of memory. It 'pools' all your memory so that it's available in whatever form your programs need—expanded or extended. You don't even need to know the difference. QEMM does it all for you. Instantly. Whereas DOS 5, for example, requires you to figure out what you need, then manually allocate memory and re-boot every time you need to change.

As for the all-important 'conventional' memory area, our new version 6 increases the amount of memory freed-up. Our exclusive 'optimize' feature automatically seeks out TSRs and device drivers and moves them into high memory—the area between 640K and 1 megabyte. All you need do is type 'OPTIMIZE'.

#1

QEMM is the number one selling PC utility.

QEMM-386 v6 finds more high memory than any other memory manager. *Byte Magazine's* tests showed it produced net memory gains of 21K to 132K over DOS 5.0 alone, for instance.



Stealth takes you to network and TSR heaven.

Our breakthrough 'Stealth' technology makes available areas normally taken up by ROM. Areas that QEMM-386 can use to load memory-hogging drivers and TSRs. Big programs can get the memory they need to run fast and efficiently. And you get to have your TSRs.

Not every PC can benefit from Stealth. But every PC can benefit from *'Squeeze'*—our new feature to manage those TSRs that need more memory at start up and less when they're resident. Memory allocation is temporarily increased, then squeezed down after it's needed.

QEMM can use idle video memory to produce a further 96K gain on EGA and VGA systems when running character-based programs.

A priceless $60 bonus.

QEMM comes with Quarterdeck Manifest, the award-winning analysis program that makes it easy to see what's going on 'under the hood' of your PC.

See and understand how your PC works with Manifest.

Manifest does for memory what PC Tools Deluxe does for disks.

Benefits for Windows, too.

Whether you're running DOS 3, 4, 5, or Windows, QEMM can improve your 386/486's performance.

That means you may not need a faster CPU. You may not need more RAM. QEMM makes your favorite programs work better by giving them more memory.

QEMM helps you get the most out of the software you own today.

Quarterdeck

Quarterdeck Office Systems, 150 Pico Boulevard, Santa Monica, CA 90405 (310) 392-9851 Fax (310) 314-4219
Quarterdeck International Ltd., B.I.M. House, Crofton Terrace, Dun Laoghaire, Co. Dublin, Ireland Tel. (353) (1) 288-1444 Fax: (353) (1) 284-4380

©1992 Quarterdeck Office Systems. PC Week Analyst's Choice Logo, ©1991, Ziff-Communications Company. PC Week is a registered trademark and the PC Week Analyst's choice logo is a trademark of the Ziff-Davis Publishing Company. Other trademarks are property of their respective owners

Circle 114 on Inquiry Card.

World Radio History

you need a full relational database. In any event, if you do need one, I recommend Borland's Paradox, which is relatively easy to set up and is certainly powerful enough.

For Windows, though, you want an object-oriented database. For the moment, the best one of those I've seen is Bell Atlantic's Thinx, which I talked about in a past column. It's clever, the tutorial is sufficient for learning it, and it gets easier to use with practice. It's certainly powerful enough for most user needs.

I'm happy to give Q&A 4.0 and Thinx the User's Choice Awards for Best DOS and Windows Applications, respectively.

Clip'nSave

Several readers nominated this for an orchid. Clip'nSave makes it easy to capture Windows screens, save them in a BMP file, and convert them to different formats. There are detailed instructions on making your own wallpaper and a lot of information on bit-map formats and how they work. It has the disconcerting feature of mucking up your desktop when you install it, but a quick trip to the control panel will fix that, after which you've got a great utility.

There's one problem. I've found a few conflicts between this and Windows 3.1. I suspect, though, that by the time you read this, the problems will be taken care of. In general, the readers are right: this deserves an orchid.

Trantor

I think of Trantor as a new company, but in fact, they've been around since CP/M days. They've since gone over to being specialists in SCSI. Their best-known product is the T338 MiniSCSI Parallel-to-SCSI Host Adapter, which enables you to use SCSI devices—CD-ROM drives, optical drives, and Bernoulli Boxes—with a portable computer. They also make Micro Channel SCSI boards and other stuff, and they're continually improving what they do; it's a company well worth watching.

A Chaos Manor orchid to Trantor, and a User's Choice Award to the T338 MiniSCSI Parallel-to-SCSI Host Adapter.

System of the Year

I like Windows and big 486 systems, but as time goes on, I get more and more attracted to Apple's Mac way of life. I had little use for the original 128-KB Mac, which I thought was an overpriced toy, but that was a long time ago. Since then, Macs have been greatly improved, and I note that many users who don't know or care what's going on inside a computer are able to sit down at a Mac and get a lot of work done.

One defect the Apple system had until this year was the lack of a decent portable. But that has been fixed with the PowerBooks.

Apple's System software was elegantly integrated, but MultiFinder did odd things and unexpectedly brought down the system at very inconvenient times. That, too, was remedied this year.

A large orchid to Apple: System 7.0 is great, and the Mac Quadra 900 is wonderful. I don't count it a defect of the Quadra 900 and System 7.0 that some older software won't run properly: Apple has been telling people for years that you must not write self-modifying code. Apple's programming standards are published and clear, for which Apple deserves yet another orchid. Two cheers for shipping machines like the Quadra 900 and the Mac Classic II with only 2 MB of memory when System 7.0 takes up more than half of that, but that's a minor quibble.

I think that the Quadra 900 and System

Electronics Workbench®

The electronics lab in a computer™

Powerful software to build and simulate analog and digital circuits.

Building and testing circuits is fast and easy with *Electronics Workbench*. Just click-and-drag with a mouse to add parts, run wires, and adjust instruments. The traces on the simulated instruments are the same as you'd get on real equipment.

Electronics Workbench really *is* an electronics lab in a computer. It's ideal for learning about electronics, experimenting, and prototyping circuits.

"*Electronics Workbench* is pretty amazing." – *Jerry Pournelle, Ph.D., InfoWorld*

DOS Professional Version – $299
Macintosh Version – $199

***Electronics Workbench* includes:**

- ***Analog Module*** with passive and active components including transistors, diodes, and op-amps; a function generator, an oscilloscope, a multimeter, and a Bode plotter.
- ***Digital Module*** with gates, flip-flops, adders, a word generator, a logic analyzer, and a unique logic converter and simplifier.

(416) 361-0333

Interactive Image Technologies Ltd.
908 Niagara Falls Boulevard
North Tonawanda, NY
14120-2060
Fax (416) 368-5799

INTERACTIVE

Prices are in US dollars. Offer valid in the USA and Canada only. Macintosh Version is monochrome only. All trademarks are the property of their respective owners.



Circle 160 on Inquiry Card.

World Radio History

Before You Upgrade To MPC, Listen To This.

BYTE

USER'S COLUMN

Sound Blaster
One of the boards we installed in the Arche 486 was Sound Blaster. With its associated software, it has quietly (no pun intended, but what the heck) become the standard sound system for advanced PCs. The Roland board has much higher sound quality for a higher price, but for anything short of professional music quality, Sound Blaster is good enough.

There are lots of other accessories you can get for Sound Blaster, including musical instrument software and a voice editor. Sound Blaster has become the standard sound board, if not for the industry, at least here at Chaos Manor. Recommended.

Jerry Pournelle

COMPUTE

SNEAK PEEKS

SOUND BLASTER PRO

In just two years, the Sound Blaster has become one of the the most widely-supported PC sound cards. It's easy to see why. The Sound Blaster contains an 11-voice FM synthesizer that makes it fully compatible with the popular Ad Lib Music Card. The day it hit store shelves, the Sound Blaster could be used with hundreds of Ad Lib compatible games and educational programs. To add even more value, the original Sound Blaster included a DAC (Digital to Analog Converter) for digitized voice and sound effects, a microphone jack for voice input, a built-in game port, a built-in 4-watt amplifier, and an optional MIDI interface.

The built-in mixer makes the Sound Blaster Pro fully compliant with Microsoft's Multimedia Level 1 Extensions to *Windows*. Multimedia software will be able to fade-in, fade-out, and pan the various audio sources to create elaborate sound montages.

The Sound Blaster Pro includes a CD-ROM interface for either an internal or external CD-ROM player.

There's also an internal connector for CD-Audio. The MIDI interface is compatible with the original Sound Blaster's MIDI interface, but adds the MIDI time-stamp that's part of Microsoft's new multimedia standard.

All in all, the Sound Blaster Pro is chock-full of new features, yet it's fully compatible with its younger brother.

DAVID ENGLISH

Scheduled Release: September 1991
For IBM PC and compatibles—$299.95

CREATIVE LABS
2050 Duane Ave
Santa Clara, CA 95054
(408) 986-1461

PC GAMES

SOUND BLASTER PRO

By Barry Brenesal

The Marines may look for a few good men, but any PC game player will gladly settle for a single good sound card: one that plays both Sound Blaster and AdLib scores, one that doesn't fry your other boards, one that never draws attention to itself, one that delivers all the sophisticated sound effects and music bundled into the latest batch of game software.

Look no further: Sound Blaster Pro does it all, and more. At $299.95 it's not cheap, but neither are its features.

Testing: One, Two . . .

Installing Sound Blaster Pro is a snap. The 16-bit card slips easily into place. It comes with [illegible]

Trying out Sound Blaster Pro is a treat. It's got great frequency response — that's the difference between listening to a film score on a tinny, muffled AM radio and hearing it on a stereo movie-theater speaker system. The orchestral soundtrack to Origin's Wing Commander is a good example, because it changes mood and melody to match the success of your current battle. Add Sound Blaster Pro to a good VGA screen and a responsive joystick (which you can plug into Sound Blaster Pro's joystick port), and the illusion of dogfighting [illegible] in a George Lucas-style film becomes 3-D, symphonic reality.

Another plus is the absence of the annoying background [illegible]

In short, Creative Labs' Sound Blaster Pro is a big winner. It's quick to install, easy to use, full-featured, and compatible with Sound Blaster and AdLib files. Signal response is excellent. And don't f[illegible]

PC HOME JOURNAL

SOUND BLASTER DOES IT ALL

Review by Harvey Bernstein

The Sound Blaster has so many audio applications packed into one half-sized board that it almost boggles the mind. First, it has an 11-voice stereo music synthesizer that is fully compatible with the widely used AdLib sound format. Older software that only supports the AdLib board will automatically turn on the AdLib mode — no adjustment by the user is necessary. A separate channel is exclusively for reproducing digitized speech. A microphone jack on the back of the card allows you to digitize your own input voices. With a 4-watt stereo amplifier built in, you can run speakers or headphones directly from the card — no additional amplification is necessary. A standard joystick port also doubles as a MIDI interface, allowing you to connect a synthesizer or any other MIDI instrument. Combine this with an excellent library of software, and it is easy to see why the Sound Blaster has become so popular.

The Sound Blaster [illegible] is the Sound Blaster worth the investment? Yes, yes, a thousand times yes!!! When you hear how much the Sound Blaster increases the capabilities of your PC, you'll wonder how you ever got along without one. PC

Now you can get the number one sound card as part of our new Multimedia Upgrade Kit. Which also comes with a MIDI kit, an internal CD-ROM drive and 5 CD-ROM titles, including Microsoft® Bookshelf® and Windows™ with Multimedia Extensions. In all, $2,000 worth of goodies for just under $850.

So before you get into multimedia, call 1-800-544-6146 or see your dealer. You'll like what you hear.

CREATIVE LABS
SOUND BLASTER PRO

Creative Labs, Inc., 2050 Duane Ave., Santa Clara, CA 95054 Telephone: (408) 986-1461 Fax: (408) 986-1777 For international information, fax Creative Technology at (65) 773 0353. Sound Blaster is a registered trademark of Creative Labs, Inc. Windows and Bookshelf are registered trademarks of Microsoft Corporation.

Circle 154 on Inquiry Card.

World Radio History

7.0 are a giant step forward for computer users and now set the new standard for productivity—as well as being a lot of fun to use. The Chaos Manor User's Choice Award for Machine of the Year goes to the Quadra 900.

Portable Computers

This was the year I abandoned my back-breaking Zenith 386SX portable. It's not that it isn't a great machine; indeed, once I get to my destination, I sometimes wish I had brought it for the large bright screen and big keyboard. On the other hand, I don't miss lugging 20 pounds of computer, case, power supply, and accessories while racing from gate to gate to catch an airplane.

This year, I tried a number of portable machines and one palmtop. I found that I'm too set in my ways to make much use of a palmtop, but my son Phillip uses a Poqet every day. He's a Navy officer and has found the little machine invaluable and rugged enough for his needs. He does advise that you get rechargeable batteries and a recharging device, since his early version of the Poqet uses up penlight batteries like mad.

I used about a dozen notebook computers this year, and two stood out: the Safari NSX/20 and the TravelMate 3000 WinSX from Texas Instruments (TI).

We've taken them both all over the country. The TravelMate bounced around in the Bronco while we drove down to Baja for the eclipse, and the NSX/20 traveled with us to Tahoe for the Hackers' Conference and then down to Las Vegas for Comdex.

The TravelMate is preferable as a general-purpose DOS and sometimes Windows machine, largely because the ROM character set is more aesthetically pleasing. It's also better for Desqview users because it is able to use QEMM's Stealth technology to get larger windows.

The NSX/20, on the other hand, has wonderful provisions for communications and does Windows extremely well. Also, it is a more handsome—and handy—unit. I especially like the battery arrangement that lets you change batteries on the fly.

In a word, they're both good enough. What's happened is that Roberta, who still prefers Desqview to Windows, has taken over the TravelMate. She now carries it in preference to Toshiba-san, the Toshiba T1000 she's had for many years. Given that the TravelMate weighs about twice what the T1000 does, that's quite a concession. That leaves the NSX/20 for me, which works out well because I'm working hard at getting used to Windows; also, I do much more communications, including faxing, when I'm on the road. What I really like is that TI and Safari Systems aren't the only companies working on improving laptop computing.

I'm pleased to give User's Choice Awards to the TravelMate 3000 WinSX and the Safari NSX/20.

Logitech TrackMan Portable

Safari considered the Microsoft Ballpoint mouse, which was my previous favorite choice for a pointing device for portables, but chose the Logitech TrackMan Portable trackball to bundle with the NSX/20—a wise decision. Whatever portable you get, if you use Windows, get the TrackMan Portable. It's wonderful. In fact, it's so good that I am strongly tempted to attach it to the keyboard of my regular machine and abandon regular mice altogether. This gadget just plain feels right. It's also rugged enough for portable use.

A very large Chaos Manor orchid and a User's Choice Award to Logitech for the Pointing Device of the Year. Try this one. I bet you'll love it. I did.

CD-ROM

There were about a zillion CD-ROMs this year, far more than any one human could keep track of. However, one stands out above the others: the Bureau of Electronic Publishing's Monarch Notes are likely to have a major impact on the country. Monarch Notes, like *Cliffs Notes*, are short booklets that summarize various great works of literature, point out the intellectual lessons, draw conclusions, and ask questions.

They are supposed to be used in conjunction with the works they discuss rather than as a substitute for reading them, but we all know how that goes. I suppose it was inevitable that CD-ROMs would not only make available the world's great literature, but also make it easier to avoid reading it and still get college credit. Putting every one of the Monarch Notes on one CD-ROM certainly hastened the process. Having said that, I sure wish I'd had this disc when I was an undergrad; and on reflection, I think every college literature teacher had better get one in self-defense.

In any event, the User's Choice Award for CD-ROM of the Year goes to Monarch Notes from the Bureau of Electronic Publishing.

Games

This is an unusual situation. I had already chosen Broderbund's Patton Strikes Back, a Battle of the Bulge game by Chris Crawford, the genius dean of war-game designers, as game of the month and a candidate for game of the year. Like all Crawford designs, it's unique. The bias is toward playability and just having fun, and it does that. It also presents live-action video in small pop-up screens. There are sounds, advice from generals, and just all kinds of interesting features.

Then, just before Christmas, came another box: MicroProse's Civilization, the newest game by Railroad Tycoon designer Sid Meier.

"Too late to be considered," I thought, as I opened it. "But it doesn't hurt to have a look."

Six hours later it was dawn, and I was still playing. Look: do yourself a favor and do not buy this one just when you have an important deadline coming up. It's fascinating. Worse, it's addictive. Maybe more than addictive. In theory, it resembles the Avalon Hill board game of the same name; in some ways, it resembles Mark Baldwin's classic Empire; and overall, it's like nothing you've ever tried before.

Like Patton Strikes Back, you can play Civilization with very little attention to the manual; but like Railroad Tycoon, you will not play it well unless you study the manual very closely. This is a complicated game, and everything interacts with everything else. I like Crawford's game a lot, but Civilization stands out as the Chaos Manor Game of the Year and gets the User's Choice Award for that.

Winding Down

The CD-ROM of the month is Library of the Future, Series Second Edition, from World Library, Inc. (12914 Haster St., Garden Grove, CA 92640, (800) 443-0238). Nine hundred titles on one CD-ROM for $695.

There's more here, and I'm out of space. Next month, disk drives, both conventional and optical, CD-ROM drives, modems and communications, and backup systems. I'll be giving out more onions and orchids (including the Orchid and Onion of the Year) and more User's Choice Awards. I'll also have a look at multimedia and make some predictions about the Brave New Worlds the computer revolution is bringing us. ■

Jerry Pournelle holds a doctorate in psychology and is a science fiction writer who also earns a comfortable living writing about computers present and future. Jerry welcomes readers' comments and opinions. Send a self-addressed, stamped envelope to Jerry Pournelle, c/o BYTE, One Phoenix Mill Lane, Peterborough, NH 03458. Please put your address on the letter as well as on the envelope. Due to the high volume of letters, Jerry cannot guarantee a personal reply. You can also contact him on BIX as "jerryp."

World Radio History

GO

START HERE

Imported EISA board has no tech support

START OVER

Discount board has compatibility problems

GO BACK 1 SPACE

50 MHz Now Available

Cheap board fails in UNIX system

Select Dependable AMI EISA motherboards

No AMI EISA BIOS

Discount boards not worth the savings

Imported board proves unreliable

GO BACK 1 SPACE

Use AMI EISA for reliable network file server

MOVE AHEAD 2 SPACES

Slow SCSI interface ruins reputation

GO BACK 3 SPACES

AMI EISA

The Only Game In Town



For EISA, there is only one player to consider—AMI. Whether it's motherboards, BIOS, utilities, or SCSI host adapters, AMI is the single source for advanced EISA technology.

EISA UTILITIES MAKE THE JOB SIMPLE

AMI designed and developed the EISA Configuration Utility to make configuring EISA products a snap. Run the ECU and select the auto configuration option, or modify the I/O ports, interrupts, or DMA settings as you desire.

ADVANCED EISA & MODULAR CPU MOTHERBOARDS

With AMI leading the way in EISA motherboard designs, you will benefit from bulletproof performance and proven reliability.

- EZ-Flex—A new modular CPU design offering easy upgrades to future technology.
- Enterprise II—A proven EISA performer, popular for critical applications.

EISA ADD-ON CARDS

The Fast Disk EISA SCSI Host Adapter, with a combination of 16 MB cache, and intelligent 386SX I/O management, is the fastest SCSI host adapter on the market today. Look to AMI for other EISA cards in the near future.

THE LEADING EISA BIOS

AMI is the worldwide standard for BIOS. AMI's EISA BIOS provides the reliability, compatibility, and features you desire. Plus, it's compatible with AMI's BIOS Configuration Utility, providing on-site customization for the Integrator or OEM.

THE AMI DIFFERENCE

AMI's expertise covers the entire EISA environment. With research, engineering and support functions under one roof, AMI is unmatched in knowledge and support. Call AMI, and you will understand why AMI's "monopoly" on EISA makes it the only game in town.

AMI

SINGLE SOURCE TECHNOLOGY

Circle 40 on Inquiry Card
(RESELLERS: 41).

AMERICAN MEGATRENDS, INC.
800-U-BUY-AMI or 800-828-9264, 404-263-8181, fax 404-263-9381

Discount EISA boards have high failure rate

GO BACK 3 SPACES

Discount board has slow video speed

LOSE TURN

Use highly compatible AMI EISA BIOS

PROFITABLE PARKING

GO TO BANKRUPTCY

World Radio History

ITEMS DISCUSSED

Ascend
with Planner $299
NewQuest Technologies, Inc.
2550 South Decker Lake Blvd.
Salt Lake City, UT 84119
(800) 877-1814
(801) 975-9992
fax: (801) 975-9995
Circle 1150 on Inquiry Card.

Civilization.....$69.95
MicroProse Software, Inc.
180 Lakefront Dr.
Hunt Valley, MD 21030
(410) 771-1151
Circle 1151 on Inquiry Card.

Graphics Ultra
with 1 MB.....$799
ATI Technologies, Inc.
3761 Victoria Park Ave.
Scarborough, Ontario,
Canada M1W 3S2
(416) 756-0718
fax: (416) 756-0720
Circle 1152 on Inquiry Card.

HyperStore 1600.....$650
configuration modules.....$250–$325
Perceptive Solutions, Inc.
2700 Flora St.
Dallas, TX 75201
(800) 486-3278
(214) 954-1774
fax: (214) 953-1774
Circle 1153 on Inquiry Card.

LaserJet III.....$2395
Hewlett-Packard, Inc.
11311 Chinden Blvd.
Boise, ID 83714
(800) 752-0900
(208) 323-2551
fax: (208) 344-4809
Circle 1154 on Inquiry Card.

LaserMaster TrueTech 1000.....$6995
LaserMaster Corp.
6900 Shady Oak Rd.
Eden Prairie, MN 55344
(800) 477-7717
(612) 944-9457
Circle 1155 on Inquiry Card.

Mac Quadra 900.....$8499
Apple Computer, Inc.
20525 Mariani Ave.
Cupertino, CA 95014
(408) 996-1010
Circle 1156 on Inquiry Card.

Microsoft Windows 3.1
(price not available)
Microsoft Corp.
1 Microsoft Way
Redmond, WA 98052
(800) 426-9400
fax: (206) 883-8101
Circle 1157 on Inquiry Card.

Monarch Notes CD-ROM.....$99
Bureau of Electronic Publishing
141 New Rd.
Parsippany, NJ 07054
(800) 828-4766
(201) 808-2700
fax: (201) 808-2676
Circle 1158 on Inquiry Card.

PM2011/90.....$595
PM3011/70.....$835
Distributed Processing Technology
140 Candace Dr.
Maitland, FL 32751
(407) 830-5522
fax: (407) 260-5366
Circle 1159 on Inquiry Card.

Q&A 4.0.....$399
Symantec Corp.
10201 Torre Ave.
Cupertino, CA 95014
(800) 228-4122
(408) 253-9600
fax: (408) 253-4092
Circle 1160 on Inquiry Card.

QEMM-386 6.02.....$99.95
Quarterdeck Office Systems
150 Pico Blvd.
Santa Monica, CA 90405
(800) 354-3222
(213) 392-9851
fax: (213) 399-3802
Circle 1161 on Inquiry Card.

Safari NSX/20
with 80 MB.....$5749
Safari Systems
14K World's Fair Dr.
Somerset, NJ 08875
(908) 302-5800
fax: (908) 469-4578
Circle 1162 on Inquiry Card.

Sota Lightning VGA
with 1 MB.....$445
Sota Technology, Inc.
559 Weddell Dr.
Sunnyvale, CA 94089
(800) 933-7682
(408) 745-1111
fax: (408) 745-1640
Circle 1163 on Inquiry Card.

Thinx.....$495
Bell Atlantic Thinx Software
9 South High St.
Morgantown, WV 26505
(800) 688-4469
Circle 1164 on Inquiry Card.

TrackMan Portable.....$169
Logitech, Inc.
6505 Kaiser Dr.
Fremont, CA 94555
(800) 231-7717
(510) 795-8500
fax: (510) 792-8901
Circle 1165 on Inquiry Card.

TravelMate 3000 WinSX
with 120 MB.....$3999
Texas Instruments, Inc.
P.O. Box 202230
Austin, TX 78720
(800) 527-3500
Circle 1166 on Inquiry Card.

T338 MiniSCSI Parallel-to-SCSI Host Adapter.....$179
Trantor Systems, Ltd.
5415 Randall Place
Fremont, CA 94538
(510) 770-1400
fax: (510) 770-9910
Circle 1167 on Inquiry Card.

Windows 3 Secrets.....$39.95
IDG Books
155 Bovet Rd., Suite 730
San Mateo, CA 94402
(415) 358-1250
Circle 1168 on Inquiry Card.

Word for Word.....$149
Mastersoft, Inc.
6991 East Camelback Rd., Suite A320
Scottsdale, AZ 85251
(800) 624-6107
(602) 277-0900
fax: (602) 970-0706
Circle 1169 on Inquiry Card.

ORCHID PARADE

Am386-40.....OEM
Advanced Micro Devices
901 Thompson Place
P.O. Box 3453
Sunnyvale, CA 94088
(800) 538-8450
(408) 732-2400
fax: (408) 982-6161
Circle 1170 on Inquiry Card.

Clip'nSave.....$79.95
Dynalink Technologies, Inc.
P.O. Box 593
Beaconsfield, Quebec,
Canada H9W 5V3
(514) 489-3007
Circle 1171 on Inquiry Card.

The Far Side Computer Calendar.....$69.95
Amaze, Inc.
11810 115th Ave. NE
Kirkland, WA 98034
(800) 367-4802
(206) 820-7007
fax: (206) 823-0568
Circle 1172 on Inquiry Card.

System 7.0.....$99
Apple Computer, Inc.
20525 Mariani Ave.
Cupertino, CA 95014
(408) 996-1010
Circle 1173 on Inquiry Card.

World Radio History



850 CPS & TOUGH AS NAILS!

850 CPS. That's right – 850 characters-per-second!

TOUGH AS NAILS. Why take a chance? Thousands of owners use the 850XL printer from 2 to 18 hours per day. It just keeps on printing, day-in, day-out! And, over 50% of all 850XL printers sold are purchased by existing owners. That alone tells the story for this American-made printer.

FREE 30-DAY TRIAL. We offer a free, 30-day trial to any qualified buyer. No strings attached. What other manufacturer believes this strongly in their product?

Call Us Today! **(800) 468-8788**

GSA Pricing: 800-633-9433
GSA Contract #GS00K-91-AGS-5268

NOW UNDER $2,000!

OTC OUTPUT TECHNOLOGY CORPORATION

Should you need service, there are over 400 service locations nationwide to serve you.

2514 N Fancher Road Spokane WA 99212 1381

Circle 98 on Inquiry Card.



WE DIDN'T HAVE TO PUT OUR OPTICAL PRODUCTS ON PEDESTALS. JERRY POURNELLE DID.

"**I am pleased to report that I'm sold. The Pioneeer optical drive... is as solid as a rock**.... Thus, I'm discontinuing testing. Now I'll just use the drive. ...I now rely on the Pioneer erasable optical disks for backup, for primary storage of really big files, and for archive copies of software...you really need something **so easy** to use that you'll routinely use it for backup... **the Pioneer DE-S7001 will do the job very well indeed. Recommended.** *Byte (9/91)*

The Pioneer six-pack CD-ROM Minichanger is great. We've had it in operation for the best part of the year now, on a number of different systems.... **It has always performed flawlessly**...it changes drives a lot faster than you'd expect it to.... **It's really fast**.... Accesses that used to take many seconds are now nearly instantaneous. Accesses that took over a minute now take a few seconds. **I always did like the Minichanger.... Now it's even better**.... Incidentally, the Pioneer Minichanger will work just fine with a Mac. *Byte (10/91)*

The Pioneer DE-S7001 dual-purpose external optical disk drive I've written about before. Log your wordprocessor to that, save early and often, and you'll have it all.... In a word, WORM drives look like **the ultimate in backup storage.** *Byte (12/91)*

Suppose you erase a file? Overwrite one you wanted to keep? And suppose your house burned down? You don't have any off-site backup at all.... **I could remedy that by installing the DE-S7001 on the network server and archiving on that**.... *Byte (11/91)*

I have the DRM-600 running not only with QEMM386.SYS, but inside DESQview windows, which has the amusing result that I can actually have several CD-ROM windows open at once.... **It's surprising** how fast you can switch back and forth among them.... The Pioneer DRM-600... **it's very convenient** to have a bunch of CD-ROMs available without swapping. *Byte (1/91)*

It's quite intuitive [the Pioneer CD-ROM Minichanger]: no instructions are required.... **Recommended**. *Byte (1/91)*

This technology is coming of age. *Byte (1/91)*"

JERRY POURNELLE
RENOWNED COMPUTER COLUMNIST

For more information or for a free VHS videotape "Pioneering The Future," about Pioneer optical disk products, call 1-800-LASER-ON, and find out why Pioneer is the leader in optical disk technology.

PIONEER

Pioneer DE-S7001, Pioneer DRM-600, and Pioneer DD-S5101 are trademarks of Pioneer Communications of America, Inc. QEMM386.SYS and DESQview are trademarks of Quarterdeck Office Systems.

Circle 106 on Inquiry Card.

World Radio History



BYTE editors debate the issues with contributors, readers, and industry experts

THE FUTURE OF PEN COMPUTING, PART 2

Roundtable is a forum in which BYTE editors, contributors, readers, and industry experts debate key issues that affect how you purchase and use hardware and software. The "conversations" take place on BIX, where you can participate in the round.table conference.

Last month, we talked about the markets for pen computers and the competing pen operating systems. Let's turn now to hardware issues. In many cases, pen computers have to be able to run for an entire workday without being recharged. What impact does that have on system design?

NEIL KATZ: Vertical users require that their batteries provide at least a full day's work. With current 386 designs and [the need to] minimize weight, this is virtually impossible. However, most vertical users do not run their machines continuously for 8 hours. They need a system with sophisticated power management. The system should sleep and draw minimal power when not in use.

Also, vertical users are more sensitive to battery life than laptop users are. When you're mobile, outside, and away from AC power, battery life becomes even more critical.

DAVID MENTLEY: It's amusing to see new microprocessor designs that save a few hundred milliwatts while the backlight for the display takes 3 to 4 watts. LCDs themselves burn up about half a watt. Nickel-cadmium batteries store about 40 watt-hours per kilogram or 18 Wh per pound. So a 1-pound battery at a 4-W consumption rate provides only 4½ hours of operation—when everything is working right. This analysis is just for a monochrome display. You can double the consumption, at least, for color.

These are not just temporary obstacles. Increasing the efficiency of backlights (both tube and film types) and batteries is more than a simple engineering task. Thousands of people have been working on it for decades. The question is whether or not you need a backlight. The clipboards clearly do not need it. Everything else does.

In bright, ambient lighting, [nonbacklit monochrome LCDs] reflect more light and look better. Backlit units look nice in a dark room and get progressively worse as the ambient lighting increases. A compromise is needed for covering both indoor and outdoor applications.

In the near term, a lot of these systems are going to be plugged into a vehicle's cigarette lighter socket if they are to be used all day.

Handwriting recognition is very slow on today's pen computers. Can we expect dramatic improvements in the near future?

JEFF DAO: The perception that handwriting recognition is too slow happens when people wait for the recognition response after writing each character. Those who write continually and naturally usually have the impression that current technology is fast enough.

DAN BRICKLIN: Current handwriting recognition is fine for many uses. For naming files, index topics, or objects, it often beats going from a mouse to a keyboard. When choosing from a constrained list (numbers only or city names, for example), many pen systems are quite good.

NICHOLAS BARAN: The single-tasking pen operating systems will not be able to offer the necessary performance for responsive handwriting recognition. But for basic forms entry, Communication Intelligence Corp.'s (CIC's) PenDOS, a pen-aware driver on top of MS-DOS, may be all that's necessary, let alone Windows for Pens or PenPoint.

STEVE LIFFICK: Unfortunately, handwriting recognition will never meet the expectations of the public at large. I tell folks who are disappointed that they should go back and try to read something they wrote a few weeks ago. How many letters can they make out? Is it reasonable

NICHOLAS BARAN
Co-editor,
Pen-Based Computing: The Journal of Stylus Systems

DAN BRICKLIN
Vice President,
Boston Development Center
Slate Corp.

JEFF DAO
Director of Applications
Engineering, Communication
Intelligence Corp.

NEIL KATZ
Tablet Systems Planning
Manager
IBM Corp.

STEVE LIFFICK
Program Manager,
Windows for Pens
Microsoft Corp.

DAVID MENTLEY
Director of
Display Industry Research
Stanford Resources

World Radio History

Circle 51 on Inquiry Card
(RESELLERS: 52).

CD-ROM

BUREAU OF ELECTRONIC PUBLISHING

MPC Multimedia PC

NEW

Great Literature Personal Library Series
The Full Text Of Over 900 Works!!!
Multimedia disc includes celebrity narrations of famous quotes, selected period music excerpts, pictures & engravings. PC & Mac
Breakthrough Price ------- Only $99

Multimedia CIA World Tour
MPC Title! With info straight from the CIA -- Plus Maps from Hammond, Inc. and flags & National Anthem segments New Version! $99

Monarch Notes on CD-ROM
Over 200 Study Guides on One CD-ROM Disc - The Entire Collection *(many out of print)*
The definitive multimedia source for understanding the world's greatest literature. PC & Mac Only $99

Countries of The World Encyclopedia
Full text of over 100 Study Books, Maps, National Anthems, Flags, Photos & More!
Includes the latest info from over 100 embassies. The perfect research tool for students and anyone who wants to know more about our world. PC & Mac $395

U.S. History on CD-ROM
WINNER 1991 OPA BEST EDUCATIONAL PRODUCT
Full Text & Images of 107 books providing you with social, economic, political, scientific and military perspectives of U.S. History. PC/Mac $395

Pioneer CD-ROM 6 Pak
6 PC/MAC DISCS BUNDLED FOR ONLY $395!
• U.S. History • Countries/World • Shakespeare • Holmes • Birds • Software Potpourri
Six Pack & Minichanger (Save over $1000) $1489

SONY Laser Library Enhanced BUNDLES! With Monarch Notes! CALL

High Performance SONY CD-ROM Drive Kits
Fast, MPC compatible drive kits in-stock
Also: Pioneer Minichanger, CDT, NEC, Hitachi, WORM & Erasable drives, in-stock - Call

Multimedia CD-ROM Titles

Microsoft Bookshelf	best selling CD-ROM disc	Best Price
Beethoven's Multimedia MPC	classic disc	$79
Grolier's Encyclopedia	21 volumes, VGA pictures	Call
Mammals - Nat. Geographic/IBM	pictures & text	Call
Presidents - Nat. Geographic/IBM	pictures & text	Call
Between Heaven & Hell II	even stranger	99
Street Atlas	Windows map with every US street	Call
Family Doctor	home medical guide	98
McGraw-Hill Ref. Set	100,000 terms, 7,300 articles	495
Speed Dial	entire U.S. Yellow Pages on one disc	Sale
Oxford Textbook of Medicine	general reference	595
PC-Sig Library	new edition, newest version	Call
Compton's Family Encyclopedia		Call
Oxford English Dictionary	over 250,000 headwords!	889
Phonedisc USA	Telephone Directory - East or West	989

Bureau On-Line CD-ROM Library. FREE access to 12 different CD-ROM Discs. CALL ! ! !
GSA# GS00K91AGS5280
HOURS M-F 8:30am - 6:30pm EST

VISA DISCOVER FEDERAL EXPRESS

Bureau of Electronic Publishing, Inc.
Same Day Shipping
Dept. B, 141 New Road, Parsippany, NJ 07054
FAX # 201-808-2676
CALL: 800-828-4766 ORDERS
201-808-2700 INFORMATION

ROUNDTABLE

[to expect] a machine to read their writing better than they do?

There seems to be a consensus that handwriting recognition is slow. That hasn't been our experience with Windows for Pens. It recognizes *behind* the writer as text is being entered, so the delay upon finishing should never be very long—in essence, just enough to make segmentation (letter break) determinations and shape matching for the last two characters. This results in nearly immediate response.

We developed our recognition algorithms from the beginning to support cursive recognition. The problem boils down to insufficient CPU horsepower. The segmentation problem becomes worse by an order of magnitude because of ligatures. Combine this with the fact that people tend to write cursive more sloppily than block text, and one ends up with a requirement for lots of prototypes and lots of computation to perform recognition.

The situation with block versus cursive text recognition is analogous to interrupted versus continuous speech recognition. Continuous speech recognition is possible. It just takes a lot of CPU power.

DAO: Current handwriting-recognition technology uses a variety of methods: AI, neural networks, and fuzzy logic. Whatever one chooses to call it, handwriting-recognition software attempts to emulate what humans do very well at a very young age. We are exceptional recognizers, or image processors. We do a lot of pre- and postprocessing that these glorified calculators have not even begun to tackle. Yet the technology is useful in its current form with mixed upper- and lowercase printing. CIC's recognition system keeps up with a writer writing 30-plus words per minute. This is more than adequate.

As for cursive recognition, we're talking about a lot more million instructions per second [MIPS]. CIC already has a CR system running in the lab; however, today's 386 CPUs are not adequate for CR. Expect hardware capable of running a commercial CR product from CIC in a year's time.

What improvements will pen-computer designers make to achieve adequate performance, weight, display quality, and battery life at a reasonable price?

MENTLEY: I wouldn't look for full-color video-capable flat-panel displays on pen computers in the near future. Color-active matrix LCDs must have a backlight that requires 8 to 15 W of power. Other light-emitting flat panels are not yet available in full color, but when they are, they will be in the same power-consumption range as backlit LCDs. Another problem is the thickness. Placing the backlight behind the display makes the module nearly an inch thick. Light pipes and edge-mounted lights help, as Sharp has demonstrated with an edgelit active-matrix LCD for notebook computers. Digitizers also absorb light, increasing the backlight requirement.

Faster supertwist monochrome displays are clearly the trend. Supertwist technology is inherently slow, but producers (all in Japan) are desperately trying to get the speed up to video rates. The response time is temperature sensitive, however, and this is where pen computers may get into trouble. LCD response times get down to 1 second or so at winter temperatures. This leads to serious cursor "submarining."

On the other end, many of these pen computers are going to be sitting on car seats in direct sun in the summer. LCDs don't like high temperatures. The vertical-market environments are going to be much tougher on these systems than the broad-based horizontal applications in which we find laptops.

BARAN: There are several possibilities for storing data—PC cards with capacities of up to 16 MB are already available, and 40-MB cards are expected in the next couple of years.

Certainly, wireless networks will play a role, and PenPoint supports the AppleTalk network protocol. But again, PC cards will be the primary storage medium.

The PCMCIA memory-card specification is becoming the standard storage medium on pen-based systems (Momenta notwithstanding). And undoubtedly, there will be database applications designed to operate with these memory cards. However, this is all under development—not available right now.

Might stylus-based systems be integrated with voice-based systems in the future?

LIFFICK: The integration of voice and pen control is inevitable. The strengths of the pen complement perfectly the weaknesses of voice input. Voice is inherently undirected. The pen is inherently very directed. Combine [voice recognition] with scenarios where the pen is appropriate, and the future of the pen is ensured.

The major factor delaying voice input in the marketplace is CPU speed. The 386 cuts it for nonconstrained (i.e., no required grammar) interrupted small-vocabulary input. High-end 486s bump up the vocabulary considerably for interrupted input and enable continuous input for a very small vocabulary. But if one considers

World Radio History

ATLAS SOFTWARE

A NEW DIMENSION IN DATA MANAGEMENT



Most business and government professionals view and analyze data only on spreadsheets, databases and occasionally in business graphics packages. While these types of software are useful for displaying statistical data, they fall short of communicating information about geography—such as income by sales territory, population by county, or customers by ZIP codes or street addresses.



Atlas Software® is changing that. By linking data from spreadsheets, databases and even other applications—on your PC or Macintosh®—you can now add the important geographical dimension to your information system.

And when we say important, we mean mission critical. For example, *Atlas Software* can help business professionals answer "what if" and "show me where" questions for optimizing sales territories, targeting customers, and selecting ideal site locations. Government professionals can use *Atlas Software* for everything from political redistricting to land-use planning and public safety analysis. Without *Atlas Software* these tasks would be difficult or impossible.

Atlas Software programs come equipped with built-in data management capabilities, map file importing and a generous base map and data sampler from our comprehensive library, containing over 75 gigabytes of geographic files, business statistics and demographic data.

Atlas Software comes in a variety of "flavors" to suit your specific needs and supports MS DOS®, MS Windows® and Macintosh operating systems.

So if you're ready to add a dynamic new dimension to the way you use information, like 25,000 other Strategic Mapping customers, call us for a free *Desktop Mapping Guidebook* and demo disk. We'd be happy to map out a plan for you.

Phone: (408) 985-7400
FAX: (408) 985-0859

STRATEGIC MAPPING INC

In Canada, call 416 693 4166
In the UK, call 44-81-994-2780
In Belgium/LUX, call 32 2-771-25-75
In the Netherlands, call 31 340 256 336
In Germany, call 49 228-62-73-82
In Australia, call 61 3 866-1766
In France, call 33-1-45-27-20-61
In New Zealand, call 644 4791-731

The Strategic Mapping, Inc. logo and Atlas Software are registered trademarks of Strategic Mapping, Inc. All other trademarks are of their respective companies.

Circle 127 on Reader Service Card.
World Radio History

handwriting recognition a hungry user of processing power, voice recognition is ravenous.

How would you sum up the current state of pen computing?

BRICKLIN: We have to realize that pen computers are a different beast. You don't want a traditional GUI on many of these machines (other than the Windows machine that happens to have a pen instead of a mouse), but rather a *PUI* (for pen user interface). Go Corp. has developed one such interface, which it calls *NUI* (for notebook user interface), but there will be others.

As the handwriting-recognition people point out, we need more MIPS. We need them for better recognition. We also need them to make the screen respond fast enough to feel "as good as paper, and better" (Slate's motto). When you turn a page, it should turn instantly. "Ink" should look as sharp as it does on paper but take up as little storage space as possible.

LIFFICK: Pen computing has become the favorite child of PC industry hypesters—with good reason. The prospects for pen input are particularly compelling: portability, natural pen and paper input, and bringing the benefits of powerful and easy-to-use computing to large, untapped markets.

The economic reality of pen computing is that inexpensive machines appropriate for the masses are two years out. There will always be "heat seekers" adopting the technology before it is economically reasonable to do so. But the large market for pen computing in the next two years will be with those entities that can justify its price in terms of real and immediate cost benefits. Those entities are corporations seeking increased productivity and prospective notebook buyers looking to extend the reach and scope of their current computing power.

KATZ: We're on the verge of a new era in computing, possibly as great or greater an opportunity than the original IBM PC. The opportunity is to bring the power of the computer to workers who cannot or will not use a keyboard in their day-to-day jobs.

[It will take] hardware that is competitively priced, rugged, easy to use, and lightweight. More important, [it will take] an operating system and set of applications that are intuitive and friendly and present a noncomputerlike interface. All aspects of input will need to be brought to bear to make this market happen, including handwriting, voice, and wireless communications. The synergy of these will make this new market take off. ■

Circle 86 on Inquiry Card.

Just Add Code.

NEW! Version 5.0 Includes Phar-Lap 386|DOS-Extender



32-bit protected-mode Fortran

Your Fortran code is important. Trust it to the company that has been writing award-winning Fortran language systems for 25 years.

(800) 548-4778

Lahey
Computer Systems, Inc.

Fortran is our forte

(702) 831-2500 ■ Fax: (702) 831-8123 ■ P.O. Box 6091 ■ Incline Village NV 89450

Circle 121 on Inquiry Card.

World Radio History

Why do they call it a dongle?

He wasn't famous. He didn't drive a fancy car, but dressed in his favorite Comdex T-shirt and faded blue jeans, he set out to change the course of the computer software industry. Quite a task for a lonely software developer.

Sitting in front of his computer, drinking pots of coffee and smoking cartons of cigarettes, he'd write pages of code.



It took time. Years in fact. But he did it. He wrote the most powerful computer program in the world. Now came the hard part. Selling it.

The Most Powerful Program in the World

Determined to make those long years pay off, he called on every distributor, VAR and dealer in the world. He drove from Beantown to San Diego. Flew from Dublin to Borneo. Everyone loved the program.

So he sold a few. Only a few.

Back in Boston he waited. After a long year with only 13 orders he set out to see what happened. As he drove across the country and flew around the world he discovered everyone knew about his program. Everyone had it too.

The Global Marketplace

From Paris to Prague, his program was everywhere in Europe. When he got off the plane in Hong Kong he found his program stacked to the ceiling in every computer store. Amazed in disbelief, he bought a hundred cartons of cigarettes and a hundred pounds of Indonesian coffee and flew back to Boston.



Beaten, battered and bruised he went back to the drawing board. This time he would really change the face of the software industry. He would develop a device that would prevent unauthorized distribution of software programs.

Call It What You Like

He developed a hardware key. His peers applauded his efforts. Finally, a solid solution for revenue protection.

But he didn't know what to call it. He thought of naming it after an exotic place he visited in his travels. Madagascar was a bit too long, though.

"Name it after you, Don!", urged his peers. So he did. Soon everyone was calling the key a dongle, after Don Gall— the lonely software developer who did what he had to do.

You've Come A Long Way, Baby

Today, dongles are different. Fact is, they've come a long way. Leading the industry with security solutions, Rainbow Technologies has changed the face of hardware keys. They work with multiple applications, are programmable and network versions control concurrent usage. And they're always transparent to the end-user.

Sentinel Family from Rainbow

Truth is, more and more developers are using keys. And the Sentinel Family is the most widely used in the world. In fact, over 6,000 developers use Sentinel from Rainbow. Why? They are simply the most effective, reliable and easy to implement keys on the market.

Learn more about securing your software and how keys provide developers with extra value. Call for a free copy of **"The Sentinel Guide to Securing Software."** And see just how easy it is to install a hardware key into your application in just minutes. Try it with our low cost Sentinel Evaluation Kit. Order one for your DOS, OS/2, Windows, Macintosh or UNIX based application.

And remember, when you need a dongle, you need Sentinel — the only dongle Don Gall would use.

CALL
800/ 852-8569
FOR YOUR FREE GUIDE TO SECURING SOFTWARE

SENTINEL
Securing the future of software

Some call it a dongle. Those who know, call it Sentinel.

RAINBOW TECHNOLOGIES

9292 JERONIMO ROAD, IRVINE, CALIFORNIA 92718 ▪ 714/ 454-2100 ▪ fax 714/ 454-8557
International offices are located in the United Kingdom, Germany and France.

Circle 116 on Inquiry Card (RESELLERS: 117).

World Radio History

BEST DOS.

REPORT CARD NOVEMBER 4, 1991		INFO WORLD
	DR DOS Version 6.0	**MS-DOS Version 5.0**
Performance		
Memory handling	Excellent	Very Good
User interface	Very Good	Very Good
Speed	Good	Very Good
Compatibility	Very Good	Very Good
Documentation	Excellent	Very Good
Setup	Good	Very Good
Ease of learning	Very Good	Very Good
Ease of use	Very Good	Good
Error handling	Satisfactory	Satisfactory
Support		
Support policies	Good	Satisfactory
Technical support	Satisfactory	Satisfactory
Value	Excellent	Excellent
Final Scores	**7.6**	**7.1**

When the competition is good, you have to be better. And the critics agree: DR DOS® 6.0 delivers more of what today's PC users are looking for in a state-of-the-art DOS operating system. That means better performance:

"...tops [MS-DOS 5] with better disk performance, faster task switching, access to more RAM, and improved security, while providing full Windows™ support." *PC World, January 1992*

Flawless operation of all your PC applications, with advanced capabilities that help you be your productive best:

D R D O

Digital Research and DR COS are registered trademarks, and MemoryMAX, DiskMAX, TaskMAX, ViewMAX and FileLINK are trademarks of Digital Research Inc. Novell and the Novell logo are registered

World Radio History

BEST VALUE.



"...complete MS-DOS 5 compatibility with more features and functions." PC Magazine, November 12, 1991

And a complete package of indispensable utilities that normally would cost nearly $400 extra:

"...an excellent value."
InfoWorld, November 4, 1991

Find out today why DR DOS 6.0 is the best DOS. And the best value, too. Get the facts by fax: 1-800-955-DOS6. Request document 702. Or call us today for details and the name of the DR DOS reseller nearest you: 1-800-274-4DRI.

S 6.0

trademarks of Novell, Inc. Other product names are trademarks or registered trademarks of their respective owners. Copyright © 1992, Digital Research Inc.

NOVELL
Digital Research Systems Group

Circle 66 on Inquiry Card.

World Radio History

COVER STORY

FEATURE

Practical Desktop Video

PART 1 - The BYTE Multimedia Lab introduces desktop video production in this first article in a series on desktop video

TOM YAGER



Few things in today's world are growing faster than our dependence on video-based information. The video medium incorporates the elements of color, movement, and sound in a way that we're powerfully drawn to. As a result, video can persuade and motivate more effectively than any other medium. It's no wonder that advertisers spend billions of dollars each year producing ads and placing them on TV: If you've got a point to make, you presently have no more efficient path into other people's minds than through video.

Today the power of video communication can be applied in a way you might not have considered: as a vehicle for *your* message. Desktop video production means that you, with the help of a computer, can express your ideas through sights and sounds that can make a powerful impression on your audience.

This article, produced by the BYTE Multimedia Lab, is the first in a series on desktop video. The focus of the series will be on practical uses for existing video technology. At the end, you'll know enough about desktop video production to get started creating your own professional-looking videos.

What Good Is It?

Even if you're willing to take for granted that you *can* produce your own videos, you might wonder why you'd ever want to. Consider this example: You run a construction company, and you're bidding on a contract for a huge office building. The client firm is looking for skill, experience, and an uncompromising dedication to quality. How do you convince the client's representatives, in the short time you have their attention, that your firm has these qualities and deserves to be placed above the competition? Today you'd probably pitch to them using time-honored methods: overhead transparencies, flip charts and magic markers, and perhaps even 35mm slides. The overheads might summarize your company's financial history, the flip charts might show rough plans for the project under consideration, and the slides might depict similar buildings already constructed by your firm.

The problem with these presentation methods is that they do nothing more than put dry facts in front of your audience: Everything else is up to you. When you place your presentation on video, however, all you do is insert the cassette and press Play—the presentation speaks for itself. No facts are forgotten, no slides get inserted upside down, and no smudges or fingerprints obscure your message.

Beyond such mundane considerations, video lets you present facts and figures as

PHOTOGRAPHY: MARK ROCKWOOD © 1992

World Radio History

World Radio History

computer graphics—using animation if you like. The graphics can be interspersed with live video, voice-overs, and music that advance the audience's respect for your company and ensure that the facts are interpreted the way you want them to be. The building plans can become a virtual prototype—a shaded, three-dimensional model that you can view from several angles, rotate, and even place in simulated surroundings. Video lets you transport your audience to other places. You can take them to a building site where your engineers can be seen working closely with construction crews, include them in a planning meeting where your staff is discussing a project similar to the one in question, and let them see the people behind the numbers and the plans. Finally, you can show them your completed projects.

Video can provide the edge that gets you, your ideas, and your company noticed.

The value that video adds can be seen in several ways. Of the traditional methods mentioned earlier, none offers the combination of sound, color, and motion. Video combines them all, and these things attract and hold an audience's attention. Also, a well-done video presentation always makes a more professional impression than a stack of transparencies or slides. Finally, video is unique in its ability to condense information. A 5-minute video can hold the equivalent information of innumerable transparencies because you have the freedom to combine graphics, video, voice, music, animation, and other elements to tell your story.

You'll see as this series progresses that video works well in settings outside the boardroom, too. In these days of intense competition, it can provide the edge that gets you, your ideas, and your company noticed.

Its Noble Heritage

Computers have a long history of involvement with video, dating back to the days when videotape recorders (VTRs) were first cabled to specialized computers called *edit controllers*, so raw video could be edited into a finished product. Like most of desktop video's roots, these early editing systems were expensive and were seen mostly at TV stations and organizations with deep pockets and a knowledgeable staff. Specialized computers were also used to switch smoothly from one video signal to another, as when a newscast goes from the anchor to a tape, back to the anchor, and then to the weather reporter.

More expensive versions of these systems (called *switchers*) could do more than just cut or fade between two video sources: They could apply special effects. The least of them did *wipes* (i.e., the new video replaces the old in a sweep across the screen), but the best of them could do advanced effects like mapping video sources to the sides of a cube and spinning it through space. Computers were also used to generate text (*character generators*) and graphics (*paint systems*). There are many other examples of computer technology in video, and the amount of digital hardware used in today's broadcast and professional facilities far outstrips what existed in the early days.

Even today, however, many of these capabilities—editing, switching, special effects, character generation, and graphics—are handled by several specialized systems capable of doing nothing else. The old-fashioned edit controllers still exist, as do stand-alone character generators and specialized graphics systems. To be fair, each has advantages (though sometimes small) over its desktop video equivalent.

The Quality Question

Among the advantages of expensive, component-based gear is quality: Everyone who spends large sums of money on specialized equipment expects *broadcast quality*. That's a phrase you'll hear often in association with video, and it has different meanings depending on who's saying it. For our purposes, I'll simply place broadcast quality as a far right tick on a quality scale. It's the best you can get, and to get it, you need to invest in the kind of gear you'd find at CNN or CBS. On the far left side of the scale, place a tick at consumer-quality, or hobby-level, video. This is where standard VHS VCRs and most camcorders fall. You can also find inexpensive titlers, editors, enhancers, and other modules at this level, but what works well for video snapshots falls apart on a 20-inch monitor in the boardroom. And what starts out bad only gets worse during editing and duplication processes.

Our domain will be somewhere between these two boundaries. Between consumer quality and broadcast quality lies a somewhat newly defined market area known by several names. Some call it *prosumer*, while others call it *industrial*, or *commercial*, quality. Whatever you call it, it's easy to spot. The video side is dominated by equipment that often looks and acts like broadcast gear but is at least slightly less capable. The VTRs and players themselves are tuned to producing stable, high-quality images with enhanced resolution (compared to VHS).

But perhaps most important, most video gear in this category can be computer controlled. That's where the real computer assist comes in. The computer takes control of the VCR, telling it when to play, record, pause, and so on. If you add a card to your system that handles an incoming video signal, you can display what's playing on the tape on your computer's monitor. If that card also has a video output, you immediately gain the ability to take an incoming video signal, add computer graphics to it (e.g., a title), and send it back out again to be recorded. Once you've done these few things (and added the not-so-incidental software, of course), you've built yourself a very inexpensive editing, titling, and graphics system.

The Multimedia Lab

This feature series on desktop video is the first major undertaking of the BYTE Multimedia Lab, and there's a reason desktop video is the first subject. Among the many concepts and technologies that come under the multimedia umbrella, desktop video has developed to the point where widespread adoption and

BYTE ACTION SUMMARY

Video presentations are unparalleled in their ability to make a point. With technology available on the desktop today, you can harness the power of video for your own presentations.

World Radio History



All three systems in the BYTE Multimedia Lab are equipped to handle video I/O. The end of the line is always the video input of the AG-7750 S-VHS VCR. If only the real interconnections were as neat and manageable as in this diagram.

use is possible. While standards for other types of multimedia applications are just beginning to emerge, it's already possible to build effective desktop video setups around the platform (more or less) of your choice.

Like BYTE, the Multimedia Lab takes a multiplatform view of the world. I decided to employ three systems I believe represent the bulk of BYTE's readers. The PC system is an ALR PowerVEISA 486/33 with 13 MB of memory and a 600-MB hard drive. The Mac IIci has 8 MB of memory and an 80-MB hard drive. The Amiga 2500/30 has 7 MB of memory and a 370-MB hard drive (330 MB of which is on a Micropolis SCSI drive I installed). You'll notice that these are all pretty beefy configurations—everything you've heard about multimedia being demanding of memory and disk space is true.

The video-related hardware came next. Since I'm not evaluating products per se, I chose not to duplicate equipment where it could be avoided. In this endeavor, three veterans of the video industry—Panasonic, Diaquest, and Truevision—made building the lab much easier. Panasonic provided most of the video equipment: a pair of computer-controllable Super VHS video decks (one AG-7750 recorder and one AG-7650 player), three (model BTM1310Y) professional monitors, and a Super VHS camcorder. Diaquest outfitted all three computer systems with the video-synchronized, intelligent serial interfaces needed to control the decks. They not only tell the decks what to do, but also collect input from the decks regarding tape position, status, and so on. The Diaquest DQ-422 board in the PC also acts as the main source of video synchronization for the entire lab. (Its importance will be made clear in the next article.) The Mac and the Amiga have DQ-Animaq and DQ-Taco boards, respectively.

Truevision provided the professional video cards for the PC and the Mac. The PC's ATVista card uses an external signal converter (called the VidI/O Box) to translate composite (or recordable) video signals to RGB for processing and then convert the board's RGB output to video for recording. The ATVista doesn't replace the PC's main display card, so it must be specifically supported by applications. Fortunately, the ATVista is popular enough that support is widespread. On the Mac, the NuVista+ handles video I/O directly (without the external converter). Both cards offer 24-bit (or true color) graphics, video overlay (i.e., computer graphics added to an incoming video signal), and limited special effects. The Amiga's video I/O and

World Radio History



The most basic desktop-produced video starts with live material (top left), blends in computer graphics (which either share the frame with the live video or use the entire screen) (top right), and then brings together all the various pieces through editing (bottom right).

nearly everything else is handled by a NewTek Video Toaster. The Toaster has most of the same capabilities the Truevision boards have, but the Toaster has custom chips on-board that perform dazzling digital special effects and other functions.

The figure shows the lab's video setup more clearly. There's more to the picture than this, and I will go into more detail in future articles. I plan to introduce you to the various products in the lab as they come into use.

Making the First Connection

Video I/O boards (actually a misnomer, because these boards do much more than just process video) like the Truevision NuVista+ and ATVista let you mix computer graphics and incoming video in just about any way you can imagine. These boards, however, do not drive the main display of your computer system—that is, the display on which program interfaces appear. That's because a recordable video signal, thanks to its use of interlacing and its reduced resolution, makes a poor carrier for complex user interfaces.

The Mac in the Multimedia Lab uses an 8•24 GC card to drive its interface display, while the PC uses a standard VGA adapter. The Amiga uses three displays (the third is for the "preview" signal, described later). But when the Video Toaster is in use, all the displays flicker because the Amiga can synchronize its on-board video controller to an external signal (a process called *genlocking*), and the Video Toaster asks it to do that. As a result, the Amiga's interface display flickers when the Toaster is being used, but the Toaster software adapts its interface appropriately.

Using two (or three) monitors on your system may seem redundant and wasteful, but it has a distinct advantage: The separate interface display lets applications interact with you using

World Radio History

Discover the Avis Corporate Account Program. Because small businesses deserve large perks.

Small, growing businesses like yours deserve the kind of benefits that used to be reserved only for big business. That's why we've created the Avis Corporate Account Program.

Sign up and the savings begin. It doesn't cost anything to enroll in the program, not even a registration fee. As soon as you enroll, we'll assign an Account Representative and a unique Avis Worldwide Discount (AWD) number to help assure that everyone in your company will start getting economical corporate rates.

Get 5 Upgrade Certificates – Free! Just for signing up now, you'll get 5 free Upgrade Certificates. These entitle your company's travelers to a car from the next-higher car group than the one reserved at participating U.S. locations. But the low corporate rate stays the same.

5 Free Upgrades

The more you rent, the more you save with the Avis Corporate Awards Program. Based on rental activity using your AWD number, we'll send you free Rental Day Certificates. And check your monthly statements for a variety of money-saving bonuses.

And Free Rental Days

We'll even help with your bookkeeping. As part of the Avis Corporate Awards Program, you'll receive a detailed monthly statement outlining all qualified rental activity – including renters' names, rental dates, locations and more. So you'll spend less time on paperwork and more on helping your business grow.

Plus, other Avis services like Avis Express® and Roving Rapid Return® can save precious time for you and your travelers. **Call Avis at 1-800-321-3709, Operator 54,** for more details. Or send in the coupon below and sign up today. It's the best way to get the big perks your small business deserves.

©1992 Wizard Co.,Inc.

❑ Yes! I'd like to find out how the Avis Corporate Account Program can help my company grow.

Send to: **Avis Corporate Accounts**, P.O. Box 690360, Tulsa, OK 74169-0360. Or fax to: 1-918-621-4820. Please send me more information about the **Avis Corporate Account Program**.

NAME _____ TITLE _____

COMPANY _____

ADDRESS _____

CITY _____ STATE _____ ZIP _____

PHONE ( ) _____

NATURE OF BUSINESS _____

ESTIMATED NUMBER OF MONTHLY CAR RENTALS _____

Do you currently have a Corporate Account with another car rental company? ❑Yes ❑No

INT 051

AVIS®

We try harder.®

Circle 159 on Inquiry Card.

World Radio History

all the screen space they need, without worrying about getting out of the way when it's time to record. And since the second monitor is typically for the signal being sent to your recording VCR, you can use a single monitor to view both the live, recordable computer output and the playback of the videotaped result. Some applications, however, require the broader color range of the video I/O board for their interfaces.

While it's often worthwhile to create a computer graphic and record it to tape, it's much more valuable to combine computer-generated graphics with external video. Take, for example, the image in the screen on page 110. The background image of a person working on a piece of manufacturing machinery came from a videotape that was shot with a camcorder. I hooked the video output from the AG-7650 video player to the video input on the Mac's NuVista+ board. I then used a presentation graphics package to construct the text and graphics, leaving the background a solid color. Next, I used AT&T Graphics Software Labs' StudioMaster Pro software to turn the graphic into an overlay by selecting the graphic's background as the *key color*. StudioMaster Pro moved the playback tape into position, loaded the graphics file, and switched on the NuVista+'s video overlay. The key color becomes transparent, so the video on the NuVista+'s input appears wherever the key color (the background, in this case) is painted. The combined image—video input plus computer-generated graphics—appears on the NuVista+'s video output, suitable for recording to tape.

This entire exercise took about a minute to complete, and it wouldn't have been much more difficult on the PC or the Amiga. This bird's-eye view of a titling exercise is only for illustration, but it should start you thinking. Any system that does video overlay (including inexpensive systems like external Amiga genlocks and specialized VGA cards for PCs) is generally capable of combining computer graphics and video in whatever way you like, provided the video fills the entire screen. Nearly all video input cards also allow you to capture an incoming video signal, freeze it, and store the frozen image as a file for use elsewhere. The combination of moving video, captured images, and computer-generated graphics is a powerful one, as you'll see. But for now, I will digress and put a couple of thorny issues to rest.

The Great Format Wars

It would save a lot of time if you could take the video side of desktop video for granted, but you can't. The gear required to do the job properly can't be found in a department store or even in most video specialty stores. The equipment I selected for the lab, based on criteria I think most desktop video producers would use, falls into the industrial and "prosumer" classes I described earlier. What sets these units apart from consumer equipment are cost, quality, and computer controllability.

There are a number of standards for methods of recording video on tape. These are referred to as *video formats*, and there are more of them than you can imagine. But if you limit your scope to the formats that are affordable to people less well-off than Ted Turner, some cost/capability isobars begin to emerge.

Closest to the average desktop video producer's comfort zone lie two relatively new video formats: Super VHS (S-VHS) and high-band 8 mm (Hi8). As their names suggest, both are improvements

The Ultimate True-Color Image Presentation Tool For Windows™

Presentation Power
- Full 16-bit and 24-bit support, with optimized polette color compression on 256-color systems
- Attention-grabbing transitions between images: tile, louvre, wipe and snap with control over direction, style and display speed
- Ultra fast loading of BMP, TIF, PCX, GIF, Targa(TGA, VST) and other formats
- Portable presentation generation: one file contains the entire runable show – copyright free!
- Speaker notes: print your notes and images
- File conversion: save any image as a Windows bitmap
- ImageQ Viewer (sold separately): can be controlled by your application through Windows DDE

Ease Of Use
- Slide sorting by name or visual matrix
- Automatic, multiple visual image directories
- Preview window for full size image display
- Cut and paste of text, graphics and images from any other Windows application that supports the clipboard

Presentation Control Language
- Full multi-media support at the MCI string level
- Control of image sequence with keyboard and mouse
- Define "click-on" regions in your image for even greater flow control
- Looping, conditional branching, random image access
- Adjustable run level adapts presentation to audience



ImageQ™ $349 • Contact (800)363-3400

International: (519) 570-9111 Fax: (519) 570-9140
Image North Technologies Inc. • 180 King St. S., Suite 360
Waterloo, Ontario, Canada • N2J 1P8 • Dealer Inquiries Welcome

ImageQ is a trademark of Image North Technologies • Windows is a trademark of Microsoft Corporation • Images courtesy Truevision Art Contest © 1991

Circle 157 on Inquiry Card (RESELLERS: 158).

World Radio History



How much longer can you afford to wait?

Create Overlaid Programs-Fast.

BLINKER™, the world's first and fastest dynamic overlay linker, reduces your link time to seconds and reduces program memory requirements. Now you can use one linker for all your software projects.

One Linker, Many Languages.

BLINKER 2.0 links and automatically overlays DOS programs written in Microsoft® C, BASIC, Assembler, QuickBASIC™, Fortran, Pascal, Watcom™ C, Zortech® C++, Clipper®, FORCE® and in Borland® C, C++, Assembler, and more.

Save Time and Memory.

BLINKER removes the need for overlay structures, simplifies program design and reduces memory requirements to save you time, effort and memory.

Memory Swap Function.

BLINKER is the ONLY linker to offer an integrated memory swap function, so you can run other large programs from within your program, with negligible memory overhead.



BLINKER™
High Performance Dynamic Overlay Linker

Don't Settle for Less.

Other major features include full CodeView® support, use of EMS/XMS at program run time, and enhanced execution speed of overlaid code.

Time is Money.

BLINKER offers all this in a fraction of the time it takes to link with your current overlay linker. You know time is money, and link time is no exception.

Free Demo

To try our free demo on your own code

Call: 804-355-4444
FAX: 804-355-1676 or

Order now!

If you can't wait any longer, we offer a risk free 30 day money back guarantee. Available in 5.25" or 3.5" diskette format.

Price $299
plus shipping & handling

VISA MasterCard

Blinkinc
P.O. Box 7154
Richmond VA
23221

© 1991 Blinkinc. Blinker is a trademark of ASM, Inc. Offer only applicable in US and Canada.

Circle 165 on Inquiry Card (RESELLERS: 166).

World Radio History

over the existing VHS and 8-mm formats. At a minimum, these improvements increase the resolution of the basic formats, but most S-VHS and Hi8 decks also employ other image-quality enhancements.

Even though these two standards deliver roughly the same image quality and call for similar levels of investment, they are at odds with each other. Just as in the VHS-versus-Beta wars of old, proponents of S-VHS and Hi8 are battling for the same audience. In my view, it shouldn't be so; the Multimedia Lab incorporates both formats into its work, and I couldn't imagine it any other way. Hi8 is attractive because of its mix of high quality and light weight. My Canon A1 Digital camcorder weighs less than 4 pounds—battery, tape, and all—and it's considered a heavyweight among midrange Hi8 camcorders. It travels well, and despite its birdlike physical attributes, it doesn't skimp on features or quality.

Hi8 suffers, however, from the very things that make it so appealing. Because the tape is so compact, the video heads have less surface area on which to "spread out" their signal. Dropouts (i.e., image degradation caused by flaking of the tape's magnetic coating) are common after several plays and tend to be much more noticeable than on larger formats. Some Hi8 tapes are less susceptible to dropouts than others, but in general, Hi8 is not durable enough for the thrashing that tapes get in a typical editing session. For gathering material, however, Hi8 is perfect.

An S-VHS tape weighs a ton by comparison. S-VHS tapes and gear are not nearly as easy to carry and use as Hi8. But S-VHS has proven, in my experience, to be equal to the demanding requirements of editing and multiple plays. A number of highly capable professional S-VHS video decks have been released recently, and these units are, in all ways except cost and image quality, the equal of broadcast decks costing much more. It's a fringe benefit that these decks are also capable of recording and playing standard VHS tapes; there's no need for a specialized VHS mastering deck.

The equipment mix I finally settled on for the Multimedia Lab takes advantage of the best attributes of both formats. All the live video is collected using Hi8 camcorders and then is transferred to S-VHS for editing. Animations and other strictly computer-generated material are sent directly to the AG-7750, which has frame-accurate computer control and other attributes that I will describe later.

Segue Alert

Now that you understand some of the basics, it's time to take a breather until the next article in this series. There, you'll begin doing some *real* work, pulling together the raw materials that are part of a typical desktop video production.

You'll learn more about live video acquisition, film transfers, video capture, and image enhancement. I'll discuss the products and techniques used to acquire and shape these materials, which can later be combined to form finished productions. ■

Tom Yager is the director of the BYTE Multimedia Lab. You can reach him on BIX as "tyager" or on Internet as tyager@bytepb.byte.com.

COMPANY INFORMATION

ALR
(PowerVEISA systems)
94091 Jeronimo
Irvine, CA 92718
(714) 581-6770
Circle 1131 on Inquiry Card.

Apple Computer, Inc.
(Macintosh systems)
20525 Mariani Ave.
Cupertino, CA 95014
(408) 996-1010
Circle 1132 on Inquiry Card.

AT&T Graphics Software Labs
(Video processing software)
3520 Commerce Crossing, Suite 300
Indianapolis, IN 46240
(317) 844-4364
fax: (317) 845-6917
Circle 1133 on Inquiry Card.

Canon USA
(Digital camcorders)
1 Canon Plaza
Lake Success, NY 11042
(516) 488-6700
fax: (516) 354-5805
Circle 1134 on Inquiry Card.

Commodore Business Machines
(Amiga systems)
1200 Wilson Dr.
West Chester, PA 19380
(215) 431-9100
Circle 1135 on Inquiry Card.

Diaquest, Inc.
(VTR controllers)
1440 San Pablo Ave.
Berkeley, CA 94702
(510) 526-7167
fax: (510) 526-7073
Circle 1136 on Inquiry Card.

Micropolis Corp.
(Hard drives)
21211 Nordhoff St.
Chatsworth, CA 91311
(800) 395-3748
(818) 709-3300
fax: (818) 709-3497
Circle 1137 on Inquiry Card.

NewTek, Inc.
(Video switching and effects)
215 Southwest Eighth St.
Topeka, KS 66603
(800) 843-8934
(913) 354-1146
fax: (913) 354-1584
Circle 1138 on Inquiry Card.

Panasonic Broadcast and Television Systems
1 Panasonic Way
Secaucus, NJ 07094
(800) 524-0864
Circle 1139 on Inquiry Card.

Truevision, Inc.
(Desktop video adapters)
7340 Shadeland Station
Indianapolis, IN 46256
(317) 841-0332
fax: (317) 576-7700
Circle 1140 on Inquiry Card.

World Radio History

Finally.
A *Real* PC
for Windows®
Users



World Radio History

Hauppauge PC's:

Designed by Hauppauge

You've been using our Hauppauge MotherBoards for years. Now, you'll love our new computer systems. Designed by our engineers and built in the U.S., they're for Windows users like you who need more performance at an affordable price.

Our new 486M PC's use the Hauppauge Modular local-bus MotherBoards, while the 386N PC's use the famous Hauppauge SmorgasBord. We've made our GUIacc standard and provide generous cache RAM and high-speed system RAM, features other companies call options. Your favorite Windows applications will run like never before. For the best PC values; buy Hauppauge Direct!



All Hauppauge Windows PC's include:

- Microsoft DOS 5.0
- Microsoft Windows
- MS mouse - two button
- Factory installed software on hard disk, with floppy disk backups. We scan all disks for computer virus's before shipping.
- 30-day satisfaction guarantee
- One year warantee with lifetime free labor
- Unlimited technical support

MICROSOFT WINDOWS READY-TO-RUN

33MHz 486M PC $2,595

Modular local-bus PC

- Intel 33MHz 486DX, upgradeable to 50MHz +
- 128KB cache, expandable to 1MB
- 4MB RAM, expandable to 64MB
- 130MB< 16MSEC cached IDE disk drive
- Local bus GUIacc with 1MB video RAM
- 14" super VGA monitor
- 1.2MB, 1.44MB floppy drives
- 2 serial, 1 parallel port
- Maxiswitch 101 keyboard

33MHz 386N PC $1,995

Next generation 386 PC

- 128K cache memory, expandable to 256K
- 4MB RAM, expandable to 32MB
- 130MB < 16msec cached IDE disk drive
- GUIacc with 1MB of video RAM
- 14" Super VGA monitor
- 1.2, 1.44 MB floppy drives
- 2 serial, 1 parallel port
- Maxiswitch 101 keyboard

World Radio History

for Power Windows.

Win/TV $495

Watch TV in Windows!

Watch your favorite TV show while running your Windows application. Then, grab a video image and store it in BMP, TIF, TGA, or MMP format. Drop the image into any word processing, desktop publishing or paint program to bring your document to life!

- Movable, resizable TV window
- Channel tuner for connection to cable TV
- 2 external video sources let you watch video from a VCR or camcorder.

GUIacc $495

Make Your Windows Graphics Go Faster!

Our Graphic User Interface Accelerator, based on the S3 chip, will blow the doors off Windows!

- Accelerates Windows graphics up to 5 times faster
- Supports Windows resolutions from 640x480 to 1024x768
- Includes 1MByte of high-speed Video RAM
- Based on the S3 graphics coprocessor

Includes Norton Desktop for Windows

Buy any of our PCs for Windows and get a free copy of Norton Desktop, featuring Windows utilities, backup and data recovery tools.

$149 Value

THE NORTON DESKTOP™ FOR WINDOWS

Who is Hauppauge?

In 1982, two former Intel engineers founded Hauppauge Computer Works to develop ways to make PCs run faster, better and longer. Over the years, our industry-first 386 and 486 MotherBoards have been used by some of the largest PC and minicomputer companies in the world. And we've earned design and performance accolades including PC Magazine's "Editor's Choice" and PC World's "Upgrade Product of the Year."

Now, in 1992, our new division, Hauppauge Direct, brings you complete PC systems. We've designed them to be faster, more reliable and more cost-effective than the biggest names in the PC business. Whether you use our PCs for business or home use, education or research, you'll find they raise the performance level of all your applications.

When you buy a Hauppauge PC, you get unlimited technical support free of charge. Call us for more information today:

800-443-6284

Hauppauge!

Trademarks: Windows, DOS: Microsoft Corp.; AutoCAD: Autodesk; Intel Inside, i486: Intel Corp.; Norton Desktop: Symantec Corp.; i860, Win/TV, GUIacc: Hauppauge Computer Works; IBM PC: IBM Corp.; S3: S3, Inc.

World Radio History

PCs For Professionals

33MHz 4860 CADstation $6,995

(Autodesk AutoCAD and RGB monitor not included)

Our 4860 CADstation is designed for specific, heavy-duty applications. We've packed it with both a 33MHz 486 processor for fast overall performance and an Intel i860 RISC accelerator to speed up AutoCAD® and 3D-Studio.® And you'll get our 1152x900 24 bit-per-pixel local bus frame buffer for high speed photo realistic drawings. Dual monitor support plus the Hauppauge GUIacc top off the feature list to make the 4860 CAD station the world's best PC for CAD!

AUTODESK REGISTERED DEVELOPER

- i486 33MHz processor
- i860 RISC processor
- 16 MBytes 64-bit main memory
- 200 MB EISA SCSI disk drive and controller
- 1.4, 1.2 MByte floppy disk drive
- FrameBuffer: 24-bits-per-pixel, 1152x900 pixels, local-bus, RGB output
- ADI/860 for AutoCAD refill and 3D-Studio
- Demo copy of CadART/860 photo realistic renderer
- GUIacc with 1MB RAM
- 14" Super VGA monitor
- 2 serial, 1 parallel port
- Maxiswitch 101 keyboard, MS mouse

Rendered using CadART/860 on AutoCAD DXF file

Hauppauge!

Hauppauge Direct
91 Cabot Court
Hauppauge, New York 11788-3706

In New York: 516-434-1600
Fax: 516-434-3198
In Europe: (49)2171-17063
In U.K.: (071)378-7309

800-443-6284

Circle 276 on Reader Service Card

Trademarks: Windows, DOS: Microsoft Corp.; AutoCAD: Autodesk; Intel Inside, i486: Intel Corp.; Norton Desktop: Symantec Corp.; i860, WIn/TV, GUIacc: Hauppauge Computer Works; IBM PC: IBM Corp.; S3: S3, Inc.

World Radio History

FEATURE

Windows Goes Real Time

The iRMX for Windows operating system provides the best of both worlds: real-time and DOS/Windows applications together on a single PC

KRISHNAN RAJAMANI, NARJALA BHASKER, RICK GERBER, AND STEVE SNYDER

Real-time applications have long been the domain of expensive proprietary hardware. But the relatively low cost of personal computers, the range of GUIs they can support, and the variety of software packages available for them make small systems an attractive alternative. The question is, can real time on personal computers work with acceptable response times and without losing access to popular DOS and Windows applications?

DOS certainly does not provide the bed for the multitasking necessary for real-time applications; nor does it provide adequate run-time support for them. TSR programs provide only a semblance of multitasking. Even Windows doesn't provide the preemptive priority-based multitasking that sophisticated real-time applications need.

Equally important, neither DOS nor Windows guarantees a bounded interrupt-response time (i.e., the time that elapses from when an interrupt occurs to when its interrupt handler starts to execute). Historically, proprietary kernels (i.e., operating systems) have provided the bounded interrupt latency, deterministic task-switch time, and other features that real-time applications need.

However, completely abandoning DOS and Windows in favor of a proprietary real-time kernel is not attractive, either. Such a solution forsakes the wealth of GUI, data-analysis, and display packages that are available under DOS and Windows. Without these packages, it's hard for real-time applications to meet the expectations of personal computer users. "Reinventing the wheel" on proprietary kernels also is not cost-effective.

Systems designed to support real-time applications must respond to external asynchronous events within a predictable time frame. Whereas *real time* is often interpreted to mean *fast*, a better synonym would be *predictable* or *deterministic*. The technology inherent in making a system real-time can add significant benefits to any application that requires a predictable response time. Real-time systems must support asynchronous I/O to maximize predictability. This support goes further than just making I/O fast; it enables a system to concurrently execute other portions of an application during I/O.

Intel's iRMX for Windows operating system forms a bridge between DOS/Windows and real time. (Note: We use the term DOS/Windows here to imply either DOS alone or DOS and Windows together.) This operating system runs DOS/Windows as a single task under the iRMX (for real-time multitasking executive) 32-bit protected-mode operating system. It allows you to use the capabilities of iRMX with the Windows GUI to develop real-time applications supporting a wide

ILLUSTRATION: RAPHAEL LOPEZ © 1992

World Radio

range of configurations, from single CPU systems to multiprocessor systems based on networks or Multibus II. (For more information on iRMX for Windows, call (800) 438-4769.)

In the past, the iRMX family of operating systems was focused on either component-level applications or applications using Multibus. (For more information on the characteristics of the iRMX operating system, see the text box "Exploring the iRMX Pedigree" on page 122.) With the advent of iRMX for Windows, iRMX has been unbundled from such proprietary hardware. iRMX for Windows will run on any IBM- or Compaq-compatible 386 or 486 machine.

The extended features of the 386 architecture, such as V86 mode, multiring protection, and multiple address spaces, make the marriage between DOS/Windows and iRMX possible. (Note that the term iRMX by itself refers to the non-DOS/Windows aspect of iRMX for Windows.)

A Real-Time Windows Application

Picture a hypothetical control system, say a luggage-tag engraver, running on a personal computer. The luggage tags sit in three bins, each bin containing different colored tags. For each engraving request, a tag is retrieved from the appropriate bin and placed on a conveyer. The conveyer moves the tag to an engraving station where a robotic arm moves it to an engraver. A vacuum pump activates to hold the tag in place and clean the station of engraving debris. The engraver activates and engraves the tag. When the engraving is complete, the robotic arm places the tag back on the conveyer, which moves it to a collection point.

The upper section of figure 1 shows the real-time components of such an application. Typically, they consist of control tasks of varying priorities and, perhaps, some hardware interrupt handlers. Together, these tasks and interrupt handlers control and respond to hardware events in a timely manner.

Imagine that a Windows screen (e.g., an Excel window performing order entry for the system, a custom window displaying a graphical representation of the control system replete with moving parts, a soft-control panel, and so forth, illustrated at the bottom of figure 1) conceals the control system illustrated at the top of the figure. Now picture a PC simultaneously running the control system with the user interface at the bottom of the figure. iRMX for Windows lets you do that.

Figure 1 shows how the iRMX nucleus schedules DOS/Windows and its applications as a task along with the other real-time control tasks. (You would probably want to set the priority of the control tasks higher than that of the DOS/Windows task.) The control tasks communicate not only among themselves, but also with DOS/Windows applications through a variety of interfaces.

Under iRMX, Windows can run in real or standard mode. Since iRMX applications can install 32-bit interrupt handlers at Ring 0 (the most privileged execution state on an Intel processor, and the state where operating-system kernels normally run), they get control directly, regardless of the processor mode, with a bounded latency.

BYTE ACTION SUMMARY

Combining real-time applications with the relatively low cost of personal computers, the range of GUIs they can support, and the variety of software packages available for them is an exciting new development. Accessing DOS and Windows capabilities in a real-time environment provides the best of both worlds.

A Multitude of APIs

Since iRMX for Windows merges different operating systems, it contains a rich set of application programming interfaces. An application may not need all of them, but their availability provides flexibility. The APIs fall into three categories: native iRMX APIs for iRMX tasks, native DOS and Windows APIs for DOS/Windows programs, and Bridge APIs that allow DOS/Windows programs to communicate and synchronize with iRMX tasks.

The iRMX APIs include system calls that support preemptive priority-based multitasking, interrupt management, exception handling, 32-bit memory management, and intertask communication, synchronization, and mutual exclusion. These APIs also provide device-independent I/O and network access.

DOS and Windows provide the native DOS and Windows APIs. Since DOS and Windows actually coexist with iRMX, the full range of native DOS APIs is available. Windows is optional, and its associated APIs are available if you load it.

The typical application envisioned for iRMX for Windows includes the interaction of real-time components; of user-interface and non-real-time components; and of real-time components and non-real-time components, including the user interface. With these functions in mind, you would use iRMX APIs to implement the real-time components of the application; DOS/Windows APIs to run the user-interface and non-real-time applications, such as a spreadsheet; and the Bridge APIs to bridge between the real-time components and the user-interface components.

Bridge APIs

The Bridge APIs come in three forms: real-time extensions, network interfaces, and Dynamic Data Exchange. The RTEs provide a critical subset of iRMX services—including semaphores and mailboxes—to DOS/Windows programs. A DOS/Windows program can use these primitives just as any other iRMX task would. The standard networking interface lets DOS/Windows programs use the NetBIOS interface to talk to iRMX tasks. Windows provides the DDE mechanism for programmatic communications between applications. Many popular applications, including Excel, Intouch, Visual Basic, and Toolbook, support DDE largely to implement the notion of links between documents. DDE is therefore the key to providing iRMX applications with the ability to communicate with standard Windows applications.

The DDE communications model considers each application to have a set of data items named by strings. Each application defines the format and meaning of data-item names (e.g., Excel requires that data items referring to cells use RnCn notation). Data items are located using an address with three elements: the application name, the topic name, and the data-item name.

The topic name distinguishes among multiple application instances. For example, with two instances of Excel active, the DDE mechanism uses the name of the file that each instance is running to distinguish between them.

Applications can set and query data items owned by each other. They can also ask to be notified if a data item's value changes for event-driven operation. An application that actively makes DDE requests is called a *DDE client*. An application that passively responds to them is called a *DDE server*.

DDE support in iRMX for Windows consists of two elements: a DDE Library to enable iRMX applications to participate in DDE communications, and a DDE Router Windows program that converts them to network communications. The DDE Library contains simple calls that iRMX DDE clients use to set and reset

World Radio History

Mathematica 2.0: the standard for technical computing

"The importance of the program cannot be overlooked ... it so fundamentally alters the mechanics of mathematics."
New York Times

***"Mathematica* has the potential to change the world of science at least as much as word processing has changed the world of writing."**
InfoWorld

***"Mathematica* is a startlingly good tool."**
Nature

Macworld 1991 World Class Software Award Survey



Mathematica has also received best software/new product awards from:

Macworld, 1990-91
Discover, 1990
BYTE, 1989
MacUser, 1989
Business Week, 1988
InfoWorld, 1988

Available across PC, Macintosh, Unix, and VMS platforms, *Mathematica* includes a full range of interactive numerical, graphical, and symbolic computation capabilities, all linked to the powerful built-in *Mathematica* language. *Mathematica* 2.0 adds still more features to the proven leader in technical computing software, including sound generation and flexible external program communication.

Mathematica has rapidly become the standard for technical computing, with more than a dozen textbooks, a quarterly journal, and several newsletters devoted to the system. *Mathematica* is in use at all of the 50 largest U.S. universities, all of the technical Fortune 50 companies, and most of the world's larger engineering firms. In fact, more than 100,000 technical professionals and students around the world are working with *Mathematica* every day.

To find out what *Mathematica* can do for you, call Wolfram Research at 1-800-441-MATH.

Mathematica 2.0
A System for Doing Mathematics by Computer

For Macintosh information circle 136,
For IBM/Compatible information circle 137,
For UNIX information circle 138 on Inquiry Card.

***Mathematica* is currently available for:**

MS-DOS 386, Microsoft Windows, Macintosh, CONVEX, DG AViiON, DEC VAX (ULTRIX and VMS), DEC RISC, HP 9000, Apollo, IBM RISC System/6000, MIPS, NeXT, Silicon Graphics, Sony, Sun-3, and SPARC.

Prices in U.S. and Canada start at $595. Educational discounts and student versions are available.

Wolfram Research, Inc., 100 Trade Center Drive, Champaign, IL 61820-7237, USA
217-398-0700; fax: 217-398-0747; email: info@wri.com

Wolfram Research (UK) Ltd., P.O. Box 114, Abingdon, Oxon OX13 6TG, United Kingdom
+44 (235) 550 440; fax: +44 (235) 550 445; email: info-uk@wri.com

© 1991 Wolfram Research, Inc. *Mathematica* is a registered trademark of Wolfram Research, Inc. *Mathematica* is not associated with Mathematica Inc., Mathematica Policy Research, Inc., or MathTech, Inc. All other product names mentioned are trademarks of their producers. Photo: George Retseck



***Mathematica 2.0* for Windows Now Shipping**

World Radio History

Exploring the iRMX Pedigree

The iRMX family of real-time operating systems has been on the market for more than 13 years. It is widely used in such mission-critical applications as check and mail sorting using high-speed imaging, medical instrumentation, machine and process control, satellite communications, energy management, financial trader workstations, and Automatic Teller Machines.

The basis of the new iRMX for Windows operating system is iRMX III. The new system is a true 32-bit multitasking operating system with real-time programming facilities, including the following:

- Preemptive, priority-based task scheduling with optional round-robin (or time-slice) scheduling within a priority level.
- Advanced interrupt-management facilities that provide a deterministic response to asynchronous external events.
- Efficient memory management with 4 gigabytes of memory accessibility.
- Multiple intertask communication and mutual-exclusion mechanisms to provide optimum task cooperation.
- Full integration with the protection mechanisms of the 386 architecture for clean-code enforcement and program isolation.
- An extensible set of system objects with built-in type checking for increased programming clarity.

The iRMX model for program isolation is an object called a *job*. A job defines the environment for a program and contains all the resources that its various components use. Each job has its own memory segments. Its resources are by default private but can be made public, if desired, so other jobs can use them.

A job can have multiple threads of execution, each of which is called a *task*. Tasks are the active objects within a job. Each task has its priority specified when it is created.

Tasks progress through a number of action states while they exist, between running (in control of the CPU), ready (preempted by a higher-priority task), and delayed (waiting for an event). Tasks communicate with each other through system calls, which include the following:

- `send_message` lets a task send system objects, such as segments, to object mailboxes.
- `receive_message` lets a task receive system objects, such as segments, at object mailboxes.
- `send_data` lets a task send data to data mailboxes.
- `receive_data` lets a task receive data at data mailboxes.
- `send_units` lets a task send several abstract counting units to a semaphore.
- `receive_units` lets a task receive several abstract counting units from a semaphore.
- `catalog_object` allows a task to catalog the name of a mailbox or semaphore in a job's object directory so that other tasks can look it up by name and use it for intertask communications.
- `lookup_object` lets a task look up the name of a mailbox or semaphore in a job's object directory and use these exchanges for intertask communications.
- `signal_interrupt` lets an interrupt handler signal an interrupt task to provide additional processing for an interrupt—processing that the interrupt handler itself cannot provide.
- `wait_interrupt` lets an interrupt task wait for an interrupt that needs special processing.

Task priorities and these intertask communications mechanisms provide all the tools necessary to meet the real-time requirements of even the most demanding applications. Other calls allow the creation and deletion of these various exchanges, as well as the removal of objects from object directories. The various receive calls have time limits associated with them, so tasks that use them may be blocked (or delayed) until the requested information is received.

Other system calls also exist and provide management for memory, objects, exception handlers, interrupts, files (including device-independent I/O), and operator interfaces. The iRMX III operating system also allows you to define new object types and produce new system calls to manipulate objects of these new types. Such extensibility provides a great deal of flexibility.

data items in DDE servers. It also provides calls that iRMX DDE servers use to advertise data-item or topic names and register handlers to invoke when requests arrive for any data item.

The DDE Library communicates with the DDE Router using a simple applications protocol built with standard network interfaces. This protocol extends DDE addressing by adding the network name of the machine. So a DDE address has four components: a machine name, an application name, a topic name, and a data-item name. Both polled and event-driven operations are possible for iRMX applications.

Of the Bridge APIs, RTE is more efficient than the network interface or DDE, but it is not natural for DOS/Windows programmers. NetBIOS and DDE are more familiar. In fact, many Windows software packages already support data manipulation via DDE. So, it may be more convenient for iRMX tasks to communicate with those packages in that way.

Using NetBIOS or DDE to communicate between DOS and iRMX has another subtle advantage. NetBIOS and DDE lend themselves to transparently distributing the real-time and user-interface components across multiple machines. The user interface and non-real-time components could execute on one machine while the real-time elements execute on another. Communications between the components could then occur over the network.

However, you don't need network hardware if the entire application resides on a single PC. The networking interfaces work transparently whether short-circuited on one machine or dispersed across several systems. Similarly, the network-based DDE Router provides transparent scalability for the DDE interface.

continued

World Radio History

About the only thing Superbase 4 can't contain is your imagination.

Imagine this.

A Windows™ database that can handle virtually any data type.



It's called Superbase®4 from Software Publishing Corporation. With it, the development possibilities are, well, thought provoking.

Consider bar coding. Think creatively and anything's fair game. One high-security prison, for example, uses Superbase 4 to keep track of their prisoners.

Or how about video? Through DLL you can store still shots from a full-motion video camera. Or grab key images from a previously recorded tape.

What's more, any photographic or graphic image can be included in any data file. So you can dress up product catalogs. Personnel records. You name it.

And through DDE you can even pull in everyday business accessories. Like maps, graphs, charts, and spreadsheets.

But this versatility doesn't come at the expense of power. Superbase 4 is fast. It lets you include an unlimited number of characters in any text field. And supporting SQL, it connects with some formidable databases—SQL Server, Oracle, Sybase, dBase, and DB2, among others.



In fact, Superbase 4 already manages a direct mail database containing over one million records. It could handle a lot more.

So it's no wonder Superbase 4 is the worldwide market leader in Windows databases.

Just imagine what it can do for you.

Imagine, a free demo disk just by calling 1-800-336-8360, Operator 626.

SPC SOFTWARE PUBLISHING CORPORATION

Superbase is a registered trademark and Superbase 4 is a trademark of Software Publishing Corporation. Windows is a trademark of Microsoft Corporation.
© 1991 Software Publishing Corporation, 3165 Kifer Road, Santa Clara, CA 95051.

World Radio History



Figure 1: *The top part of the figure details the real-time components of a luggage-tag engraving application, including control tasks and hardware interrupt handlers. The bottom part shows a Windows screen (e.g., an Excel window for order entry, a custom window showing the control system graphically, and a soft-control panel), which might conceal the control system at the top. The iRMX for Windows operating system establishes the linkages to accomplish this on a PC.*

File Systems and Other Devices

Under iRMX for Windows, DOS and Windows programs continue to access I/O peripherals and the DOS file system as usual. They can also access remote file systems through any of the available network products (e.g., NetWare and MS-Net). Other iRMX tasks can access these file systems simultaneously via native iRMX I/O APIs. Here, iRMX requests are internally translated into DOS service requests.

Optionally, iRMX also provides a native iRMX file system that can reside on a separate disk, co-reside with the DOS file system on a partitioned volume, or exist elsewhere on the network. However, iRMX tasks use the same iRMX APIs to access either the DOS or the iRMX file system.

DOS programs can also map drive letters to iRMX file systems and access the iRMX files via the usual DOS I/O APIs. In this case, requests are internally translated into iRMX service requests.

A special iRMX for Windows API allows iRMX tasks to invoke real-mode software interrupts. Thus, the tasks can directly access special DOS device drivers as well as standard DOS or ROM BIOS services.

Remote file sharing includes both client and server capabilities. Since the DOS file system is visible to iRMX, a system running iRMX for Windows can enable remote clients to access the DOS file system while simultaneously allowing DOS/Windows and iRMX tasks to access remote servers. And since remote file systems are also visible to iRMX, that same system can act as a gateway for clients that can't access them directly. For example, an MS-Net client could access a Novell server in this environment.

iRMX for Windows also provides ISO transport services to iRMX tasks via Intel's PCL2A Ethernet controller. A network redirector subsystem allows NetBIOS applications from DOS/Windows to share that controller. DOS/Windows programs can also access a wide variety of other network hardware and software.

Under iRMX, applications can dynamically install new device drivers at run time. These drivers have a well-defined interface to the iRMX I/O system. Applications access them via device-independent APIs and through special driver-specific APIs.

The device drivers in iRMX for Windows run at Ring 0. The associated interrupt handlers obtain control directly, regardless of processor mode. This not only improves interrupt latency for device drivers, but also removes the burden of installing dual-mode interrupt handlers. Under iRMX for Windows, applications can also install operating-system extensions to define new APIs and even new object types at run time.

The Inside Story

To establish DOS as an iRMX task, you first boot DOS and load a special iRMX TSR, which reserves a small portion of conventional memory for iRMX. Next, the iRMX for Windows loader puts iRMX in extended memory, where it takes control of the CPU in protected mode and initializes each of the operating system's internal layers and system tasks.

This initialization creates a special system task and dispatches it in V86 mode to the loader's return address. Then the loader cleans itself up and returns to COMMAND.COM, which resumes the DOS idle loop. DOS is now set up as an iRMX task, and all subsequent DOS programs will execute in this context

World Radio History

Now Supports Both Windows & DOS

Close-Up Wins Remote Honors

PC WORLD

Close-Up is fast, easy to use, and reliable. What else do you need in a remote package?

Close-Up Dual Pack 4.0 earns its Best Buy by virtue of lightning speed, an easy interface, reliable error handling, and a complete set of tools for controlling one computer from another and collaborating with a partner. It's also the only package that can run Windows reliably from afar—even in extended mode. Runner-up **Remote2** isn't quite as fast, and its toolbox is smaller, but it is perfectly dependable with graphics.

"Close-Up is the undisputed speed champion."
—PC World, February 1992

Excellent ★★★★
Good ★★★
Fair ★★
Poor ★

	Reader service number	Performance	Ease of use	Controlling the host	Collaboration	Service and support	Standard communications	Price	Overall value
Carbon Copy Plus 6.0	671	★★½	★★½	★★	★★★½	★★½	★★	★★★½	★★½
Central Point Commute 1.1	673	★½	★½	★★	★★	★★	½	★★★★	★★
Close-Up Dual Pack 4.0	672	★★★★	★★★★	★★★★	★★★★	★★	★★★	★★★½	★★★★
CO/Session 6.0	674	★★★½	★★½	★½	★★	★★★½	★½	★★★½	★★½
pcAnywhere 4.03c	675	½	★★	★½	★★★★	★★	★	★★★½	★½
Remote2 2.1	676	★★★	★★★★	★★½	★★½	★★★½	★★½	★★★½	★★★
Takeover Lite 2.0	677	★½	★½	★★	★★★	★★★	★★★	★★★½	★★

Overall value is calculated by multiplying each category rating by the category's weight percentage, summing the results, and rounding to the nearest half number.

Actual test results reprinted from PC World's Review of Remote Communications Software, February 1992.

Remote Performance: Why Close-Up is Best

- *Supports both Windows and DOS with the same program.*
- *Fastest VGA, EGA and CGA graphics.*
- *Fastest file transfers and remote screens.*
- *Runs Windows in all 3 modes. No restrictions.*
- *Runs multiple Windows and DOS applications simultaneously, full-screen or windowed.*
- *Remote mouse and keyboard control.*
- *Self-installing, fully-automated for fast, easy operation.*

Call for FREE Working Model

"Close-Up...The Best Program You Can Buy for Remote Control"

—Reprinted from PC Magazine, January 14, 1992

The Ultimate Remote Program

"Norton-Lambert's Close-Up is the fastest, easiest, and the most reliable program we looked at..." —PC World, February 1992

The results are in and the experts agree. New Close-Up 4.0 has proven time and again to be the most advanced remote control system available.

Close-Up lets you view & control PCs miles away *by modem*. Now with full support for Windows, DOS, graphics and mice at record-breaking speeds, Close-Up is the fastest, easiest way to handle all your remote communications needs.

What You Can Do:

- ✔ Take control of PCs at any location.
- ✔ Work remotely on the road via laptop.
- ✔ Control your office PC from home.
- ✔ Access your company's branch offices.
- ✔ Train your associates on any application.
- ✔ Help customers miles away, remotely.
- ✔ Transfer text, data, any file between PCs.
- ✔ Remotely install and run Windows.
- ✔ Automate remote operations at night.
- ✔ Access networks all over the world.

Winner of the Top Awards

"Close-Up has been highly polished and it's flexibility and capability clearly make it the best program you can buy for remote control."
—PC Magazine "Best of 1991," January 14, 1992

"If you're serious about going remote, check out Close-Up. The program's handling of Windows is simply dazzling."
—PC World "Best Buy," February 1992

"Close-Up is one of the fastest products we've seen. It had the fastest file transfer times and the shortest times redrawing the screens."
—LAN Times, November 18, 1991

"You will not find a better all-around remote-control program."
—PC Magazine "Editors' Choice," February 25, 1992

Control both Windows and DOS with just one program

Now with double the remote power, Close-Up gives you full support of *both* Windows and DOS. That's like getting two remote programs for the price of one!

Spectacular Savings!

Now you can receive the Close-Up 4.0 Dual Pack including both sides for only $199—you save $240!

Upgrade Now!

Upgrade your current remote program to new Close-Up 4.0. Call for special pricing.



Call 805-964-6767

Norton-Lambert

Bringing People Together

P.O. Box 4085, Santa Barbara, CA 93140 USA
Phone 805-964-6767 Fax 805-683-5679

Limited time offer. All prices in US Dollars. Prices exclude shipping. © 1992, Norton-Lambert Corp.

Circle 97 on Inquiry Card.

World Radio History

Circle 59 on Inquiry Card (RESELLERS: 60).

Space - Savers

NEW



Stand-Alone LCD Monitor **$995.00**

This 10" black on white monitor is easy-to-read, yet compact. Resolution is 640x480 for sharp, flicker-free image. Sharp's high refresh rate, triple supertwist nematic technology with back lighting provides a super bright, low radiation screen with a wide viewing angle. The adjustable monitor base is only 29x14 cm. It lets you mount the LCD monitor on vertical surfaces or fold for transport. Comes with 1.5 m cable and VGA adaptor card. No external power required. IBM AT compatible.

NEW PRICE ONLY $98.00

Popular Space-Saver Keyboard **$98.00**

First successful alternative to conventional keyboard saves 60% desk space with a foot print of 27.3 x 15.2 cm. Has full travel tactilly responsive keys with standard left-right spacing for easy touch typing. 100 keys, compatible with IBM XT/AT PS/2. Many language versions available.

9" VGA Monochrome Monitor **$198.00**

640 x 480 resolution black on white screen with a foot print to match the Space-Saver Keyboard of only 25.0 x 25.7 cm. Tilt and swivel stand. No adaptor card included.

To Order Call Toll Free **1-800-328-2589**

1 year warranty on all products shown. Order direct from stock with 15 day full return privileges. Visa, MasterCard, AmEx charges and COD accepted.OEM and reseller volume discounts available.

Spec Sheets Sent By Automatic 24 hr. FAX Transmission **1-703-662-1675**

DATALUX

First Choice In Space-Saver Peripherals

2836 Cessna Drive • Winchester, VA 22601

Phone 703 662-1500 • Fax 703 662-1682

MasterCard VISA AMERICAN EXPRESS



Figure 2: *DOS runs as an iRMX task like any other in V86 mode. The DOS task contains a normal DOS system complete with drivers, ROM BIOS, and applications. In that same iRMX task, you can initiate Windows just as you would on a dedicated DOS system.*

(see figure 2). Now you can start Windows from DOS, if you wish. It will run in the same iRMX task that DOS does.

An application's real-time components can be loaded as protected-mode iRMX jobs at any time, either automatically after system initialization or manually from the console. Several jobs can run in the background, and each can contain multiple tasks.

The iRMX kernel runs in protected mode at Ring 0, while DOS and real-mode Windows run in V86 mode. If you load Windows in standard mode, it runs in protected mode but at a less-privileged level than iRMX. iRMX owns the global descriptor table and interrupt descriptor table, as well as its own local descriptor table. Standard-mode Windows has a private LDT.

Initially, iRMX owns and manages all the extended memory. Standard-mode Windows obtains extended memory from an iRMX Extended Memory Specification driver. Windows is then responsible for managing its own extended memory. The XMS driver provides functionality similar to that of HIMEM.SYS. Figure 3 shows how DOS, Windows, and iRMX use system memory.

The iRMX kernel schedules native iRMX tasks along with the DOS/Windows task according to priority. iRMX switches the CPU between V86 mode and protected mode as required when switching between tasks or dispatching interrupt handlers.

Any task, including the DOS/Windows task, can take hardware interrupts. The system first traps those that DOS/Windows handles in Ring 0 and then reflects them to the appropriate real-mode handler or Windows protected-mode handler (see figure

World Radio History

Blockbuster Presentations

Businessman's Budget

Curtain Call™ Presents... Titles, Effects, Backgrounds, Paint, Slide Show, Sound and Music for Windows.

Dazzling Titles

Dynamic Graphics

Powerful Effects

Get Rave Reviews.
Produce top-of-the-line presentations or videos that look good on the bottom line. You've got to try Curtain Call.

Talent Not Needed.
Because Curtain Call provides the cast and crew, making spectacular images is now a breeze. Start by producing a rainbow of beautiful backgrounds with just a click of the mouse. Then transform any Windows fonts into dazzling titles with shadows, outlines, metallics and 3D extrusions. Add your own artistry with Curtain Call's full-featured and easy-to-use paint tools. Finish it off with pictures, text, graphs, or still-frame video imported from other programs through Curtain Call's clipboard.

It's Show Time.
Your images can be sequenced and controlled with the mouse or menu-driven script editor. Slick variable speed transition and overlay effects add lots of polish. Preview any portion of your show at any time. Synchronize voice, sound effects and music, through Sound Blaster or another PC sound board. It's a blast!

Curtain Going Up.
It doesn't take an M.B.A. to figure it out. What used to cost thousands can now be yours for under $200.

Make Curtain Call your Windows presentation star and listen to the applause. Break a leg for $199.95.

ZumaGroup

Brown Wagh

160 Knowles Drive, Los Gatos, CA 95030
(800) 451-0900 (outside CA)
(408) 378-3838 (inside CA)
(408) 378-3577 (fax)

Circle 172 on Inquiry Card.

All names of companies and products as they appear are the registered trademarks and/or trade names of the respective companies.

World Radio History

Circle 76 on Inquiry Card

ANY CAMERA
ANY VCR
ANY TV

VGA VIDEO GALA

The Complete Desktop Video Graphics Solution

BEST 3 in 1 VALUE

3 IN 1

1. Its a Super VGA board!
2. Recordable output to VCRs and TV monitors!
3. Live TV in a window and frame grabbing!

HIGH RES TECHNOLOGIES INC.

The VGA Video Gala is only $595

To order or for more information, call or fax us at:

High Res Technologies Inc.
PO Box 76 Lewiston, NY 14092 USA
Tel: (416) 497-6493 Fax: (416) 497-1636

COMPUTER SECURITY PRODUCTS

COMPLETE LINE OF PROVEN AND EASY TO INSTALL COMPUTER SECURITY PRODUCTS FOR COMPUTERS.

PREVENT COMPUTER THEFT!

Kablit™Security System

This system allows you to secure all your computer components: CPU, monitor, keyboard, printer. **Internal component security:** Kablit fasteners secure the rear panel of CPU protecting internal boards and hard drives. Fasteners available for all applications. Prices **$34.95** to **$49.95** depending on system.

DISK DRIVE LOCK™

IBM PS-2 DLK-270 Series

Now you can lock a diskette into your disk drive and force the computer to boot from the diskette. Disk Drive Lock models available for PS/2 - 30, 55SX, 50, 70 and 90. Protect your data from viruses or from being copied. Other drive locks to fit most non IBM PS/2 and Macintosh disk drives. List price **$24.95**

Order your free catalog of these and many other security products. Purchase orders accepted. Quantity pricing available. Shipping not included. MC/VISA accepted. Dealer inquiries invited.

Secure-It, Inc. 18 Maple Court East Longmeadow, MA 01028 **1-800-451-7592**



Figure 3: *How do DOS, Windows, and iRMX share system memory? At first, iRMX has all the extended memory. Then, standard-mode Windows obtains some from an iRMX XMS driver, which functions as a high-memory manager, taking responsibility for its management.*

4). It also traps the return from these handlers to ensure that the interrupted task resumes execution in the appropriate CPU mode.

Similarly, the system traps all software interrupts from DOS/Windows programs and reflects them to the appropriate DOS/Windows handler. It also traps any attempt by Windows to switch the CPU between real and protected mode. iRMX for Windows performs any mode switching.

In addition to CPU sharing, iRMX shares other hardware resources with DOS and Windows. DOS and Windows can use the numerics coprocessor for floating-point instructions, as can iRMX applications, since iRMX maintains the numerics register context on a per-task basis. Both iRMX and DOS/Windows need the timer, so iRMX traps timer interrupts and reflects them to DOS or Windows at appropriate intervals. Also, iRMX and DOS/Windows can share hard and floppy drives. iRMX uses DOS APIs to access these resources. The iRMX TSR serves as a surrogate DOS process in whose context iRMX can obtain these services.

Remaining Predictable

Despite the presence of DOS/Windows and their applications, iRMX for Windows guarantees real-time response for critical iRMX tasks. First, the priority of a DOS/Windows task is low; it will run only when higher-priority tasks are idle. Higher-priority real-time tasks can preempt DOS/Windows tasks at any time.

Second, by using 386 protection features, iRMX traps any attempt to disable CPU interrupts from DOS or Windows. The actual CPU interrupt flag is always set to enable interrupts whenever DOS/Windows is running. However, iRMX maintains the DOS virtual state of this flag so that it won't reflect any hardware interrupts while DOS/Windows has disabled CPU interrupts. This ensures the integrity of DOS/Windows while it bounds the latency for iRMX hardware interrupts.

Third, iRMX traps DOS/Windows' I/O instructions that modify the interrupt masks of the programmable interrupt controller. The

Circle 118 on Inquiry Card (RESELLERS: 119).

World Radio History

WE CHANGED THE SHAPE OF COMPUTING. . .

We put the best features of your favorite computer into a keyboard.

Before KNS (Keyboard Network Station), when you purchased a computer system, the manufacturer threw-in the keyboard. Now, when you buy a KNS keyboard, we'll throw-in the computer.

And what a computer! Choose from 286 and 386SX models in a variety of CPU speeds. Specify up to 4MB of RAM. Your KNS comes standard with Super VGA adapter, 3.5" floppy disk drive, 2 serial ports, 1 parallel port and a 16-bit expansion slot–all housed in a lightweight, portable, AT-style keyboard.

A network interface card can be installed in the built-in 16-bit expansion slot; installation is quick and easy. And, KNS is compatible with most popular network operating systems.

We changed the shape of computing and the KNS will change the way you add workstations to your network.

"ULTRATEK–Everything for the LAN Builder"

ULTRATEK Products, Inc.

Distributed by: AIC (U.S.A.) • (714) 894-1675 **AIC (U.K.) 081-961-9661**

Circle 167 on Inquiry Card.

World Radio History

AccSys™ for

C

dBASE

- Set of C libraries for easy access to dBASE data and index files.
- Source available but not required.
- Increased performance shortens processing time.
- Total control over data memo, MDX and NDX index files.
- Network and single-user versions available.

Copia International Ltd.

Wheaton, Illinois 60187
708/682-8898 FAX: 708/665-9841

Instant info. via FaxFacts: 708/924-7465 Press: 889832#



Figure 4: *Any iRMX task, including DOS/Windows, can initiate hardware interrupts. The system traps DOS/Windows interrupts in Ring 0; reflects them to the appropriate handler, whether real-mode or protected-mode; and then traps the return to route the tasks to the appropriate mode.*

operating system emulates PIC operations in such a way that DOS cannot change the mask for iRMX's interrupt levels. Each interrupt controller has two logical parts: iRMX owns one, and DOS/Windows owns the other.

Finally, iRMX ensures that tasks above a certain priority do not take DOS/Windows interrupts. Thus, an application task can guard itself from long interruptions, such as a long list of TSRs triggered by the timer.

Making Trades

Trade-offs occur in uniting iRMX and DOS/Windows. To preserve the determinism of iRMX-owned interrupts and high-priority tasks, DOS and Windows pay a performance penalty.

Similarly, to maximize the device independence of standard AT peripherals, iRMX does not access them directly, but uses DOS and the BIOS to do so. iRMX for Windows doesn't require special device drivers to access a drive or file system. An alternative would have been to emulate DOS file and other I/O services with higher-performance device drivers and file systems.

This marriage sacrifices the functionality of enhanced-mode Windows (e.g., virtual memory and multiple DOS sessions). But it supports the faster standard-mode Windows. Despite these trade-offs, however, iRMX for Windows brings real-time applications to the PC. More than that, it encourages their cohabitation with DOS/Windows applications, providing the best of both worlds. ■

Krishnan Rajamani, Narjala Bhasker, Rick Gerber, and Steve Snyder are senior software engineers at Intel Corp. in Santa Clara, California. You can reach them on BIX c/o "editors."

A MESSAGE TO OUR SUBSCRIBERS

FROM TIME TO TIME WE MAKE THE BYTE SUBSCRIBER LIST available to other companies who wish to send our subscribers material about their products. We take great care to screen these companies, choosing only those who are reputable, and whose products, services or information we feel would be of interest to you. Direct mail is an efficient medium for presenting the latest personal computer goods and services to our subscribers.

Many BYTE subscribers appreciate this controlled use of our mailing list, and look forward to finding information of interest to them in the mail. Used are our subscribers' names and addresses only (no other information we may have is ever given).

While we believe the distribution of this information is of benefit to our subscribers, we firmly respect the wishes of any subscriber who does not want to receive such promotional literature. Should you wish to restrict the use of your name, simply send your request to the following address.

BYTE Magazine
Attn: Subscriber Service
P.O. Box 555
Hightstown, NJ 08520

World Radio History

Power Reading for Power Users

Read these in-depth Computing 'Know How' books





PC Intern – For the DOS Programmer

PC Intern is a completely revised and expanded edition of our bestselling *PC System Programming* book. It's a literal encyclopedia for the DOS programmer. If you program in assembly language, C, Pascal or BASIC, you'll find dozens of practical, parallel working examples in each of these languages. **PC Intern** clearly describes the technical aspects of programming under DOS. More than 1200 pages are devoted to making DOS programming easier, including:

- COM and EXE programs, the BIOS and services
- Writing device drivers, overview of ports and accessing them
- Interrupts, interupt calls and their significance
- New and expanded appendices and much, much more

1200+ pages with 3½" companion diskette.
#B145 ISBN 1-55755-145-6 **$59.95**

DOS 5.0 Complete: *Special Edition*

It's the practical user's guide to learning Microsoft's new DOS and is loaded with helpful time-saving techniques. Contains dozens of easy-to-follow examples in a friendly, easy-to-understand writing style. From installing DOS 5.0 to using the new features for file, directory and storage maintenance, you'll find all you need to get the most from your computing sessions. Topics include:

- Using DOS' new memory management features
- Using EDIT, the new DOS 5.0 editor
- Using QBASIC, the new BASIC programming language
- Complete, comprehensive DOS command reference section and more

This *Special Edition* includes **Tempest**, the Intuitive Graphic Shell for DOS 5.0. **Tempest** provides a graphical program manager and Shell for all DOS computers, using pull-down menus, dialog boxes and windows. Whether you need to move files, rename directories or launch programs, **Tempest** is the answer to easier computing. 920 pages with 3½" companion diskette.
#B151 ISBN 1-55755-151-0 **$39.95**

Order Toll Free 1-800-451-4319

Available at B. Dalton Booksellers, Waldensoftware, Software Etc. Crown Books, and other fine bookstores nationwide. In the UK contact Computer Bookshops 021-706-1188. In Australia contact Pactronics 02-748-4700

Abacus Dept. B4, 5370 52nd Street SE
Grand Rapids, MI 49512

Orders: 1-800-451-4319 • Phone: (616) 698-0330 • Fax: (616) 698-0325

In US and Canada add $5.00 postage. Foreign orders outside North America add $13.00 surface rate or $20.00 air mail per book. We accept Visa, Master Card or American Express.
Call or write for your free catalog of PC Books.

Circle 33 on Inquiry Card (PESSU-5BS-34)

For fast delivery Order Toll Free 1-800-451-4319 EXT. 24, or FAX (616) 698-0325

Or mail this coupon to: Abacus, 5370 52nd Street SE, Grand Rapids, MI 49512

❑ Yes, please rush the following items ❑ Yes, please rush your free PC catalog

_____ PC Intern ..... $59.95 _____ DOS 5.0 Complete *Special Edition* $39.95

Payment:
❑ Visa
❑ Master Card
❑ Am.Express
❑ Check/M.O.

Sub Total: _____
CA residents add 7.25% sales tax, MI residents add 4% sales tax: _____
In US and Canada add $5.00 postage and handling: _____
Foreign orders add $13 surface rate or $20 air mail per book: _____
TOTAL amount enclosed (US funds): _____

Card#: _____ Expires: ___/___

Signature: _____

Name: _____

Company: _____

Address: _____

City: _____ State: ____ Zip: _____

Phone#: _____ Fax #: _____ Dept. B4

World Radio History

Now getting fre isn't limited to hoo part-tim

Even honest, upstanding, people can experience the joy of getting something for nothing. All you have to do is buy one of the new PocketBooks personal productivity applications and you'll get a second one, absolutely free.

Choose *DayBook+*, the everyday calendar with address book and auto-dialer. *Make Your Point*, the graphics-rich presentation builder. Or *Instant Database*, the versatile data manager.

The PocketBooks library is a dynamic line of Windows software that gives you powerful, yet simple applications designed to make running your life a little easier.

Others will be introduced over the year. And starting at $49.95, they're a fraction of the cost of competitive software packages.

Initial purchase must be made by April 30, 1992. To order by phone, call 1-800-626-3225 and ask for Source Code PBK2F1A.



©1992 Asymetrix Corporation. 110 - 110th Ave., N.E., Suite 700, Bellevue, WA 98004, (206) 462-0501. For international inquiries, fax (206) 454-0672. Asymetrix, the Asymetrix logo, PocketBooks

World Radio History

e PocketBooks dlums, bullies and e thugs.



Or visit your local dealer. Then send in your proof-of-purchase with the coupon below and receive a complimentary PocketBooks title of your choice.

And don't worry. It's perfectly legal.

Asymetrix
Software Redefined

Please send me my free PocketBook (Circle One): DayBook+, Instant Database, Make Your Point.

Name _____

Title _____

Company _____

Shipping Address _____

_____

Phone _____

Attach this coupon with proof-of-purchase and a copy of your PocketBooks registration card and mail to: Asymetrix Corporation, PO Box 4100, Crawfordsville, IN 47933. Allow 4-6 weeks for delivery. For more information on this offer, call Asymetrix sales at (206) 637-1500.

Sales Tax Rates for applicable states: California=6.25% (plus local option tax); Massachusetts=4% (plus local option tax); New York=4% (plus local option tax); Texas=6%; Washington=8.2%

POCKETBOOKS

A

DayBook+, Instant Database and Make Your Point are trademarks of the Asymetrix Corporation. All other trademarks or registered trademarks are the property of their respective holders.

Circle 169 on Inquiry Card.

World Radio History

ILLUSTRATION: JAMES ENDICOTT © 1992

World Radio History

KINDER, GENTLER COMPUTING

Natural I/O technologies make your computer work for you, instead of the other way around

MAUREEN CAUDILL

It's April 1993, and you've just purchased a top-of-the-line personal computer from Big Apple. You open the box and begin to assemble it, but to your surprise, you don't see a keyboard, only a special pad and pen that resemble those in an executive portfolio. The box also contains clothing: a body suit, a pair of gloves, and a headband. You see no monitor, only a helmet and goggles. What's going on here?

What you're about to experience is your first taste of natural computing: making computers interact with users in a humanlike manner. Natural computing emphasizes how computers interface with humans on a sensory level rather than through the cognitive command logic today's devices use.

Natural computing intrinsically deals with human sensory perception. Neural networks, or processing systems modeled after the human brain, are particularly good at the low-level sensory tasks that digital computers find difficult to perform.

Natural input includes such technologies as speech and handwriting recognition and gesture interpretation. Natural output includes speech; meaningful, humanlike gestures and motions; and virtual-reality environments.

Natural I/O is the ultimate user-friendly interface. It places the burden of communication squarely on the computer rather than on the human: Instead of the user having to learn the computer's preferred interface, the computer must deal with the user's preferences. Although computers have been moving in the direction of natural I/O for years, the relevant enabling technologies are only now becoming mature enough to make this capability a reality in the immediate future.

Learning to Talk

Probably the first thing you thought of when you read the term *natural I/O* was a speech interface, so it's no surprise when you discover that your Big Apple system comes complete with a microphone and stereo sound. (Speech I/O is new; sound in general is not. Since 1990, systems such as the Next machine and the Macs have included sound capabilities as a part of their standard configurations.)

With natural-speech input, you face the two separate but interdependent problems of speech-to-text conversion and natural-language processing (NLP). Natural-speech output technologies confront the problems involved in speech generation.

Some excellent systems use hybrid expert-network technology married with traditional digital signal processing (DSP) techniques. Because words and phonemes frequently require several fractions of a second to utter, the sonograms (visual patterns representing sound waves) for even discontinuous words represent very large, complex blocks of data. Also, because of variations in pitch, tone, accent, dialect, and pronunciation, computers have an extremely difficult time recognizing even simple words like *cat*. They can do it, however, under limited circumstances.

Any number of commercial products offer single-speaker, single-word voice-recognition capabilities with various levels of competence. A few can handle single-speaker continuous speech with a small vocabulary, and some can process multiple-speaker discontinuous speech with limited vocabularies. But very few can handle many speakers, continuous speech, and large vocabularies.

"Speak," Typewriter

In the late 1980s, Teuvo Kohonen of the Helsinki University of Technology developed a

Kinder, Gentler Computing
BY MAUREEN CAUDILL
134

The Power of Speech
BY SUBRATA DAS AND ARTHUR NADAS
151

Even as We Speak
BY JOSEPH J. LAZZARO
165

The Ultimate User Interface
BY BOB JACOBSON
175

Resource Guide:
NATURAL I/O
187

World Radio History

voice typewriter using a combination of all available technologies: DSP, rule-based systems, and neural networks. It's this blend of the traditional and the new that made it such a success.

Using the voice typewriter, you speak into a noise-canceling microphone. The sounds you make are digitized into a 12-bit Gray Code and are sampled every 10 milliseconds, and a Fourier transform (a mathematical technique that converts time-sampled data to the frequency domain) is applied. The transform, of course, discards phase information in the signal—a weakness in this preliminary design.

The frequency-smoothed logarithms of the transformed signals are reduced in dimension to normalized 15-element vectors. A series of vector-quantizing neural networks categorize these vectors into probable phoneme-text conversions. The main neural network handles simple conversions; specialized networks process more subtle distinctions (e.g., between the sounds of \k\, \p\, and \t\) separately. A rule-based expert system then corrects mistakes and handles contextual or coarticulation problems (a coarticulation effect is one where the pronunciation of a phoneme is affected by the previous or the following phonemes; see figure 1).

The voice typewriter has achieved some remarkable results. It was tested using the most extreme speech-to-text case: multiple speakers, continuous speech, and a large vocabulary. Although the first 100 or so words from each speaker were used as training data for the neural network, the system did not have to be trained on the complete vocabulary of each speaker—only on a representative sample of words.

Under these conditions, the voice typewriter achieved between 92 percent and 97 percent accuracy in converting speech to text. Further, it was able to type the text on a system monitor with a time delay of only about a quarter of a second.

These results are not quite good enough for widespread commercial use; the voice typewriter is a little too slow and inaccurate for the average user to accept. Nevertheless, this marriage of multiple technologies into a finely crafted solution provides strong clues to how future speech solutions may be constructed.



Figure 1: *The Kohonen voice typewriter marries conventional digital signal processing with neural networks and rule-based experts to produce an excellent speech-to-text system that responds in about ¼ second with accuracy in the 92 percent to 97 percent range.*

BYTE ACTION SUMMARY

Finally, there are easier ways to interact with your computer. With the coming of natural I/O technologies—innovative GUIs, better speech I/O, and novel interfaces—your computer will do more of the work for you.

Say What You Mean

Although great strides have been made in speech-to-text conversions, the ability to convert sounds to characters doesn't mean you can construct a system that comprehends words. Solving this essential piece of the puzzle falls into the realm of NLP.

NLP is probably the most difficult challenge that AI researchers face. If they can build devices that truly understand human language—natural language—they will have a powerful tool that will open the way for breakthroughs in other areas.

NLP involves a series of issues that begins with straightforward syntactical analysis of a sentence parsing and continues with semantic analysis, in which the structures identified in parsing are interpreted as pertaining to objects in the known environment. Once these steps are complete, each sentence has to be correlated with the entire conversational history.

The challenges of producing NLP systems are enormous, and research is going on in many areas. The greatest successes have been in the realm of syntactical and semantic processing in highly restricted knowledge domains (see the text box "Giving Feeling to Speech" on page 168).

Scripts and Frames

Two basic components of NLP, context correlation and pragmatic interpretation, are far less developed than semantic and syntactic parsing. Each of these basic components requires access to one or more databases that contain extensive knowledge about the world; thus, knowledge representation becomes a critical issue.

One classic technique for storing such knowledge is a *script*, which is an environment in which actors and objects have stereotypical roles that are correlated with objects in a sentence. Semantic parsing associates words with these stereotypical notions and can use the known roles in the stereotype to reveal the meaning of the sentence.

A restaurant script, for instance, might contain roles for the waiter and the diner, as well as the associated actions (e.g., reading a menu, ordering a meal, or serving a meal) of the appropriate actors. People mentioned in a sentence who look at or receive a menu might be assigned the role of diners. The comprehension/reason for their visit to the restaurant (i.e., hunger) would be coupled with the probable aftermath of having eaten food (a satisfied appetite and a smaller amount of money).

Another common way of representing knowledge is by using a frame system. In this scenario, each object has associated inheritable properties and attributes. These individual frames are linked as nodes in a directed graph structure (i.e., a semantic network) that illustrates the relationships between the frames. Usually systems identified as *frame-based* have more organization than those labeled *semantic networks*, but the general characteristics of both are the same.

AI researchers have recently realized that cooperating processors can achieve more, faster, than any one processor. As a result, many more NLP systems are being implemented using parallel architectures—preferably on parallel hardware (e.g., hypercubes or transputers). However, using multitasking operating systems provides limited parallel performance.

Interprocess communication is handled most frequently by the *blackboard* method, a technique that allows independent processing modules to post information in a common area (i.e., a blackboard) for other modules to access. Alternatively, message-passing systems can direct information to

World Radio History

Music: A Natural Link to Our Emotional Selves

TOD MACHOVER

Many of us believe that the most significant element missing from computers is emotion. One of the ways people convey information is through emotional content. Because music is an important way people communicate emotions, why not use it to interface with our computers?

New Ways to Use an Old Friend

People often think of music as a pleasant enhancement to their everyday lives. They listen to music on the radio while driving a car, on a Walkman while exercising, as a soundtrack of a motion picture, and as soothing ambience while dining or reading.

Various domains of research are transforming the way people learn, perform, listen to, and understand music—the way they naturally integrate it into their lives. These changes suggest that music may soon assume a more central role in our lives.

Researchers are developing a new generation of musical instruments intended to combine virtuosic performance and intelligent computer monitoring. For instance, the MIT Media Lab's hyperinstrument project, which I've directed since 1986, has developed techniques that allow musicians to use their skills on a traditional acoustic instrument to control many simultaneous layers of computer sound. Recently, researchers at the media lab developed a hypercello for the artist Yo-Yo Ma.

A hyperinstrument is a computer simulation of a musical instrument that goes beyond the capability of the real instrument it's based on. Hyperinstruments are intended to greatly expand a human's control of the instrument and the sound it produces. Few other human skills involve such direct and natural translation of mental concepts into physical movement. Hyperinstruments provide examples of the future of human-computer interface devices.

In their design of hyperinstruments, researchers are trying to develop a purely musical interface: to have the control information transmitted from the user to the computer (and vice versa) either through the natural gestures of the musical performance or through the music itself. This model is important because music seems to represent an abstract outline of people's psychological states.

Although most hyperinstruments are designed for skillful musicians, examples of similar technology are surfacing in applications for music students and music lovers. Researchers are developing systems that will allow people to learn to play instruments, to conduct a virtual orchestra at home, or to learn about musical structure through interactive video games.

The Role of Technology

Ideas such as these bring up important philosophical questions: Should technology encourage creativity or simulate it? Should human-computer interfaces enable everyone to perform certain difficult tasks equally well (serving a kind of prosthetic or compensatory function), or should they allow individual differences to produce different results?

My own work has led me to believe that technology should always promote individualism. Natural applications of technology should permit people to use their skills to control and shape uncharted expressive regions. Certainly, new possibilities discovered through increasingly natural uses of technology should stimulate individuals to master new skills. Musical models truly can help people create new and increasingly natural tools—that is, if they listen carefully.

Tod Machover is an associate professor of music and media at the MIT Media Lab (Cambridge, MA) and director of the lab's experimental media facility. He is a pioneer in the development of hyperinstruments, and his recordings have won many awards both in the U.S. and internationally. You can reach him on BIX c/o "editors" or on Internet as tod@media-lab.mit.edu.

specific modules for action. The blackboard approach was used by L. Erman in the Hearsay II and Hearsay III speech-recognition systems.

In Hearsay II, each independent processing module contains semantic or syntactic information about the language. The blackboard posts hypotheses about the meaning of a particular sentence organized along two axes: time and processing level. A control system supervises the modules to improve the likelihood of success.

On activation (as determined by the control system), each module examines the state of the blackboard and either modifies the existing hypothesis or writes a new one. When it completes its task, another module performs the same procedure. Specific situational triggers determine when each module should be activated.

Some of the latest NLP systems use neural-network or fuzzy-logic technologies to enhance these AI approaches. In particular, researchers are considering the use of neural networks to implement semantic networks and frames (as well as other directed acyclical graph applications). Fuzzy logic is useful in implementing semantic grammar and in coping with certain knowledge-representation problems.

Hearing It Talk

Converting text to natural-sounding speech is one of the functions of natural I/O. You may already have encountered applications of speech-output technology in automated voice mail, telephone directory assistance, and over-the-phone banking systems. And you may have listened to

World Radio History



Figure 2: *The hierarchical neocognitron can recognize handwritten numerals. Each processing stage contains two layers of neurodes: One observes the previous stage's output, and the other provides limited translational independence of the image. Each successive stage detects higher-level features in the input image; the last stage makes the final character determination.*

digitized music output (e.g., background music) from devices such as answering machines and voice-mail systems.

The most natural-sounding text-to-speech systems available use digitized and edited human-voice recordings combined with pitch, intonation, and speed controls to generate fluent sentences. Individual phonemes and combinations of phonemes are recorded and edited for use as needed (see the text box "Toward Continuous-Speech Recognition" on page 158).

Natural-sounding speech is not easy to achieve because word intonation depends to a great extent on the context and meaning of what you say. English has many words that sound alike but have different meanings (e.g., *read*, which can sound like either *red* or *reed*), depending on the context. Further, for many speech-output applications, such as telephone directory assistance or automated banking, the text contains abbreviations, telephone numbers, and other nonword information. Thus, a good speech-generation system must perform some of the same syntactical and semantic processing that NLP systems do.

Once the system translates the text into the appropriate phonetics, it must convert these tokens to specific phonemes that the speech synthesizer can process. But this process can result in an atonal, artificial-sounding output unless the phonemes are further manipulated.

Individual phonemes are not the only factors that make speech sound natural. The transitions between phonemes add a natural flow to what you say. In addition, phonemes in human speech have varying durations in different words and sentences.

To compensate for these effects, many good text-to-speech systems use a rule-based system to help them determine the correct parameters for each sentence. The rules are based on the sentence structure of the message, and they help provide a humanlike sound.

Emotional Highs

Natural I/O deals with human emotions. One of the key ways humans express their feelings is through music. Computers of the future may have to accept, understand, and generate music to participate fully in this type of communication (see the text box "Music: A Natural Link to Our Emotional Selves" on page 137).

Many researchers have developed music-generation systems, using a wide variety of techniques. One example illustrates how such systems can learn to compose their own music.

Teuvo Kohonen began development of a unique music-composition system by analyzing the works of about two dozen composers, from Bach to Beethoven to Brahms. Out of these analyses, he created a collection of grammars that describe how each composer used notes, chords, and themes.

Kohonen trained a series of neural networks with these grammars; some trained on the grammar of only one composer, and others received training on grammars from two or more composers. Kohonen set up the networks so that they were given signals after training (the details of which Kohonen has kept private) that caused the networks to compose music in the style of a composer it learned from.

The music composed by the networks trained on one composer's grammar is fresh and pleasing. The music generated by networks trained on multiple composers, however, is extremely unusual and extraordinarily interesting, sounding much like a collaboration between, say, Mozart and Bach, or Brahms and Beethoven. Kohonen even has one network trained on all the grammars. That network generates an oddly atonal, quite modernistic music that has a peculiar appeal of its own.

This and other music-synthesis systems can provide computers with a range of emotional response, which soon may well match humans' natural expressiveness.

Reading Your Writing

As you consider the pen and pad in your Big Apple system, it occurs to you that people not only talk to each other, they also write notes. Handwriting recognition is another key form of natural input.

Using a keyboard is a skill that many people never acquire. But most children are taught to print and write. Thus, a computer that recognizes your handwriting is more natural than one that requires you to type in your commands.

Generally, there are two methods by which a system can recognize handwriting. One method is *dynamic recognition*, a process in which the system notes stroke sequences and uses that information to identify the characters. For example, a system might distinguish a capital *E* from a capital *B* in part by the order in which you make the character's strokes. Alternatively, you can use *static recognition*, a technique in which the system only receives the image of the finished character.

Static recognition can be more difficult than dynamic recognition because there is less information available to identify the letter you have written. Stroke order often gives clues to where each character starts and ends—clues that are missing in a static image of the final character. This problem, called *character segmentation*, is probably the most significant challenge faced when constructing a handwriting-recognition system.

Before they develop a handwriting-recognition system, vendors must decide if

World Radio History

they want it to recognize cursive writing as well as printed text. Most commercial systems process only printed letters.

Handwritten characters do not have a fixed size or position, and they can overlap each other in the field of view. They can be translated, rotated, misshapen, or incomplete—all of which makes it hard for the system to recognize the characters.

Neural Networks That Read

Researchers and developers have used a variety of neural-network algorithms to attack the reading problem, from the Reduced Coulomb Energy algorithm to backpropagation networks to the neocognitron (which was developed by Kunihiko Fukushima of Osaka University). A backpropagation network iteratively learns to recognize characters by adjusting the network's weighted connections using backpropagated errors. The neocognitron is a complex hierarchical series of overlapping feature detectors that identify images.

It has the ability to handle most translation and distortion variations with little or no preprocessing (but less success with rotated characters). It pays a price in complexity for this capability, however. A neocognitron network that can recognize only the 10 arabic numerals requires tens of thousands of connections and several layers of neurodes. To achieve such recognition capabilities, the neocognitron uses a complex hierarchical collection of *stages*. Each stage contains two layers of neurodes.

The first layer consists of neurodes that receive small overlapping segments of the image of the image-capture layer. These neurodes extract features from the image, and control neurodes embedded in the layer prevent each small group of neurodes from responding to more than one feature. The second layer of the stage provides limited translational independence by blurring the exact position of each detected feature (see figure 2).

The neocognitron idea is to extract more complex features at each progressive stage. The stages closest to the original image deal with low-level features; later stages handle more complex features and combinations of low-level features. This enables the final stage to identify the letter.

Neatness Matters

Other handwriting-recognition schemes frequently use similar designs, although the technology that is used may not be a neocognitron or even another neural-network model. As with other image-processing systems, the general rule is to determine low-level features, synthesize these into more complex features, and identify the image from this hierarchical series.

Except in the case of notepad computers, it's rarely sufficient for a handwriting system to recognize the writing of just one person. It usually must be able to process legible handwriting samples from many people. The greatest difficulty here arises from the large training sets required to provide good general recognition.

Because of this problem and the hardware limitations that require network development to be performed in software simulation, parallel network microprocessors that can learn on the chip are just now becoming available. Developing a neural-network handwriting-recognition system requires patience. Training can take weeks, and (depending on the network design used) the networks may never train well.

Taking Notes

Several products can recognize the handwriting of one person (sometimes of a few

Three Good Reasons for Choosing Videx Bar Code Readers:

Portable Durable Programmable

Proven performers in any environment–from the office to the outdoors–Videx's family of bar code readers leads the industry as the most portable, durable, programmable data collectors. Make your job easy. Keep track of time, attendance, assets, inventory, work-in-process, shipping and receiving with a bar code reader from Videx®.

TimeWand® I, DuraWand™, and TimeWand II are designed for today's world of diverse applications and demanding environments. All at prices that make them the obvious choice.

TimeWand I	**$248**
DuraWand	**$495**
TimeWand II	**$698**

For a free information kit, call Videx today at 503-758-0521.

Videx®

See us at Comdex/Spring, April 6-9, Chicago, Booth #1065, and at ID Expo, June 16-18, Chicago, Booth #358

Videx, Inc., 1105 NE Circle Blvd., Corvallis, OR 97330-4285 • 503-758-0521 • FAX 503-752-5285

Videx and TimeWand are registered trademarks and DuraWand is a trademark of Videx, Inc. **Circle 134 on Inquiry Card.**

World Radio History

people). Most notable of these are notepad computers, which use a stylus and a touch-sensitive screen that reacts to the user's handwriting. Such pen-based personal computers must interpret the user's handwriting and convert it into text, as well as process user interactions with software buttons and other interface elements selected by stylus touches.

Pen interfaces offer a number of advantages. You don't have to learn such "unnatural" skills as typing. Additionally, they are portable, and you can use them almost anywhere. Many businesses have found them to be very effective in situations where a lot of data is collected off-site and analyzed or used in other locations.

Disadvantages include having to deal with a system that holds relatively small amounts of data (handwritten text generally takes up more screen space than an equivalent amount of screen-font characters), and the necessity of training the system to recognize each person's handwriting. In addition, pen interfaces still can't reliably comprehend everyone's writing. If you scribble or use cursive writing instead of printing, there's a good chance the system won't be able to translate it correctly.

Notepad computers still make occasional errors, although at least one device uses a rule-based system to correct obvious typos and convert them into reasonable guesses. Among the extensions of these notepad computers are drawing-pad peripherals that let you draw on the screen using a similar pad-and-stylus arrangement.

The best of these drawing devices use a pressure-sensitive surface to relay relative-hand-pressure information to the drawing program. The graphics software uses that data to simulate an artist's heavy (or light) hand with a brush, a pastel, or a pencil. In the best cases, the resulting screen effects are almost indistinguishable from the variety of effects you can achieve with real-life painting tools.

Body Language

Among the other obvious forms of natural input are biological feedback devices that deal with your hand and body motions (see the text box "Feedback Devices: The Human Machine Connection" on page 148). These particular inputs can be processed either through a direct connection between you and your computer (often using fiber optics) or by having your computer watch your motions and interpret them. The first kind of input is most common today, but some systems can also use intelligent machine vision.

In a body suit or glove, you literally wear the interface. Sensors attached to the fabric of the glove measure angular motions of your fingers, hands, arms, legs, or other body parts. In one product, VPL's DataGlove, the sensors detect the dimming of light passing through a short fiber-optic cable that is aligned over two knuckles of each finger. The cable must be accurately positioned over the center of each joint so that the cable bends when you flex the finger. The bending of the fiber-optic cable causes the light passing through the cable to dim, which provides a measure of the angular deflection of that joint.

A DataGlove subsystem determines the overall position of the hand. The motion of your hand through a magnetic field induces a current in three axial coils on the back of the glove. The magnetic field is generated by three similar coils on a stationary mount within about 3 feet of the glove. A small device mounted on the wrist detects the resulting currents, and microprocessors compute the hand's

Point, Click, and Send

Aggravation Free Faxing for Millions of Windows Users

BitFax for Windows makes sending a fax as easy as printing. Point, click, and send. It's as simple as that. Fax any combination of fonts or graphics from any **Windows application** with a few clicks of a mouse.

There's no need to quit your application, or print a hard copy, or line up for the fax machine. Just point, click, and send. BitFax for Windows does the rest.

BitFax for Windows works with just about any fax/modem card. It's **compatible with all EIA Class I and Class II cards** including AT&T, AST, Best, Cardinal, NEC, TI, Sharp, Zoltrix, and Zoom to name a few.

And Say good-bye to ugly faxes. BitFax for Windows sends your image at an incredible **200 x 200** dpi resolution.

Bypassing the feeble scanner found in most fax machines means your faxes will be clear, precise, and very readable.

A special **Quick Dial** feature allows single click transmissions and the easy to use phone Book is in **standard dBase format.** Other productivity features include background auto re-dial and fax logging.

BitFax for Windows offers the freedom to send and receive documents and forms directly from your desktop, laptop, or notebook computer. It's available in German, Spanish, Italian, and **French** versions and includes an comprehensive manual. **MS/DOS and OS/2** versions are also available.

But best of all, BitFax for Windows won't cost you a fortune. The suggested list price is **$79.00** and dealers may even sell for less.

BIT Software Inc.
47987 Fremont Blvd.
Fremont, CA 94538

Tel: (510) 490-2928 Fax: (510) 490-9490

*All registered trademarks are the property of their respective owners.

Circle 47 on Inquiry Card.

World Radio History

GO FIGURE!

DesignCAD 2D. Like Leonardo da Vinci's concept of a rotary blade aircraft, it is ahead of its time, not only in technology, but also in cost and value.

DesignCAD 2D is only $349, and it has more and better features than the other CAD programs that cost $3,000!

And, if you're ready for a three dimensional CAD program, there is the state-of-the-art DesignCAD 3D . . . for only $499!

So, how come theirs costs several thousand dollars and ours costs a couple hundred? Go figure. (Why do you think the Mona Lisa is smiling like that?)

CAD/CAM Software

PC MAGAZINE EDITORS' CHOICE

PC MAGAZINE EDITORS' CHOICE

BUYERS ASSURANCE SEAL

Your product designed with DesignCAD? Let us know, and maybe we'll put it in one of our ads.

For a *free* demo disk and 16 page color brochure, contact:

American
Small Business Computers, Inc.
One American Way • Pryor, Oklahoma 74361
(918) 825-4844 • FAX (918) 825-6359

European Headquarters:
102 Rue La Fontaine • 75016 Paris, France
Phone 331 4520 6540 • FAX 331 4520 6539

Other offices in:
Athens • Barcelona • Brussels • Bucharest • Istanbul • London
Mexico City • Paris • Prague • Sao Paulo • Tokyo • Warsaw



Also Available for Macintosh

Circle 43 on Inquiry Card.

World Radio History



Figure 3: *Dickmanns and Graefe's dynamic monocular machine vision system uses custom hardware. The 286-based board has multiple processors that receive four video channels in parallel to provide a wider viewing angle. The on-board RISC controller chip performs many of the image-processing correlation computations.*

position within the field.

You must connect this system to a large computer that monitors, controls, and interprets the glove's sensor data. One of the greatest drawbacks to using this device is the physical constraints it involves. Not only must you keep your hand within range of the transmitter coils, but you usually must keep the other end of the glove's cable attached to a large computer that is not particularly portable. Other disadvantages of this kind of system lay in their inherent inaccuracies in measuring and interpreting data.

The most common body suits and gloves are made of stretchy lycra fabrics that fit tightly on the body or hand. The same fabric elasticity that enables you to put on the garment can cause the positions of the sensors relative to the joints and bones to slip and vary as you gesture and move. Some attempts have been made to overcome this predicament, including the development of Exos's Dexterous HandMaster (DHM), which replaces the glove with an external articulated cage.

To use the DHM, you put your hand inside an awkward-looking but lightweight and natural-feeling metallic articulated skeletal structure. The very nature of this design keeps the angle sensors accurately aligned with your hand and fingers. The result is more accurate input data. Furthermore, this design allows the DMH to detect side-to-side motion, using additional sensors. Overall hand position is determined using the same induced-current technology found in the DataGlove.

Other types of human-interface devices have been developed, and new, improved generic and application-specific equipment is evolving. The development of human-machine interfaces is a dynamic field, where researchers and vendors are rapidly making significant progress.

Watching You Move

Perhaps a better way to make your computer understand your gestures is to have it interpret them the same way a human would—by watching you move. There are several approaches to natural machine vision systems. In the long run, sophisticated machine vision systems may become more popular for natural I/O than the direct-wire link devices.

Interpreting gestures is not the same as identifying objects in a fixed-frame image. Hand and body movements are actions, and one way to interpret them is to use a dynamic machine vision system. Two German scientists, Ernst Dieter Dickmanns and Volker Graefe, have created such a system. Their dynamic monocular machine vision system provides human-like characteristics to interpret moving images. The ideas behind the system are both simple and profound.

First, assume the system has processed one frame of a movie and located a specific object using traditional image-processing techniques. To locate the same object in the next frame, it's not necessary to search the entire image. Because real objects don't blink in and out of existence, the most probable location of the object in the next frame is near its position in the first frame.

Using this insight, the Dickmanns and Graefe system localizes the search space for known objects from frame to frame. Rather than searching the entire image for the ball that was in the upper-right corner of the frame in the previous image, their system looks for the ball in a localized search box somewhat larger than the ball's position in the previous image. If it doesn't find the ball there, it expands the box until it locates the ball's new position. In a typical 512- by 512-pixel video camera image, this simple procedure can dramatically reduce the search time for all interesting objects in view.

Because the system is searching each local area for a specific object, its method of search can be optimized for that object. The system can scan the entire locator box using edge-detecting algorithms or another machine vision technique, or it can search the box by looking for a specific kind of surface. Dickmanns and Graefe noted that the human visual system is not perfect when exposed to objects that move rapidly in and out of view (see figure 3).

Although Dickmanns and Graefe have not applied their machine vision system to interpreting hand or body gestures, they have high hopes for its evolution into other related areas. For instance, it provides feature tracking in dynamic scenes, which is just what is needed for gesture interpretation and other applications in the natural-input environment.

A Smile Says It All

A key element missing from all these systems is the ability to perceive and interpret facial expressions. Much human communication occurs through smiles, frowns, and grimaces. The MIT Media Laboratory is a pioneer in this area of study.

Another research group—split between the University of California at San Diego and Dartmouth College—has trained neural networks to recognize facial expressions associated with specific emotions and to identify gender. These scientists used a series of standard 512- by 512-pixel video images of faces expressing emotions (e.g., anger, boredom, and astonishment). The images were reduced to 64 by 64 pixels by averaging the relative gray-scale level in each pixel and normalizing the brightness; they were then passed through a data-compression network. The I/O layers are the same size in this neural network—in this case, 64 by 64 neurodes—but the middle layer is significantly

World Radio History



Some people would knock down walls for the kind of freedom we're offering.

Remember images of the Berlin Wall falling: people dancing and singing because, for the first time in generations, they could move freely, with no restrictions?

Today, freedom-loving people have another reason to celebrate: the Super Cordless Mouse from Z-Nix. With no annoying cord to get in the way, it promises ultimate freedom of movement -- from distances up to 6' away -- to take full advantage of the Windows® revolution. And it won't discriminate between right- and left-handed users. No cord, no getting hung up around your coffee cup.

If you think we're exaggerating how much better it can be, just think back to the first time you used a remote controlled TV. In fact the Super Cordless Mouse works on similar, dependable technology, using infrared light to transmit data.

And to give you free, uninterrupted use, we designed our mouse with two rechargeable batteries. One is in the mouse, and the other is kept fully charged inside the handy mouse holder which doubles as your infrared receiver. On top of that, as the pioneer of 400 dpi resolution technology, Z-Nix delivers the industry's most developed, intelligent driver software to put special preferences for cursor control in your hands.

The Super Cordless Mouse offers both IBM and Macintosh users unsurpassed freedom and ease of use. For more information on how to get your hands on our mouse, call **(714) 629-8050.** *And let freedom ring.*

Z-NIX COMPANY, INC.
211 Erie Street, Pomona, CA 91768
No Strings Attached.

Circle 142 on Inquiry Card.

smaller. The idea is to train the output layer to reproduce the input image after it has passed through the small middle layer.

Once the data-compression system was able to accurately reproduce the original images, each image was passed through the network, and the resulting response vectors of the middle-layer neurodes were extracted. These compressed vectors became the inputs to a second two-layer network, which identified the emotion expressed by the person in the image.

The scientists achieved good research results. The neural networks were able to correctly identify most of the portrayed emotions, and when the network erred, the mistakes were usually similar to those human judges made on the same photos. In particular, the network more often confused negative emotions (e.g., anger, boredom, and misery) than positive ones (e.g., astonishment, delight, and pleasure). These results are consistent with those derived in human psychological tests.

Given an expanded, enhanced version of this technology, it is conceivable that your Big Apple computer may one day be able to tell when you're feeling blue and offer a cheery joke to lighten your day.

Reading Your Mind

The Big Apple system you purchase in 1993 includes a headband for you to wear, which provides yet another form of natural input: It can read your mind. You wear the headband (or skullcap, depending on design) so that the computer can monitor your brain waves and do what you mean instead of what you say.

Prototype telepathic controllers have already been constructed at the Nippon Telegraph & Telephone labs in Japan and at Stanford University in the U.S. The devices that users wear on their heads can be as simple as a headband or as complex as a lycra helmet. Sensors attached to the device detect the user's brain waves, just as an electroencephalograph detects brain waves (an EEG was the basis for many of the prototypes). The telepathic controllers usually transmitted a few dozen signals to a neural network for interpretation.

The neural networks train as a user concentrates on specific word commands, and the thoughts generate characteristic brainwave variations. Researchers are just beginning to learn how thoughts affect brainwave variations.

One or more neural networks interpret the signals and translate them into controlling commands. In one prototype system, a user was asked to concentrate on the words *left*, *right*, *up*, and *down*. The neural network (usually a back-propagation network) learned to interpret the brainwave characteristics of each word, and it associated them with the appropriate control commands for a joystick. The ultimate result: The joystick moved as a direct response to the user's thoughts.

Several problems must be overcome before this technology becomes part of any commercial product: ensuring the precise positioning of the sensors on the head, shortening the response time of the system, and avoiding the necessity of training the system for each user. Also, it isn't clear how hard you must concentrate on a word to provide an adequate signal for the system to reliably detect.

Ubiquitous Computing

Your Big Apple computer is only one part of what has been termed *ubiquitous computing*. What this term means is that smaller, faster, cheaper, and smarter computers will become essential components of every

Attention U.S. BYTE Subscribers

Watch for the next BYTE DECK mailing that will be arriving in your mailbox soon!

Use this as a fast, convenient tool to purchase computer products and services. It's loaded with essential hardware and software products that you should be aware of when making your buying decisions. . .and it's absolutely FREE!

If you have a computer product or service, and would like to reach 275,000 influential BYTE magazine subscribers, please give Ed Ware a call today at (603) 924-2596.

BYTE DECK



Here's what a BYTE Deck advertiser has to say:

"Ten years ago we advertised in the very first BYTE Deck—the number of sales leads we received was enormous! The BYTE Deck was so successful for us, that we have continued to use it over the past ten years!"

Lisa Tarpoff, Marketing Manager, Heath Company, Benton Harbor, MI

World Radio History

"I can't believe it's not UNIX."

–Sean Fulton, UNIX Today!

Take it from the critics, Coherent is so close to UNIX, you won't believe your eyes. Or the price.

"Mark Williams Co. seems to have mastered the art of illusion; Coherent comes so fully qualified as a UNIX clone, you find yourself thinking 'I can't believe it's not UNIX.' "
–Sean Fulton, UNIX Today!, November 26, 1990

"...(Coherent) may be the best thing that has happened to UNIX yet."
–William Zachmann, PC Week, November 5, 1990

"If you want to come as close as you can to real UNIX for a low price, COHERENT can't be beat."
–Warren Keuffel, Computer Language Magazine, November 1990

"If you want a UNIX-like development and learning system for less than $100...I don't see how you can go wrong with Coherent."
–David Fiedler, BYTE Magazine, November 1990

OVER 30,000 USERS, AND MORE EVERY DAY!

Why is Coherent now the world's best-selling UNIX clone?

	MWC COHERENT Version 3.2	SCO XENIX 286 Version 2.3.2.
No. of Manuals	1	8
No. of Disks	5	21
Kernel Size	64K	198K
Install Time	20-30 min.	3-4 hours
Suggested Disk Space	10 meg	30 meg
Min. Memory Required	640K	1-2 meg
Performance*	38.7 sec	100.3 sec
Price	$99.95	$1495.00

*Byte Exec benchmark, 1000 iterations on 20 MHZ 386. Hardware requirements: 1.2 meg 5¼" or 1.4 meg 3½" floppy, and hard disk.

NEW RELEASE 3.2

$99.95*

Because like the original UNIX, Coherent is a powerful, multi-user, multi-tasking development system with a complete UNIX-compatible kernel and C compiler.

Features include Lex and Yacc, a vi editor, SCSI support and UUCP capabilities.

And Coherent comes with a full set of over 200 UNIX commands including text processing, program development, administrative and maintenance functions. All of it fully documented in our highly acclaimed 1200 page manual.

WHAT UNIX WAS MEANT TO BE.

Unlike current versions of UNIX, Coherent is lean and efficient. Small and beautifully powerful, the way UNIX was originally designed.

Coherent runs on affordable 286 as well as 386 and 486 based IBM-PCs and compatibles with space to spare. Enough space to keep DOS co-residing on your hard disk.

And it's so fast to install, so fast to learn and just so fast, Coherent leaves UNIX in the dust.

HARD TO BELIEVE? IT KEEPS GETTING BETTER.

Like Coherent, all Mark Williams products are incredible values. Including regular updates with new and enhanced features. Our write-your-own device driver kit. And COHware, contributed software on diskette.

There's also on-going free technical support via telephone. An active user network and a UUCP Bulletin Board System. *Plus, with our new 3.2 release:*

- A new Korn shell with sophisticated command-line editing.
- Postscript and PCL support for troff adding access to hundreds of new fonts.
- Improved UUCP support.
- International keyboard and character set support.

TAKE 60 DAYS TO CONVINCE YOURSELF.

Will you agree with the critics and Coherent's 25,000-plus users?

Try it. And if you don't think Coherent is everything you ever wanted in UNIX, we'll refund your money. No problem. No hassle.

You can't go wrong. So get to a phone, FAX or mailbox now and order Coherent today. At $99.95, it's unbelievable.

1-800-MARK WMS

(1-800-627-5967 or 1-708-291-6700)
FAX: 1-708-291-6750
60-DAY MONEY BACK GUARANTEE!

Mark Williams Company
60 Revere Drive
Northbrook, IL 60062

*Plus shipping and handling. Coherent is a trademark of Mark Williams Company. UNIX is a trademark of AT&T. XENIX is a trademark of Microsoft.

Distributors: Australia (07) 266-2270, Czechoslovakia 632-62877, Denmark 42-88-72-49, Finland 47-871-201, France (1) 46-72-80-74, Germany (0511) 53-72-95/(030) 313-7015, Norway 211-0950, Singapore 336-0188, Sweden (0) 660-192-90.

World Radio History

item you deal with every day.

When this environment becomes commonplace, ordinary items will naturally adapt to you instead of your having to unnaturally adapt to them. You will become so used to this way of interacting with inanimate objects that you won't realize there is a computer inside them.

Xerox Palo Alto Research Center scientist Mark Weiser envisions such a day arriving perhaps as soon as the turn of the century. The scientists in his lab foresee computers embedded in objects at three different scales: inch-scale, foot-scale, and yard-scale. Inch-scale computers include microprocessors buried inside everything from identification badges to electronic chalk to paperless notes. These systems would connect via infrared links to other computers in each room of your home or in your office.

A room will contain countless small computers, none of which needs to be particularly smart. But when they are massively linked via wireless channels, your house or office becomes a place where electronic chalk writes on a yard-scale blackboard and your inch-scale coffee-machine computer asks if you want it to start your morning brew.

Note that many of these computers need recognize only "yes" and "no"; they do not need to understand language. To you, these devices operate as naturally as they always have, except that now your bulletin board displays information from across the country and your identification badge forwards your calls without any effort on your part.

Today's operating systems and networks, however, can't handle the loads needed to deal with the hundreds of computers that make up your ubiquitously computerized world. To implement this notion, we will have to solve significant problems in software and communications.

For example, operating systems will have to deal with hardware configurations that literally walk out of (or into) the system. And what happens when the window of an application has to move from computer to computer as you walk through a building? We must also enhance our networking technology so that we can seamlessly integrate wireless and hard-wired systems and cope with system configurations that change in the blink of an eye.

The World as You Know It

The last elements of your new Big Apple computer are the helmet and the goggles, with their wraparound three-dimensional display. These devices provide the ultimate in natural I/O—a virtual-reality environment (VR is an artificially generated domain in which you can experience and interact with a complete 3-D world).

The best-known example of this type of virtual space is often portrayed on "Star Trek: The Next Generation" in the Enterprise's holodeck. Simply by programming the computer, crew members can create the London of Sherlock Holmes's time, the Genesis planet, and any other place or time— real or imaginary.

Although the holodeck is fictional, simpler VR systems are already very real. Some of the first impressive VRs were the flight simulators used to train pilots. Using this technology, pilots can experience takeoffs and landings, enjoy calm flights, and deal with emergencies. Through practice, they learn to handle airplanes skillfully in every kind of situation.

A good VR system uses some or most of the technologies I've discussed, but it adds at least one more: realistic, often 3-D

Attention U.S. BYTE Subscribers

Watch for the next BYTE DECK mailing that will be arriving in your mailbox soon!

Use this as a fast, convenient tool to purchase computer products and services. It's loaded with essential hardware and software products that you should be aware of when making your buying decisions. . .and it's absolutely FREE!

If you have a computer product or service, and would like to reach 275,000 influential BYTE magazine subscribers, please give Ed Ware a call today at (603) 924-2596.

BYTE DECK



Here's what a BYTE Deck advertiser has to say:

"Ten years ago we advertised in the very first BYTE Deck—the number of sales leads we received was enormous! The BYTE Deck was so successful for us, that we have continued to use it over the past ten years!"

Lisa Tarpoff, Marketing Manager, Heath Company, Benton Harbor, MI

World Radio History



T560i

Come A Little Closer

Yes, it displays images that crisp. Yes, it does conform to the strict new Swedish MPR II *and* TCO guidelines, the world's toughest VLF and ELF emission standards. Yes, it does have an *intelligent* front control panel. Yes, it is a NANAO monitor. And the closer you get, the better we look.

T660i

Take a close look at the increased clarity and brightness of Trinitron technology through graphic applications such as CAD, Desktop Publishing and Windows, and see their true colors.

With flicker-free 1280 x 1024 ultra high resolution and .26mm trio pitch, the 17-inch FLEXSCAN T560i gives you more work space without sacrificing desk space. For those who prefer a larger work area, the FLEXSCAN T660i's 20-inch screen size is ideal.

With the innovation and ergonomics of NANAO's FLEXSCAN T-Series monitors, no other monitor can come close. That's why the T560i won the **1991 BYTE AWARD OF DISTINCTION.**

1991 BYTE AWARD OF DISTINCTION

Take a closer look at your nearest NANAO dealer today, or for more information call NANAO.

NANAO®

1-800-800-5202

1-310-325-5202 (CA)

Fax: 1-310-530-1679

Trinitron, Windows and FLEXSCAN are trademarks of their respective companies. "Satellite" graphic images created by Jerry D. Flynn, Design Engineer, Cocoa Beach, FL. "Lunar Landing" created by Design Visualization Group, McDonnell Douglas Space Systems Company

Circle 18 on Inquiry Card (RESELLERS: 19).

World Radio History

Feedback Devices: The Human Machine Connection

BETH MARCUS

Imagine trying to pick a flower with one eye closed or grasp an egg wearing heavy gloves. That's precisely what we're doing in most computer applications. The link between the human and the computer can be either a barrier to productivity or a natural conduit for information and experiences. Now there are new, more natural ways for you to interact with your computer. Feedback technology is ready to reduce the barriers between you and your computer.

Pick any three-dimensional application and describe what you want to accomplish with it and what kinds of variables and objects must be manipulated, and you are defining the specifications for a feedback device. The applications that feedback technology can enhance are as varied as the applications of virtual reality (VR), 3-D graphics, and high-speed computing.

One of the research institutions now investigating teleconferencing, a feedback-technology application for use in business, is AT&T Bell Laboratories. Obviously, holding teleconferences would be easier and more practical if all parties only had to *feel present* rather than travel to various sites to hold critical meetings. This is just one area in which feedback technology can play a major role.

In medicine, the applications are many, varied, and increasing. Medical students and practicing surgeons must watch videos and observe actual surgery to learn new procedures. With VR, they will have an expert lead them through a procedure, and they can practice as often as they wish.

What's Out There?

Feedback technology has been evolving concurrently with the complexity and capability of computers and applications (see figure A). Following the development of this particular process, the technology diverged into two different directions: toward general-purpose and



ILLUSTRATIONS: R. KENTON NELSON © 1992

World Radio History

special-purpose devices.

3D Trackers, a pioneering effort in the process, measure the position and orientation of a sensor-implanted object in free space. Three of the most widely used products are the Bird by Ascension, the 3Space Tracker by Polhemus, and the 3-D Mouse by Logitech.

To mold an object, manipulate something in your fingertips, or grab an object in a particular orientation, you are required to measure finger and hand motion. By identifying hand gestures and postures, whole-hand devices permit you to do that—and more. Some common examples are the VPL DataGlove, the Dexterous HandMaster (DHM) from Exos, and the Virtex Cyberglove.

Imagine inserting a key into a lock without feeling any contact or force. That's what it feels like to use most VR systems. But providing the sense of touch, motion, and force feedback is essential to accomplishing useful tasks with VR. If you take the DHM or any whole-hand sensor and add the TouchMaster (a simple tactile-feedback device), you have an inexpensive, easy-to-use method of displaying contact information. Exos has shown that tactile feedback can sometimes provide performance comparable to force feedback.

Force feedback has been around for a while in the world of robotics, but recently it has taken hold in virtual environments. Tskuba University researchers are developing a system to apply force to the thumb, two fingers, and the palm. The system is being used to preview new products.

The Sensing and Force Reflecting Exoskeleton is Exos's effort in this direction. The aim of SAFIRE is to provide accurate feedback to the free-moving hand without encumbering or restricting its movement.



Solving Specific Problems

Bell Laboratories has developed a high-performance, compact-force feedback joystick intended for engineering, business, and scientific applications. It could also provide an effective interface for disabled users. This device has been used to navigate through an electronics CAD program. It is not in production, but it could be priced within the reach of workstation or PC power users.

The MIT CAD Lab has developed a controller for sheet-metal design that is like a mouse with a hinge in the middle. Although the first prototype did not provide force feedback, that feature could easily be implemented. With evolution, this device could become a simple, low-cost method of specifying complex CAD shapes.

What's Next

Today, general-purpose feedback devices are probably not cost-effective or available enough to plug in and solve most problems. However, soon these devices will become lighter, more available, and more capable.

In the near future, equipment may exist that will resemble thin, flexible armor with embedded integrated sensor/actuator components. Then newly created techniques and technologies can be turned into a toolkit for designing application-specific devices that will effectively and economically solve problems.

Beth Marcus is president and founder of Exos (Burlington, MA), a company that manufactures medical measurement and rehabilitation equipment. You can reach her on BIX c/o "editors" or on Internet as bam@media-lab.media.mit.edu.

World Radio History

graphical computer output—natural output, if you like—to make the experience look and feel correct and complete. VR can also involve the use of data gloves and body suits, NLP, and sound generation. Some systems, like Autodesk, interface a stationary bicycle to the system so that you appear to pedal your way through a virtual world.

Because VR makes use of a combination of emerging technologies, it makes certain factors more important—for example, the key issue of *response speed*. This term refers to the speed at which the system can receive and interpret your input—whether it may be gesture, handwriting, speech, or thoughts—and react to that input by generating an appropriate output. Again, this output may be sound (e.g., speech, music, and sound effects) as well as text display or graphics. The response can also be a combination of some or all of these.

But don't confuse response speed with the raw sampling rate of each device. For example, the hand-tracking technology that some data gloves use is able to check the position of a hand approximately 60 times a second. However, internal processing performed by the tracker creates a lag of ¼ to ½ second between the input and when the information reaches the master computer. Therefore, there is a discernible delay between what you do and what you see and hear the system do in response.

Another yet-to-be-resolved issue concerns your navigation and manipulation of virtual objects. The system must have prior detailed knowledge of how objects behave in the constraints of the virtual world they inhabit. If, for instance, you attempt to walk through a solid wall or into an empty space, your VR system should provide you with appropriate feedback to inform you that such movements are not acceptable—unless, of course, the VR is a fantasy world with walls you really can walk through.

If you reach for an object, the visual display must not only show you picking it up but also provide some resistance feedback (via the glove) that makes you feel the weight of the object in your hand. Today's technology is still perfecting ways to deal with this issue, but active research and vendor efforts are now under way to provide you with sophisticated feedback mechanisms.

The virtual-world technologies exemplified by the Big Apple computer are very much a reality today. VPL (Redwood City, CA) has just brought its Microcosm VR system to market. Selling for less than $60,000, Microcosm includes a top-of-the-line Mac Quadra, 3-D authoring software, a helmet with goggles for 3-D viewing and audio, and a glove to control the system. Using the Microcosm, you can tour computer-generated worlds and structures and even pick up objects you find there.

Natural I/O encompasses technologies that range from the here and now to the blue-sky future. One thing is certain: When you purchase that Big Apple a few years from now, you'll find that interacting with it will be vastly different from interacting with today's computers. You may well experience your system rather than use it. ■

Maureen Caudill is a consultant based in San Diego, California, the author of the forthcoming book In Our Own Image, *and the coauthor of* Understanding Neural Networks: Computer Explorations, *which is due to be published soon. She has written dozens of articles and papers in technical journals. You can reach her on BIX c/o "editors."*

Put an end to software piracy!

Meet the growing family of security keys from Software Security.

Each one a specialist at enforcing your license agreement in virtually any user environment you can think of. Whether it's DOS, UNIX, Macintosh or OS/2...whether it's a single user installation or a LAN.

Simply connect the appropriate key to a single user computer, or a non-dedicated file server in a network, and you control all access to your protected application.

Users, however, won't even know it's there. The keys are transparent and won't impact software functionality or the ability to make back up copies. Normal node and LAN operations are unaffected.

Simple. Unassuming. Ever vigilant. Easy to incorporate into your application package. And quite possibly the most profitable hardware investment a software developer can make.

To find out more, call: **1-800-333-0407**

IN CONNECTICUT CALL: 203-329-8870
FAX 203-329-7428
EUROPE AND UK: +44 784 43 00 60

SOFTWARE SECURITY INC
1011 High Ridge Road
Stamford, CT 06905
Proudly Made in the USA

THE ULTIMATE PROTECTION FOR SOFTWARE PUBLISHERS

COMDEX/Spring
Booth #6479

All product names are trademarks or registered trademarks of their respective holders

Circle 122 on Inquiry Card.

World Radio History

THE POWER OF SPEECH

Many people talk to their computers. Now, the computer may be listening.

SUBRATA DAS AND ARTHUR NADAS

The promise of ubiquitous automatic-speech-recognition (ASR) technology has been tempting people for two decades. Imagine your voice commands understood and obeyed and your speech transcribed automatically and instantaneously.

Today, ASR systems are used to ease or expedite many tasks. Systems that handle a small vocabulary of several hundred words or less are the most prevalent due to their ease of design. This article introduces a simple ASR configuration and cites examples of what you can do with this technology. After delving into some technical details about ASR, we will conclude by previewing some future possibilities.



Putting ASR to Use

Figure 1 shows a typical ASR configuration. The I/O interface consists of the usual assortment of devices (e.g., a monitor, a keyboard, and a mouse) but also contains a microphone for speech input. When you speak into it, the ASR system analyzes your speech, determines what you said, and displays the results on the monitor.

In addition to straight speech transcription, you can also use speech input to control or execute command functions. When entering the contents of a memo, you can create a new paragraph by uttering a command (i.e., "new paragraph"). Similarly, you can scroll up and down the screen or move the cursor using voice commands.

Ideally, an ASR system would work error-free under normal circumstances. But ASR technology is limited by the size of the vocabulary it can handle, the accuracy of its recognition, and other factors. Still, many of the applications within reach of today's technology are impressive.

continued

ILLUSTRATION: JAMES ENDICOTT © 1992

World Radio History



Figure 1: *To an ASR system, a microphone is simply another input device for a computer system.*

Consider an ASR-based medical reporting system. Promptly after examining an x-ray image, a radiologist normally must prepare a written report for the referring physician and the insurance carrier. The normal procedure of dictation by the radiologist and subsequent transcription by a typist—these days using a word processor—is time-consuming, sometimes taking as long as several weeks. It's also expensive, because typists with a knowledge of medical terms command hefty salaries. Using an ASR system, a radiologist can prepare a written report directly.

ASR technology lets medical workers input specialized medical terms by using dedicated built-in vocabulary modules designed for specific tasks. Another application for such technology is hands-busy, eyes-busy situations (e.g., a voice-dialer in a car phone). Speech input is also used to get credit-card authorizations, to query databases (e.g., stock-market quotations), or to access various business information in an organization. Such querying can be done remotely by telephone or in a conversational manner, where a speech synthesizer can enunciate the computer's response. ASR also promises to enable hearing-impaired people to converse over a standard telephone line by transcribing incoming speech and to eliminate the need to use a keyboard to create text documents (see the text box "Voice-Activated Word Processing" on page 156).

Voyager, an interesting experimental prototype of a conversational system, was developed by an MIT team as part of the Defense Advanced Research Project Agency's spoken language system program. Voyager can answer interactively some questions regarding hotels, hospitals, restaurants, and other establishments in a local area. If you ask, "How far is MIT?" it verbally asks for your present location before answering your question.

The Tangora system, an experimental prototype of a voice-operated typewriter for office applications, has come out of the pioneering work of a research group headed by Frederick Jelinek at the IBM Thomas J. Watson Research Center in Yorktown Heights, New York. Its vocabulary consists of 20,000 of the most common words found in office correspondence. Its special-purpose VLSI hardware card plugs into an IBM AT, PS/2, or RISC System/6000 chassis. Demonstrated publicly on numerous occasions since 1987, this is the first large-vocabulary ASR system to operate in real time with high accuracy. One restriction is that you have to pause briefly between uttering successive words when using the system. This technology is characterized as *isolated* or *discrete* speech entry. If some sacrifice in speed and performance can be tolerated, this technology is readily extendable to a larger vocabulary or to the normal continuous manner of speech entry.

Inside ASR

To illustrate the technology that makes up an ASR system, we have chosen a typical system that can handle a large vocabulary of several thousand words. The components of such a system are illustrated in figure 2, and their functions are summarized in the text box "ASR System Component Glossary" on page 154. Later, we will examine alternative configurations.

In a typical ASR system, speech input picked up by the microphone is analyzed by the signal processor. The analysis produces a set of numbers, or features, that represent a centisecond (one one-hundredth of a second) time segment of speech. These features capture important characteristics of speech (e.g., energies in different frequency bands, similar to the energies you control with the equalizer in your stereo) in a compact form. Generated every centisecond, they constitute a vector of speech parameters.

To understand the captured features, an ASR system uses a vector quantizer and acoustic-model and language-model parameters derived through design or training. The VQ parameters are templates for classifying different speech sounds that roughly correspond to the phonemes in spoken language (e.g., the \k\, \ae\, and \t\ of the word *cat*). ASR designers obtain the templates by examining several thousand vectors of speech parameters belonging to all sound categories that they want to incorporate in the system.

The output of the VQ reflects speech input by matching the incoming vectors against stored templates to determine the sound category of each centisecond. Thus, when you say "cat" to an ASR system, you will probably produce several instances of \k\ labels, followed by some labels of \ae\ and \t\, corresponding roughly to the times it took you to pronounce these sounds. However, because no one knows how to design a perfect VQ, the output of a typical VQ usually contains labels of similar sounds interlaced with the \k\, \ae\, and \t\ labels. Thus, you may find several occurrences of \eh\ (as in the word *pet*) and \uh\ (as in *cut*) labels, which sound similar to \ae\. In addition, transitional portions of speech (i.e., where the sound changes from one phoneme to another) tend to get mislabeled because the intermediate speech-parameter vectors poorly match the templates of either the preceding or the following sound.

Matters are complicated further because you practically never say a word or a sentence twice in the same way. Usually you are unaware of such diversity because of effective compensation by the human auditory system. Because this compensation mechanism is not well understood, these variations are usually attributed to noise in the auditory system. Thus far, the most successful approach to dealing with such noise is based on the hidden Markov model (HMM) principle rooted in information theory and statistics.

An HMM consists of hidden states (S), hidden transitions between the states, and observable outputs (L) associated with the states. In ASR, you assume that each state gives rise to one or more labels, or outputs (L): Each state accounts for one or more centisecond's worth of speech data.

These models need two kinds of probabilities: transition probabilities for going from state S to state S' and output probabilities for producing the label L during such a transition. These probabilities are organized to form a transition-matrix (P||) and an output-probability matrix (||Q).

continued

BYTE ACTION SUMMARY

A computer that responds to spoken commands is no longer the stuff of science fiction. Automatic speech recognition is emerging from the research lab to radically change how we can work with computers.

World Radio History

MICROSOFT SOFTWARE DEVELOPMENT TOOLS

Windows helps FORTRAN users create bigger apps.



The Microsoft Windows graphical environment lets you have multiple windows in your FORTRAN applications. This means that you can resize and scroll input and output displays to view data...



...and to analyze data, simply cut and paste your FORTRAN output into programs such as Microsoft Excel for Windows and you can view it instantly in graphical form.

With the new Microsoft® FORTRAN Professional Development System version 5.1, your existing code taps into the power of the Microsoft Windows™ graphical environment. FORTRAN 5.1's new QuickWin library lets you develop 16-bit apps that access greater memory than ever before – breaking the 640K barrier on 286 and 386 machines.

You can use the FORTRAN QuickWin library to take advantage of multiple I/O windows, multitasking, and cut and paste. Or write FORTRAN routines called from mixed-language Windows apps. And FORTRAN 5.1 has Programmer's WorkBench, with a new CodeView® debugger and Source Browser.

To see the advantages of bigger, multi-windowed 16-bit applications, give us a call at (800) 541-1261, Department R34 and order your FORTRAN update today.

"As used herein, "DOS" refers to MS-DOS or PC-DOS operating systems. © 1991 Microsoft Corporation. All rights reserved. Printed in the U.S.A. Inside the 50 United States, call (800) 541-1261, Dept. R34; outside the 50 United States, call (206) 936-8661. Customers in Canada, call (416) 568-3503. Microsoft, MS-DOS, OS/2, CodeView and the Microsoft logo are registered trademarks and Windows and Making it all make sense *are trademarks of Microsoft Corporation.*

Key Features

- Create Windows .DLLs in FORTRAN using new or existing code.
- QuickWin Features:
  - QuickWin child windows are easily created using the OPEN statement.
  - User-defined positioning and titles for child windows.
  - Automatically generated scroll bars for output that extends past a single screen.
- CodeView debugger supports DOS*, Windows-based and OS/2® applications.
- Extended CodeView debugger for large DOS programs.
- Complete online documentation for the FORTRAN language and all compile and link switches.
- DOS and OS/2 run-time libraries are compatible with other Microsoft languages.
- Floating-point support includes co-processor, emulation, and alternate math libraries.
- 100% ANSI 77 compatibility and numerous IBM®, VAX® and ANSI 8X extensions.
- New BYTE keyword emulates VAX data types.
- Language Extensions include DOUBLE COMPLEX variables, precision and maxexponent inquiries.

PROGRAMMER'S TIPS

- *Use the new /MW option with the FL command to invoke the QuickWin library. For example: "FL/MW MYAPP.FOR" is all it takes to make MYAPP a Windows-based program.*
- *Use the ALLOCATE statement to dynamically size arrays and to access more than 16MB of memory on a 386.™*

Microsoft

World Radio History

ASR System Component Glossary

acoustic model—Models acoustic behavior of words by gluing together models of smaller units, such as phonemes.

decoder—Analyzes VQ label streams with the help of acoustic and language models to determine what was spoken.

interface—Contains I/O devices, including a microphone for user input to the ASR system.

language model—Models a language probabilistically based on context.

signal processor—Converts speech into a set of characteristic numbers at a regular interval, typically every one one-hundredth of a second.

vector quantizer (VQ)—Converts signal-processor output into a stream of labels identifying various sound categories.

Typically you start the model in a state at time 0. Now assume S_0 equals 1, and imagine that at times 1, 2,...T—some sequence of states $S_1, S_2,...S_T$—is traversed. The state after state S is chosen according to the probabilities in row S of the matrix P||. This is the *Markov property*. The label L produced at this time is chosen according to the probabilities in ||Q.

To apply the HMM principle to acoustic modeling in ASR, you first represent each word in the vocabulary of the system with a *baseform*, or a string of phonetic symbols specifying the cardinal pronunciation for the word. The baseform for *cat*, for example, would be \k\ \ae\ \t\. Each phonetic symbol is viewed as an HMM whose output corresponds to a part of the stream of labels received from the VQ. The model for a word is constructed by combining HMMs for the phonemes.

Speech Training

The probabilities associated with HMMs are estimated from training data obtained by reading a known script. The method for this estimation is known as the *maximum-likelihood principle*, which maximizes the probability of the data as the statistical parameters of the assumed HMMs vary. The maximization is performed by an efficient iterative training procedure invented by L. E. Baum and his colleagues at the Institute of Defense Analyses, and the procedure is variously known as the Forward-Backward, Baum-Welch, or Expectation-Maximization algorithm.

The statistical parameters that an ASR system has to learn are the transition probabilities (P||) and the output probabilities (||Q) of the various models. If the hidden states were observable, this training would be very simple. The estimate of any transition probability would be the fraction of the number of times the transition occurred. Similarly, the estimate of any output probabilities would be the fraction of the number of times a particular label occurred. Because states are hidden, however, the training algorithm cannot make such straightforward extrapolations.

Training algorithms do the next-best thing—they compute these fractions using estimates of the hidden numerators and denominators. For example, a typical training algorithm might consist of the following steps:

1. *Initialization.* Fix reasonable initial values for each of the transition and output probabilities.
2. *Expectation.* Using the last estimates of all probabilities, compute the expected value of all counts of numerators and denominators.
3. *Reestimation.* Reestimate each probability as ratios of the expected values in the expectation step.
4. *Iteration.* Jump to the expectation step or stop.

In practice, five or six iterations of steps 2 and 3 are usually sufficient.

Because our primary modeling unit is based on phonemes, not words, the training data need not (and usually does not) contain examples of each of the thousands of words in the system's vocabulary. Only sufficient data is needed to model the 50 or so phonemes in the language.

Another component of our ASR system is the language model, which helps predict a future word based on past input words. For example, if the Shakespeare in you recites, "To be or not to," and then says "be," the ASR system should understand that you mean *be*, and not *bee* or *B*. The language model makes such decisions with the help of probabilities that reflect how often a word appears in a given context. For instance, *bi-gram* probabilities represent this context in terms of word pairs. The system precomputes probabilities by examining a body of text containing several million words.

The last component of an ASR system is the decoder, which examines the input stream of VQ labels and applies acoustic-model and language-model probabilities to convert the label stream into a sequence of words. A two-stage operation is typical. The first stage is a quick approximate search to trim down the list of potential



Figure 2: *The components of an ASR system work in synchrony to produce the best possible interpretation of speech input.*

World Radio History

The world's most advanced input device is right under your nose.

Speech Recognition

For People and their Machines.

Imagine an input device so advanced that it's not only fast, easy and reliable, it's absolutely hands-free! Imagine making your computers easier to use and your users more productive. Right now!

For the past decade, **Dragon Systems** has successfully pioneered high performance, computationally efficient, flexible **speech recognition** technology. As the world leader in PC-based **speech recognition** systems, **Dragon Systems** makes speech input genuinely practical and powerful.

With vocabularies up to 30,000 words, our systems handle everything from simple commands and data entry tasks to full scale dictation. Our revolutionary speaker adaptation dynamically learns people's voices as they use the system. This feature saves user time and maximizes performance and throughput. Automatically!

For System Designers and Integrators.

Face the future with a strategic advantage. Enhance your word processing and database applications. Breathe fire into your new visions. **Dragon Systems** can help you create the unique market advantage that sets you apart from – and ahead of – the competition.

Dragon Systems Speech Recognition

The computer interface of the 21st century, a decade early!™



For more information on our full line of developer and end-user products, call us today at 800 TALK-TYP (800-825-5897).

DRAGON SYSTEMS, INC.

320 Nevada Street, Newton, MA 02160
617-965-5200 Fax: 617-527-0372

Circle 67 on Inquiry Card.

World Radio History

Voice-Activated Word Processing

RAYMOND C. KURZWEIL

Three years ago, the only people using large-vocabulary automatic speech recognition to create written documents were technology enthusiasts, including a number of speech-recognition developers. Today, large-vocabulary ASR has moved significantly beyond these classical early adopters, and it's used by thousands of people every day to create professional reports.

These users (most of them doctors) benefit from the integration of robust large-vocabulary ASR with an expert system for creating reports in specific domains. These systems combine a free-text mode for general-purpose dictation with detailed knowledge bases (in such areas as emergency medicine, radiology, and pathology) to assist rapid dictation of structured reports.

Large-vocabulary ASR has also found acceptance by hands-impaired individuals. Products for this population have been marketed by Kurzweil Applied Intelligence (KAI), Dragon Systems, and IBM.

ASR technology has always benefitted from high processing speeds and lots of megabytes of storage, and the ongoing geometric advances in semiconductor technology have been very much in its favor. With 20-million-instruction-per-second personal computers a reality and 100-MIPS personal computers waiting in the wings, you will see continued progress in the viability of ASR over the next several years. Knowledge-base applications will continue to evolve, with applications developing outside medicine in such areas as law and financial services.

Of particular significance to the average computer user will be the emergence of viable voice-activated word processors (VAWPs) for general-purpose text creation. Key to this application is a very large vocabulary (on the order of 50,000 words), true speaker independence (i.e., the ability to recognize a user's voice without previous exposure to that voice), high accuracy, and noise immunity. Such systems will combine the ease of use and the speed advantage of dictation with the immediate inspection and error-correction power of the keyboard. Not all people have keyboard skills, but most of us readily communicate through speech.

KAI is progressing toward the VAWP. It's working on a discrete-speech ASR system with a 50,000-word vocabulary (40,000 core words and the ability to add 10,000 user-specific words) and quickly accessible knowledge of 200,000 words. The system is speaker independent for most users, although it improves its performance as it adapts to a particular user.

In a joint project with Fuji and Xerox, KAI has also developed a large-vocabulary continuous-speech system for Japanese. Because of the enormous size of the kanji character set (over 7000 symbols), the Japanese have greater difficulty than English-speaking people do in entering text by keyboard, so large-vocabulary ASR will be particularly useful with the Japanese language. Late last year in Tokyo, KAI demonstrated a research system that recognizes continuous speech in near real time and has a 20,000-word vocabulary. KAI is also adapting similar techniques toward development of a fully continuous, large-vocabulary English system.

Speech is our most powerful way of communicating, and it has long been assumed that ASR will ultimately be a ubiquitous interface between man and machine. The only question has been when suitable ASR technology would become available.

There already are thousands of users who are harnessing this technology to create most of their written documents. As a result of strides made in ASR algorithmic development and the stunning pace of the semiconductor revolution, you will see increasing acceptance of ASR as an input method in the years ahead.

Raymond C. Kurzweil is the founder, chairman, and co-CEO of Kurzweil Applied Intelligence (Waltham, MA). He has been a pioneer in the area of speech-pattern recognition since the mid-1970s. You can reach him on BIX c/o "editors."

words. The second stage is a more thorough search. The search strategy takes advantage of the stack-decoder algorithm.

The decoder computes probabilities of word strings (partial and complete sentences) and searches for the most probable complete sentence given the speech data (i.e., the string of labels produced by the VQ). The decoder maintains a stack of partial sentences, with the entries ordered from the top down in order of decreasing probability. A special end-of-sentence word must be at the end of each sentence. The stack entries are extended one word at a time, and the stack is reordered. The process stops when the top of the stack has a word string with an end-of-sentence word. This word string is the decoded sentence.

Combine all these components, and you have a user-ready ASR system. When you speak, the signal processor puts out speech-parameter vectors every centisecond. The VQ receives them and emits a stream of labels for the decoder. The decoder analyzes these labels and attempts to determine the sequence of words that you said.

Limitations of ASR

Ideally, an ASR system would have an unlimited vocabulary, allowing you to say any word that comes to mind. In reality, practical considerations limit your options. Large vocabularies tend to increase the error rate and processing time.

When the vocabulary is sufficiently small (i.e., limited to several hundred words or less), simpler systems based on dynamic programming matching are often adequate. Such systems use a matching procedure between speech-parameter vectors of two utterances that have time segments that can be deleted or extended to accommodate normal temporal variations in the utterances. To apply this matching, you ensure the beginning and the ending

World Radio History

Your favorite technical handbooks are now available in soft editions.



A new approach to math.

Introducing the Mathcad 3.1 Software System for Microsoft Windows or UNIX. It revolutionizes math by letting you zip through problems naturally and logically—because it works the way you think. And now it's even more powerful, thanks to new Electronic Handbooks.™

PC MAGAZINE EDITOR'S CHOICE
Mathcad 2.5
3-14-89 issue.
Best of '88
Best of '87

More than a number-cruncher.

With Mathcad 3.1, you type your work anywhere into the live screen—just like you'd write on a scratchpad—and Mathcad does the calculating. Updates answers when a variable changes. Even graphs in 2-D or 3-D.

Symbolic calculation capabilities let you do integrals, Taylor series, or infinite sum calculations with click-n-drag simplicity.

And when you're done, Mathcad prints out presentation-quality documents complete with equations in real math notation.

Fast electronic access to commonly used methods, formulas and diagrams.

Mathcad's new Electronic Handbooks give you instant access to the formulas, methods, diagrams and tables you rely on every day. Just open an Electronic Handbook and select your topic. They're interactive, so you can modify formulas for specific calculations. Change parameters, plots and variables, and let Mathcad automatically calculate your answers within the Handbook. Or double-click on a Handbook entry and paste it into your Mathcad document—with the correct units!



Three new optional Mathcad Electronic Handbooks* are now available, each created in conjunction with a leading publisher of technical reference handbooks:

- **Mathcad Treasury of Methods and Formulas** offers you a host of the methods, formulas and diagrams you use every day, along with interactive explanations of every feature and algorithm of Mathcad.
- **Machine Design and Analysis** from Hicks' *Standard Handbook of Engineering Calculations* from McGraw-Hill, contains more than 125 practical calculation procedures including shaft and gear mechanics, time and power to cut, drill, bore, countersink, and a lot more.
- **The CRC Materials Science and Engineering Handbook** contains more than 140 tables of data, bit-mapped illustrations, and Mathcad plots. Includes densities, melting points and crystal structures of elements, properties of ceramics and superconducting materials, and much more.

PC MAGAZINE THE BEST OF 1991 COVER STORY

Also Available:

- **Optional Applications Packs**—adaptable Mathcad templates for Electrical, Mechanical, Civil and Chemical Engineering, Statistics, Advanced Math, and Numerical Methods.
- PC DOS and Macintosh® versions also available.

Free demo disk.

For a FREE Mathcad demo disk, or upgrade information, call 1-800-MATHCAD (or 617-577-1017, Fax 617-577-8829). Or see your software dealer.

UNIX Version now available

*Electronic Handbooks require Mathcad 3.1 and Microsoft Windows 3.0 (or higher) or UNIX.

©1992 MathSoft, Inc.
TM and ® signify manufacturer's trademark or registered trademark respectively.

1-800-MATHCAD

The answer is Mathcad®

MathSoft, Inc. 201 Broadway, Cambridge, MA 02139 USA • Phone: 1-800-628-4223 • 617-577-1017 • Fax: 617-577-8829

Australia: Hearne (03) 866 1766; Belgium: SCIA 013/55 1775; Denmark: Engberg 42 25 17 77; Finland: Zenex 90-692-7677; France: ISE (1) 46 07 24 00; Germany: Softline (0 78 02) 4036; Italy: Channel 02-90091773; Japan: CRC 03-3665-9741; Netherlands: Klaasing 01620-81600; Sweden: AkademiData (018) 24 00 35; Switzerland: Redacom 032 41 01 11; U.K.. Adept Scientific (0462) 480055. In other locations, contact MathSoft, USA.

Circle 89 on Inquiry Card.

World Radio History

Toward Continuous-Speech Recognition

BART VERHAEGHE

Continuous-speech recognition on a personal computer is the use of natural, fluent speech to input text or a command (e.g., open a file). The various methods used to implement this technology are based on three primary techniques: speaker-dependent, speaker-adaptive, and speaker-independent recognition.

Many commercial products feature continuous-speech recognition, but they use only the speaker-dependent and speaker-adaptive methods. The process of training involves pronouncing words or phonemes for the computer and correcting its speech-recognition errors until it becomes familiar with your voice.

Speaker-independent recognition lets anyone use voice commands without specific training. Lernout & Hauspie Speech Products in Belgium has produced such systems for English, French, and Dutch, and it's working on Spanish, German, Italian, and Japanese versions. A system demonstrated by the company recognizes 2500 speaker-adaptive words and 200 speaker-independent words.

Speaker-independent phoneme recognition lets you easily modify the set of words to be recognized. An automatic text-to-phoneme algorithm converts words into their corresponding phonetic transcriptions. The phoneme templates are concatenated to form the new word template. Text-to-phoneme conversion is part of the linguistic processing in speech synthesis. (See "Even as We Speak" on page 165.) Companies that develop speech synthesis and speech recognition combine the two technologies for this reason.

Until now, speech recognizers could not distinguish between relevant and irrelevant information. *Word spotting*, a technique that allows users to speak fluently and naturally to a computer, helps them make this distinction. Both Bellcore and Lernout & Hauspie are developing this technique.

For example, starting an application under Windows could sound like, "Please start...euh...spreadsheet." The command is recognized as "start application spreadsheet." Word spotting allows the system to detect keywords in continuous-speech input strings; you don't have to pronounce the commands exactly or as discrete utterances. Coughing, background noise, and irrelevant words don't result in the recognition of a wrong command.

Word spotting is useful for command and control applications, although it cannot be used for the dictation of large vocabularies. The larger the vocabulary, the more complex the linguistic knowledge involved becomes. For example, transcribing "two plus two equals four" involves (among other things) distinguishing *two* from *to*, *too*, or *toe* and recognizing the difference between *four*, *for*, and *fore*. Semantic analysis calculates the highest probability of correct interpretation in the context of usage. In this example, the words *plus* and *equals* determine the correct recognition of *two* and *four*.

The future of continuous-speech recognition will be in speaker-independent continuous-speech recognition with large vocabularies. Making machines that can recognize any speech from any person, without training, is at least five to 10 years away. In the meantime, useful applications of the technology are emerging. As personal computers become more powerful and the price of digital signal processor power and memory drops, your own voice will become the ultimate input device.

Bart Verhaeghe is manager of U.S. operations at Lernout & Hauspie Speech Products. He has been working in the speech I/O field for four years and is a speaker at the American Voice Input Output Society's voice and speech technical conferences. You can reach him on BIX c/o "editors."

segments of the words remain unchanged and adjust the intermediate time segments within certain constraints to achieve an optimum match.

Recognition systems typically work much better if you input isolated words as opposed to a continuous word stream (see the text box "Toward Continuous-Speech Recognition" above). Also, speaker-dependent systems (i.e., where the VQ templates and acoustic model probabilities are tailored to each user after being trained with some of the user's speech) generally outperform speaker-independent systems (i.e., where parameters are based on a common pool of data from several speakers).

Another approach is to start with the recognizer on a speaker-independent footing and adaptively improve its performance during operation by continually modifying the parameters to suit the characteristics of the user. Language-model probabilities can also be updated to capture the composition style of the user.

In laboratory studies of speaker-dependent 20,000-word ASR systems, we typically register 98 percent word-accuracy rates with isolated-word speech input and 90 percent accuracy rates with continuously spoken utterances. Problematical factors for ASR include sounds of lip smacking, breath noise, and the "uh" and "um" sounds that many people produce unconsciously. Background noise and speech entry through a telephone line tend to degrade the performance as well.

Speech recognizers make mistakes, and you need an efficient way to correct them. This is where some human factors surface. Would you prefer to correct an error as soon as it's made or to wait until the document is complete and then proofread it?

continued

World Radio History

Coprocessor Power Tools!

No matter which coprocessor you choose, Microway's family of NDP compilers do the best job of creating globally optimized 32-bit code to drive them. Users throughout the world have found that if they want their code to run fast, there is only one choice, NDP.

We recently heard from a customer who spent over six months porting his application to extended DOS with a competing product. He discovered that his 386/387 vector routines ran a factor of two faster when they were compiled with Microway's NDP C-386. The speed gain was so large that he wrote an interface library to call the NDP routines from his human interface.

All of our compilers are available for DOS, UNIX, and XENIX driving the 387, 387EMC, 3167, 4167, and Number Smasher-860. EZWIN32 provides an easy to use 32-bit Windows environment for software development. Microway's i860 card now runs in the SUN 386i and HP-9000. Our i860 compilers are now available for the Samsung MagicStation.

No matter which Microway language or accelerator you choose, it will run faster and cooler on our 486B^{2}T, the only 486 Tower that combines elegant style with industrial grade power and cooling and the best technical support in the industry.

Microway has been serving the PC numerics community for ten years. We wish to thank all of our customers for their continued support.

For more information, please call Microway's Technical Support Dept. at (508) 746-7341

386, i486 and i860 Compilers

Our NDP family of compilers generate globally optimized, mainframe quality code that runs on the 386, i486, or i860 in protected mode under Windows, DESQview, UNIX, XENIX, SunOS, or extended DOS. The compilers address 4 gigabytes of memory while supporting the 287, 387, Weitek, and Cyrix EMC coprocessors. Applications can mix code from all four compilers and assembly language.To simplify your ports, we offer ClearView, our full-featured, windowing symbolic debugger that works with DOS versions of NDP 386 and i486 compilers.

NDP Fortran™ is a full F77 with F66 and DOD extensions that is 99% VMS compatible. Also contains new F90 features & MS compatibility.

NDP C|C++™ runs in three modes: K&R with Sys V and MS C extensions; 100% ANSI C; and C++ Release 2.1 compatible.

NDP Pascal™ is a full ANSI/IEEE Pascal, with extensions from C and BSD 4.2 Pascal.

NDP Language Pricing
NDP Fortran, C|C++, or Pascal — all products include NDP Tools except for 386|486 UNIX and XENIX.

386 DOS (includes DOS Extender) . . . $895
486 DOS (includes DOS Extender) . $1195
386|486 UNIX or XENIX $1195
i860 Compilers $1995

EZWIN32™ — Our 32-bit Windows extender runs extended versions of our 32-bit compilers under Windows, eliminating the worry about calling the Windows GUI. EZWIN32 provides a character-based environment that supports standard FORTRAN, C, C++, and Pascal I/O. Price includes one NDP 386 compiler $595

GREX 386/860 — A library of 160 lower level graphics routines (free with DOS compilers): $495
ClearView™-3/486 Symbolic Debugger: $395
NDP-CrossRef™ Our full function cross reference utility that produces comprehensive data and function listings. Available for all NDP compiler versions $195
NDP Plot™ $325
NDP/FFT™ NDP or 80x87 version . . . ea. $250
Halo Professional for 386. . . . . $595

NDP NAG™ Workstation library is a subset of the NAG mainframe libraries. Has 172 routines for differential equations and eigenvalue problems, matrix operations, fitting curves, statistics, and regression analysis . . . . . 386 Version: $895
T800 NAG for Transputers $2750

NumberSmasher-860™

Number Smasher-860 is the highest performance coprocessor card ever to run in an ISA or EISA bus or as part of a transputer system. Delivers up to 80 million floating point operations per second at 40 MHz and produces 11.8 double precision Linpack megaflops. The board comes standard with an EISA or ISA interface, 8 meg of high speed memory, and your choice of NDP Fortran, C|C++, or Pascal for the i860 running under MS-DOS, UNIX, XENIX, SunOS, or DESQview . . . . . 33 MHz: $5000
40 MHz: $6000 32 MB version: add $2500

i860 Vectorizers and Libraries

NDP NAG/860 is a Microway port of the NAG workstation library to the i860 . . . . . $1495

NDP HALO-860 includes HALO Professional and an interface library which makes HALO directly callable by the i860 . . . . . $995

860 Vectorizer includes PSR VAST-2 which converts a C or FORTRAN program into a new program which calls the Intel Vector library. Includes the Intel Vector Library and Microway's i860 Profiler $1495

860 Vector Library — Written for Intel, includes over 400 vector primitives that take advantage of the i860's cache, dual instruction mode, and pipelined multiplier accumulator. $495

NDP IMSL/860 is a Microway port of IMSL mainframe library to the 860.
Math Library: $995 Statistical Library: $995
Special Functions: $500 Complete pkg: $2000

IGL — a 3-D Graphics Pipeline that does geometry and rendering using routines which use the i860's built-in graphics hardware: $495

Kuck & Associates (KAP) Hand coded libraries for the i860. DSP and Dense Solvers require Basic Math Library which includes BLAS 1, 2 and 3: $500

- **DSP** — Over 100 routines including 1 and 2-D correlations and convolutions. Does 1024 Complex FFT in 1 msec. $250
- **Dense Array** solver package $250

SX Your AT!

FASTCache-SX/Plus™ — The "Windows Solution" — easily converts your 286 into a powerful 25 MHz 386SX by combining Microway's award winning FASTCache-SX accelerator ($299) with up to 16 megabytes of extended memory. Features a 486-style 8K internal cache from Intel and a 387SX coprocessor socket. Uses a 16-bit slot.
FASTCache-SX/Plus-25: $595 Cable: $95

486 Workstations

One of Microway's Black Towers is the ideal choice for a cost-effective desktop system, personal supercomputer, file or computation server, or an industrial PC. They come standard with two or more thermostatically controlled fans, 250 Watt motherboard power connectors, and American-manufactured industrial power supplies. Our 386 and 486 motherboards are carefully burned in and tested. Top speeds are 40 MHz for the 386 and 50 MHz for the 486. Each user can choose from a full line of high quality options to customize the workstation to his specific needs. Our 486B^{2}T was a recent *Digital Review* Target Award nominee. The base system includes a sleek, black tower case, a black tactile response keyboard, four megabytes of memory, a 250 Watt American power supply and one floppy drive. Each system is backed up by a one year warranty and the best technical support in the industry.

486B^{2}T-33	ISA	64K cache	250W	$2500
486B^{2}T-33	EISA	256K cache	250W	$3195
486B^{2}T-50	EISA	256K cache	250W	$4495
486B^3-50	EISA	256K cache	350W	$5095

Parallel Processing

Microway's ongoing R&D is based on the INMOS T800, T9000, and Intel i860. We recently achieved 90% efficiency and 132 megaflops running two i860s in parallel. Our T800 products are T9000 object compatible, making them ideal development platforms for this new superscalar RISC processor.

Quadputer™ — This board for the AT or 386 can be purchased with 1 to 4 transputers and 1 or 4 meg of memory per transputer. Two or more Quadputers can be linked together to build transputer networks . . . . . from $1845
Monoputer™ — Includes one T800 and up to 16 meg of RAM . . . . . from $1295

Math Coprocessors

WEITEK: 4167-25/33 . . . . . $750/$995
3167-20/-25/-33 . . . . . $350/ $600/ $750
mW3167 Micro Channel-25/33:from $1295
mW3167/80387 Board $200

INTEL:	**8087:** $80		**8087-2:** $115
	387-16SX: $120		**387-20SX:** $135
	387 16-33: $190		**287XL:** $80
Cyrix:	**SX16MHz:** $90		**SX20MHz:** $100
	SX25MHz: $110		**287 20MHz:** $75
	DX20 MHz: $145		**DX25 MHz:** $145
	DX33 MHz: $155		**DX40 MHz:** $185
	EMC-33 MHz: $250		**EMC-40 MHz:** $300

Micro Way

World Leader in PC Numerics

Corporate Headquarters: P.O. Box 79, Kingston, MA 02364 USA (508) 746-7341
32 High St., Kingston-Upon-Thames, U.K., 081-541-5466
USA FAX (508) 746-4678 Germany 069 75 2023 Holland 40 836455 Italy 02-74.90.749 Japan 047 423 1322

World Radio History

1	Exxon	25	Standard Oil (Ohio)	49	Consolidated Foods
2	General Motors	26	AT&T Technologies	50	Lockheed
3	Mobil	27	Boeing	51	Georgia-Pacific
4	Ford Motor	28	Dow Chemical	52	Monsanto
5	IBM	29	Allied	53	W.R. Grace
6	Texaco	30	Eastman Kodak	54	Signal Companies
7	E.I. du Pont	31	Unocal	55	Anheuser-Busch
8	Standard Oil (Ind.)	32	Goodyear	56	Nabisco Brands
9	Standard Oil of Cal.	33	Dart & Kraft	57	Johnson & Johnson
10	General Electric	34	Westinghouse Elec.	58	Coastal
11	Gulf Oil	35	Philip Morris	59	Raytheon
12	Atlantic Richfield	36	Beatrice Foods	60	Honeywell
13	Shell Oil	37	Union Carbide	61	Charter
14	Occidental Petroleum	38	Xerox	62	General Mills
15	U.S. Steel	39	Amerada Hess	63	TRW
16	Phillips Petroleum	40	Union Pacific	64	Caterpillar Tractor
17	Sun	41	General Foods	65	Aluminum Co. of Amer.
18	United Technologies	42	McDonnell Douglas	66	Sperry
19	Tenneco	43	Rockwell Int.	67	Gulf & Western Ind.
20	ITT	44	PepsiCo	68	Continental Group
21	Chrysler	45	Ashland Oil	69	Bethlehem Steel
22	Procter & Gamble	46	General Dynamics	70	Weyerhaeuser
23	R.J. Reynolds Ind.	47	3M	71	Ralston Purina
24	Getty Oil	48	Coca-Cola	72	Colgate-Palmolive

27 million Americans can't read. And guess who pays the price.

While American business is trying to stay competitive with foreign companies, it's paying an added penalty. The penalty of double-digit illiteracy.

Believe it or not, 27 million American adults can't read and write. Another 47 million are literate on only the most minimal level. That adds up to almost one third of our entire population. . .and probably a disturbing number of *your* employees.

What does illiteracy cost you? Get out your calculator. Illiterate adults make up 50%–75% of our unemployed. Every year they cost us an estimated $237 billion in lost earnings. They swell our welfare costs by $6 billion annually and diminish our tax revenues by $8 billion.

Illiteracy costs you through your community, too. It robs the place where you work and live of its resources. It undermines the potential of the people who make your products and the people who buy them. No dollar figure can be assigned to this. But over the years, this may be the costliest loss of all.

What can your company do about this? It can join in local efforts to fight illiteracy. It can volunteer company dollars and facilities for better school and tutorial programs. It can invest in a more literate community.

The first step is to call the Coalition for Literacy at **1-800-228-8813** or fill out the coupon below. Do it today. You may find it's the greatest cost-saving measure your company has ever taken.

A literate America is a good investment.

Ad Council

Coalition for Literacy

☐ I want my company to join the fight against illiteracy
Please send brochure with additional information

☐ We want to discuss funding the Coalition for Literacy
Please have a representative contact me

Name _____

Title _____

Company _____

Address _____

City _____ State _____ Zip _____

Phone _____

Please return to Coalition for Literacy
Business Division
PO Box 81826
Lincoln, NE 68501-1826

THE POWER OF SPEECH

Do you prefer to use voice commands or a keyboard and mouse to negotiate your cursor to the erroneous word? These are just a few of the questions faced by interface designers of ASR systems.

There are many other ways to design an ASR system. Signal processors in some ASR systems derive parameters (e.g., linear predictive coefficients) that attempt to capture speech characteristics in the time domain rather than in the frequency domain. If the background is noisy, a noise-adjustment scheme may be needed to maintain good system performance. Some ASR systems use speech parameters directly for acoustic modeling and decoding, bypassing the VQ step. The language model in some cases can be implemented in a more traditional linguistic framework. Another discipline under study for speech recognition is artificial neural networks.

ANNs for ASR describe x, y plots, where x is speech and y represents a range of some interesting linguistic objects (e.g., words, phonemes, and labels). Given speech x, the ANN chooses a word y. The word *neural* in ANN is derived from similarities (not to be taken too seriously) between the ANNs and the way biological neurons are connected to each other. An advantage that ANNs offer over HMMs is that any set of characteristics can be well approximated with ANNs. An advantage that HMMs offer over ANNs is better time-warping ability. The jury is still out on which technique delivers the best results.

What's Next?

Scientists are busy trying to overcome the limits of ASR technology. Projects dealing with issues such as speaker independence or adaptation, continuous speech, unlimited vocabulary, and noise immunity are under way. Commercial systems are already integrating speech recognition into everyday applications. In a related area with vast potential to augment international communication, researchers are developing techniques to automatically translate speech over the telephone from one language to another. A speech synthesizer can be used to reproduce the translated version, preferably in the user's own voice.

Based on the progress achieved over the past decade or so, we expect that these issues will be substantially resolved by the dawn of the twenty-first century. ■

Subrata Das and Arthur Nadas are researchers in the Continuous Speech Recognition Group at the IBM Thomas J. Watson Research Center (Yorktown Heights, NY). You can reach them on BIX c/o "editors" or on Internet as das@watson.ibm.com and nadas@watson.ibm.com, respectively.

World Radio History

Developers:
Lock Up Your Profits

We have the key for protecting your software profits and your copyright.

Software piracy's a crime! What it can do to a developer's profit margin is shameful. The cost of development and marketing products demands you receive the revenue you are entitled to. We have the solution.

- Custom hardware and software for each developer
- Encrypted interrogation routines and debug disablers. Over 140 language interfaces available.
- Available active read/write memory and on-board microprocessor provide the ultimate protection
- Keys for PC "compatibles," Macintosh, UNIX and RS-232C standard
- Total compatibility, reliability and end user satisfaction

We have the key. Call us for more information or a demonstration package.

1-800-843-0413

MICROPHAR

In EUROPE:
MICROPHAR, 122 Ave. Ch. De Gaulle 92200,
Neuilly-Sur-Seine, **FRANCE**, Tel: 33-1-47-38-21-21 Fax: 33-1-46-24-76-91

For Distributors in:
*BELGIUM, E2S (091 21 11 17)
*GERMANY, AUSTRIA: Microphar Gmbh (06223 - 73730)
*HUNGARY, Polyware Kft (76-22-307)
*ITALY, Siosistemi (030 24 21 074)
*POLAND, Microphar Poland (32 586 848)
*PORTUGAL, HCR (1 56 18 65)
*SCANDINAVIA, Microphar Nordic (45 53 51 70 33)
*SPAIN, Microphar España (032 37 31 05)
*SWITZERLAND, SAFE (024 21 53 86)
*THE NETHERLANDS, Infotic (015 15 88 37)
*UNITED KINGDOM, Clearsoft (091 378 91 91)

See Us At Booth W2460
WINDOWS WORLD '92
April 6-9, 1992
McCormick Place • Chicago, Illinois USA

PROTECH MARKETING, INC

9600-J Southern Pine Blvd.
Charlotte, NC 28217
Tel: 704-523-9500 FAX: 704-523-7651
Hours: Mon-Thurs: 8:30-7:00, Fri: 8:30-5:30 ET
Open late to better serve our west coast clients.
Se Habla Español

For Europe, circle 109 on Inquiry Card.

For Americas & Pacific, circle 110 on Inquiry Card.

World Radio History

How Can Northgate® Offer You A Powerful, Upgradable 486SX™ System For Only $2449?

Like The Great Sphinx, Some Phenomena May Never Be Explained.

If new technology is always the most expensive, how is it possible that Northgate brings you our latest upgradable Elegance™ ZXP™ 486SX and DX computers at such a phenomenally low cost?

Our new ZIF (Zero Insertion Force) socket lets you quickly upgrade to faster, more powerful processors – even the clock doubler chips now under development. A new chip and a flip of the lever is all it takes. Features include:

- 486SX/16MHz processor
- 4MB of RAM; expands to 32MB
- 100MB IDE hard drive
- 64K cache
- 1.2MB 5.25" and 1.44MB 3.5" floppy drives
- Space-saving 5-bay desktop case; 7-bay Vertical Power case optional
- 14" SVGA color monitor
- Northgate 101-S keyboard
- MS-DOS® 5.0, Microsoft® Windows™ 3.0 and Mouse
- DiagSoft™ QA Plus™ software
- FCC Class B Certified

You also get 24-hour, 7-day a week toll-free technical support, a limited one year parts and labor warranty with on-site service from NCR® (second and third year plans available) and overnight shipment of replacement parts at our expense. Order today and remember – our 30-day money back guarantee means you have

©Copyright Northgate Computer Systems, Inc 1992 All rights reserved Northgate, Elegance, ZXP, and the Northgate 'N' logo are U S trademarks or registered U.S. trademarks of Northgate Computer Systems 80486SX and 80486 are U S trademarks of Intel MS-DOS, Windows and Microsoft are U S trademarks or registered U S trademarks of Microsoft Corporation All other products and brand names are U S trademarks and registered U.S trademarks of their respective companies Prices shown are in U S dollars and do not include shipping/handling charges or appropriate sales taxes Offer valid in U S and Canada only Prices and specifications subject to change without notice. Northgate reserves the right to substitute components of equal or greater quality or

World Radio History



Gazing out over the shifting sands of Giza, Egypt is the Great Sphinx – one of the world's most baffling mysteries. How were the ancients able to carve its massive features over 40 centuries ago? How come the Sphinx shows extensive signs of erosion – not by wind and sand but by water? Who made the Sphinx – ancient Egyptians or a still-earlier civilization? Why was it created? And when? Although scholars continue to look for answers, the centuries-old mystery of the Great Sphinx may never be fully solved.

intel inside™

nothing to lose. And a phenomenal computing solution to gain.

Elegance ZXP 486SX/16 $2449
*Lease as low as $85.57/mo.**

Other systems as configured above

Elegance ZXP 486SX/20 $2499
*Lease as low as $86.47/mo.**

Elegance ZXP 486SX/25 $2799
*Lease as low as $96.85/mo.**

Elegance ZXP 486DX/33 $2899
*Lease as low as $100.31/mo**

Add $150 for Vertical Power case.

Call for a free Decision-Maker's Kit, complete pricing and custom configuration information.

800-345-8709

Major corporations, volume purchasers and government agencies call National Business Accounts: 800-545-6059

Charge it to your VISA, MasterCard, Discover, American Express or Northgate Big 'N' card.

NORTHGATE COMPUTER SYSTEMS, INC.

7075 Flying Cloud Drive, Eden Prairie, MN 55344

CODE B3404

performance. All items subject to availability. We support the ethical use of software. To report software copyright violations, call the Software Publishers Association's Anti-Piracy Hotline at 1-800-388-PIRA. *Monthly lease payments are based on a 36-month standard, fair market value open-ended lease. †2-60-month leasing options available for qualified businesses.

World Radio History

BEFORE PROTECTING YOUR SOFTWARE...

...against piracy and unauthorized use, make sure that your protection system has all the following qualities:

A GOOD HARDWARE KEY

Hardware-based software protection systems are now the standard worldwide. However, not all keys are the same. A good key should have all the following features:

✔ Compatibility and transparency. The key should work without any problem on your customers' computers. The user should be able to forget the key after connecting it.

✔ Unbreakable electronics. A customized ASIC (Application Specific Integrated Circuit) component should be integrated in the key. This prevents reverse engineering and makes cracking virtually impossible.

✔ A unique and inaccessible software developer's code burnt into the ASIC. (This code should not be held in the key's memory, where it can be read and altered.)

✔ A Read Write Memory inside the key should be available on demand. The memory should be writable in the field, on any PC, without any special programming equipment.

✔ Very low power consumption, enabling the key to work even under the worst power conditions, on PCs and laptops, with or without a printer.

POWERFUL SOFTWARE

Since it's practically impossible to crack or duplicate a key having all the features mentioned above, a pirate will usually go for the software linking the protected program to the plug. Therefore, check that your protection software has all of the following:

✔ A Linkable Protection Module with which calls can be made to the key from any point in the protected program.

✔ An "Envelope" installation program. Such programs enhance security while making it possible to protect a software even without its source code.

✔ Sophisticated antidebugging and encryption mechanisms.

HASP, THE PROFESSIONAL SOFTWARE PROTECTION SYSTEM, OFFERS YOU ALL THESE FEATURES AND MORE:

HASP was designed by a team of computer experts, professional cryptologists, and electrical engineers. As a result, HASP keys are supported by what is probably the best software in the market, and the HASP system has worked on every computer it has been tried on. In addition to all the features mentioned above, HASP provides:

✔ A Full Authorization System for protecting dozens of programs using only one key.

✔ A Pattern Code Security System (PCS) enabling parallel processing of multiple calls by the Linkable Protection Module.

✔ A Virus Detection option that can be incorporated in the protected program to check whether it has been infected by a virus or tampered with in any way.

✔ Operating systems supported: DOS, SCO Xenix & Unix-386, OS/2, WINDOWS, AIX, AUTOCAD, PHAR-LAP, ERGO and RATIONAL DOS Extenders.

✔ NetHASP provides full support for protecting DOS and WINDOWS software under network environments, including Novell dedicated & non-dedicated servers, Lan Manager, Lantastic, Banyan, DLink, and all NET-BIOS based LANs.

IN A TEST CARRIED OUT BY AN INDEPENDENT LAB, HASP WAS THE ONLY KEY WHICH WAS NOT BROKEN*.

AND THE BOTTOM LINE:

we offer some of the most competitive prices in the market.

During the last seven years, HASP has enabled thousands of software producers in more than 40 countries, including several Fortune 500 companies, to protect their software.

To learn more about why so many professionals have chosen HASP, please contact:

ALADDIN KNOWLEDGE SYSTEMS LTD.

15 Beit Oved St., Tel-Aviv, Israel
P.O.Box:11141 Tel-Aviv 61110
Tel: 972-3-5375795
Fax: 972-3-5375796

In North America:

ALADDIN SOFTWARE SECURITY

306 Weymouth St.,
Dix Hills, NY 11746, USA
☎ **800-223 4277**
516-586 2845
Fax: 516-586 1602

✔ **Australia** Conlab Pty. Ltd., Tel: 3 8985685, Fax: 3 8995759 ✔ **Belgium** Akkermans bvba, Tel: 3 2338826, Fax: 3 2315438
✔ **Czechoslovakia** ATLAS Ltd., Tel+Fax: 2 821280 ✔ **Denmark** SC Metric a/s, Tel: 42 804200, Fax: 42 804131
✔ **France** Logidata Intl., Tel: 50707375, Fax: 50753144 ✔ **Germany** CSS GmbH, Tel: 201 749860, Fax: 201 748644
✔ **Greece** Unibrain SA, Tel: 1 6856320, Fax: 1 6474943 ✔ **Holland** Akkermans BV, Tel: 45 241444, Fax: 45 245515 ✔ **Italy** Partner Data S.r.l., Tel: 2 33101709, Fax: 2 347564
✔ **Korea** Hanil System Inc., Tel: 2 5639161, Fax: 2 5538079 ✔ **New Zealand** Training Solutions, Tel: 4 666014, Fax: 4 697190
✔ **Poland** Systherm Tel: 061 45065, Fax: 061 324134 ✔ **Portugal** Futurmatica Lda., Tel: 1 4116269, Fax: 1 4116277
✔ **Spain** PC Hardware, Tel: 3 2493193, Fax: 3 3337497 ✔ **Switzerland** Opag AG, Tel: 61 7112245, Fax: 61 7115355

* CT Magazine, May 1990.

© Aladdin Knowledge Systems Ltd. 1985-1992

Design Ilan Peer

Circle 38 on Inquiry Card.

World Radio History

EVEN AS WE SPEAK

The use of voice synthesis delivers the world of computer information in a natural form of human communication

JOSEPH J. LAZZARO

The fax you've been waiting for all day hasn't arrived. It's six o'clock; you know it's coming—soon. You have spent many nights like this chained to your office, but tonight is different. You grab your coat and head to the car. Dinner is at seven, the kids' school play is tonight, or you have a stress headache—all good reasons why waiting around the office for a fax that could affect the rest of your career is out of the question.

After 15 minutes of sitting in traffic, you dial into your new voice-automated fax machine. You punch in your code number, and the machine replies, "I'm sorry; there are no new fax messages in your in basket." You try again 20 minutes later. The same pleasant-sounding semirobotic voice confirms there is a fax transmission addressed to you, and it reads you the message's contents as it simultaneously prints a copy of the message on your printer. No more long, lonely nights in front of the fax machine.

As personal computers continue their evolution, it's only logical that they be granted the power of the spoken word through speech synthesis. Speech synthesis is the artificial generation of the spoken word using computer-based hardware and software.

If you tend to view the development of computers in biological terms, the electronic species are gaining more flexibility as their I/O devices continue to acquire greater capabilities. If you carry this idea to its limits, the ultimate natural I/O system for a computer is voice recognition combined with voice synthesis, because it emulates our own normal communication methods.

continued



ILLUSTRATION: JAMES ENDICOTT © 1992

World Radio History

Circle 53 on Inquiry Card.

EVEN AS WE SPEAK

Climbing the Linguistic Ladder

The human species is one of the rare forms of life on this planet that can claim a spoken form of language. Our natural verbal ability has often been declared our most powerful attribute, and the biological hardware and firmware that make this possible took millions of years to evolve to their present state. Thanks to R&D performed more than a decade ago, computers have also begun their climb up the linguistic ladder.

We have a competent understanding of how to duplicate the human speech mechanism, and there are numerous voice synthesizers and software packages that are a direct result of this knowledge. The presence of dozens of speech products might lead you to believe that all the problems have been solved, but there are still areas to be colored in and refinements to be made.

The most difficult aspect of speech synthesis is that it is an attempt to replicate a human function that is not perfectly understood. Speech synthesis is not confined to generating the correct pronunciations of words in isolation. Many rules must be followed to produce correct synthetic speech. The pronunciation of a word is different if it appears at the beginning, middle, or end of a sentence. A word or phrase can be given special meaning merely by raising its pitch or volume when spoken. (See the text box "Giving Feeling to Speech" on page 168.)

Computer-based speech-synthesis systems emulate our natural-language ability with the help of megabytes of computer code and millions of instructions per second of raw processor power. With all this advanced technology, the finest voice synthesizers on the market today can still be distinguished from a human speaker by an inexperienced listener. Many speech-synthesis systems are obviously robots, sounding like computerized characters from science fiction; other systems come close to our subconscious ability to articulate.

BYTE ACTION SUMMARY

Voice output is no longer just a glitzy option for your computer. Now it's a practical method for accessing information, and there are many mature hardware and software products available to make voice output a reality.

The typical personal computer can be fitted with speech by merely adding a circuit card or external voice box and the appropriate text-to-speech software to make it all work together. There are even speech-synthesis products for laptop and notebook computers, making these portable machines efficient talkers as well. Even the GUI is starting to become verbal as speech packages designed for these systems hit the market.

Speech synthesis is valuable in a telephone environment, where video screens are not present to display information to you. Unlimited-vocabulary text-to-speech systems are important for verbalizing large, dynamic databases.

Speech is capable of verbalizing the contents of a computer screen for those unable to read because of vision or learning problems. Speech can also add life and emphasis to multimedia applications, as color text and graphics combine with natural-sounding voice output to create user-friendly applications. With all this in mind, I'll take a look at how a typical speech-synthesis system works.

Worth a Thousand Words

A speech synthesizer is essentially a dedicated microcomputer that is committed to running its text-to-speech software. It can come bundled as an internal circuit card capable of being plugged into the bus slot of most personal computers. Voice synthesizers can also be external units designed especially for serial or parallel interface ports.

Voice synthesizers contain many of the same components found in microcomputers. These include RAM for running the text-to-speech software, which is loaded into the system memory from floppy or hard disks.

The more powerful speech units include an on-board microprocessor, which provides enough computing power for their operation and takes a significant amount of pressure off the host microcomputer system. Voice synthesizers also contain digital signal processors (DSPs) to crunch the sheer bulk of numbers necessary to re-create the complex waveforms that make up human speech. The D/A converter is also a major player in many speech-synthesis products, because these dedicated chips reproduce complex waveforms based on high-speed digital signals.

The DECtalk PC is a high-end internal speech synthesizer and a self-contained microcomputer in its own right. The board is based on the previous DTC01 synthesizer and has nine different voices onboard. The heart of the system is an 80186 microprocessor, a megabyte of RAM, and

World Radio History

Circle 54 on Inquiry Card.



Introducing *OS/RAM32plus*™ for the Micro Channel™

- Provides from 2 to 128 Mbytes of fast memory.
- Works in 16 or 32 bit mode to meet your needs.
- Provides extended and expanded memory.
- Fast software and hardware for LIM 4.0 included.
- Automatic configuration for DOS, OS/2 and UNIX.
- Easy to install. Risk free guarantee. Two year warranty.
- Add a disk cache and RAM disk using OS/RAM32*plus* to get maximum performance from your computer.
- Free up low memory by moving your drivers and TSR's to OS/RAM32*plus*. We guarantee compatibility!

Call today 617-273-1818 or 1-800-234-4CEC

cec Capital Equipment Corp.
Burlington, MA. 01803

PS/2 and Micro Channel are trademarks of IBM

a Texas Instruments (TI) TMS320 DSP. The DECtalk PC can speak at a rate of 120 to 550 words per minute and contains more than 1400 letter-to-sound rules.

Street Electronics' Echo PC II is another example of an in-board speech synthesizer for AT-bus computer systems. The synthesizer has an unlimited vocabulary and comes bundled with an external speaker and text-to-speech utilities. In addition to generating speech by rule, the board can also play back digitized sound samples.

The Echo contains a TI TMS50C10 sound chip and a 2-watt audio amplifier. The board can play back 10-bit sound samples at rates of 8, 9.6, and 11 kHz. The Echo can also play back 8-bit samples at rates of 16, 19.2, and 22 kHz. The bandwidth of the Echo synthesizer is about 100 to 4500 Hz. This board is well suited for the programmer who wants to build speech applications, because it's inexpensive and well supported.

Street Electronics is about to roll out a new version of the Echo PC aimed mainly at persons with vision impairments. This synthesizer is portable and powered by a standard 9-volt battery. It's driven by a Motorola 6805 microprocessor and contains 32 KB of internal ROM. The synthesizer can be driven by any serial port capable of communications at 9600 bps.

The unit will come with a headphone, a jack, and text-to-speech software in firmware. Street Electronics hopes to sell the unit for less than $150. The company also has plans to roll out a clone of the popular Sound Blaster that is capable of performing synthesized and digitized speech functions.

The Mac has its own built-in speech hardware and software, and it was one of the first successful platforms to accomplish this feat. The Mac comes from the factory with a built-in text-to-speech program called MacInTalk, which drives the built-in speech hardware and is capable of generating an unlimited vocabulary. The new Mac platforms also come bundled with a built-in microphone, which makes it easy for developers to create custom voice applications.

The Amiga also comes out of the box with built-in speech capability, and files can easily be dropped into the voice module for reading with an unlimited vocabulary. The speech-output system for the Amiga is part of the operating system, which makes it accessible to programmers interested in incorporating speech into an application.

Speak to Me

The complex process for converting text to speech requires multiple layers of intelligence. Because speech synthesizers are dedicated microcomputers designed to produce speech, their software can be designed to run on specific boards for maximum efficiency. Speech software can also be written in languages that can easily be ported to different systems, making it possible to take advantage of different microprocessors and hardware configurations across platforms.

The software is often broken down into tasks, with each job assigned to one or more modules. These duties include normalization of the incoming text information, conversion of text to phonemes, and processing for sentence and accent stress. These modules work hand in hand, with the output of one module providing the input for the next.

Many speech systems are based on the three-tiered approach developed by Dennis Klatt at MIT. Refinements have been made to this model over the years, including stress parsing and larger dictionaries.

The first software module in a typical text-to-speech system is known as a *text normalizer*. This module is the entry point for incoming ASCII text, and it's responsible for converting the printed word into a form compatible for voice output. The text normalizer strips punctuation from the incoming text, and it converts numbers to words and changes dates to a more pronounceable format.

For example, the dollar amount $19.95 would not be verbally expressed comprehensibly in its current form. As the figure is written, it would be pronounced "dollar sign one nine point nine five," which would be difficult for a listener to comprehend. The text-normalizer software would convert this phrase to a more manageable form, such as "nineteen dollars and ninety-five cents," resulting in a more easily understood phrase.

The next module to come into play is the *lexicon*, which is responsible for stripping suffix and prefix information from incoming words. This is done to determine the root word so that it can be more easily found in a text-to-phoneme directory. If the lexicon saw the word *goodness*, it would convert it to *good*, greatly simplifying the directory search. The lexicon is useful for weeding out letter combinations that are not true words (e.g., IBM and FBI).

The subsequent program module is the *phoneme converter*, which translates the incoming text from the previous module into phonemes using a RAM-resident dictionary. A phoneme is the smallest sound byte of a language, and English contains about 40 phonemes.This dictionary simplifies the text-to-speech process greatly, because it can guide the synthesizer to perfect pronunciation for the most common words.

The next program segment is *intona-*

World Radio History

Giving Feeling to Speech

JAN ZIMMERMAN

From the subtly sarcastic voice of HAL in *2001* to the subtly sultry voice of the computer in *Star Trek: The Next Generation*, fictional computers speak as if they are your best friend—or your worst enemy. How disappointing to hear nonfictional computers speak in a scratchy voice with the monotonous pace of a marching army on a long, long trek. Thanks to market demand and advances in text-to-speech synthesis, however, the picture is changing.

The advent of hand-held devices that speak, ranging from foreign-language translators to the Bible, has created a demand for an authentic voice. Without natural-language parsing, however, these types of synthesized voices simply consist of a chorus of robots that can't carry a tune.

Parsing Improves Text-to-Speech Synthesis

Natural-language parsing is the ability to understand the underlying structure of a spoken language. It deals with the complex grammar of spoken (i.e., natural) languages, such as English and French, rather than the limited grammar of Pascal or C. Parsing is similar to diagraming sentences, as you used to do in school. With parsing, a text-to-speech synthesizer can operate on the sentence level rather than just word by word, leading to much more natural-sounding speech. (See "A Natural Solution," February BYTE.)

Words whose pronunciation changes according to their use can be handled only with a parser that "knows" how each word functions in a sentence. In the expression "Let's record that record-setting score," the stress is on the second syllable of the verb *record* but on the first syllable of the same word when it's used as a modifying noun. English has many words like this (e.g., *use*, *convict*, *invalid*).

The science of *prosody* deals with the pitch, amplitude, and duration of sounds in relation to one another. Because it varies according to the construction of a sentence, prosody provides cues that aid in understanding speech. The incorporation of prosody is less obvious, but more important, than simple stress in increasing the intelligibility of synthesized speech.

Almost all medium-priced to expensive synthesizers (e.g., Berkeley Speech Technologies' Bestspeech, Centigram Communications' CallText, or DEC's DECtalk) can raise inflection (i.e., stress) when a question mark appears. "Am I tired?" is pronounced very differently from "Am I tired!" They can also adjust pause length for commas, semicolons, and periods.

But without a parser like the one found in Emerson & Stern's Sound Bytes, it's impossible for synthesizers to adjust pause length at the end of unmarked phrases and clauses (e.g., "I would go...but I'm busy") or to change intonation when a noun is used as an adjective (e.g., "Green is my favorite color" versus "The green leaves turned yellow"). The glue words of English (e.g., articles and prepositions) are generally spoken quickly unless they are important ("I want that"). Without a parser, no way has yet been developed to determine importance. Human speakers provide all these prosodic cues unconsciously to help their listeners understand.

Natural-Language Parsing Trade-Offs

Computer parsers are not as capable as people at handling pronunciation that changes based on meaning or outside knowledge. In "I read well," the word *read* is pronounced as "red" when used in the past tense, but as "reed" when used in the present tense. The sentence alone cannot convey the writer's intention.

Parsers take up some memory and processing power, but not as much as some computationally intensive forms of synthesis. It's not parsing but the type of synthesis technology that drives the cost-versus-performance trade-off. Synthesizer prices range from $200 to $5000.

Bellcore's Orator synthesizer trades the ability to handle free text for the ability to handle names in a telephone directory, which often don't follow English phonetic rules. Some low-cost synthesizers have trouble with words such as *tough*, *through*, *though*, and *thought*, which don't follow English rules either.

What's Coming for Microcomputer Users

With more and more emphasis being placed on multimedia, you can expect PCs to have built-in sound-output capability like that already found in Mac and Next machines. The proliferation of machines and software will eventually lower the cost of high-quality synthesis, and system vendors will try to incorporate at least some parsing capability.

Get ready to buy some headphones or drive your officemates crazy. The talking computer is on the way!

Jan Zimmerman is CEO of Emerson & Stern Associates (San Diego, CA). She speaks and writes frequently on issues concerning speech and language. You can contact her on BIX c/o "editors" or on Applelink at D3881.

tion control, which is responsible for managing word and sentence pauses and pitch, and is mandatory for more believable pronunciation. This program segment bases its decisions on context and word placement. The bulk of inexpensive synthesizers don't use sophisticated intonation control, which results in a flat, monotone voice that is more difficult to understand. Many developers are focusing their attention on this module, because proper intonation is fundamental to more natural-sounding speech with less robotic tones.

Sound Bytes from Emerson & Stern Associates (San Diego, CA) is an example of speech software that is geared toward parsing for intonation and stress control. The software runs on the Mac platforms.

World Radio History



Texas Instruments' top executives get to the bottom line instantly with Microsoft client-server computing.

Every business wants to know the bottom line. Thanks to Microsoft's client-server computing solution, Texas Instruments' upper management sees it instantly. Right on their own PCs.

"PEOPLE DON'T JUST WANT ACCESS TO DATA. THEY WANT TO CREATE IT, CHANGE IT AND MAKE IT THEIR OWN."

They can also track inventory, monitor sales, check raw material prices and find other information needed to make decisions.

And that's how Jim Powell likes it. Because as Texas Instruments' Manager of Distributed Information Services, it's his job to provide his co-workers with the computer support they need. And with Microsoft client-server computing, his job is a lot easier.

Two years ago, a lot of people at Texas Instruments found the mainframes difficult to use and inflexible.

So Jim started to look at possible solutions. He wanted to find a system that would utilize their existing equipment, allow MIS to rapidly develop applications, and provide the end users with an easy-to-use interface.

He discovered Microsoft client-server computing was just what Texas Instruments needed.

The Windows™ environment was placed on the desktops and Microsoft® LAN Manager and SQL Server were integrated into the system.

There were dividends right away.

Jim's group was able to quickly develop client-server applications, like the executive decision support system. Which means the users didn't have to wait forever to get the computer support they

"NOW I CAN PUT APPLICATIONS INTO THE HANDS OF PEOPLE THAT WOULDN'T HAVE GOTTEN THEM OTHERWISE."

needed. And with Windows, the information on the mainframes was easier to access.

Simply put, Jim was able to get the right information, to the right people, the right way.

If you'd like a case study on Texas Instruments' migration to Microsoft's client-server solution, call us at (800) 992-3675, Dept. X32. We'll tell you how you can profit from their experience.

Microsoft

© 1992 Microsoft Corporation. All rights reserved. Printed in the U.S.A. Offer good only in the 50 United States. In the United States, call (800) 992-3675, Dept. X32. For information only: In Canada, call (800) 563-9048. Outside the United States and Canada call (206) 936-8661. Microsoft is a registered trademark and Windows is a trademark of Microsoft Corporation.

World Radio History

Circle 84 on Inquiry Card (RESELLERS: 85).

Kingston's memory upgrade products offer a variety of solutions for enhancing **Silicon Graphics** workstations including:

Personal IRIS
- 4D/30, 35
- 4D/RPC Indigo
- 4D/20, 25

Professional IRIS
- 4D/40, 50, 70, 80

Power IRIS
- 4D/100—400 series

All Kingston memory enhancements are individually tested, fully warranted, and 100% compatible.

For more information call Kingston today at:

1-800-835-2545
Ph. 714-435-2667
Fax 714-435-2699

Manufactured by
Kingston TECHNOLOGY CORPORATION
17600 Newhope Street
Fountain Valley, CA 92708

Silicon Graphics Memory



All trademarks and registered trademarks are of their respective companies.

and there are plans for it to run on the IBM PC in the near future. The text-to-speech software uses the Mac speaker and D/A converter. The company is now writing a speech toolbox for developers to create their own voice applications.

According to the company, Sound Bytes contains a parser that can determine a word's exact pronunciation from its context. The software can detect the difference between words that are spelled the same but pronounced differently, aiding pronunciation dramatically. The software also configures itself to avoid a monotone voice and automatically adjusts its rhythm to provide a more natural quality. The program is written entirely in C, which makes it portable from one platform to another.

We can look forward to higher-quality synthesizers over the next two to five years.

Sound Bytes' first step is to input ASCII text, which is fed into a 50-KB word-phonemic dictionary. The next step is to feed incoming text into a parsing system that sets parameters for rhythm and intonation. The following level involves feeding the output into a module that selects the proper diphones for the target text, and the result is sent to the D/A converter for verbalization.

Lernout & Hauspie (Woburn, MA) is working on an open-systems approach to software for text-to-speech synthesis, and it's collaborating with a number of companies in the U.S. and Europe, with the aim of providing multilingual speech software for a number of markets. The software supports American English, Spanish, German, French, Dutch, and Korean, and there are plans to add Italian and Japanese in the second quarter of this year.

Depending on the language, the software uses between 400 and 750 KB of memory. The code is written in C and is easily ported to a number of platforms, making it easier to develop specific applications for a number of markets. The software can be loaded into the RAM of a synthesizer board or box.

Lernout & Hauspie developed a reverse telephone directory using voice recognition and speech synthesis for the Belgian Post Telephone & Telegraph. The software uses heuristics to determine the proper pronunciation of names and addresses from multiple languages. The system is capable of determining the French, German, or Dutch pronunciation of a target phrase. The company also developed a telephone-based E-mail system using speech output for the South Korean government.

Berkeley Speech Systems (Berkeley, CA) is a leader in the speech-synthesis market, and it is offering speech technology to such players as Franklin Home Electronics for a line of portable information-retrieval systems. Berkeley is also keenly interested in the growing fax-to-speech market. First Byte (Santa Ana, CA), maker of the familiar Smooth Talker software, also markets speech software for MS-DOS and Windows. With all this in mind, I'll now look at some of the applications for speech output.

Automatic Mouths

Numerous productive applications take advantage of speech technology, and the list continues to grow. These include conversion of fax to speech, screen-reader software for persons with vision impairments, and telephone voicing of dynamic databases.

One of the most powerful applications of speech technology is reading fax messages with voice. Several cutting-edge companies are working on the problem, and Berkeley Speech Technology has obtained a patent for this money-making process. Fax-to-speech technology is a market that's almost certain to be a winner, because fax messages are so ubiquitous in today's business and industry.

The first step in fax-to-speech conversion is to translate the fax message to ASCII using optical-character-recognition technology. The typical one-page fax message can be converted to ASCII text using OCR in less than a minute. The Calera text-recognition board can convert a fax file stored on disk, or a flatbed scanner can scan paper-based faxes.

Once the fax is scanned into ASCII format, it's readable by a text-to-speech synthesizer. The text is sent to the speech synthesizer, which reads the message in any language that is chosen by the end user. The phone's Touch-Tone keypad is used to control the reading mode, and it can be used to start or stop reading at any time.

The Malibu Software Group (Malibu, CA) is developing a prototype OS/2-based

World Radio History

While Our Competitors Are Diligently Trying To Emulate The SummaSketch® II...

We Proudly Announce SummaSketch II Plus.

The world's best selling, most emulated, most acclaimed desktop tablet just got better. We've taken SummaSketch II, the industry standard, and added several new features to create a tablet that is, unquestionably, the world's best.



Unlike some competitors, we put everything in the box—4-button cursor *and* 2-button stylus (or 16-button cursor), interface cables and a utilities diskette with Windows® 3.0 and ADI® drivers. Plus we've added things like 2000 lines per inch resolution and 10 mil accuracy—standard. Plus the fastest, easiest set-up and configuration procedure. Plus an offer for a free AutoCAD® or CADKEY® Master Template (a $245 value). Plus software compatibility with over 400 programs, and hardware compatibility with PCs and Macintosh.® Best of all, it's still 100% pure SummaSketch—the editor's choice, winner of every major editorial accolade for graphics tablets. And the people's choice, with well over one-half million sold to demanding computer graphics professionals.

Every decision should be this easy. In fact, the only tough decision is which Plus to choose: 12" x 12" or 18" x 12" Professional. For literature, or the name of your local dealer, call 1-800-729-7866. For technical information call 203-881-5400.

PC MAGAZINE EDITORS' CHOICE November 28 1989 SummaSketch II

CORPORATE COMPUTING MACWEEK SATISFACTION POLL

CADENCE BEST OF 1990

C 1990

Summagraphics®

Every decision should be this easy.™

© 1991 Summagraphics Corporation. Seymour, CT 06483. All rights reserved.

Circle 128 on Inquiry Card.

World Radio History

Circle 173 on Inquiry Card

Boost your Basic!

ProBas 5.0

ProBas professional programming library provides 938 routines that will boost your Basic programs into orbit! And at 21 cents per routine can you afford to be without it? Join thousands of professional developers who rely on ProBas to write efficient, sleek programs fast! *Just $195!*

ProFont

Display any of 24 fonts in any color, size or rotation with ProFont! Use CGA, EGA, VGA or ProBas virtual screens. Link fonts into your EXE. Make your screens shine! *Just $125!*

ZBF

Zero Bytes Free transparently bypasses Basic's symbol table limits to let you develop larger programs! *Essential!* *Just $39!*

And many more...

Comms, Financial, HyperHelp... To make your programs better, faster, and written in less time - call for your FREE copy of "Ten Easy Ways to Boost Your BASIC".

New for Visual Basic:

Dazzle, VBlite & ProMath

now available - call for details.

"A Super Charger for BASIC" -BYTE

TeraTech

Dept B4A, 3 Choke Cherry Rd,
Suite 360,Rockville MD 20850

800-447-9120x102

Int'l: (301)330-6764 Fax: (301)963-0436
BBS: (301)963-7478
Visa, m/c, COD, checks and approved

system that's aimed at converting fax messages to voice in real time. It should be out by the time you read this, and it's anticipated that the system (including a dedicated workstation to house the fax server) will sell for about $15,000. It will allow a user to play back a fax message through a text-to-speech synthesizer with an unlimited vocabulary under the control of a phone's Touch-Tone keypad. The end user will be able to tie this system into a voice mailbox, and faxes can be played back through the speech board.

Vision-impaired people use talking computers to access text- and graphics-based systems. Sounding Board and the Vocal-Eyes screen reader from GW Micro (Fort Wayne, IN) form a state-of-the-art voice-access package that is capable of working with most DOS-based applications. The software and hardware can provide an unlimited vocabulary for most word processors, databases, spreadsheets, and other software. Outspoken from Berkeley Speech Systems is a GUI-oriented speech package for the Mac, and it's one of the most powerful graphics-based speech packages available to persons who have vision impairments. IBM is also developing Screen Reader/PM, a graphics-based screen-reader program for the visually impaired.

Answering machines were once the only device connected to most telephones. Now, thanks to text-to-speech synthesis, Touch-Tone keypads, and some newer devices linked to the phone line, reams of information can be as close as your fingertips. Speech synthesis is being combined with fax and telecommunications technology to offer a complete data-handling system with remote control.

Centigram Communications' voice-processing technologies are examples of telephone-based information systems. The company specializes in using voice output for transaction processing, data inquiry, text-to-speech applications, and visual output via fax and data. A caller can control a massive database containing technical documentation, listen to a series of voice menus, make selections using the Touch-Tone keypad, and have page after page of technical text and graphics faxed immediately to a distant location.

The Touch-Tone keypad and voice interaction with unlimited vocabulary can be used to trigger downloads from a remote location to a far-off office or job location. The system can also be used to trigger pagers to contact personnel that are in the field or on job calls. Speech-synthesis technology can be used to take the load off workers in an office, particularly when their time is spent delivering simple or repetitive information to clients (e.g., opening and closing times or address information).

A.B.C.D...

The future of speech synthesis is full of promise. The global market for this technology continues to expand as more foreign languages are added to the electronic vocabulary. There are few natural-sounding voice synthesizers on the market, however, with most synthesizers still clinging to their robotic tones.

We can look forward to higher-quality synthesizers over the next two to five years, with high-end products dropping in price as their technology is rendered less expensive by technical progress. We can also look forward to more equal opportunity among synthesizers, because the bulk of voice-output systems now use male voices. The future will offer greater opportunities to customize synthesizers, allowing the end user to choose the voice that is most pleasing for a particular application.

Multimedia will give a boost to the text-to-speech market this year, as it's applied to messaging systems, applications designed to aid the disabled, and database access over the phone. In 1993 and 1994, automobile-navigation systems will use speech to provide directions to drivers. These verbal-output systems will indicate when to turn and what routes to follow.

Speech support is being added to many platforms. Phoenix Technologies is incorporating support for Walt Disney's Sound Source digital-sampling system at the BIOS level, which will likely force other OEMs to jump on the voice bandwagon. In three to five years, voice synthesizers may appear in the form of single chips or dedicated chip sets that will allow integration of speech into everything from home appliances to workstations.

The growing applications of speech synthesis are driven by a basic force: Speech is simply one of the most powerful and natural forms of communication among humans. ■

ACKNOWLEDGMENT

Special thanks to Tony Vitale of DEC.

Joseph J. Lazzaro is the cofounder of Talking Computer Systems (Cambridge, MA) and project director of the adaptive-technology program at the Massachusetts Commission for the Blind. He is a freelance writer and the author of a forthcoming book on assistive technology for disabled persons. You can contact him on BIX as "lazzaro" or on Internet as Lazzaro@world.std.com.

World Radio History



With and Without ULSI Coprocessing

Not just another math coprocessor–the ULSI Math·Co™ is state-of-the-art, full double-metal CMOS 1.0μm technology. Designed with all the enhancements and performance features one would expect from leading edge silicon valley technologists, the Math·Co will increase your computing speed by up to 500%.

You can take advantage of over 2,100 different software applications designed to handle the floating point instructions necessary for screen redraws, regenerations, zooms, and other math intensive operations on 386™ computers.



Price performance leader–ULSI has incorporated in this new generation math coprocessor many performance enhancements not found in ordinary coprocessors.

- Reduced (by as much as 75%) number of clock cycles needed by the Intel 80387 to do floating-point mathematics.
- Built in automatic sleep mode to reduce battery drain in SX lap-top computers.
- Reduced power consumption, and heat radiation for the industry's best Mean Time Between Failure (MTBF) rating.
- Reduced noise sensitivity for superior hardware compatibility.

Lifetime Warranty–ULSI Math·Co's superior design allows us to offer the industries first lifetime warranty.

Wise choice–To get the finest math coprocessors available, call your local computer dealer or contact ULSI North America (512) 795-8033 or ULSI Europe 0734-462247 for the name of the dealer nearest you.

Math·Co
The Original Math Coprocessor
from
ULSI SYSTEMS

Math Co is a registered trademark of ULSI Systems. Other product names are trademarks and/or trade names of their respective manufacturers. Screen shots courtesy of Structural Measurement Systems, a GenRad Product line.

Circle 163 on Inquiry Card.

World Radio History

News for small computer users:
Blackout protection for just $169!

At last! A real-value Standby

BEST has made finding an SPS with real value easy. If you've made the decision that all you need is basic power protection, take a look at our new Patriot™ Standby Power System. Patriot, available in sizes from 250 to 850 VA, provides great performance at the lowest cost — just $169!

Blackout protection on a budget

Patriot offers reliable backup power. It's a new power protection solution from Best Power Technology, Inc., the world's leading manufacturer of single-phase UPS. Patriot features:

Exceptional lightning and surge protection. Patriot passes ANSI/IEEE C62.41 Categories A and B tests. It also passes rigorous UL 1449 tests for surge suppression — few standbys can say this.

Full-time EMI/RFI noise filtering. Patriot filters electrical noise that locks up your computer and scrambles your data.

High voltage protection. Patriot steps in to prevent high voltage from damaging your computer. No other standby offers this feature.

Output designed for computer loads. Patriot's backup power is designed for switch-mode power supplies.

Safe, assured transfer time. Patriot transfers to inverter in four milliseconds or less. A proprietary microprocessor-controlled detection system ensures quick, reliable operation that keeps your system running during a power failure.

Interface Port for LANs and multi-user systems. Patriot has an interface port (450 VA model and larger) that lets it trigger an unattended, orderly shutdown on many computer systems.

Status indicator and alarms. Patriot's two audible alarms and triple-mode status indicator light warn you of overloads and low battery runtime.

Users are surprised by Patriot, BEST's new real-value Standby Power System (SPS): maximum performance at a low price!

The Double Lifetime Warranty

We're so sure Patriot stops any surge that we're offering an incredible Double Lifetime Warranty! It covers our surge suppression circuitry from failure as long as you own your Patriot. If Patriot ever fails to protect the equipment plugged into it from lightning, surges, or spikes, we'll replace it and repair the protected equipment. Certain restrictions apply. Ask for details.

We're your Power Partner™

We've always been trendsetters in the power protection field. Now we're your total Power Partner, offering everything from advanced surge suppressors, to standby power systems, to on-line uninterruptible power systems, at prices you can afford.



Everything you need to choose the right power protection devices.

Which Patriot fits your needs?

Patriot Model	Capacity (VA/Watts)	Runtime Full/Half Load	Dimensions (in inches) H/W/D	Weight (in lbs.)	Output Receptacles Qty.	Type	Price
SPS 250B	250/170	10M/30M	7/5.5/11	18	2	5-15R	$169
SPS 450B	450/300	5M/15M	7/5.5/11	21	4	5-15R	$279
SPS 650B	650/430	5M/15M	7/5.5/16	25	4	5-15R	$449
SPS 850B	850/600	5M/15M	7/5.5/16	30	4	5-15R	$599

We can ship you a Patriot via UPS or Federal Express!

Express-order service
Order a Patriot now!
800-356-5794, ext. 3500

You'll receive a copy of our FREE "Guide to Power Problems." Learn to spot and solve your power quality problems.

BEST

Best Power Technology, Inc.
P.O. Box 280 - Necedah, WI 54646
Toll-Free 800-356-5794, ext. 3500
(U.S.A. and Canada)
Telephone (608) 565-7200, ext. 3500
Telex No. 701934 (Best Power UD)

Circle 45 on Inquiry Card (RESELLERS: 46).

World Radio History

THE ULTIMATE USER INTERFACE

Research from many fields is being synthesized to create a design philosophy for information environments

BOB JACOBSON

The physical and symbolic worlds in which we live and work are *information environments*. In them, we find the clues and cues we use to create the multidimensional mental maps and models that help us get around and do things in the real world. An encyclopedia, a TV broadcast, and a computer are IEs that produce virtual worlds with different qualities. The IEs addressed in this article are created by a computer, alone or as part of a network.

Successful IEs express a high degree of *virtuality*: a good fit between the external worlds they are intended to represent and the virtual worlds they actually produce. Today's hypermedia and virtual reality systems are the forerunners of tomorrow's highly virtualized IEs. With the best of today's systems, people will be able to work with information naturally, manipulate data comfortably, and share knowledge easily.

Tomorrow's highly virtualized IEs will be composed of synthesized sights, sounds, and tactile fields. Their sum will far exceed their parts, because future IEs will respond to more than an inhabitant's overt commands and requests: They'll respond to his or her mood and disposition as well. In tomorrow's IEs, people will work and play smarter and better, and they will have more fun. Over time, as richer IEs appear and more people experience better-designed virtual worlds, the information age will finally become participatory.

All these predictions will be realized, however, only if IEs are well designed. To create effective IEs, designers must shift their focus from the machines that generate IEs to the virtual worlds people experience.

continued



ILLUSTRATION: JAMES ENDICOTT © 1992

World Radio History

IE Design Is the Key

Good design is conscious and systematic, part art and part science. Its rules apply equally to the design of things, places, and processes. The best designs start by considering people, not things. For IEs, this practice yields a central rule for good design: Mirror an inhabitant's internal states to most effectively get information to and from the inhabitant (see the text box "What I Look for in an Information Environment" on page 178).

"The human body is admirably equipped for deeply interactive real-time communication via sounds, and even more admirably equipped to receive all sorts of information visually," says Jim Gasperini, author of the eerily real-world computer strategy game *Hidden Agenda*. "However, when it comes to sending visual information, the unmediated body fails. When it comes to storing information, the body quickly reaches limits set by memory and mortality. The Holy Grail of interactive design is to make it intuitive—meaning that the electronic-information environment so neatly mirrors the way people imagine themselves that it seems like a direct extension of their minds."

More than acting as a temporary extension of the mind, IEs will truly extend the mind by providing a strong component of learning as a continuous part of an ongoing, multisensory interaction. Meredith Bricken builds virtual-world models for the Human Interface Technology Laboratory (also known as the HIT Lab). She advises that "designing virtual-learning environments is substantially different from both traditional-interface design and traditional-curriculum design. Because the entire person is engaged in activity, designers must work on many levels" to build a multisensory, multimodal, personalized interface and curriculum. "The conceptual design of a virtual world defines what you do there, how you do it, what elements and behaviors you include [and exclude], and the context of the experience."

BYTE ACTION SUMMARY

Although the technologies for building virtual worlds are progressing rapidly, the design of the information environment that a virtual world represents will determine success. Designers are drawing on methods from a great many fields to guide their efforts to create effective IEs.

The ultimate goal in IE design is an understanding of the intended user.

The ultimate goal in IE design is an understanding of the intended user. IEs should fit the people for whom they're intended. Designers can customize IEs so that within them inhabitants can follow their own methods to navigate, perceive, identify, evaluate, choose, modify, and share information. To do these things, designers need parameters to guide them in their work in multidimensional realms. They have to find ways to guide users through the IEs.

Navigating in Information Space

Some methods designers employ to help users navigate IEs are derived from architectural theory. Architects, like IE designers, work in space, although the space they work in obviously has a physical component and is not wholly perceptual. They depend on an architectural discipline known as *wayfinding* (i.e., knowing how to get around), which is useful for designing IEs.

Wayfinding is behavior that may be embedded in our genes. The modern practice of wayfinding, discussed by Montreal architect Romedi Passini in his book *Wayfinding in Architecture* (Van Nostrand Reinhold, 1984) and by his Toronto-based colleague Arthur Frank in *Guidebooks for Public Works Canada* (Public Works Canada, 1984–1986), is a systematic method of designing comprehensible architectural space. Environmental cues located at key decision points help a wayfarer build a mental model and find a path to his or her destination. Similar cues can be designed in IEs.

A navigator sailing from island to island, an Australian aborigine on a walkabout in the outback, and an Inuit crossing an apparently featureless white landscape are navigating by environmental cues. The markers may not be directive; they may simply offer information that a well-educated wayfarer can use to plot a course, even in a dynamic environment. These cues may have meaning only in the context of their environment, however, so understanding how one's environment works is often crucial to finding one's way in it.

Syracuse University's Mike Nilan reinforces the need for deep knowledge: "The spatial characteristics of the IE must be structurally similar to the semantic dimensions used by the people who are trying to make sense of the problem, decision, or sought-after experience. At Syracuse, we are working on an IE for students. Its interface will be a three-dimensional map of the university that will enable students to go around the campus and get access to a variety of information and the campus computing facility."

When Navigation Doesn't Work

The navigation metaphor doesn't represent a universal solution. Psychologist Don Norman, author of *The Design of Everyday Things*, formerly titled *The Psychology of Everyday Things* (Basic Books, 1988), believes that navigation, in the sense of following a chart, "is unworkable once the size of the data set gets large." He foresees the incorporation in virtual interfaces of teleports: "I walk to the teleport and describe what I am interested in (by talking, typing, drawing, pointing, selecting—what have you), and then, whoosh, I am teleported to the place."

"The problem," says Alan Wexelblat, a virtual worlds theorist with Bull Worldwide Information Systems (Billerica, MA), "is that most information spaces have no natural order or arrangement. Architecture, CAD, and so forth—all have a natural order imposed by the 3-D geometries and laws of the physical world. But nothing like that works for the information space of all the artifacts generated in a software project (e.g., code, documentation, specifications, requests for change, requirements, and design rationale). The amount of data in such spaces is truly massive (millions to hundreds of millions of objects). Only by imposing some kind of order on it can designers possibly make it comprehensible. That is the central challenge of information-space design."

The massive complexity of information envisioned for many IEs may not be the problem it first appeared to be, because the information is in digital form. "In fact," remarks HIT Lab researcher Suzanne Weghorst, "the value of digital information is that it is mutable. You can transform it systematically or idiosyncratically, through

World Radio History

DATABASE WORLD

Conference & Exposition
June 29 – July 1
Boston, MA

DATABASE WORLD returns to Boston bigger and better than ever and brings CLIENT/SERVER WORLD* with it!

The result is . . . .

- **7 Conferences, covering a variety of issues in-depth, are:**

  Database:
  - Database Technologies
  - Object Oriented
  - PC Databases
  - DB2/CSP

  Client/Server:
  - Client/Server Applications
  - Client/Server Databases
  - Client/Server Networking

- **7 Technical Co-Sponsors**
  - Byte Magazine
  - Communications Week
  - DBMS
  - Data Based Advisor
  - Database Management Magazine
  - Database Programming & Design
  - Network World

- **Over 200 industry experts**

  George Schussel, Shaku Atre, Larry DeBoever, David Fulton, Richard Finkelstein, John Gallant, Nathan Goodman, Ken Jacobs, Dominique Laborde, Bruce Lindsey, Robert McDowell, Ronald G. Ross, Jeff Tash

- **Special Event: "Object/Relational Test Lab"**

- **A 70,000 sq. ft. Exposition with special industry co-sponsors:**

  Andersen Consulting, Apple Computer, Borland, Cognos, Computer Associates, Data Access, GeoVision Systems, K-C Computer Services, Microsoft, ONTOS, Oracle, TechGnosis

* (**CLIENT/SERVER WORLD** is endorsed by the Client/Server Roundtable, a non-profit industry organization).

Call 508-470-3880 to register or to receive a complete brochure.

DCI
Digital Consulting, Inc.

Circle 168 on Inquiry Card.

World Radio History

What I Look for in an Information Environment

In my meanderings around the information universe, there are few things more important to me than the quality of the virtual worlds that I build in my head, using cues from the worlds outside and what I already know. How well these mental maps and models take shape is directly attributable to the care with which various information environments (IEs) were designed.

Everyone has favorites among today's IEs (including virtual environments, The Well, Usenet, CompuServe, and even Prodigy). The best of these share characteristics that you may want to apply to future nonscreen-based IEs, such as virtual worlds:

coherence—The best IEs are clear. Their embedded meanings are, if not immediately evident, at least not cloaked. There is an internal logic to the relations within the IE and (if it aspires to represent the external world or some element of it) a reasonable correspondence between what is represented and what happens in the virtual world and what happens in the objective world.

inclusiveness—I like IEs that take me in. When I visit the Well, even though only my visual sense is stimulated (and then only by the characters on the CRT), I feel as if I'm in a living community made up of acquaintances and friends. In a state-of-the-art virtual world, my aural machinery is also used, and the visual stimuli are fast-changing pixels that, taken together, represent for me another place entirely, with its own rules and processes. I am there, inside.

malleability—A malleable IE is one that I can sculpt to fit my own instrumental needs and aesthetic tastes—a virtual world, for example, in which I can add sound to the color of the sky, reduce gravity, or realize (a step up from visualize) a complex financial process. A hypertext database that has been thoughtfully designed can be a thing of beauty if I can easily reconfigure my progression among the records to seek knowledge in my own idiosyncratic way.

engagement—The engaging IE takes me seriously and invites my complete participation in its processes. It's a place where little time is spent carrying out bureaucratic rituals (e.g., reprogramming an arcane operating system) and plenty of time is available for exploring what is the essence of the IE—the opportunity it offers the inhabitant. And I feel very disappointed if I am asked to leave the engaging IE prematurely, before I have experienced some epiphany.

authorship—Like a signature on a lithograph or the proprietor's estate on the label of a bottle of wine, the identity of the designers of memorable IEs is always evident. A good IE designer may leave just a vanishing trace of his or her identity before getting out of the way to allow an inhabitant to turn the world upside down, or the IE may be so stylistically strong that you meet the designer everywhere.

responsiveness—There is great pleasure to be found in IEs that acknowledge human difference and permit an inhabitant to customize the IE in his or her own image. A transaction with a bank automatic teller machine is not characterized by responsiveness. Responsiveness is exemplified by the designer of an IE who holds forth the rules by which the IE runs and then allows (or even exhorts) me to learn and change those rules. Well-designed IEs liberate their inhabitants.

purpose—There is nothing so priceless in today's time-starved world as a thing that does what it is intended to do—and does it well. Allow me to enter a virtual world that shows me what it's about, and I'm thrilled. If it's a place to poke about in and explore—a learning environment—have it say so loudly and directly. If it's where a task is to be done, have it so inform me, and let me at it. A design that dithers is unforgivable. Clarity of purpose is nirvana, in IEs as in life.

your own eyes or through the eyes of other people. Moving about in a collective world, the inhabitant can use the comparative experiences of other inhabitants as a filter: What does he see? What did she think was significant? The next step is IEs that incorporate this filtering mechanism so that copious information, far from being discouraging, becomes grist for the inhabitants' perceptual mills."

For Brenda Laurel, a principal in the IE research firm of Telepresence International (Los Gatos, CA), "the interface to a world of information can't be about representing information; it must be about *doing* things with information, from experiencing it to more subtle goals like identifying [its author's] point of view." Laurel identifies two crucial R&D targets: creating systems that can generate multiple representations of information that are responsive to an individual's sensory characteristics, preferences, skills, and needs; and providing contexts and materials in the interface for cognitive and emotional synthesis of information, not as post hoc analytical tools but as part of an individual's real-time process of constructing meaning.

Guides for IE Design

Just as designers borrowed architecture's concept of wayfinding, so they can borrow methods from many other fields (e.g., information-systems design, library science, and organizational theory) to design IEs that people can comfortably inhabit. *Sense-making*, an information-sciences design discipline, is one example.

In the mid-1970s, Ohio State University

World Radio History

WHAT MAKES SOME PRESENTATIONS MORE COMPELLING THAN OTHERS?

CAPTIVATING PRESENTATIONS ARE EASY WITH DECPRESENT FOR SUN SPARCSTATIONS.

Now your presentations can really excite your audience. All you need to turn your great ideas into compelling visuals is your Sun® SPARCstation™ and DECpresent™ software.

With DECpresent, you can build clear and attractive slides from a simple outline in minutes, mix and match slides from other presentations, and even link your slides to live data on the network. The sorter view displays your entire presentation on the screen, and speaker notes ensure that you'll make the most convincing points. You'll create presentations that look like they took hours to prepare in just a few short minutes.

Call your favorite reseller listed below for our demonstration disk and see how DECpresent can make you a star.

digital™

Qualix Group	UNIX Central	RAD Technologies, Inc.	DUX Corporation
1-800-245-UNIX	1-800-553-UNIX	1-800-2GET-RAD	1-800-543-4999

DIGITAL. THE OPEN ADVANTAGE.

© Digital Equipment Corporation 1992. The DIGITAL logo and DECpresent are trademarks of Digital Equipment Corporation. Sun is a registered trademark and SPARCstation is a trademark of Sun Microsystems, Inc.

World Radio History

Virtual Worlds Research Today

RICHARD HOLLOWAY

Imagine you're walking through a house—a fire crackles in the brick fireplace, an ebony grand piano plays in the living room, and glasses clink around the wooden dining room table. The images you see and the sounds you hear are quite lifelike, yet you're not actually in this house at all. You're in a virtual world.

A system developed at the University of North Carolina at Chapel Hill that allows you to walk through scenes like those I've just described consists of a VPL EyePhone for displaying the images, an optoelectronic tracker for monitoring head position and orientation, and a massively parallel graphics engine for generating the images that are displayed on the head-mounted display (HMD). Although the latter two components are unique to the UNC system, the system I've described is representative of the state of the art in virtual worlds technology.

Even though this technology may seem new, much of the virtual worlds research was inspired by Ivan Sutherland's pioneering work in the 1960s. In 1965, he postulated that "the ultimate display would, of course, be a room within which the computer could control the existence of matter. A chair displayed in such a room would be good enough to sit in. Handcuffs displayed in such a room would be confining, and a bullet displayed in such a room would be fatal."

For years, research in virtual worlds technology was pursued by a relatively small core of organizations, among them Wright-Patterson Air Force Base (and other military labs and contractors), NASA-Ames, MIT, and UNC. Recently, however, the number of researchers working in this field has skyrocketed, probably because of the technological advances in small LCD TV screens (used inside many HMDs), more powerful graphics systems, and magnetic tracking systems. These advances have increased system performance and decreased the cost of the components of a virtual worlds system to an affordable level.

Yet despite all these advances, the major technical problems that existed in the late 1960s remain with us today. Image generation of complex scenes is still quite difficult at real-time rates (around 30 frames per second). It must be possible to track at least a user's head and hand in real time and with considerable accuracy. In addition, HMDs must produce high-resolution images and wide-angle views for both eyes. And researchers still have not perfected force feedback to simulate even simple objects.

At UNC, researchers are addressing each of these issues, and they are carrying out projects for using this technology in real-world applications. Research is taking place on the visualization of protein structures, architectural building walk-throughs, radiation-treatment planning, and medical x-ray vision.

Some of the UNC system's capabilities illustrate what is possible today. In terms of image generation, the system's graphics engine (called PixelPlanes 5) can draw more than 2 million Phong-shaded z-buffered triangles per second. The ceiling system can track a user over a 10- by 12-foot area at an average rate of 50 to 70 updates per second. The VPL EyePhone Model 2 HMD has a horizontal field of view of 80 degrees per eye and a resolution of approximately 210 by 140 full-color pixels (the newer Eyephone HRX model has roughly twice this resolution). The system provides force feedback for a user. Its Argonne Remote Manipulator can give a user feedback via three forces and three torques at the handgrip.

Current systems are often too slow and cartoonlike for a user to truly suspend disbelief. Yet each year, faster hardware and new technologies bring us closer to a system that can let users believably experience another world. In the future, faster graphics systems will allow for more complicated and realistic virtual worlds. Faster trackers will improve a system's response to user movement. Higher-resolution HMDs will display more compelling images. And force feedback will allow a user to "reach out and touch" virtual objects. Virtual worlds such as those produced by flight simulators are already convincing enough to be useful. In time, there should be virtual worlds systems that are good enough for real work in other fields (e.g., medicine and scientific visualization).

Richard Holloway is a student at UNC at Chapel Hill who works on the HMD project. His Ph.D. project is on x-ray vision for craniofacial surgery planning. You can reach him on BIX c/o "editors" or on Internet as Holloway @cs.unc.edu.

professor and communications theorist Brenda Dervin began asking her subjects the following questions: What are the problems most important to you right now? What obstacles block your way? What assistance is available to you to solve those problems? Tens of thousands of questionnaires and interviews later, Dervin and her team of researchers discovered why, in particular situations (e.g., a person trying to get across town, a welfare mother dealing with a faceless bureaucracy, or a student looking for a citation), some people can accomplish their goals while others remain helpless and frustrated.

Making sense depends on two important ingredients: the accessibility to the person in the predicament of comprehensible information, and the ability of people to conceptualize and cognitively bridge gaps in their understanding. "If you look from the inside (i.e., as the person sees the world), you find there are many ways to attain goals. The variety can be bewildering." One method of IE design is to limit goal paths to those most desirable to an inhabitant. Another is to train a person to

World Radio History

WORD PROCESSING FOR WINDOWS AND OS/2

SIMPLICITY SPEED SUCCESS

You're on your way with WINDOWS and OS/2 Word Processing from DeScribe 3.0

Simple to use, DeScribe® Word Processor 3.0 places power at your fingertips. Let your thoughts fly because DeScribe smoothly matches your pace to help you streak across the finish line in record time.

Best of all, simplicity does not mean sacrifice. DeScribe includes all the advanced features you expect in a modern word processor and more! Like multilingual spell checking and thesaurus. Built-in definitions dictionary. Dynamic Data Exchange. Tables, drawing tools and more import filters for text and graphic formats than any other word processor on the market.

Plus, formatting is just a mouse click away with the unique Text Toolbox. Merge text and graphics. Draw lines. Be creative. Have fun. DeScribe is there to help you.

All done? Restore past work with DeScribe's unlimited UNDO. Snapshot automatically protects you from WINDOWS UAE's and those times when power goes out.

Still uncertain? Ask for a Trial Disk and take DeScribe for a test drive.

DESCRIBE®
WORD PROCESSOR

Call Department 222 at:
1-800-448-1586
FAX 916-923-3447
MCI MAIL DESCRIBE

MICROSOFT WINDOWS
Version 3.0 Compatible Product

OS/2
PRESENTATION MANAGER
COMPATIBLE PRODUCT

See us at COMDEX/Spring '92 Booth 3221, April 6-9

Circle 87 on Inquiry Card.

World Radio History

choose goal paths more wisely. A third is to propose new goals. Each method has its adherents among designers.

Sense-making's investigative methodology is also a reliable research tool that produces dependable qualitative and quantitative results. These results indicate what and how information works in a defined setting. With this tool, designers can refine IE prototypes and ensure that they accomplish the inhabitants' purpose.

From library science, designers can borrow methods found in guidebooks that spell out, in the simplest terms, how to help library patrons identify, find, and act on useful information. Organizational analysis offers some guidance for the design of multiple-inhabitant IEs, which will become increasingly common as technology develops.

Tomorrow's IEs that are built on data networks will be variegated. Many may be consensual (i.e., defined by their users). Users will enter the networked IE from many locations and situations, likely with different motives and personalities. Should we make it easy for inhabitants to hide their personalities and intentions, or should we encourage candor and direct communication? For some situations (e.g., the workplace), the networked IE will be deemed most successful when all participants share the same perceptions and meanings.

How will an appropriate group environment be designed? An understanding of group dynamics and mediated communications will help, although it may not provide all the answers. A designer may have to rely on anecdotes and metaphors for a fuller understanding of a multiple-inhabitant IE and how best to design it.

Finally, usability research is valuable for IE design. Such research can also bridge the potential gap that might otherwise separate the design of IEs from the design of their supporting platforms. Usability research, properly used, can determine the capacity of a specific system to support a desired IE. In a virtual classroom, for example, designers want an IE to be driven by a computer system that can generate a seamless visual and aural (and eventually tactile) presentation while being responsive to rapid inputs from diverse participants. The IE must provide its inhabitants with a high degree of interactivity and malleability. Usability research makes it possible to test these properties using both qualitative and quantitative indicators.

Involving the User in Design

Users should be involved in the design of IEs. "I guess I like the term *participatory design*," says Michael Good, director of DEC's Presence project, which conducts virtual worlds research. In DEC's software usability engineering group, according to Good, users define usability, work influences user experience, and collaboration in the design process melds users and designers into a team.

The design of multiuser IEs is ultimately more complex than simply defining an environment for group interaction. Advises Charles Grantham, group-work consultant and member of the Association for Software Design, "Data becomes information when it is placed in a social context. Information technologies are coevolving with human organizations. Designing information environments for work today is really engaging in wholesale community reconstruction." Or as Marshall McLuhan so presciently said more than 25 years ago, "The medium is the message." If so, IEs should be well-designed, for their very form and construction inherently convey the worldview—the meta-message—of their designers better than the artifacts they overtly contain.

Designing IEs for work today is really engaging in wholesale community reconstruction."

Eventually, IE design will mature from an idiosyncratic art to a craft and, perhaps, an industry. Well-designed IEs will make it easier for more people to use computers, both for traditional purposes and in new ways.

Rapidly changing technology capable of supporting highly developed IEs will spur this evolution (see the text box "Virtual Worlds Research Today" on page 180). IE design will subsume (not replace) on-screen 2-D visual graphics. Graphical interfaces, multimedia, and hypermedia (including virtual interfaces and databases) will continue to develop and eventually merge into tomorrow's IEs.

But will the new media of telecommunications—especially high-speed broadband networks—deny designers ultimate control of their IEs, as technocontrarian Tom Hargadon contends? Hargadon, publisher of the multimedia newsletter *The Green Sheet*, predicts "users will complete their worlds for themselves, in whatever media they choose. [Designers and vendors] will be transmitting useful but clearly incomplete products; value will be added at many places. We are moving toward pervasiveness and completion at the end, not the beginning!" The best IEs, like the best places to live, work, and play, will be capable of being customized.

As IE platforms increase in number, decrease in size, and become less expensive, inhabitants will be able to build in multiple dimensions of sight, sound, and tactility. They will routinely generate and refine personal and collective IEs. In time, perhaps many people will fancy themselves IE designers. It's wise to remember, however, the plague of poorly designed documents that resulted from widespread desktop publishing. Although well-designed IEs will make more of us good designers, as Steve Feiner proposed, the best designers will always remain members of a select guild. It will be their responsibility to train talented aspirants so that IE design develops from an art to a craft. Will IE design finally become an industry, as has software design before it? In that case, something very dear might be lost: the designer's sensitivity to what is right.

Janey Fritsche, who codesigned the Guides project for the Apple Media Lab, implores future IE designers to know empathy: "The success of a design depends on sensory reaction, as opposed to analytical stimulation. It behooves designers to exercise artistic sensibilities that are well honed. Most of the impact of interactive multimedia and virtual reality is a 'feeling' thing. It helps to approach each project as a work of art. Just as each piece of stone speaks to the sculptor, each project speaks to the designer. Listen with the heart and be guided." ■

ACKNOWLEDGMENTS

Thanks to all who contributed, especially Craig Hubley and Scott Overmeyer for their sage thoughts and advice.

Bob Jacobson is president of Worldesign, a company that designs televirtual worlds for industrial applications. He is a research professor of landscape architecture at the University of Washington. You can contact him on BIX c/o "editors" or, as the moderator of the Usenet newsgroup sci.virtual-worlds, on Internet as @well.sf.ca.us.

World Radio History

Find out why your PC won't talk to your LAN. And what you can do about it.



Shop. But don't drop. Need a 100% cotton pinpoint oxford shirt with button-down collar? In ecru? Try on our Electronic Mall.®



Dive deep into aquarium lore. Like whether a canister or protein filter is better for a 110-gallon salt-water tank.

Price a new Mustang. Or just learn everything about it.

Finally, a computer information service you can't outgrow. No matter how hard you try.

Learn how to monitor military satellites. (They watch us, why shouldn't we watch them?)



Find out just what the heck a zither is.



Talk to twice as many people about parallel universes.

No matter what you're into, you can get more out of CompuServe.

You can range widely over a list of services that will help you, entertain you, teach you, and challenge you. Or delve deeply into your favorite topics, learning (or even teaching) more, meeting experts, and making friends with people who share your interests.

CompuServe lets you do everything from keeping in touch with our communication services, to getting advice from online hardware and software experts. It's the one computer information service you won't outgrow.

But you will have a good time trying.

For a low one-time membership fee and $7.95 a month, you can use our most popular services as often as you like: news, sports, weather, shopping, reference materials, our electronic mail service of up to 60 messages a month, and more. Plus, there's a whole universe of other, extended options available at nominal additional charges. Your first month on CompuServe will be free, and we'll give you a $25 usage credit to explore our extended services.

To buy a CompuServe Membership Kit, see your computer dealer. For more information, or to order direct, call 800 848-8199 (614 457-0802 for international inquiries).

CompuServe®

The information service you won't outgrow.

Circle 56 on Inquiry Card.

World Radio History



INTRODUCING MICRO-CAP IV.™ MORE SPICE. MORE SPEED. MORE CIRCUIT.

PC-based circuit analysis just became faster. More powerful. And a lot easier. Because MICRO-CAP IV is here. And it continues a 12-year tradition of setting CAE price/performance standards.

Put our 386/486 MICRO-CAP IV to work, and you'll quickly streamline circuit creation, simulation and edit-simulate cycles — on circuits as large as 10,000 nodes. In fact, even our 286 version delivers a quantum leap upward in speed. Because, for one thing, MICRO-CAP IV ends SPICE-file-related slowdowns; it reads, writes and analyzes SPICE text files and MC4 schematic files. It also features fully integrated schematic and text editors. Plus an interactive graphical interface — windows, pull-down menus, mouse support, on-line HELP and documentation — that boosts speed even higher.

Now sample MICRO-CAP IV power. It comes, for example, from SPICE 2G.6 models plus extensions. Comprehensive analog behavioral modeling capabilities. A massive model library. Instant feedback plotting from real-time waveform displays. Direct schematic waveform probing. Support for both Super and Extended VGA.



AC Analysis

And the best is still less. At $2495, MICRO-CAP outperforms comparable PC-based analog simulators — even those $5000+ packages — with power to spare. Further, it's available for Macintosh as well as for IBM PCs. Write or call for a brochure and demo disk. And experience firsthand added SPICE and higher speed — on larger circuits.

Spectrum

1021 S. Wolfe Road
Sunnyvale, CA 94086
(408) 738-4387 FAX (408) 738-4702

Circle 123 on Inquiry Card.

World Radio History

Natural I/O

You can communicate with your systems and they with you more naturally by using speech-recognition or speech-synthesis technology products provided by these and other companies that make products for these applications.

Aicom Corp.
1590 Oakland Rd., Suite B112
San Jose, CA 95131
(408) 453-8251
fax: (408) 453-8255
Circle 1174 on Inquiry Card.

Animated Voice Corp.
P.O. Box 819
San Marcos, CA 92079
(800) 942-3699
(619) 744-8190
fax: (619) 744-8903
Circle 1175 on Inquiry Card.

Antex Electronics Corp.
16100 South Figueroa St.
Gardena, CA 90248
(800) 338-4231
(310) 532-3092
fax: (310) 532-8509
Circle 1176 on Inquiry Card.

Apex Voice Communications, Inc.
14900 Ventura Blvd.,
Suite 200
Sherman Oaks, CA 91403
(800) 727-3970
(818) 379-8400
fax: (818) 379-8410
Circle 1177 on Inquiry Card.

Apple Computer, Inc.
20525 Mariani Ave.
Cupertino, CA 95014
(800) 776-2333
(408) 996-1010
Circle 1178 on Inquiry Card.

Arkay Technologies, Inc.
5 Tsienneto Rd., Suite 2
Derry, NH 03038
(800) 786-2419
(603) 425-2149
fax: (603) 434-5674
Circle 1179 on Inquiry Card.

Artic Technologies International, Inc.
55 Park St., Suite 2
Troy, MI 48083
(313) 588-7370
fax: (313) 588-2650
Circle 1180 on Inquiry Card.

Berkeley Speech Technologies
2246 Sixth St.
Berkeley, CA 94710
(510) 841-5083
Circle 1181 on Inquiry Card.

Berkeley Systems, Inc.
2095 Rose St.
Berkeley, CA 94709
(510) 540-5535
fax: (510) 540-5115
Circle 1182 on Inquiry Card.

Compass Technology, Inc.
2201 Cantu Court, Suite 116
Sarasota, FL 34232
(813) 371-8000
fax: (813) 377-5600
Circle 1183 on Inquiry Card.

Covox, Inc.
675 Conger St.
Eugene, OR 97402
(503) 342-1271
fax: (503) 342-1283
Circle 1184 on Inquiry Card.

Dialogic Corp.
300 Littleton Rd.
Parsippany, NJ 07054
(201) 334-8450
fax: (201) 334-1257
Circle 1185 on Inquiry Card.

Digital Equipment Corp.
146 Main St.
Maynard, MA 01754
(800) 332-8000
(508) 493-5111
fax: (508) 493-8780
Circle 1186 on Inquiry Card.

Dragon Systems
320 Nevada St.
Newton, MA 02160
(617) 965-5200
fax: (617) 527-0372
Circle 1187 on Inquiry Card.

Emerson & Stern Associates, Inc.
10150 Sorrento Valley Rd.,
Suite 210
San Diego, CA 92121
(619) 457-2526
fax: (619) 457-1876
Circle 1188 on Inquiry Card.

Farallon Computing, Inc.
2000 Powell St.
Emeryville, CA 94608
(510) 596-9000
fax: (510) 596-9020
Circle 1189 on Inquiry Card.

First Byte
19840 Pioneer Ave.
Torrance, CA 90503
(310) 793-0610
fax: (310) 793-0601
Circle 1190 on Inquiry Card.

GW Micro
310 Racquet Dr.
Ft. Wayne, IN 46825
(219) 483-3625
fax: (219) 484-2510
Circle 1191 on Inquiry Card.

IBM
Old Orchard Rd.
Armonk, NY 10504
(800) 426-2468
(914) 765-1900
Circle 1192 on Inquiry Card.

InterActive, Inc.
204 North Main
Humboldt, SD 57035
(800) 292-2112
(605) 363-5117
fax: (605) 363-5102
Circle 1193 on Inquiry Card.

Kay Elemetrics Corp.
12 Maple Ave.
P.O. Box 2025
Pine Brook, NJ 07058
(800) 289-5297
(201) 227-2000
fax: (201) 227-7760
Circle 1194 on Inquiry Card.

Kurzweil Applied Intelligence, Inc.
411 Waverley Oaks Rd.
Waltham, MA 02154
(617) 893-5151
fax: (617) 893-6525
Circle 1195 on Inquiry Card.

Landmark Research International Corp.
703 Grand Central St.
Clearwater, FL 34616
(800) 683-6696
(813) 443-1331
fax: (813) 443-6603
Circle 1196 on Inquiry Card.

Lernout & Hauspie Speech Products
800 West Cummings Park,
Suite 3900
Woburn, MA 01801
(617) 932-4118
fax: (617) 932-9209
Circle 1197 on Inquiry Card.

Medisoft
300 North Newport Blvd.
Newport Beach, CA 92663
(800) 451-3111
(714) 642-3910
fax: (714) 548-3091
Circle 1198 on Inquiry Card.

Microcomputer Systems, Inc.
1814 Ryder Dr.
Baton Rouge, LA 70808
(504) 769-2154
fax: (504) 769-2155
Circle 1199 on Inquiry Card.

Mimic, Inc.
P.O. Box 705
Islington, MA 02090
(617) 329-9593
Circle 1200 on Inquiry Card.

World Radio History

This publication is available in microform.



UMI reproduces this publication in microform: microfiche and 16 or 35mm microfilm. For information about this publication or any of the more than 16,000 periodicals and 7,000 newspapers we offer, complete and mail this coupon to UMI, 300 North Zeeb Road, Ann Arbor, MI 48106 USA. Or call us toll-free for an immediate response: 800-521-0600. From Alaska and Michigan call collect 313-761-4700. From Canada call toll-free 800-343-5299.

Please send me information about the titles I've listed below:

_____

_____

Name_____

Title_____

Company/Institution_____

Address_____

City/State/Zip_____

Phone (_____)_____

U·M·I

A Bell & Howell Company
300 North Zeeb Road, Ann Arbor, MI 48106 USA
800-521-0600 toll-free
313-761-4700 collect from Alaska and Michigan
800-343-5299 toll-free from Canada

RESOURCE GUIDE

Natural MicroSystems Corp.
8 Erie Dr.
Natick, MA 01760
(800) 533-6120
(508) 650-1300
fax: (508) 650-1352
Circle 1201 on Inquiry Card.

NCR Corp.
1700 South Patterson Blvd.
Dayton, OH 45479
(800) 225-5627
(513) 445-5000
Circle 1202 on Inquiry Card.

Personal Data Systems, Inc.
100 West Rincon Ave.,
Suite 103
Campbell, CA 95008
(408) 866-1126
fax: (408) 866-1128
Circle 1203 on Inquiry Card.

Rhetorex, Inc.
200 East Hacienda Ave.
Campbell, CA 95008
(408) 370-0881
fax: (408) 370-1171
Circle 1204 on Inquiry Card.

Rockwell International Corp.
Switching Systems Division
1431 Opus Place
Downers Grove, IL 60515
(800) 722-5959
(708) 960-8000
fax: (708) 960-8165
Circle 1205 on Inquiry Card.

Software Research Corp.
P.O. Box 6519, Depot 1
Victoria, British Columbia,
Canada V8P 5M4
(604) 721-1214
fax: (604) 721-1785
Circle 1206 on Inquiry Card.

Spectral Synthesis, Inc.
18568 142nd Ave. NE
Woodinville, WA 98072
(206) 487-2931
fax: (206) 487-3431
Circle 1207 on Inquiry Card.

Street Electronics Corp.
6420 Via Real
Carpinteria, CA 93013
(805) 684-4593
fax: (805) 684-6628
Circle 1208 on Inquiry Card.

TeleSensory Systems, Inc.
455 North Bernardo Ave.
Mountain View, CA 94043
(800) 227-8418
(415) 960-0920
fax: (415) 969-9064
Circle 1209 on Inquiry Card.

Texas Instruments, Inc.
P.O. Box 655012
Dallas, TX 75265
(800) 527-3500
(214) 995-2011
Circle 1210 on Inquiry Card.

Turtle Beach Systems
Cybercenter #33
1600 Pennsylvania Ave.
York, PA 17404
(717) 843-6916
fax: (717) 854-8319
Circle 1211 on Inquiry Card.

Voice Computer Corp.
15373 Northeast 90th St.
Redmond, WA 98052
(206) 883-3345
fax: (206) 883-2322
Circle 1212 on Inquiry Card.

Votrax, Inc.
24027 Research Dr.
Farmington Hills, MI 48335
(800) 521-1350
(313) 459-5007
fax: (313) 442-0922
Circle 1213 on Inquiry Card.

Voyetra Technologies
333 Fifth Ave.
Pelham, NY 10803
(800) 233-9377
(914) 738-4500
fax: (914) 738-6946
Circle 1214 on Inquiry Card.

Wang Laboratories, Inc.
1 Industrial Ave.
Lowell, MA 01851
(800) 835-9264
(508) 459-5000
Circle 1215 on Inquiry Card.

Inclusion in the resource guide should not be taken as a BYTE endorsement or recommendation. Likewise, omission from the guide should not be taken negatively. The information here was believed to be accurate at the time of writing, but BYTE cannot be responsible for omissions, errors, or changes that occur after compilation.

World Radio History

Access dBASE IV and FoxPro files from C or C++



Call for a FREE Browse / Edit utility.

Design CodeBase Browse/Edit screens using any resource toolkit.

- **Multi User**
- **Portable (DOS, Unix, ...)**
- **Royalty Free DLL**
- **C++ interface included**

Use CodeBase 4.5 from **Visual Basic** or **Turbo Pascal for Windows**.

Use the super-fast, super-small **FoxPro 2.0** CDX or the Clipper NTX index files.

" Our product was too slow under FoxPro 2.0, so we rewrote it in C using CodeBase. Now it is incredibly fast."

Jeff Reed, DCS Computer Services

See us at Comdex/Spring '92 Booth #W1934

CodeBase 4.5

The C Library for DataBase Management

SEQUITER SOFTWARE INC.

TEL. 403•437•2410
FAX 403•436•2999
Europe 33.20.24.20.14

#209,9644-54 AVE., EDMONTON, AB, CANADA T6E-5V1

© 1991 Sequiter Software Inc. Graphics by MicroArts. © 1991

World Radio History

How Can A Direct Supplier Like Northgate® Give You Superior LAN Solutions And Support?



Like Machu Picchu, Some Phenomena May Never Be Explained.

You may think that Machu Picchu and a Northgate OmniLAN™ solution have little in common. The fact is, both are the result of insightful design and extraordinary engineering – the elements of a true phenomenon.

Whether you need a LAN with just four workstations or hundreds, OmniLAN systems give you the outstanding performance and reliability you need for today's business applications. Best of all, installation is as easy as connecting the color-coded cabling and turning the system on. All networking cards and software have been installed for you. Here's how to select the right OmniLAN system for you:

Pick a file server. Options include an Elegance™ SP 386/33, SP 486™/33 or 486/33 EISA. All have 8 or 16MB RAM, 300MB SCSI hard drive and controller, monochrome monitor and network interface card.

Choose from four topologies: ARCNET, ETHERNET Thin Net, ETHERNET 10BASE-T or Northgate Local Area Wireless Network.

Select your operating environment. Northgate has forged a strategic alliance with Novell which allows us to offer NetWare 386 3.11 and 286 2.2.

©Copyright Northgate Computer Systems, Inc., 1992. All rights reserved. Northgate, Elegance, OmniLAN, OmniKey and the Northgate 'N' logo are U.S. trademarks or registered U.S. trademarks of Northgate Computer Systems. i80386SX and i80486 are registered U.S. trademarks of Intel. All other products and brand names are U.S. trademarks and registered U.S. trademarks of their respective companies. Specifications subject to change without notice. Northgate reserves the right to substitute components of

World Radio History

The ancient Inca ceremonial site of Machu Picchu, high up in the Peruvian Andes, has long mystified historians, scientists and engineers by the precision of its stonework. Massive granite blocks were systematically cut and set without the use of mortar – yet the joints between them are barely visible. Though they were an advanced civilization, the Incas had no iron tools or other materials to achieve this level of quality. How, then, was it accomplished? Through levitation? Psychic powers? Extra-terrestrial assistance? The answer continues to elude us.

intel inside

Your network also includes four 386SX™/20 workstations each with a 52 MB hard drive, VGA card, network interface card, 14" color monitor, and *OmniKey*® keyboard.

You get a limited one-year parts and labor warranty including on-site service from NCR® Plus, 24-hour, 7-day-a-week toll-free technical support backed by Certified NetWare® engineers. Customized service and support plans also available.

Call for a free Decision-Maker's Kit, complete pricing and custom configuration information.

800-345-8709

Major corporations, volume purchasers and government agencies call National Business Accounts: 800-545-6059

Charge it to your VISA, MasterCard, Discover, American Express or Northgate Big 'N' card.

NORTHGATE COMPUTER SYSTEMS, INC.

7075 Flying Cloud Drive, Eden Prairie, MN 55344

CODE B3804

equal or greater quality or performance. All items subject to availability. Offer good only in the U.S. and Canada. We support the ethical use of software. To report software copyright violations, call the Software Publishers Association Anti-Piracy Hotline at 1-800-388-PIRE

World Radio History

NEW LAN BACKUP TOOLS

The BYTE Lab looks at eight LAN tape backup packages that promise to keep your files safe

BYTE LAB STAFF

Flash! Lightning strikes a power pole near your building just as you are updating the company database. The power blinks out for a second, and the file server and some of your workstations crash. You reboot the systems, only to find your database wiped out. The immediate order of business is to repair your damaged data. First thing tomorrow, you'll investigate centralized tape backup systems for your network.

Reach Out and Touch Some Ones (and Zeros)

As we rely more and more on LANs for storing mission-critical applications and data, we've begun to take for granted that our data will always be secure, organized, and readily accessible. But backing up and managing data for an entire network is a daunting task that involves more than copying a network's worth of files onto a tape drive. Fortunately, a new generation of sophisticated LAN tape backup software promises to solve the complex problems of networkwide data backup and archiving, tape rotation, and disaster recovery. For network clients and administrators, this can mean that important data is safe even when mistakes and malfunctions threaten catastrophe.

In this Solutions Focus, the BYTE Lab evaluates eight DOS, Unix, and Mac products that treat your entire network as a collection of data to be safeguarded. Cheyenne Software's ARCserve supports workstations running DOS, Windows, or OS/2, as well as NetWare file servers. Four products—Maynard Electronics' LANStream, Mountain Network Solutions' FileSafe, Palindrome's The Network Archivist (TNA), and Performance Technology's Powersave—handle DOS workstations and file servers. Delta Microsystems' BudTool and Legato Systems' Legato NetWorker give your Unix network shared access to a single tape drive. Dantz Development's Retrospect Remote lets a single Macintosh back up both Mac file servers and clients' Macs. (See the table for a complete rundown of the features offered by these packages.)

All these products address both servers and workstations in their backup

World Radio History



PHOTOGRAPHY SCOTT PARKER / AVIS STUDIO © 1992

BYTE ACTION SUMMARY

WHAT LAN TAPE BACKUP SOFTWARE DOES
With a shared high-capacity tape drive on your LAN, all clients on your office network can safely store their important files on tape.

LIKES
A shared tape drive makes it easy for system administrators to back up clients' workstations in a cost-effective manner.

DISLIKES
Setting up a LAN tape backup system can be complex at best and very aggravating to debug. Many administrators will want to call in a consultant.

RECOMMENDATIONS
The Network Archivist does a remarkable job of automating NetWare backups; ARCserve and LANStream are good alternatives. Legato NetWorker is our choice for powerful yet easy-to-use Unix network backups. Retrospect Remote is an excellent Macintosh backup package.

schemes. We chose systems capable of sorting 1 gigabyte or more of data, a threshold for performing an unattended backup of an entire network (for a discussion of tape drives with more than 1 gigabyte of storage, see the text box "Life Above 1 Gigabyte: DAT vs. 8-mm vs. QIC" on page 197). Our test sample consisted of stand-alone software and software/hardware bundles. In some cases, drive vendors repackage third-party software with only minor alterations. We didn't test the variations, but let the original software represent the group.

Network Concerns

Besides safeguarding data with regular backup schemes, these products attempt to solve problems vital to networks. For example, you should devise a workable tape-rotation scheme so that the loss of a single tape is not a catastrophe. Backup software with integrated schedulers can help. Software can also perform incremental backups, copying only the files that have changed since the last backup. A good rotation scheme will include a regular schedule of full and incremental backups. In one instance, the software can fully automate the rotation process.

What if you need an earlier version of a particular file? A documented catalog of your tapes, together with ample notes,

World Radio History

LAN BACKUP SOFTWARE

The new generation of LAN tape backup software takes some of the drudgery out of administrative chores such as scheduling, file migration, and tape rotation. (● = yes; ○ = no; N/A = not applicable.)

	DOS					MAC
	ARCserve 4.0	**FileSafe 5.2.2A**	**LANStream 1.0**	**The Network Archivist 2.0**	**Powersave 2.2**	**Retrospect Remote 1.3**
Price	$295 to $1895	FileSafe: $495 FileTalk: $495	4-mm DAT:$7495 8-mm, 2.2 gigabytes: $8995 5 gigabytes: $10,795[1]	$995	$1995	$449
Architecture						
Topology	Tape server	Backup workstation	Backup workstation	Backup workstation	Backup workstation	Backup workstation
Push/pull	Push/pull	Pull	Push/pull	Pull	Pull	Pull
System requirements						
Workstations	PC running DOS, OS/2, or Windows	PC running DOS	PC running DOS	PC running DOS	PC running DOS	Mac Plus or better running System 6.0.x or 7.0
Tape server	PC running DOS	PC running DOS	PC running DOS	PC running DOS	PC running DOS	Mac Plus or better running System 6.0.x or 7.0
Network	NetWare	NetWare, LANtastic, PC-LAN, 3+Share	NetWare	NetWare	NetWare, Vines, LANtastic, 10net	Any AppleTalk protocol
User workstation TSR/INIT RAM	18 KB	35 KB	45 KB	10 KB	N/A	97 KB
Protected workstations						
Basic package	Unlimited workstations	3 workstations	5 workstations	350 MB on network	255 workstations	11 workstations/ unlimited servers
Maximum protection	Unlimited workstations	Unlimited workstations	Unlimited workstations	Unlimited network data	255 workstations	Unlimited workstations
Devices supported						
4-/8-mm	●	●	●	●	●	●
Cartridge tape	●	●	○	●	●	●
Floppy disk	○	○	○	○	○	●
Removable hard drive	●	○	○	○	○	●
Multiple devices	●	●	●	○	●	●
Security						
Workstation access password?	●	●	●	○	●	●
Workstations must be logged in?	○	○	●	○	○	●
File management						
Automatic file migration	●	○	●	●	○	○
Phantom files	○	○	○	●	○	○
Back up to other drives?	●	○	○	○	○	●
Macintosh naming support	●	●	●	●	○	●
File histories	●	○	●	●	○	●
Tape rotation						
Method	Grandfather-father-son	Manual	Prompt for blank tape	Tower of Hanoi	Manual	Manual

[1] Prices include software and hardware.

[2] Prices include device drivers but no hardware.

will enable you to restore older versions of important files. Alternatively, backup software can keep track of file histories for you, listing the version dates and prompting for the correct tape when a specific version is restored.

A good backup strategy will also address the thorny problem of disk space on the server. Unused files should be shuffled off to tape and removed from the server altogether. In some cases, a zero-length file will remain on-line so that if the file is called, the backup software will restore the original file from tape and deliver it to the application. The trend is toward tiered storage, where files migrate first to a large-volume on-line storage medium such as read/write optical before being archived to tape.

And what about the workstations on your network? More often than not, local stations will not have the resources available to maintain a regular schedule of disk backup. So what happens to all that vulnerable data? Until recently, you had to resort to third-party peer-to-peer networking extensions to make other workstations accessible to a single tape drive. Older backup software isn't always network-aware, but as long as it thinks that a drive is local, it will dutifully save its contents to tape. Anyway, clients no longer store valuable data on their hard drives—it's all on the server, right?

Not necessarily. Windows and Mac applications tend to be huge nowadays, and to speed up network operations, most clients keep their applications and data on local hard drives. While the mission-critical shared database information is probably on the server, there's likely to be more and more valuable stuff on individual workstations. Distributing data throughout the network is common in Unix installations. That's where the new crop of tape backup software comes in—it can reach through the wires and grab data from anywhere for safekeeping.

Most versions of Unix include a set of commands that handle file backup and restore operations. Despite the cost benefits, however, the standard Unix backup utilities provide only the most primitive capabilities; some even lack the ability to span multiple tapes. Berkeley Standard Distribution flavors of Unix, and those that borrow from BSD, add access to remote tape drives through the network. Again, this facility is primitive, and performance is far from optimal.

Besides using different rotation plans and having very different user interfaces, these systems exhibit substantial differences in backup topologies. FileSafe, TNA, Powersave, and Retrospect Remote put the tape drive on one worksta-

World Radio History

	UNIX	
	BudTool 4.0	**Legato NetWorker 3.0**
	Prices range from $4995 (for single tape drive support) to $29,995 (for a large jukebox)[2]	$2000
	Tape server Push/pull	Tape server Push/pull
	Unix	Unix, DOS (with PC-NFS)
	Unix	Unix
	TCP/IP	TCP/IP
	N/A	N/A
	One server, unlimited nodes Unlimited workstations	5 workstations 200 workstations
	●	●
	●	●
	○	●
	●	●
	●	●
	Through Unix ●	Through Unix ●
	○	N/A
	●	N/A
	●	●
	N/A ●	●
	Manual	Tape expiration dates

tion—most likely the system administrator's. That workstation runs a standalone application that accesses the file servers and other workstations (see part a of the figure). LANStream requires you to designate a workstation as a dedicated backup server. ARCserve treats the tape drive as a shared resource (see part b of the figure) and puts the drive on one of the system's NetWare servers. The administrator grants access to a backup queue, and clients post requests to the server. BudTool and Legato NetWorker use Unix's multitasking capabilities to turn one of the networked workstations into a nondedicated tape server.

Test-Beds

We installed each package on one of three test-beds. Our NetWare test-bed consisted of a 486/33 file server running NetWare 3.11, Dell and Tangent 386/25 workstations, and an assortment of 4- and 8-mm helical-scan tape drives. Some drives came with their own proprietary SCSI controllers and drivers; others supported an Adaptec 1522 SCSI controller.

We tested the two Unix packages on an isolated network that included an Opus System 5000 SPARC workstation, an Altos System 5000 486/33 file server, and several DOS systems. We set up the Opus as the backup server using its 150-MB internal quarter-inch cartridge (QIC) tape drive as the backup device.

Retrospect Remote ran on our Macintosh AppleShare network with a mixture of AppleShare and NetWare for Macintosh AFP–compliant servers. As workstations, we used a Mac IIfx connected to an Irwin 5080 cartridge tape drive, an Archive Python 2-gigabyte digital audiotape (DAT) drive, and an Iomega Bernoulli 90 removable cartridge drive. The clients were a Mac IIci and a Quadra 900 running System 7.0, and a Mac II with a Radius Rocket running System 6.0.5.

Testing software designed to recover from catastrophic events is a complex task. We had to simulate weeks of normal use and then create a disaster. For each package, we formatted a set of tapes and backed up the network repeatedly to test the rotation and tape overflow features. To get a feel for recovery mechanisms, we occasionally deleted directories and restored them from tape. When a package used the network storage for its own database (rather than storing it on tape), we damaged the database to see how well the software handled it.

Given so many different architectures and tape drives, we could not make objective performance comparisons. Performance on your network will depend on the particular tape drive, the network transport layer, and the I/O performance of your tape drive and interface.



Screen 1: *NetWare administrators should feel right at home with ARCserve's user interface. The Insert key brings up pick-list items, and you manage the backup job queues just like any other NetWare queues.*

ARCserve 4.0

DOS

Of the DOS packages, Cheyenne Software's ARCserve had our favorite topology: The tape drive attaches to the file server, and the system administrator establishes backup queues much like NetWare print queues. Any client with access rights can then post a backup request to the server.

ARCserve looks exactly like any other NetWare utility (see screen 1). To place a backup job in the server queue, you select a queue from a pick list and press the Insert key. A window then pops up displaying the Unattended Operations menu. You select a function and choose a predefined script or make up a new one. The job will execute at the time you specify, whether you're logged in or not. The server knows enough to prompt you for a particular tape if you've specified one by name. You make your workstation accessible by running one of three TSR programs: DOSAGENT publishes your workstation by node address and makes your files available over the Novell IPX/SPX transport layer; WINAGENT does the same for workstations running Windows; and OS2AGENT is a background process for OS/2.

ARCserve uses a grandfather-father-son tape rotation scheme. This is perhaps the most common method for desktop computers and one that works well if you're diligent about keeping track of which tapes are which. Basically, you start with a full-system backup on a given day of the week. For the rest of the week, you perform incremental backups (i.e., backing up only new or changed files), preferably on a new tape each day. On full-backup day next week, you use a fresh tape to do another full backup. The full backup from the previous week

World Radio History



(a) *Most centralized LAN backup systems place the tape drive on an administrator's workstation. On demand or on schedule, the backup software reaches out through the network and grabs files from the servers and other workstations. Workstations have to "publish" their local drives to make them look like file servers.*
(b) *A shared tape drive is a resource, just as a printer or a high-speed modem can be. In some installations, putting the tape drive on the file server makes sense. Unlike an administrator's workstation, the file server rarely gets turned off, making it ideal for backup service. Another benefit is that, to back up the server data, the files don't have to be shuffled over the network.*

becomes an archive tape or is put into a 4- to 6-week rotation, depending on your needs.

At any given time, you can bring the system to a known state by restoring the last full backup and all the incrementals. ARCserve automatically handles the rotation by giving each day's tape a different name and making the right kind of backup (i.e., either full or incremental). It's still your responsibility to manage the sets of tapes.

ARCServe for NetWare 3.11 installs as a NetWare loadable module. You simply log into the server as SUPERVISOR, run a simple installation package, and then load the NLM from the server console. You specify ARCserve queues with a given user list and priority. Tape operations can be either attended or unattended. Attended backups happen on-screen while you wait. If the tape driver is busy, you get a message on-screen, and you're asked to try again later. Unattended backups go into a backup queue and get processed later at a time you specify.

We tested ARCserve with two Python 2-gigabyte 4-mm DAT drives connected to a single Adaptec controller. ARCserve queues aren't specific to a given drive; selecting the right drive on the SCSI bus is left to the ARCserve SCSI driver, which scans the tape labels looking for a match. If it can't find one, you get a NetWare message at the bottom of your screen asking for a new tape. We had no difficulty getting ARCserve running after we updated the IPX shell to the latest version (3.10), but the constant stream of NetWare SEND messages got to be a bit annoying.

FileSafe 5.2.2A

DOS

Mountain Network Solutions' FileSafe provides two distinct user interfaces. A menued interface packs all the major functions of the software into an easy-to-use shell. Command-line utilities give you the same power through customized batch files.

The menued interface follows a hierarchical structure. The first screen presents the basic operations: backing up, restoring, and verifying. When you choose an option, such as Backup, from the main menu screen, a second screen appears with a menu offering the choice of Full, Selective, or Automatic backup. Should you choose to do a selective backup or restore, you are then presented with a list of drives, directories, and files to pick from. You can then tag the files you want to operate on. At this point, you can call an Include or Exclude box and use DOS wild cards to select or filter out specific sets of files. You can also restrict the backup to a specified range of dates, or you can back up only files created or modified since your last tape backup.

The Automatic menu option lets you schedule recurring jobs. You select the days of the week when you want the backup to run, the time to run the job, and the interval between jobs. You can then run a job every week on the specified day or at any set interval (e.g., every 2 hours).

According to Mountain Network Solutions, the tape drive has Quick File Access capability. QFA uses block addresses to locate data instead of sequentially reading through files. This feature did not appear to be operational in our setup. The drive seemed to read through the tape, trying to locate the files. At one point, the software took forever to display the directory structure of a selected drive. With the directory on-screen, we called for a backup but forgot to designate specific files. The software told us that no files had been selected. FileSafe had to search through the tape again to redisplay the directory.

FileSafe includes a full set of programs invoked from the DOS prompt. It also has a TSR scheduler that will fire off any command at an appointed time. If your system is busy at the appointed time, you can tell the scheduler to wait until the system is idle, or you can have the scheduler preempt a running program. We found the scheduler to be a bit

World Radio History

Life Above 1 Gigabyte: DAT vs. 8-mm vs. QIC

Roger C. Alford

Three primary tape-drive technologies are available that can accommodate the high-capacity storage requirements of modern LANs: digital audiotape (DAT), 8-mm tape, and quarter-inch cartridge (QIC). These alternatives offer trade-offs in capacity, speed, size, backward compatibility, and price, so you must choose the right platform based on your specific requirements.

Basic Technologies

Long popular for lower-capacity backup, QIC drives have recently reached into the 1-gigabyte-plus capacities. The QIC-1000 drives introduced last year support 1 gigabyte of data storage on a single DC6000 cartridge, and the newer QIC-1350 drives appearing this year tout a 1.35-gigabyte capacity.

DAT has been establishing itself for data backup since its introduction to the audio market in 1986. The DAT drive market has standardized on two incompatible data formats: DDS (digital data storage) and Data/DAT. DDS has achieved the greatest industry acceptance, and it is used by most current DAT drives. Data/DAT is somewhat slower than DDS but allows block and sector updating and high-speed file searches.

There are now numerous DAT drive manufacturers, including many of the established QIC drive producers. DAT drives offer 1.3 gigabytes of storage on a standard 60-meter data cartridge, and 2 gigabytes on the longer 90-meter cartridge. DAT cartridges use a 4-mm-wide metal-particle medium, and, at under ½-inch thick and smaller than a business card, the package is the smallest of the high-capacity data cartridges.

Eight-millimeter drives, introduced by Exabyte in 1987, are based on VCR technology. Exabyte remains the sole manufacturer of these drives, although many companies private-label the Exabyte drive. These drives use a data cartridge about the size of a deck of cards, incorporating an 8-mm-wide metal-particle medium. The 8-mm drives are available in 2.5- and 5.0-gigabyte capacities. The ISO recently voted to standardize Exabyte's 8-mm tape format.

Drive Comparisons

All the drives incorporate read-after-write data verification to ensure data integrity and use embedded error-correction codes to recover data if any data becomes corrupted. Most implementations of these high-capacity tape drives use the popular SCSI connection. While DAT drives are commonly available in a 3½-inch half-height form factor, QIC-1000/-1350 drives generally maintain a 5¼-inch half-height profile. The 8-mm drives have been traditionally packaged in a 5¼-inch full-height form factor, although newer half-height models are now available.

QIC standards allow the 1-gigabyte-plus drives to read tapes from lower-capacity drives (e.g., the popular 525-MB QIC drives) and permit interchange of tapes produced by different drive manufacturers. The established DDS standard also allows data cartridge interchangeability among the DAT drive manufacturers, but as I've mentioned, the DDS and Data/DAT formats are not interchangeable. Since Exabyte is the sole 8-mm drive manufacturer, compatibility is not an issue.

The different drive types vary in speed. QIC-1000 drives can transfer data at 200 KBps, while QIC-1350 drives offer transfer rates of up to 600 KBps. DAT drives transfer data at a slower 180 KBps. Finally, 2.5-gigabyte 8-mm drives transfer data at 246 KBps, and their 5-gigabyte big brother touts a 500-KBps data transfer rate. Data compression, now used almost universally by tape drive manufacturers, effectively increases these data transfer rates as well as data storage capacities.

Cost is always an important issue. It's likely that QIC drives will maintain the lowest price tag of the high-capacity alternatives, but DAT price drops this past year promise to give QIC some competition. QIC-1000/-1350 drives typically cost between $2000 and $4000, while typical DAT prices range between $2500 and $6000; recent DAT drives, however, have sold for as little as $1500. The capacity-king 8-mm drives will probably remain the premium backup alternative for the foreseeable future, generally costing well over $5000 for a 2.5-gigabyte model and over $10,000 for a 5-gigabyte unit. Media costs for all the drives are similar, at between $20 and $40 per cartridge.

Future capacity increases for the competing tape drive technologies are unclear. Current QIC plans call for capacity increases to 35 gigabytes within five years. DAT will probably reach 5 gigabytes within the next two years but may not go much higher. Similarly, Exabyte is expected to introduce a drive with an 8- to 10-gigabyte capacity within the next two years, but further capacity increases may be slow in coming.

Roger C. Alford, a BYTE consulting editor, is president of Programmable Devices, a Michigan-based electronics design firm. He can be reached on BIX as "rogera."

World Radio History

limited and unreliable. The preempting feature will not work in graphics mode or if your program is making DOS calls or accessing the hard disk.

If you prefer, you can set up batch files to automatically perform your backup chores. This takes some knowledge of DOS batch files, but Mountain offers help both in the documentation and by providing useful samples on disk. Mountain's standard `bkall` batch file does a full backup of all workstations. We added just a few lines and included full backups of all the file servers as well.

The FileTalk software provides a solution for backing up local workstation disks across the network (based on the Pipes peer-to-peer kernel). Published drives appear across the network with a user prefix (e.g., BILL:C:). You can back up any published drive from the administrator's station as if the disk were local.

We found FileSafe to be reliable and solid, if a bit slow and unresponsive at times. It will do the main job of LAN backup, but it can't help you with scheduling, tape rotation, file grooming, and other advanced administrative tasks.



Screen 2: *The LANStream interface lets you select files from a directory tree. From pop-up boxes, you can exclude or include sets of files using DOS wild cards and other filters such as date stamps and NetWare's last-access flag.*

LANStream 1.0

DOS

In automating your backup chores, Maynard Electronics' LANStream doesn't go as far as TNA (see below), but it stakes out a solid middle ground. For instance, LANStream has no rotation software of its own but prompts you for new tapes as needed. You can schedule rotation for an interval of your choosing, and at the appointed time the system asks you for a new tape. LANStream opts for a simple and effective approach, sacrificing some power along the way.

That's not to say that LANStream is a bare-bones offering. Far from it. The software treats tape drives as shared devices so that each workstation can access the drive and schedule a wide assortment

DATA COMPRESSION LIBRARIES™

PKWARE's® Data Compression Libraries™ allow software developers to add data compression technology to software applications. The application program controls all the input and output of data allowing data to be compressed or extracted to or from any device or area of memory.

- All Purpose Data Compression Algorithm Compresses Ascii or Binary Data Quickly with similar compression achieved by the popular PKZIP software, however the format used by the compression routine is completely generic and not specific to the PKZIP file format.
- Application Controlled I/O and memory allocation for extreme flexibility.
- Adjustable Dictionary Size allows software to be fine tuned for Maximum Size or Speed.
- Approximately 35K memory needed for Compression, 12K memory needed for Extraction.
- Compatible with most popular Languages: C, C+ +, Pascal, Assembly, Basic, Clipper, Etc.
- Works with any 80x86 family CPU in real or protected mode. $295.00
- No runtime royalties.

RUNNING OUT OF EXPENSIVE DISK SPACE?

PKZIP can help! PKZIP compresses your files to free up disk space and reduce modem transfer time. You can compress a single file or entire directory structures with a single command. Compressed files can be quickly returned to their normal size with PKUNZIP.

Software developers can reduce the number of diskettes needed to distribute their product by using PKZIP. Call for Distribution License information. *See us at Comdex, Booth #862*

The included PKZIP utility lets you store compressed files as a single self-extracting .EXE files that automatically uncompresses when run. Only $47.00

PKWARE® INC.
THE DATA COMPRESSION EXPERTS®

9025 N. Deerwood Dr.
Brown Deer, WI 53223
(414) 354-8699
Fax (414) 354-8559

BY492

Circle 107 on Inquiry Card.

World Radio History

ALWAYS STORE YOUR VALUABLES IN A SAFE PLACE.

On Verbatim® data storage products. They start out backed by a complete Verbatim warranty. And then they get better.

For example, our DataLife® Colors disks let you color-code your files for convenience and added security.

Teflon® is a DuPont registered trademark.

Our Teflon®-coated DataLife-Plus® disks let you wipe off fingerprints, dust, even pencil shavings. Without wiping out information.

Our 5.25-Inch and 3.5-Inch Rewritable Optical Disks are virtually incapable of losing data. Plus, they both have enormous storage capacities.

And our data cartridges, high density data cassettes, data certified 8mm/4mm data cartridges, and reel tapes live up to the same impeccable safety standards we've set with our disks.

So next time, ask for Verbatim. And get the name you can't lose with.

Circle 132 on Inquiry Card.

V E R B A T I M®

World Radio History

of jobs. One workstation on the network becomes a dedicated tape server. Ideally, you'd run the server software at the end of the day and schedule your tape backup jobs after hours. Another approach might be to set up a system and dedicate it to running the LANStream server software. You can perform certain administrative tasks from the tape server, but the bulk of the work—backup, restores, transfers, and scheduling—would be performed by the LANStream workstations.

To manage data on the network, LANStream employs NetWare's Btrieve. (You'll need Btrieve 5.16 or higher to get up and running.) We had to acquire an update patch, and even then the NLM reported some intermittent errors. Each client on the network who wants to access the tape server must install a copy of the workstation software. The software assigns the NetWare log-in name to the installed workstation, so if you have people sharing a single workstation, they have to share a single NetWare account.

Once the software is installed, the workstations can tap the tape drive as a shared resource. Each workstation's capabilities are limited by a combination of the user's NetWare and LANStream privileges. From the workstations, users can back up mapped NetWare drives as well as their local drives. They can also run a TSR (i.e., IsleLAN) and publish their local drives for other workstations on the network.

The software presents an easy-to-use menued interface. From the workstation, three basic tasks are available: backup, restore, and transfer; each task has a pull-down menu associated with it. To perform an operation, you choose the appropriate menu and select the files you want to work with. You can select entire drives, a range of subdirectories, or individual files. Files can be included or excluded by wild-card designators or date ranges (see screen 2). By selecting the Transfer operation, you can perform selective file "grooming" by transferring only those files not accessed in, say, 180 days (you can select any period up to 999 days). The files selected would then be copied to the tape drive and removed from the network drive.

LANStream makes it easy to create scripts. You simply select the operation you want scripted, designate the files to be included in the operation, and then select a menu option to save the script. The integrated scheduler lets you set up jobs to run at a particular day and time or at any interval you designate.

LANStream also supports multiple drives on the tape server. Each tape drive can be limited to a particular group of users (e.g., a department) or even to different operations (e.g., a tape drive could be set up for restore jobs only). This type of flexibility is LANStream's greatest strength. If you want a single administrator to be in charge of backup operations, that's no problem; users can simply publish their drives. On the other hand, you can off-load some of the administrator's responsibilities by leaving it up to the users to back up their own local drives while the administrator backs up the network. It's a nice compromise between the fully automated TNA approach and the traditional manual approach. You have the tools to do what you want, but it's still up to you to set up an efficient backup strategy.



Screen 3: *For manually archiving files onto tape, The Network Archivist provides an easy, point-and-shoot menu system. Automatic operations take care of themselves.*

The Network Archivist 2.0

DOS

Palindrome's TNA (see screen 3) is easily the most ambitious of the backup packages we looked at. It doesn't treat your backups as a series of tapes, but rather as a vast collection of data that just happens to be scattered among a series of tape sets. In short, you don't use TNA to copy data onto tapes, but to manage your files, and you trust it to handle the tapes any way it wants.

The way the package likes to work is through fully automatic tape rotation using a Tower of Hanoi algorithm. Popular among the minicomputer and mainframe crowd, this algorithm chooses among five or seven tape sets, depending on the parameters you select. This scheme improves on the standard father-son algorithm by making more versions of your data available with less tape and less backup time.

You start by doing a full backup to one tape set—call it A. The next day's tape will be B, and so on until you get to G. The rotation scheme calls for G to be updated every 2 days, F every 4 days, E every 8 days, and then back to A and B, which each get updated every 16 days. The algorithm gets its name from the children's game that uses a stack of different-size disks and three poles. The idea is to transfer the entire stack of disks from one pole to another by moving one disk at a time and always placing a smaller disk on a larger one. For every disk (i.e., backup tape) you add, the number of moves (i.e., backups per rotation) will double.

To save on the amount of data written to tape, TNA considers that any data that has been stored onto three tapes without being changed is *saved* and that data won't be written to tape again. The software tracks the file's access history and, once it becomes stable, makes sure that it resides permanently on three tapes. Some time later (12 weeks by default), the file becomes eligible for migration or grooming. At the administrator's discretion, eligible files can be identified and purged from the file server. The file will be replaced with a zero-length phantom file and flagged in TNA's database. If your PC then tries to access the file, TNAFNTOM (a DOS TSR) will trap the access and tell you that the file has migrated to tape.

For workstation backup, TNA uses a pair of TSRs, TNAWS and TNACNTRL, based on Fresh Technology's Map Assist, a NetWare peer-to-peer networking package. TNAWS makes your workstation's drives available to other workstations, and TNACNTRL lets the backup

World Radio History

There's only one way to get around out here.



PC/TCP® PLUS

OS2 VERSION NOW AVAILABLE!

The most comprehensive TCP/IP implementation in the industry.

SUPPORTS NFS!

No matter who or what your PC needs to communicate with, there's nothing like PC/TCP Plus. It's not only the fastest, but also the most comprehensive TCP/IP implementation in the industry. And PC/TCP Plus has NFS™ access built right in.

Providing connectivity to other PCs, minicomputers and mainframes, PC/TCP Plus communicates over Ethernet, Token Ring and StarLAN networks with operating systems ranging from UNIX and VMS to VM and MVS. And you can forget hardware incompatibility; PC/TCP Plus supports the largest selection of LAN interfaces in the business.*

From around the world to around your office, now your PC can transfer files, send and receive electronic mail, emulate VT100, VT220 and IBM 3278 terminals, access NFS servers, and much, much more. VINES™ and NetWare™ users will appreciate PC/TCP's full compatibility, as will customers of Oracle's distributed PC database products. And with our Development Kit, including a Berkeley Sockets library, you have all you need to produce custom applications.

So, the next time you want to get from here to there, get PC/TCP Plus, the TCP/IP implementation that gives you a whole new perspective on network communication. Call us at (617) 246-0900 for more information.

VAR Inquiries Welcome
Reseller Inquiries Invited

PC/TCP is a registered trademark of FTP Software, Inc.
VINES is a trademark of Banyan Systems, Inc.
NetWare is a trademark of Novell, Inc.
NFS is a trademark of Sun Microsystems, Inc.

FTP Software, Inc.
26 Princess St.
Wakefield, MA 01880-3004
Phone: (617) 246-0900
Fax: (617) 246-0901

ftp Software, Inc.®

*PC/TCP Plus supports interfaces from Acer, Allied Telesis, Apricot, AT&T, BICC, DEC, D-Link, DSC, Excelan, Gateway Communications, IBM, IMC Networks, Intel, Interlan, Longshine, MCAssociates, National Semiconductor, Novell, Proteon, Schneider & Koch, Scope, 10Net, 3Com, Tiara, Torus, TRW, Ungermann-Bass, Univation, Western Digital and YCS, in addition to the ASI, NDIS and Packet Driver specifications.

Circle 72 on Inquiry Card (RESELLERS: 73).

World Radio History

workstation see the mapped drives as local. Straight out of the box, TNA will manage up to 350 MB of data per network. As your network grows, you can add more coverage with extension disks: The first boosts TNA's capacity to 1.3 gigabytes; the second gives you the ability to manage unlimited amounts of data.

Our only reservation about TNA is that it may be *too* automatic. Tape backup should be a system administrator's responsibility. If a file server crashes and needs to be restored, it's the administrator's responsibility to restore the right files from the right tape. TNA follows a complicated algorithm and makes a number of decisions on its own without any human input. With the disk database destroyed, TNA needs you to insert the correct tape to rebuild it, and it won't know which tape it wants. If you haven't been paying attention to the rotations, you may not know, either. Tape recovery works well. The only way we found to confuse it horribly was to manually scramble its disk database.

If you wind up using TNA, we suggest you keep a small calendar nearby and jot down the tape-set ID it asks for each day. That way, if a catastrophic event occurs, you won't have to guess which tape is which and possibly restore old files by mistake. TNA's attention to data security makes it a superb choice for most LANs. Just remember—it's *your* data, and ultimately you have to take responsibility for protecting it. TNA will do the hard part; all you have to do is watch and pay attention.

Powersave 2.2

DOS

Offering a well-organized menu-driven interface, Performance Technology's Powersave is easy to install and use. Unfortunately, the software pales in comparison to the new breed of automated, full-featured programs such as ARCserve, LANStream, and TNA.

The main menu offers basic options, including save, restore, and utility selections. From the save menu, you can select an entire network or pick specific subdirectories and files. The interface includes smooth mouse support for triggering menu options and selecting drives or files. It also features sliding bars to indicate the progress of backup and restore operations—handy when you're waiting for long jobs to finish.

The utility menu option lets you check a tape's contents or perform diagnostics and maintenance tasks. From this option, you can also create automated scripts. The software creates a batch file and a data file containing control instructions passed to the batch file. You can then conduct an unattended backup session by running the batch file. The batch file performs the backup by using a command-line version of the software along with the parameters supplied by the data file. A "wait" option will hold the backup job until a specified time.

Powersave provides some of the sophisticated features of the more advanced packages, but they are not implemented in a very sophisticated way. For instance, background scheduling is offered via a bundled TSR that will run any DOS batch file at a specified time. The program simply squirts out the character string needed to start the batch file at the appointed time. As long as you are sitting at an inactive DOS prompt, it works fine. When we were in an application, however, the character string was simply fed to the application.

The solution for backing up workstations on the network also falls short. Each workstation has to run an access application, becoming in effect a temporary file server. While it is waiting to be backed up, the workstation cannot run any other application software. Workstation backups proceeded without a hitch, but other solutions offered in this review work as well without tying up all the resources of the workstation.

We also had some reliability problems with the software. When our backup job required a second tape, Powersave ejected the first tape and then refused to accept a new one. We were unable to recover data from the first tape. We also had some problems running the software with a supported 8-mm tape drive. Technical support, although helpful, was unable to re-create the problem.

Powersave works well as a simple utility for backing up local and network drives. It's quite fast and very easy to use. However, if you want the advanced features of today's more sophisticated LAN backup software—scheduling, tape rotation, and grooming—you'll have to look elsewhere.



Screen 4: *NetWorker's GUI includes a graphical file-selection window and a console screen that constantly reports the status of the backup server.*

Legato NetWorker 3.0

UNIX

Legato Systems' NetWorker is an elegant solution to a very complex problem. Its emphasis is on automating the organization that's needed to manage backups, particularly for large networks of systems. It's appropriate, therefore, that NetWorker calls on you to do a small amount of advance setup. It ships with a reasonable set of defaults, but it clearly works best when you lay out a backup strategy in advance and use NetWorker's facilities to manage that strategy for you.

The basic plan is this: You create a library of tapes (NetWorker handles QIC, 8-mm, 4-mm, and reel-to-reel tape) and mark each tape with two labels: one that you write on the outside, and one that NetWorker encodes both on the medium itself and in an index file on the backup server's disk. Backups can be kicked off automatically by NetWorker, based on a schedule that can be applied systemwide, on a per-system level, or to a group of related systems. Systems that are running the Legato client software can also request backups and restores through the network.

Because Legato NetWorker maintains

World Radio History



#1 Text Retrieval Software

"Powerful and flexible search capabilities; extremely easy to learn and use."
–Patrick Marshall
InfoWorld, August 5, 1991

Finds needed information quickly.

ZyINDEX simultaneously searches all files, thousands of pages, entire networks, with results in less than 3 seconds!

Searching is easy. To find a word, just type it. Instructions are clear and readily available.

Versatile. Powerful. ZyINDEX provides the widest range of search techniques:

- **Boolean Logic • Thesaurus**
- **Comments • Phrase Searches**
- **Numeric Range • Field Searches**
- **Wildcards • Conceptual Searches**
- **Proximity Searches... and more.**

Prepare your entire drive for searching with just one keystroke. Ideally suited for networks and frequently changing text.

ZyINDEX finds every occurrence of your search request.
Select any file for viewing.
Browse or jump from hit to hit.
Copy, paste and print.

Available for DOS, Windows and UNIX. Supports WordPerfect, Word and most other word processor formats.


Type a search request.


View file with hits highlighted.


List of files found.



ZyLAB
a Division of *Information Dimensions, Inc.*

100 Lexington Drive
Buffalo Grove, Illinois 60089
(708) 459-8000
FAX (708) 459-8054

Call 1-800-544-6339
Demo disk available

BYTE DEMO 94K Free Demo Download 617-861-9767*

©1991

Circle 143 on Inquiry Card (RESELLERS: 144).

World Radio History

a detailed index on the server's disk (an index that can be restored in the event of a server failure), a restore request can be filled quickly; a message appears on the server's console instructing the operator to insert the appropriate tape. NetWorker's index files can also be queried. If your archives contain several versions of a single file, for example, the index will let you restore any one of them.

As we said, NetWorker is plainly built with large networks in mind. It eases the management of multiple servers, multiple backup devices per server, multiple simultaneous client requests, and so on. Because NetWorker writes label data onto each tape, the common error of inserting the wrong tape or writing over an old volume is minimized. Finally, Legato's documentation includes an extensive tutorial on planning backup strategies.

NetWorker is actually a set of Unix command-line utilities that act together to handle backups and restores, tape library management, data compression, and other functions. On the Sun/SPARC version, a very effective Open Look interface is included that ties the utilities together (see screen 4).

NetWorker uses a proprietary scheme for writing the data to tape and will apply compression at your discretion. In our tests, compression seemed to work very effectively, reducing a 30-MB test backup tree to a reported 8.6 MB on tape. This surprisingly high compression ratio was partly due to a high percentage of source code files in the test tree, but Legato still deserves credit for such an effective compression scheme. It took 6 minutes to write the compressed 30 MB to tape; that's a solid 5 MB per minute, but compression played a role in that, as well.

NetWorker's interface is impressive. It's very easy to learn and use, and the file-selection mechanism (invoked by clients posting a backup request to the server) is easy enough for even the most inexperienced users to understand.



BudTool 4.0

UNIX

Delta Microsystems' BudTool 4.0 is a step away from the self-contained, proprietary approach of Legato NetWorker. BudTool is a set of programs and user-interface elements that form wrappers around existing Unix backup utilities like `tar`, `dump`, and `cpio`. What's more, while NetWorker's emphasis is on tight control and ease of use, BudTool appeals more to experienced Unix system administrators.

Many elements of BudTool are similar to those of NetWorker. BudTool maintains server-based databases of tapes and schedules and can handle both automated and manual backup requests. Also similar is the way in which clients can post backup requests through the network. In fact, both packages serve roughly the same purpose and offer roughly the same set of capabilities. There are, however, some important differences.

Because BudTool uses standard Unix commands, the data on the backup tape can be read by any system, even one without BudTool. The converse is not true, however; you can use BudTool only to manage BudTool tapes, because of the required label file placed at the front of each tape.

While portability can be seen as an advantage, it carries all the disadvantages of whichever Unix program is chosen to handle the transfer. Some are slow,

Circle 155 on Inquiry Card (RESELLERS: 156).

World Radio History

EXB-120 CHS
580 Gigabytes

EXB-8500
5.0 Gigabytes

EXB-10 CHS
50 Gigabytes

EXB-8200
2.5 Gigabytes

EXB-8205
2.5 Gigabytes

8mm Supplies
Data Cartridges
Cleaning Cartridges
Cartridge Holders

WE CREATED OUR FAMILY SO YOU CAN SPEND MORE TIME WITH YOURS.

Our family of high-capacity 8mm data storage solutions means less time storing data and more time for yourself.

Whether it is simply backing up your workstation or accessing near-online network data bases, EXABYTE's 8mm cartridge tape subsystems and cartridge handling subsystems feature native data capacities from 2.5 gigabytes to 580 gigabytes.

So from high-end PCs to super computers, EXABYTE has the right 8mm data storage solution. For more information, call the regional office nearest you or **1-800-EXABYTE.**

And remember. We created our family so you can spend more time with yours.

EXABYTE®
THE CAPACITY TO SUCCEED

Eastern U.S. (407) 352-5622, Ext. 82
Central U.S. and Canada (708) 953-8665
Western U.S. (714) 582-5211, Ext. 4
Europe (Amsterdam) 31-3403-51347

Circle 68 on Inquiry Card (RESELLERS: 69).

EXABYTE Corporation 1685 38th Street Boulder, CO 80301

©1991 EXABYTE Corporation

World Radio History

others can't span multiple tapes, and all lack the ability to compress data. While some administrators prefer to do without it, we can't imagine backing up a large network without data compression; it seems like a waste of expensive tape. To its credit, Delta Microsystems does include an option for creating a custom backup/restore command. You can specify a pipe sequence that includes compression and decompression.

BudTool's interface is somewhat sparse compared to Legato NetWorker's, but it seems to cover all the bases. The file-selection dialog box isn't as elegant, either, but the basic ability to mouse around to select files is supported.

Overall, BudTool is an extensible set of network backup tools for advanced system administrators. The back of the manual lists the formats for all the internal files used by BudTool's various modules and also includes a description of a language used to generate tape labels from symbolic expressions. This is an incredibly versatile foundation for a network backup system, but its best audience is those who are prepared to invest a lot of time in tuning and configuration.



Screen 5: *Retrospect's Browser window is the heart and soul of the package. This is the default view of a single drive, but you can select from a number of views depending on the level of detail you need.*

Retrospect Remote 1.3

MAC

The regular version of Dantz Development's Retrospect, which supports many different kinds of tape drives, is included with a number of tape drives and Iomega's Bernoulli 90 removable cartridge drive. Retrospect Remote is simply an extension that gives the program access to workstation disk drives.

After an easy installation, you fire up the application on the backup Mac and choose "Remotes" from the configuration menu. Retrospect looks out on the network and gives you a list of all the machines (by name) that are currently running the Remote INIT. You activate each workstation by assigning it a unique ID

"... ISYS replaces ZyINDEX for DOS as the industry standard for unstructured DOS text retrieval programs."† PC Sources 11/91

	ISYS 2.0	ZyINDEX 3.1 for DOS
SEARCH CAPABILITIES		
• Full range of capabilities: Boolean logic, Proximity, Wildcard and Phrase searches.	YES	YES
EASE OF USE		
• Terminate-and-stay-resident (TSR) option: ability to run search without leaving your document.	YES	NO
• Activate word processing documents from within the search program.	YES	NO
• Cut and Paste to anywhere in your document.	YES	NO
• All functions from main menu. No need to return to DOS to execute functions.	YES	NO

Text retrieval faster than a speeding bullet...

Usually, the time you want to find information most is when you're in the middle of something. Without exiting your work, pop up ISYS, get what you need, then copy and paste it into whatever you're working on!

Don't take our word for it. PC Week, May 1991, rated ISYS tops in flexibility and functionality, as well as file compatibility and quality of documentation.*

PERFORMANCE		
• Consistently faster indexing and retrieval.*	YES	NO
• Network pricing based on concurrent usage.	YES	NO
TECH SUPPORT		
• Unlimited toll-free technical support.	YES	NO

$99 TRADE-IN OFFER: Send us your ZyINDEX disk and receive your ISYS replacement by return mail. $395 value.

Free ISYS Demo Disk: 1-800-992-ISYS (1-800-992-4797)

od ODYSSEY DEVELOPMENT

17th Floor, 3900 West Alameda Avenue, Burbank, CA 91505, (818) 972-1798 Fax (818) 972-1636

*PC Week comparative review (May 20, 1991) revealed search times between 25% and 53% faster than ZyINDEX, and index creation time 32% faster than ZyINDEX (tests performed by PC Week Labs on identical databases).
†PC Sources, November 1991

Circle 161 on Inquiry Card (RESELLERS: 162).

© 1992

World Radio History

THE FIRST REWRITABLE OPTICAL DISK WITH A 30 YEAR WARRANTY.

(BUT THAT'S ONLY ONE REASON TO BUY IT.)

NOW FORMATTED

When you're selecting a rewritable optical disk, one vital thing you should consider is the length of the warranty.

But that's only one reason you should look to Sony and our new 30 year warranty.

Only Sony designs and manufactures both 5.25" rewritable optical media and drives. In fact, two out of three 5.25" optical drives in use today are made by Sony.

And each and every sector of a Sony rewritable optical disk is 100% tested, so you can be sure your disk will perform when you need it.

Even 30 years from now.

To learn more about the ideal optical media for you, send for your free 50 page Optical Media Evaluation Guide. Optical Media Division, Sony Recording Media, Sony Drive, M.D. 3D2, Park Ridge, N.J. 07656. Or fax 201-930-6806.

SONY

SONY RECORDING MEDIA™

ONLY ON SONY RECORDING MEDIA

World Radio History

number (three come with the package; you buy extra ID numbers up to a total of 2400). Once you assign an administrator's password to the backup workstation, your network is secure. If you like, you can have Retrospect encrypt the data moving over the network so that AppleTalk packet snoopers can't see anything recognizable.

The interface is all Macintosh. Protected volumes appear by name and icon, and workstations, local hard drives, and file servers all appear interchangeably. To access specific files on a volume, you just click on the volume and bring up a Browser window (see screen 5). Each file and folder appear in hierarchical order, with a very nice thumbnail on the left and each selected file marked with a check.

Backups are managed in a backup set, to which you assign a name and a set of backup rules. The set keeps track of a list of files it knows to be on tape. Scripts automate the process of selecting multiple volumes and applying access rules. For example, you may decide that on Monday you want to do full backups and that on Tuesday through Thursday you want to back up only the data files that have changed since their last backup. You can specify the backup rules by name, file type, date, and so on, to a dizzying level of detail. A scheduler allows you to have Retrospect Remote automatically start at a given time and run a script.

Besides supporting a wide variety of QIC and 4- and 8-mm tape, the software will back up to any mountable drive, including Bernoulli and SyQuest cartridges. We tested Retrospect with an Archive Python DAT drive, an Irwin 5080 (120-MB) DC2000 tape drive, and a 90-MB Bernoulli drive. With file compression, Retrospect was able to cram about 150 MB of data onto each 90-MB cartridge. Our Mac IIfx is connected to the AppleShare network through standard 230,000-bps PhoneNet wiring, so the network was the gating issue in performance. Our test backups managed to send about 1 MB per minute to the Irwin 5080—not too shabby a showing for a mere LocalTalk network.

Multiplatform Picks

NetWare network administrators will appreciate TNA. Its fully automatic tape rotation and grooming support make backups a breeze. Even so, we'd suggest that you take an active part in the tape rotation by keeping copious notes. If something does go wrong, TNA may need some help in setting it right. If you would rather use a different rotation scheme, then consider ARCserve or LANStream. ARCserve treats your tape drives as a shared file server resource using a familiar NetWare interface, while LANStream uses a workstation on your network as a tape server.

Legato NetWorker and BudTool are perfect examples of the split that exists in the Unix user community. BudTool's appeal is in its ability to combine existing Unix commands, and even custom-developed routines written by the administrator, into a total backup strategy. NetWorker, on the other hand, is completely self-contained and not nearly as adaptable.

We can appreciate BudTool's approach, but we have to give NetWorker the nod here because, of the two packages, it is better suited to supporting the full range of user types. It's easy to use without being condescending, so novices can get the system going without feeling lost, and veterans can use the tools to save time without feeling like they're playing with a toy. NetWorker seemed to be the perfect network backup tool; there wasn't a thing we could imagine wanting to do that NetWorker didn't have available and easily accessible.

Mac network administrators should be more than happy with Retrospect Remote. It's as easy to use as any Mac software we have seen, and it makes the job of backing up remote workstations as easy as pie. ■

The BYTE Lab staff can be reached on BIX c/o "editors."

COMPANY INFORMATION

Cheyenne Software, Inc.
(ARCserve 4.0)
55 Bryant Ave.
Roslyn, NY 11576
(516) 484-5110
fax: (516) 484-3446
Circle 1318 on Inquiry Card.

Dantz Development Corp.
(Retrospect Remote 1.3)
1400 Shattuck Ave., Suite 1
Berkeley, CA 94709
(510) 849-0293
fax: (510) 849-1282
Circle 1319 on Inquiry Card.

Delta Microsystems, Inc.
(BudTool 4.0)
111C Lindbergh Ave.
Livermore, CA 94550
(415) 449-6881
fax: (415) 449-6885
Circle 1320 on Inquiry Card.

Legato Systems, Inc.
(Legato NetWorker 3.0)
260 Sheridan Ave.
Palo Alto, CA 94306
(415) 329-7880
fax: (415) 329-8898
Circle 1323 on Inquiry Card.

Maynard Electronics, Inc.
(LANStream 1.0)
36 Skyline Dr.
Lake Mary, FL 32746
(800) 821-8782
(407) 263-3500
fax: (407)263-3555
Circle 1321 on Inquiry Card.

Mountain Network Solutions, Inc.
(FileSafe 5.2.2A)
240 East Hacienda Ave.
Campbell, CA 95008
(408) 379-4300
fax: (408) 379-4302
Circle 1322 on Inquiry Card.

Palindrome Corp.
(The Network Archivist 2.0)
600 East Diehl Rd.
Naperville, IL 60563
(708) 505-3300
fax: (708) 505-7917
Circle 1324 on Inquiry Card.

Performance Technology, Inc.
(Powersave 2.2)
800 Lincoln Center
7800 IH-10 West
San Antonio, TX 78230
(800) 327-8526
(512) 349-2000
fax: (512) 366-0123
Circle 1325 on Inquiry Card.

World Radio History

WE'VE LOWERED THE COST OF HIGH PERFORMANCE FOR FRAMEMAKER.

THE PERSONAL DECSTATION STARTS AT $3995.

Today's applications like FrameMaker® demand the balanced performance of a complete workstation and only the Personal DECstation™ gives it to you at such an affordable price.

Many of the features other low-priced workstations offer, such as an open bus, 8-plane graphics and color, are add-ons. With the Personal DECstation, they're standard. And it's built for the future with new CPU and graphics cards, network interconnects and upgrades, multimedia technology and full Advanced Computing Environment (ACE) compatibility.

The Personal DECstation from Digital. The power of a workstation. The productivity of a workstation. The price of a PC.

DIGITAL'S SPEED AND FLEXIBILITY ARE PERFECT FOR FRAMEMAKER.

FrameMaker and Digital combine to provide a complete document publishing system for creating business and technical documents. FrameMaker incorporates full-featured WYSIWYG word processing, graphics, page layout, tables, conditional text, equations editing, and structured document tools into a single, easy-to-use application.

FrameMaker supports the Motif windowing environment and takes advantage of the innovative tools available with Digital, such as Display PostScript. In addition, FrameMaker supports Digital's multimedia capabilities and allows you to seamlessly incorporate audio and video into your FrameMaker document. FrameMaker on the Digital platform is the complete solution for your document publishing needs.

For a trial version of FrameMaker, please call 1-800-U4-FRAME, extension 145.

ADVANCED COMPUTING ENVIRONMENT

digital™

© Digital Equipment Corporation 1991. The DIGITAL logo, DECsystem, DECstation, DECwindows and ULTRIX are trademarks of Digital Equipment Corporation. UNIX is a registered trademark of AT&T Bell Laboratories, Inc. in the USA and other countries. Motif is a trademark and FrameMaker is a registered trademark of Frame Technology Corporation. Motif is a registered trademark of Open Software Foundation, Inc. PostScript is a registered trademark of Adobe Systems, Inc.

DIGITAL. THE OPEN ADVANTAGE.

World Radio History

The Official Flag Of The

AMD Delivers The World's Fastest 386s.

The great 386 race is over. And the clear winner is the Am386 microprocessor family.

The fact is, no other 386 microprocessors available today can rival the sheer speed and performance of the Am386 microprocessors. The Am386DXL-40 CPU brings 40MHz, full 32-bit 386 performance to the desktop. The Am386SXL-33 CPU makes 33MHz the standard for 386SX machines both at the desktop and for battery powered applications.

In either case, they're over 20% faster than those run-of-the-mill 386's.

The 40MHz DXL-40 and the 33MHz SXL-33 are available in low-cost PQFP packaging.

901 Thompson Place P.O. Box 3453, Sunnyvale, CA 94088 © 1991 Advanced Micro Devices, Inc. "We're Not Your Competition" is a service mark and Am386

World Radio History



Am386 Microprocessors.

And of course, they're proven-compatible with the IBM® standard.

Best of all, they're available now, available in quantity, and available at surprisingly low prices.

So don't just keep up with the competition with ordinary 386 systems. Blow them away with the world's fastest 386 systems—built around the Am386 microprocessors from Advanced Micro Devices. Call **1-800-222-9323** for more information.

Advanced Micro Devices

"We're Not Your Competition."℠

is a trademark of Advanced Micro Devices, Inc. All brand or product names mentioned are trademarks or registered trademarks of their respective holders.

Circle 39 on Inquiry Card.

World Radio History

HARDWARE

Rough Gems: First Pen Systems Show Promise, Lack Refinement

NICHOLAS BARAN



The pen-input system is one of the most exciting recent developments in computer technology. The concept of an untethered, lightweight, notebook-size computer using a pen as the input device is compelling and opens up myriad new applications for computers. However, pen-based computers demand state-of-the-art components in almost every aspect of computer design: battery power and low-power electronics, display and digitizer technology, memory-card storage technology, ergonomics, handwriting recognition, wireless communications, and software development.

Pen-based technology is in its infancy. This review assesses some of the first pen-based computers on the market, including low-end machines using V20 and 286 microprocessors, as well as more powerful machines built on the 386SX. With the exception of the GridPad and MicroSlate Datellite, the machines reviewed here are among the first off the production lines. Several machines that made a big splash when announced (including NCR's 3125 and Samsung's PenMaster) weren't available, and much of the support software for these systems is still in development.

First Pass

Like the PCs of 10 years ago, these machines represent the first generation. In the next few years we'll see great improvements in many of their features and components, including display contrast and readability, battery life, weight, and form factors. Pen-based software will also make great strides in the next few years—faster and more accurate handwriting recognition, more "pen-centric" applications, better graphics and data-compression algorithms, and so forth.

But the application of these systems does not lie entirely in the future. The systems in this review are already finding utility in various mobile work environments, particularly those requiring the filling out of forms, such as inspection and appraisal work. And software development for pen-based systems is proceeding at a furious pace. Pen-based computers have arrived.

The First Pen Systems

I looked at five machines: the GridPad HD from Grid Systems, the TraveLite from DFM Systems, the Datellite 300 from MicroSlate, the Momenta Computer from Momenta, and the TriGem Pen386SX from TriGem. I evaluated them strictly on their merits as notepad computers in a mobile environment, although you can attach keyboards and use them as laptops or desktop machines.

All these machines weighed at least 4.5 pounds. Although that may sound light, it's pretty heavy in the crook of your arm. For comparison, *Webster's Ninth New Collegiate Dictionary* weighs slightly over 3 pounds. For pen systems to feel truly natural to the user, they will have to weigh no more than 3 pounds; I've tried the NCR 3125, and, at 3.3 pounds, it's barely acceptable.

Measuring battery life is difficult, since it depends on how the machine is used. Most of these machines have a low-power standby mode that shuts down the display and hard drive when the machine is idle. And, of course, many users will turn off the machine when they're not using it. Obviously, the actual battery life will vary greatly depending on how long the machine is powered on and the type of computing activity (e.g., activating the modem or performing lots of data transfers to disk will run down the battery faster than, say, scrolling through a RAM-resident reference document).

BYTE's standard battery-life test for notebooks relies on a script-driven hardware test rig that monitors the LCD screen and uses the keyboard to wake the machine when appropriate. Unfortunately, I wasn't able to use this test method for these machines without keyboards. Instead, I compared the machines' battery life by repeatedly running BYTE's system benchmarks until the batteries ran down. The BYTE benchmarks are compute- and hard disk–intensive and provide a worst-case scenario for testing battery life.

It was not easy to evaluate the software on the machines, since much of it is still in development or in beta testing. The NEC V20–based GridPad and the 286-based TraveLite run only DOS (Grid's PenRight environment runs on top of DOS). Thus, these machines won't be able to run Windows for Pen Computing, Go Corp.'s PenPoint, or Communication Intelligence Corp.'s (CIC) PenDOS, all of which require a 386 processor (a 286 machine can run Windows for Pen Computing, but poor performance makes this impractical). The Momenta Computer is a dual-boot machine that runs standard

World Radio History



Five of the first: These pen-input machines, ideal for mobile-computing applications, represent the first generation of pen-based systems. From left to right: the TriGem Pen386SX, the GridPad HD, the DFM Systems TraveLite, the MicroSlate Datellite 300, and the Momenta Computer.

BYTE ACTION SUMMARY

- **WHAT PEN-INPUT SYSTEMS DO**
  These first-generation pen-input systems provide an intuitive, pen-based interface for mobile-computing applications.
- **LIKES**
  The pen interface is compelling, and these machines will provide excellent platforms for data-collection applications.
- **DISLIKES**
  There are technical hurdles that need to be overcome before these systems are truly practical. In particular, weight, display readability, and battery life must improve.
- **RECOMMENDATIONS**
  For forms-based data applications, the GridPad HD is a good choice. For more advanced applications that will require Windows for Pen Computing, PenDOS, or PenPoint, you may want to wait until more players enter the market; if you can't wait, the TriGem Pen386SX is worth a look.

Windows 3.0 or the Momenta Environment. The TriGem and MicroSlate machines came with a beta version of Windows for Pen Computing.

Grid Systems GridPad HD

The GridPad HD is the most established member of this group of pen-based systems. The first GridPad shipped in early 1990—the first pen-based computer on the market. Based on the Intel 8086 architecture, the GridPad is basically an MS-DOS machine customized to accept pen input. Grid Systems has announced a 386 version of the GridPad, but it is not shipping as of this writing. The GridPad software includes an on-screen keyboard so that you can execute DOS commands using the pen.

The key to the machine is the development of custom applications. Using a variety of software development tools provided by Grid and third-party software developers, it's possible to develop custom applications for specific tasks. The machine has enjoyed some success in various vertical applications; for example, the city of San Francisco has been using GridPads for a post-earthquake building inspection program.

I evaluated the GridPad HD, a 10-MHz NEC V20 model with a 20-MB hard drive and a PCMCIA-compatible RAM card slot for backup and software installation. The model I tested weighs about 5 pounds (Grid claims 4.5) and has a 640- by 400-pixel, CGA-compatible, 10-inch backlit display. The machine is powered by an external power supply or by internal nickel-cadmium batteries.

The GridPad measures roughly 12 by 9 by 1½ inches and fits comfortably in the crook of your arm. It is well constructed, and the readable backlit display provides good contrast. The system includes configuration software that lets you turn off the backlight for outdoor use, extending battery life. The configuration software also provides options for controlling power management and other display attributes. The system comes with a well-written user's manual describing features and configuration options.

The pen is attached to the unit by its cord; it clips neatly on one side of the machine. The display is oriented horizontally with five programmable function buttons on the right side. The pen cord also connects on the right side, making left-handed use of the pen more inconvenient, since the cord drags across the screen.

When the machine boots, you are presented with a menu that lets you run the sample applications, switch to DOS, or perform diagnostics or configuration functions. You access all menu options simply by highlighting the option with the pen and then tapping on the Execute box. When you switch to DOS, an on-screen keyboard appears from which you can execute standard DOS commands using the pen as an input device, simply by tapping on the appropriate keys. I was impressed with the accuracy of the pen and the sensitivity of the digitizer.

The sample applications were a bit spotty. A sample expense report program sometimes refused to accept handwriting; the Grid Handwriting Tutorial didn't work at all. However, a legal briefing program with sample forms to fill

PHOTOGRAPHY: SCOTT PARKER / AVIS STUDIO © 1992

World Radio History



Low-level benchmark results for pen-input systems. The 20-MHz 386SX-based TriGem and Datellite systems did well, but there was relatively little variation. The Momenta Computer scored poorly, with low scores on memory-move tests. Toshiba's T2200SX is included as a baseline for comparison.

out worked very well. While frustrating, these problems are in the sample applications only and do not reflect an inherent problem with the machine or operating system.

Of the machines reviewed here, the GridPad is the only 8086 system. Naturally, its performance benchmarks are lower than those of the 286 and 386SX systems (see the figure). But for many custom applications, particularly simple forms, its performance is adequate.

Perhaps the GridPad's most impressive feature in comparison to the other machines is its battery life. The batteries held up for over 3 hours of continuous use. Along with MicroSlate's Datellite, the GridPad was a leader in battery life.

The system I reviewed sells for $3570. That's a lot of money for an 8086-class system. It won't run Windows, PenPoint, or PenDOS. However, it is well built and has a proven track record. If you need to jump in right away and do some basic forms-oriented pen-based computing, the GridPad is a viable option.

DFM Systems TraveLite

The TraveLite is included in this review because it can be operated without a keyboard, but it is actually a touch-sensitive system rather than a pen-based system. It comes with a plastic pointer shaped like a ballpoint pen for touching the screen, although you can also use your finger or the eraser of a pencil, for that matter. Like the GridPad, it has an on-screen keyboard for entering commands. The TraveLite does not recognize handwriting, but you can draw on the screen with a drawing program.

Roughly the same size as the GridPad, the TraveLite that I tested has an 80C286 CPU and a 20-MB hard drive. The system comes with a special cable that connects to the parallel port of another IBM PC compatible, giving the TraveLite logical control of the drives on the connected machine. This is the method for transferring data or installing software on the TraveLite.

The machine that I evaluated came with DR DOS 5.0 and a few sample applications. It included an optional detachable keyboard and a fax modem. DFM Systems has developed drivers for emulating the mouse in the touchscreen environment, presumably for use with Windows. However, Windows really favors a 386 processor.

The system also includes a condenser microphone for making short voice recordings and an optional voice board for delivering digitized speech.

The TraveLite is designed, much like the GridPad, for custom applications, such as forms entry. The system comes with applications development software called the EasyTouch Application Generator, which is documented in a three-ring binder. Other than the EasyTouch binder and the DR DOS user's manual, the documentation is minimal (a 12-page photocopied pamphlet is the extent of the user's manual).

The biggest disappointment with the TraveLite is its battery life. My benchmark exercise exhausted the TraveLite batteries in less than an hour. I tried the test several times, charging the nickel-cadmium batteries overnight after they had completely discharged, with the same result. The system has minimal power management and does not power down the hard drive when it is not in use, which could be part of the problem. In any case, DFM Systems needs to go back to the drawing board with its power management system.

This machine will appeal to applications developers working on turnkey mobile applications. The problem is that EasyTouch is a proprietary development environment, which will not attract software developers. And most nonprogrammers developing their own applications will find the system technically difficult to work with.

Without the keyboard and fax modem, the system I tested is priced at $3466—again, pricey for a low-end system. The company needs to make some major improvements in the documentation and in power management. On the positive side, the machine could be a good choice for simple forms applications, much like the GridPad, provided that battery life improves.

MicroSlate Datellite 300

Like the TraveLite, the Datellite 300 is a touchscreen computer. However, it is more capable than the TraveLite, sporting a 20-MHz 386SX microprocessor and support for Windows for Pen Computing. The unit I evaluated included a 60-MB hard drive and 4 MB of RAM.

The heavy-duty Datellite, which the company dubs a "pen 'n touch notebook," is probably sturdy enough to survive a game of touch football. But there's a big penalty for the rugged design—namely, the Datellite's size and weight. The machine weighs almost 7 pounds with its two battery packs installed, and it measures about 13 by 10 inches wide and almost 3 inches thick. This would be

World Radio History

The Notepad 386SX

THE ULTIMATE BUSINESS TOOL

The Notepad 386SX is the first notebook computer in a notebook. It is a leather computer that is rigidly affixed to a custom leather notebook/portfolio and can be removed in seconds. The Notepad comes standard with a built-in send and receive Fax/Modem, 20 Mhz 386SX, 2Mb Ram, Page White VGA Display, Internal 3 1/2" Floppy and 40 MB Hard Drives all in a 1.5" thick computer.

The Notepad 386SX combines leading edge technology with genuine leather for an aesthetically appealing and elegantly functional business tool. The Notepad 386SX's open face style, coupled with its sleek design, represents a uniquely different alternative to almost all other notebook computers available today.

Call for Further Information
or your Nearest Dealer

1-800-443-3446

Lighthorse Technologies, Inc. 4105 Tolowa St. San Diego, CA 92117

1-800-443-3446
Fax 619-483-1196

Circle 164 on Inquiry Card.

World Radio History

PEN-INPUT SYSTEMS

Although these systems are all designed for pen input, they display a noticeable difference in configuration.

Product	GridPad HD	Datellite 300	Momenta Computer	TraveLite	TriGem Pen386SX
Company	Grid Systems Corp. 47211 Lakeview Blvd. Fremont, CA 94538 (510) 656-4700 fax: (510) 683-9895	MicroSlate, Inc. 9625 Ignace St., Suite D Brossard, Quebec, Canada J4Y 2P3 (514) 444-3680 fax: (514) 444-3683	Momenta Corp. 295 North Bernardo Ave. Mountain View, CA 94043 (415) 969-3876 fax: (415) 969-3877	DFM Systems, Inc. 1801 48th St. West Des Moines, IA 50265 (515) 225-6744 fax: (515) 225-0388	TriGem Corp. 2388 Walsh Ave., Building B Santa Clara, CA 95051 (408) 970-0844 fax: (408) 970-0870
Tested configuration	10-MHz NEC V20 CPU; 2 MB of RAM; 20-MB hard drive; 10-inch, 640- by 400-pixel LCD	20-MHz 386SX CPU; 4 MB of RAM; 80-MB hard drive; 9½-inch, 640- by 480-pixel VGA LCD	20-MHz 386SX CPU; 4 MB of RAM; 40-MB hard drive; 9½-inch, 640- by 480-pixel VGA LCD; detachable keyboard; internal fax/modem	12-MHz 80C286 CPU; 1 MB of RAM; 20-MB hard drive; speech board; backlit, 10-inch, 640- by 400-pixel LCD	20-MHz 386SX CPU; 4 MB of RAM; 4 MB of flash memory; two PCMCIA memory card slots; 9-inch, 640- by 480-pixel VGA LCD; programmable border area; external power supply with serial port
Weight (lbs.)	4.5	6.6	6.3	5.5	4.9
Price	$3570	$5995	$4995	$3466	$3995
	Circle 1228 on Inquiry Card.	Circle 1229 on Inquiry Card.	Circle 1230 on Inquiry Card.	Circle 1231 on Inquiry Card.	Circle 1232 on Inquiry Card.

a tough machine to carry in the crook of your arm for any length of time. The machine has a handle so that you can carry it like a briefcase. Nevertheless, the size and weight of the machine make it a questionable notebook.

On the plus side, the Datellite is one of the better-constructed machines I looked at. It has a solid battery life of over 3 hours, and it offers good performance. The VGA-compatible backlit LCD is easy to read and has excellent contrast and brightness. Since it's a touchscreen, you can use any pointing device with it, but MicroSlate provides a package of plastic pens. The machine has an on-screen keyboard for entering DOS commands, and it boots up with a custom menu, giving you the option of executing sample applications or running Windows.

Like the TraveLite and GridPad, the Datellite is intended for custom data-recording applications. The machine comes with a comprehensive set of development tools. Chief among these is the extensively documented DataSlate applications generator.

The Datellite came with a beta release of Windows for Pen Computing. The touchscreen interface worked remarkably well with Pen Windows. I tried the various included handwriting applications as well as other sample programs, such as Slate's PenBook, which all ran without a hitch.

The big problem with the touchscreen interface is the lack of a second button. Most electronic pen systems include a side button on the pen, which acts like the second mouse button on the Microsoft Mouse. Many applications require this second button, as does CIC's PenDOS interface. There are ways around this limitation, of course, but if software developers must provide modified applications for systems without a second button, Datellite software may be difficult to come by.

The Datellite 300 is a well-built and full-featured computer. It even has a SCSI connector for attaching a CD-ROM drive, and it can include a 3½-inch floppy drive. But its size and weight put it more in the class of portables than notebooks. If you have to put the machine down on a workbench to really work with it, then the pen doesn't buy you as much as it could.



Momenta Computer

The "pentop" Momenta Computer is interesting and innovative, designed for both desktop and mobile use. With the keyboard attached, you can tilt the display and use the computer as a desktop, or you can operate it with a pen without the keyboard. However, the Momenta weighs in at over 6 pounds, making it heavy for extended hand-held use. The machine measures 10 by 12 inches and is wedge shaped, making it a bit bulky for the crook of the arm.

The Momenta Computer is powered by internal rechargeable nickel-cadmium batteries or by an external power supply. The company plans to support standard AA alkaline batteries in the near future and will supply the necessary upgrade to current owners. The pen is tethered by its cord, which plugs into either the left or right side of the computer—a thoughtful design feature for lefties.

The most interesting aspect of the Momenta Computer is its software. It's a dual-boot machine, booting up either with Microsoft Windows or with the Momenta Environment, which is a graphical pen-interface layer on top of MS-DOS. Windows and the Momenta Environment are mutually exclusive.

Microsoft Windows acts as expected. The pen behaves like a mouse: You can double-tap to open applications, drag the mouse cursor with the pen, pull down menus with the pen, and so forth.

The Momenta Environment is a proprietary GUI designed for pen input and control. It has unique features, such as a command compass, which is a pie menu with options for edit, cut, paste, copy, and delete. The menu appears as a background function behind appropriate icons or fields on the screen. For example, when you're writing characters in a field, you can press the side button on the pen to bring up the command compass, and then perform editing operations on what you've written.

The Momenta Environment is an ambitious software system built on Smalltalk. Its bundled applications include a

World Radio History

UNIX is changing the world of computers, the world of business – quite simply, changing the world. It's revolutionizing office automation. It's required for U.S. government computer contracts. It's the backbone of information strategies worldwide.

That's why you need ***UnixWorld*** – the magazine that keeps you up to date on the rapidly changing world of open systems computing. Each issue brings you the latest product trends and technical advances that can affect your business. The inside story on some of the biggest high-tech companies. Easy-to-understand programming tips and tutorials that can help your company use UNIX to its fullest. And unbiased hardware and software reviews to help you invest wisely when you buy.

UnixWorld's in-depth features go beyond dry technical facts to show how the pieces fit together – to tell you what's important about the advances and strategies that are changing your world. And ***UnixWorld*** consistently offers the freshest, most down-to-earth writing that you'll find in any computer publication.

Subscribe today and recieve the next 12 issues of ***UnixWorld*** for just $18.00 – half the regular newsstand price. Save even more by ordering for two or three years. You can't lose– every subscription to ***UnixWorld*** comes with a no-risk guarantee*.

Subscribe now! Call toll-free: 1-800-257-9402 ext. 29



If you're into UNIX, you need UNIXWORLD

McGraw-Hill's Magazine of **OPEN SYSTEMS COMPUTING**

**UnixWorld's no-risk guarantee: If not satisfied, cancel and receive a full refund for the balance of your subscription.*

UNIX is a registered trademark of UNIX System Laboratories, Inc.

DH1AUW9

World Radio History

handwriting trainer, a fax program, an address book and calendar, an on-line tutorial, a spreadsheet program, a presentation graphics program, and a text editor/word processor (this application was not ready at the time of this review and is to be included in a free update to all current Momenta owners).

Conceptually, the Momenta Environment is very elegant. You move from one application to another simply by opening the next application with the pen. This feels a bit like multitasking, although task switching is really what's going on. The fax application worked very well. In theory, the environment supports hand printing in all applications.

But although elegant in concept, the Momenta Environment is not quite ready for prime time. The handwriting recognition is inaccurate, much worse than other handwriting recognition systems I've seen. Even after going through the handwriting trainer program, which requires you to print about 12 screenfuls of characters, the system still interpreted my first name NICK as UL36. Users will not tolerate this level of inaccuracy.

Handwriting recognition problems are likely related to the imprecision of the pen. The system provides a calibration program, a tedious procedure in which you tap the pen on a bull's-eye that moves around on the screen, the objective being to ensure that the pen is pointing accurately at objects on the screen. However, the pen is constantly slipping out of calibration. I had to tap about an eighth of an inch to the left of a window's close box to get the window to close.

These problems are only the tip of the iceberg. The reflective display provides poor contrast and brightness, making the screen difficult to read except in very bright light. The compass menu, which is designed to appear in the background, is barely visible. To make a long story short, it takes a lot of effort both with your eyes and with the pen to use this machine. And that is contrary to the intent of pen-based computing.

But perhaps the most surprising problem with this machine is its battery life. Momenta claims to have developed some innovative power management techniques for this machine. But when running all out on the BYTE benchmarks, the batteries lasted no longer than half an hour. Each of the two battery packs delivered with the system gave dismal battery-life results.

The Momenta Computer's test results are poor when compared to those of the other 386SX systems. This is probably due to poor performance on memory-move benchmarks. The machine feels even slower when running the sluggish Momenta Environment. When running Windows, the performance is about average for a 20-MHz 386SX-based system.

Momenta plans to address these concerns with a series of software updates; the company plans three updates by July. According to Momenta, these software changes will greatly improve performance in three areas: speed, battery life, and handwriting recognition. System software updates, when available, can be downloaded directly to customers' systems from Momenta's BBS.

The Momenta Computer is a bold and innovative project. But it has been delivered to market too soon. Momenta will need to address a lot of problems with its aggressive software upgrade plans before the system will be competitive, particularly at a price of close to $5000.

continued

GREAT THINGS COME IN SMALL PACKAGES

This powerful print server can tackle your biggest network printing problems

- Connects any parallel printer directly to your Ethernet LAN
- Fully Novell Netware 286 and 386 compatible
- Can attach to 8 file servers simultaneously
- Fast and easy to install
- Combines high-speed printing and exceptional printer control
- Supports encrypted passwords, forms, notify, cancel, and others
- Full one-year warranty and unlimited free technical support
- Made in the U.S.A.



Make the Rose Connection

ROSE ELECTRONICS

10850 Wilcrest Drive • Houston, Texas 77099 • Phone (713) 933-7673 • Fax (713) 933-0044

1-800-333-9343

World Radio History

ALDUS PHOTOSTYLER FOR WINDOWS.

FOR PEOPLE WHOSE IMAGINATIONS EXCEED REALITY.

With Aldus® PhotoStyler™ you can create anything you have a mind to.

PhotoStyler is the complete color photo lab for Windows. It allows you to process scanned images in 24-bit full color or gray-scale, then separate them. And you can do it on your PC.

Featuring color correction, retouching, filtering, composition, painting, and special effects, PhotoStyler also lets you work with several open images at the same time. (The built-in JPEG compression enables you to conveniently store and access files.) And you can export your work to other DTP, multimedia, and presentation applications — such as Aldus PageMaker® and Aldus Persuasion®.

No wonder PhotoStyler's innovative graphic capabilities have been drawing rave reviews. *Publish* magazine's Reader's Choice Awards named it the "best image editing software for the IBM PC." While *InfoWorld* rated its image editing tools "Very Good"— and found PhotoStyler easier to use than its two leading competitors.

To learn more, call 1-800-685-3580 for a free trial version. And discover the high-end PC color photo lab that's nothing short of unreal.

ALDUS®

This ad was produced using Aldus PhotoStyler and Aldus PageMaker 4.2. Aldus and the Aldus logo are registered trademarks of Aldus Corporation. PhotoStyler is a trademark of U-Lead Technologies. Windows is a trademark of Microsoft Corporation. PageMaker and Persuasion are registered trademarks of Aldus Corporation. ©1992 Aldus Corporation. All rights reserved.

Circle 8 on Inquiry Card.



TriGem Pen386SX

The Pen386SX was designed by a firm in Rainow, England, called the Eden Group, and manufactured by TriGem of Korea. Several other hardware vendors have licensed it, so it may appear on the market under a variety of monikers. The Pen386SX represents what I think will be the typical first-generation 386SX pen-based computer. It's a flat tablet about 1 inch thick and about 10 by 12 inches on a side. It is surprisingly heavy, weighing in at 4.9 pounds.

The machine I tested has a 20-MHz 386SX processor, 4 MB of RAM, 4 MB of flash memory, two PCMCIA memory card slots, and a backlit 640- by 480-pixel VGA display. The flash EPROM consists of 512 KB of boot memory, dedicated to the boot sector and operating system, and another 512 KB (up to 1.5 MB) devoted to the Microsoft flash file system.

The pen operates through a cable attached under the computer. One feature that seems a bit shortsighted is that the serial port is built into the external power supply and connects to the computer via the power cable. Obviously, you can't use the serial port without the power supply—not an ideal solution for mobile users running the computer on the rechargeable nickel-cadmium batteries.

The unit I evaluated was one of the first off the production line. I found the contrast a bit weak for a backlit LCD, and the pen was poorly constructed. On the plus side, the machine had excellent proximity sensing—almost too sensitive, in fact. Bringing the pen near a Windows icon or dialog box highlights the box. A gentle tap activates it. The pen operated smoothly and required little pressure.

One interesting feature is a user-programmable border area about 1 inch wide that surrounds the active screen. Programmers can set up icons and functions that can be accessed in this area.

My battery-life exercises yielded a battery life of about 2 hours. I found this a bit disappointing considering that the machine does not have a hard drive. The benchmark performance was consistent with that of other 386SX machines.

Ultimate Pens

If you urgently need forms-based data retrieval in a mobile environment and can get by with MS-DOS, the GridPad may be a good choice. However, the pen-based market is shifting toward Windows for Pen Computing, CIC's PenDOS, and Go's PenPoint. For these environments, you'll need a 386-based system, preferably with an electronic pen.

I'd recommend waiting until this summer when more machines will be available and at more competitive prices. But for now, TriGem's Pen386SX is the best bet among the systems in this review. With a few improvements, it will be a solid contender in this nascent market. ■

Nicholas Baran is a BYTE consulting editor and coeditor of Pen-Based Computing, *an industry newsletter based in Sandpoint, Idaho. You can contact him on BIX as "nickbaran."*

PERISCOPE

JUST RELEASED
Model IV for 386SXs
OS/2 Driver Support
32-Bit Toolkit
Rent Model IV
Windows 3 Driver Support

Professional Software and Hardware-Assisted Debuggers for 80386 & 80486 Systems

If you need a debugger but have no room left in the lower 640K of your 386™ or 486™ system, Periscope now has a new SOFTWARE-ONLY solution for you—Periscope/EM.

- Periscope/EM takes advantage of the extended memory you already have, rather than using any memory in the lower 640K.
- No runaway program can corrupt Periscope/EM because it's write-protected.
- You don't have to use a slot since there's no board to install.
- You can add an optional break-out switch to recover from crashes.
- Periscope/EM costs only $295, half the cost of Periscope Model I, with most of the same functionality.

Periscope/EM requires 386MAX® or BlueMAX™, version 5.11 or later; a 386 or 486 system with about 300K of extended memory; 32K of memory between 640K and one megabyte; DOS 3.0 or later.

Booth #812
SOFTWARE DEVELOPMENT '92

New Debugging Tools

"I needed a means to debug interrupt handlers where I could really see what was going on. The hardware trace buffer is great. I was able to debug code in 3 days that I have been trying to debug for months!"

...writes Peg Sestrich with Prime Computer, on why she chose Periscope Model IV.

If you need more than your current software-based debugger gives you, Periscope Model IV, with these advanced NEW features, may be just what you're looking for:

- Supports 386 and **486** systems running up to **33MHz** with its ICE-like capabilities.
- Real-time hardware trace buffer holds up to **16K** CPU events.
- Enhanced analysis and display of trace buffer makes you more productive.
- Periscope/EM functionality, built-in at no extra cost, saves you money.

Just call toll-free 800/722-7006 for details or to order.

The Periscope Company, Inc.
1197 PEACHTREE ST.
PLAZA LEVEL
ATLANTA, GA 30361
404-875-8080
FAX 404-872-1973

Real-time Periscope Model IV, shown with new 33MHz board and 486 pod.

Circle 103 on Inquiry Card (RESELLERS: 104).

World Radio History

Big Screen for Windows

No question... this 17-inch monitor from ViewSonic is the ideal "big screen" choice for Windows. In fact, in a recent InfoWorld product comparison, the ViewSonic 7 was rated #1. Our monitor was designed for people who know what they want and won't accept second best.

The competition claims we're unfair. That's because the up-graded ViewSonic 7, with resolution up to 1280 x 1024, features microprocessor-based memory along with 26 programmable preset modes. And it has a flat square, anti-static screen to eliminate distortion and provide a sharp to-the-edge picture. Plus, for a flicker-free image, it boasts of ultra-high 76Hz refresh rate. This monitor even meets low-radiation strict Swedish MPR-2 standards!

ViewSonic 7—the ideal 17" big screen monitor for the full-scale Windows environment.

ViewSonic®

12130 Mora Drive/Santa Fe Springs, CA 90670
(800) 888-8583 (310) 946-0711 FAX (310) 946-1618

All products and brand names are trademarks of their respective companies

World Radio History

CAPTURE ◆ PAINT ◆ EDIT ◆ SCAN ◆ PRINT ◆ PRESENT

What is Tempra?

The Only Complete, Affordable Multimedia Solution!

TEMPRA™

Now is the perfect opportunity to jump on the multimedia bandwagon. Mathematica's family of TEMPRA products forms the fastest and easiest, yet most advanced and affordable, color imaging and multimedia tools for DOS- and Windows-based PC computers. TEMPRA's revolutionary graphic user interface makes the products incredibly easy to learn and use.

Scan, edit, create, capture, paint and print images in TEMPRA PRO and TEMPRA GIF — up to 16.7 million vibrant colors! Then import your images and video into TEMPRA SHOW to produce dynamic presentations with audio, animation, and sophisticated wipes.

Our TEMPRA products provide the functionality, performance, and sophisticated paint tools found in other products costing more than $2000. Plus, you'll find unparalleled speed with our TEMPRA turbo charger add-on feature, which brings 32-bit power to graphics and imaging — use your 386/486 to the fullest now!

TEMPRA's powerful integrated features include:

- **Intuitive GUI with a variety of adjustable paint tools, including airbrush, pens, geometry shapes, text, mask, tranformation, filters, color swap, and color protection.**
- **Support of ComputerEyes/RT™ — real-time, 24-bit video frame grabber for capturing high-quality images from any video source in 1/30th of a second.**
- **Photorealistic scanning and printing, including special tools for the best quality image.**
- **Support of Animator™, Animator Pro™, and 3D Studio™ flick (.FLI and .FLC) files.**
- **Audio support from CD-ROM, MIDI, or recorded onto the hard drive with a Sound Blaster™ card.**
- **Fast enough to run on even a 286 system. And on a 486, fasten your seat belts!**

World Radio History

The Complete Solution

Type "Go Tempra" on CompuServe

	The Solution	Draw Programs		Image Programs		Paint Programs	
	Mathematica, Inc. TEMPRA	Corel CorelDRAW	Micrografx Designer	Micrografx Picture Publisher	Aldus PhotoStyler	RIX WinRIX	ZSoft Paintbrush
Drawing Effects	**72**	13	8	64	10	64	8
Drawing Styles							
Arc	**16**	N/A	4	N/A	N/A	N/A	N/A
Circle	**12**	4	8	3	N/A	N/A	4
Curve (Parabola)	**8**	N/A	1	N/A	N/A	N/A	N/A
Ellipse	**8**	4	8	3	N/A	8	4
Freehand	**3**	3	4	2	2	4	3
Irregular Polygon	**2**	N/A	2	3	N/A	N/A	8
Line	**7**	7	6	2	4	8	6
Parallelogram	**4**	N/A	N/A	N/A	N/A	N/A	N/A
Rectangle	**12**	4	8	3	N/A	8	4
Regular Polygon	**24**	N/A	N/A	N/A	N/A	N/A	N/A
Spline (Bezier)	**2**	3	3	N/A	N/A	N/A	3
Square	**12**	4	8	3	N/A	N/A	4
Load/Display Times							
42K PCX	**:03**	:39	:11	:36	:05	:13	:05
330K TIFF	**:04**	:18	:14	:47	:05	:17	:06
289K Uncomp. TGA	**:03**	N/A	N/A	:45	:05	:16	:07
708K Comp. TGA	**:06**	N/A	N/A	N/A	N/A	N/A	:17
Image Formats							
!IM	✓	N/A	N/A	N/A	N/A	N/A	N/A
GIF	✓	N/A	N/A	✓	✓	✓	✓
PCX	✓	✓	✓	✓	✓	✓	✓
PTN	✓	N/A	N/A	N/A	N/A	N/A	N/A
TGA	✓	N/A	N/A	uncompressed	uncompressed	✓	✓
TIF	✓	✓	✓	✓	✓	✓	✓
WIN	✓	N/A	N/A	N/A	N/A	N/A	N/A
Hardware							
Batch Printing	✓	✓	✓	N/A	N/A	N/A	N/A
Scanners	✓	N/A	N/A	✓	✓	✓	✓
Video Capture	✓	N/A	N/A	N/A	N/A	N/A	N/A
B/W Printing	✓	✓	✓	✓	✓	✓	✓
Sierra HiColor VGA	✓	✓	✓	✓	✓	✓	✓
Color Models							
CMYK	✓	✓	✓	✓	✓	✓	N/A
RGB	✓	✓	✓	✓	✓	✓	✓
HLS	✓	N/A	✓	✓	✓	N/A	✓
HSV	✓	✓	N/A	✓	✓	✓	N/A
Environments							
DOS	✓	N/A	N/A	N/A	N/A	N/A	N/A
Windows 3.0	✓	✓	✓	✓	✓	✓	✓
Multimedia/Authoring	✓	N/A	N/A	N/A	N/A	N/A	N/A
Audio Support	✓	N/A	N/A	N/A	N/A	N/A	N/A
Suggested List Price	$149 — $495	$695	$695	$695	$795	$495	$495

All tests were performed on an Orchid Technology Privilege 386-33 with 8MB RAM and a Conner 200MB HDD. Windows applications were tested in 386 enhanced mode with no other tasks running. TEMPRA is a trademark of Mathematica, Inc. All other products are trademarks of their respective owners. TEMPRA speeds clocked before turbo charger feature. Copyright 1991 by Gary A. Klein. All Rights Reserved.

"Mathematica's Tempra 24-bit paint program was another winner, providing unparalled editing speed."
Adam Osborn
NewMedia, November/December 1991

"A top-flight painting/photo retouching program with amazing capabilities. Video speed, even for 24-bit color files, is remarkable. Highly recommended."
Susan Glinert-Stevens
PC Sources, November 1991

"Tempra Pro has some very powerful features. The package's color manipulation and control are hard to beat. Overall, Tempra Pro is an excellent graphics editor that's very easy to use and quite powerful. You will find it possible to create and edit images whether you are a beginner or a professional."
Marc Greenfield
Computer Buying World, November 1991

"Tempra really stands out when working with true-color images. The output from Tempra is excellent. Overall Tempra is a good program. Those who work with full-color images — and any of the supported color scanners — may find it a valuable tool. And the ability to work with video input offers interesting possibilities."
Leonard Hyre
PCM, November 1991

"Tempra gets our nod for PC-based programs. It's the least expensive of the lot and handles a variety of image formats."
Tom Thompson
BYTE Magazine, June 1991

DREAM SYSTEMS 1991

BEST SPRING 1991 BYTE FINALIST

See us at Comdex, Booth M869

mathematica

402 S. Kentucky Ave., Lakeland, FL 33801
813-682-1128 • Fax 813-686-5969
1-800-852-MATH

Circle 16 on Inquiry Card (RESELLERS: 17).

World Radio History

ART

For Business's Sake



Designing eye-catching visuals isn't just for artists anymore. One of these packages is sure to make it easier for you to create good-looking pictures, charts, and graphs.

D. BARKER, RAYMOND GA CÔTÉ, DAVID L. EDWARDS, TOM THOMPSON, AND STAN WSZOLA

In this highly visual age, looks are nearly everything. And the business of doing business is more closely linked than ever to putting the best-looking graphics forward. Whether trying to communicate ideas, disseminate information, or enhance their corporate image, enterprises today increasingly rely on sophisticated computer graphics software. Drawing, painting, and charting packages are pressed into service for everything from designing logos, developing product designs, and rendering illustrations for manuals or catalogs to making presentations and sprucing up a report or proposal. Gone are the days when you could pass out an unembellished pie chart done up on a dot-matrix printer and expect praise for your efforts.

Once confined to the art department, graphics packages are making their way to desks further afield. Many a spreadsheet ace has developed a fondness for graphing programs, engineers in the lab frequently depend on drawing programs to illustrate new designs, and even CEOs have been known to crank up their favorite charting programs to make sense of the next quarter's projections.

Heightened interest in marrying information and compelling images isn't the only explanation for the growing importance of business graphics software, however. Personal computers that have the horsepower to crank out good graphics are no longer too exotic or too expensive. As a result, an increasing number of IBM compatibles are—like their Macintosh brethren—equipped to handle gloriously realistic color. Likewise, color printers and plotters have come down in price.

Finally, as we found when testing the products for this report, the software itself has gotten more powerful and less intimidating. While it takes practice to master Bézier curves—the design department needn't worry about accountants taking over those job responsibilities—you probably can find a package that overcomes many of your artistic limitations.

There is, as of yet, no digital substitute for aesthetic sense, but computer graphics programs are here to stay and here to play a critical role in business communications. But how do you even start to choose from the smorgasbord of business graphics software on the market today? Our approach was to search the field. In the process, we turned up nearly 100 programs for PCs and Macs—programs that handle the basic needs of business: drawing, painting, charting, and graphing. (Although slide-show presentations are a big part of business graphics today, we feel presentation software deserves separate coverage.) To maintain our

World Radio History



sanity while taking into account the constraints of space, time, and fairness, we pared the final report down to products we found most effective or ones that are newly revised or new to the market. Ours is not a complete survey of the field; rather it's a subjective roundup of what we consider some of the best software for producing the kinds of visuals today's businesses demand.

DRAWING PACKAGES

If you routinely produce illustrations that are heavy on lines and geometric shapes, or that require precise placement of graphical elements, you need an object-based drawing program. You could go out and buy a CAD package, but unless you're an architect or an engineer, you can get by with something less capable, complex, and expensive. While Aldus FreeHand and Adobe Illustrator are the granddaddies of object-based drawing packages for personal computers, or at least are perceived as market leaders, other programs currently on the market offer similar capabilities but cost less and are easier to learn. For professional illustrators and designers, Aldus FreeHand and Adobe Illustrator still are the top packages to consider. But for everyone else, the choices are both varied and impressive.



ACCUDRAW FOR WORDPERFECT 2.1

AccuDraw 2.1 is a likable DOS and vector-based drawing package designed to support the WPG graphic format of the widely used WordPerfect word processor. It performs basic drawing functions quickly and is also easy to use. Although tailored as a companion to WordPerfect, its ability to import and export a broad selection of files makes it compatible with many other programs, as well.

With 18 drawing tools, 64 fill patterns, 1000 line widths, and over 500 clip art images and symbols included, AccuDraw gives you the wherewithal to create myriad diagrams, floor plans, technical drawings, flowcharts, as well as other

BYTE ACTION SUMMARY

■ WHAT GRAPHICS SOFTWARE DOES

Drawing programs generate line art that can be scaled without distortion; paint packages create realistic images using collections of dots, or bit maps; charting and graphing software provide a wide range of tools to graphically display data.

■ WHAT YOU'LL LIKE

The precise line and curve tools of drawing packages, the color-mixing capabilities and the free-form tools in paint programs, and the simplicity with which charting and graphing programs turn raw data into attractive images.

■ WHAT YOU'LL DISLIKE

The more sophisticated programs take time to learn and run best on high-end hardware.

■ RECOMMENDATIONS

As with art, graphics software is a highly subjective matter. Most of these packages have similar capabilities but differ in their manner of operation and ease of use. The best way to ensure that you get a package that will suit your needs is to compare the capabilities of a variety of products, single out the three or four packages that seem most promising, and get a demo of all of them before deciding which one you'll enjoy working with.

World Radio History

business-type images. The program supports only 16 colors, but then it needs only 400 KB of memory to run.

Because it was developed as a companion to WordPerfect, AccuDraw has some rather unusual graphics file-handling methods that revolve around the WPG format. The bit-mapped graphics from paint programs, clip art libraries, and scanned images can be edited on-screen, or you can convert them to the WPG format with WordPerfect's conversion utility. Any file formats not supported by the program's GRAPHCNV utility can be captured using the GRAB screen-capture program also supplied with WordPerfect.

To edit bit-mapped images, you must use the package's built-in pixel editor. For other editing functions (e.g., moving, scaling, and rotating) a bit-mapped image is treated as a vector object, and pixel data can't be changed. AccuDraw renders pixels into *vector space* using a floating-point calculation for each pixel. Vector objects may be drawn on top of bit maps.

AccuDraw's latest release, 2.11, includes PostScript laser printer drivers, an extrusion function that lets you push an object into the shape of another object, and a feature that lets you draw a curve and then lay text down on it. For the millions of WordPerfect users, AccuDraw has ample tools, is simple to use, and is versatile enough to create respectable artwork.

—D. E.



ADOBE ILLUSTRATOR 3.0.1

Still one of the best object-based drawing packages for the Mac, Adobe Illustrator 3.0.1 has an excellent set of drawing tools for freehand curves, text, and objects (circles, rectangles, and so on). Its interface allows you to draw, modify, and color objects with a minimum of fuss and great precision. On top of that, Illustrator provides ample text-handling capabilities. You can type text into a window, set the color of the text's outlines and fill patterns, and then wrap the text around an object—a circle, perhaps—or get it to conform to a freehand curve. The package's Compound Objects feature lets objects in the background show through openings in foreground objects or in text.

Illustrator's method of coloring objects is disconcerting at times. It leaves messy black blobs composed of intermediate curves on the objects being colored. Fortunately, these blobs don't show up in the preview screen or on the printout. The package won't let you edit images in preview mode and also needs some sort of layering control to help organize and manage complex images.

The beta version of Adobe Illustrator 4.0 for Windows, which I recently got a glimpse of, promises to be as capable as its Mac counterpart and, thankfully, eliminates the preview editing flaw.

—T. T.



ALDUS FREEHAND 3.0

Aldus FreeHand 3.0, another object-based drawing package, is available in both Mac and Windows versions. FreeHand's strengths lie in its ability to organize your artwork's objects into layers and in its superb color-blending facility. Placing a blended color in an object is a simple matter of selecting the object and picking two colors and the fill direction. Furthermore, no black blobs appear after an object is filled, which makes it a snap to edit artwork.

A Layers palette enables you to design and manage very complex artwork. With it, you can create and name a layer, then selectively hide or reveal the objects that belong in that layer. This capability would prove useful if, for example, you were working on an aerospace drawing that required separate layers for the plane's fuselage and landing gear layer. Better still, you can edit the preview image.

Like Adobe Illustrator, Aldus FreeHand lets you wrap text around objects and curves and construct compound objects, which permits you to create special effects with text. FreeHand's big weakness is its interface: You sometimes must trek laboriously through menus and dialog boxes to set up the colors or color blends, and you must go through a dialog box to enter text into the artwork.

—T. T.



ARTS & LETTERS APPRENTICE 1.0

Arts & Letters Apprentice 1.0 is an object-based drawing program for Windows. The package includes over 3000 clip art images, 24 typefaces, tools for manipulating objects and creating charts, and a powerful mixing feature that can blend over 16 million colors.

The program's file-handling capabilities are average: You can export just seven graphic file formats and import five formats, including TIFF and PIC. GED, the program's native file format, is not a common one.

Another drawback is that, if you are working on a fairly large image, screen redraws are frequent and time-consuming on a 386 machine. Even when you close a dialog box, the graphics in your work space are refreshed, slowing any additional drawing and editing tasks.

If you need a virtually unlimited number of personally mixed colors, then Apprentice will serve you well. It offers three color-modeling methods: RGB, CMYK (cyan, magenta, yellow, black), and one based on hues. You combine colors by sliding a bar that controls the proportion of the mix; Apprentice immediately displays the resulting color on screen. Another very clever color mixing utility is Graduated Fill, which you can use to gradually change the color of an object—making it dark blue at the bottom and light blue at the top, for instance.

continued

World Radio History

We understand how you feel when your presentation goes badly.

If your LCD projection panel doesn't perform as well as you do, you're the one that ends up looking foolish. That's why we gave the MagnaByte® 6001 true color saturation and outstanding image clarity. And we made it so easy to set up and use, virtually anyone can give a professional, glitch-free presentation. Anywhere.

With the lightweight MagnaByte 6001, whatever appears on the computer screen is projected in thousands of crisp, rich colors through an overhead projector. And you can still use your mouse or key commands to manipulate graphics, call up different screens or type in new text. All in brilliant 640 x 480 resolution.

Seeing is believing. Ask your AV dealer for a comparative demonstration. For the Telex dealer nearest you, call 1-800-828-6107.

Because if you can't show it as well as you know it, your presentation isn't the only thing that will suffer.

©1991 Telex Communications, Inc.

The MagnaByte® 6001.

Compatibility: IBM and IBM-compatibles with VGA output; Macintosh II and LC.

TELEX®

Circle 26 on Inquiry Card (RESELLERS: 27).

Arts & Letters Apprentice is a capable desktop graphics package and is a good choice if you are looking for a wide variety of prepackaged, high-quality clip art objects and symbols, powerful color mixing capabilities, and a charting tool.

—D. E.



CANVAS 3.0

Part drawing program, part painting program, Canvas has enough features to cover nearly any situation. The object-based tools in this $399 package are well suited to creating technical designs, such as architectural documents and engineering drawings that make heavy use of lines. Grids, alignment functions, Smart Mouse, and the Object Specifications dialog box (a CAD-like feature that positions an object according to user-defined constraints) help you place and modify a drawn object with precision. Canvas's Bézier curve-drawing tools are as good as any in the more expensive, PostScript-based programs.

But you also can paint away in free-form fashion. Tools for painting and editing bit-mapped images include the usual brushes, pattern buckets, spray can, and pencil (for freehand work). Canvas, which supports 32-bit color, treats whatever you paint as an object. After selecting an item you've painted, you can apply effects to it, move it around, and change its size.

Beginning with version 3.0, Canvas incorporates a number of impressive features for working with text. Not only can it fill a shape with text, wrap text around a shape, or superimpose text on a curve, the program can convert Adobe Type 1 and TrueType fonts into editable Bézier curves. Because Canvas 3.0 treats each text character as an object, you can modify text characters in just about any way you want—by scaling, slanting, stretching, and even coloring them.

Other highlights include support for System 7 and its Publish and Subscribe feature, the ability to produce color separations and slide-show presentations, and a comprehensive kit of special effects.

A program with 48 tools and dozens of customizable functions runs the risk of being overwhelming. Luckily, Canvas's developers have given users enough control that they can avoid too-many-things-on-the-screen syndrome.

With its extensive toolbox and wonderful flexibility, Canvas 3.0 is more than adequate for producing technical drawings, artistic illustrations, and textual graphics. Like the great DaVinci, this program is at home in the spheres of art, science, and business. If I could buy only one Mac graphics package, Canvas 3.0 would be the one.

—D. B.



CORELDRAW 2.01L

Windows-based CorelDraw is a capable object-oriented drawing package endowed with both extensive drawing tools and good text-handling capabilities. Its Extrude feature, for instance, lets you reshape an object—allowing you to push a circle into a cylinder, for example, or blow up text to fill a balloon shape. CorelDraw also lets you superimpose one object on another and drop color blends into an object.

The package's excellent Align feature lets you line up objects by their sides or by their centers, which is handy for organizing complicated, overlapping objects. You can examine your results in a full-screen preview mode, or in a unique split-screen mode that presents the editing window along with the corresponding preview image.

But CorelDraw does have its faults. Like Adobe Illustrator, CorelDraw's blending feature leaves a huge mass of curves that get in the way whenever you try to modify artwork. And it lacks layering control and the ability to temporarily conceal objects. As a result, creating complex artwork can prove a daunting task. Finally, CorelDraw is slow. Running it on anything other than a fast 386- or 486-based computer with lots of RAM and a high-speed hard disk is torture.

—T. T.



DESIGNER 3.1

Micrografx's competitor to CorelDraw, Designer 3.1, comes with a flexible set of drawing tools that makes the package a strong contender as a technical illustration package. The $695 Designer has numerous drawing tools for creating pie shapes, rectangles, lines, Bézier curves, arcs, and parabolas, as well as special tools for skewing objects, rotating text, or making text or other elements conform to curves. This abundance of tools makes Designer powerful, hard to learn, and sizable. Installing the complete program requires 10 MB of hard disk space.

Designer is customizable, however. You can change or simplify the screen display, adding or removing tools in the toolbox. You can also customize the program's menuing system by adding fill patterns, colors, and other attributes to dialog boxes. In addition, Designer lets you create and edit drawings with as many as 64 layers, and edit drawings in either full-color or wire-frame modes.

To insert or edit text included in an illustration, you don't need a separate editing window. Designer permits you to apply typographic controls to individual characters or to blocks of text, and you can easily superimpose editable text on curves. You cannot, however, apply gradient fills to text objects without first converting them to curves. To vary the appearance of your text, you can use Bitstream- and URW-compatible fonts—or choose from among the 41 typefaces supplied with the program.

Designer doesn't skimp on color. It offers support for 256- and 24-bit color files and can accommodate video cards and monitors with resolutions as high as

World Radio History

Not only is the Phaser™ II PXi the first thermal wax printer with Adobe's PostScript™ Language Level 2 software, it also has HP-GL. What more could you want from a printer?

Now make your ideas even brighter.



You say you want brilliant color fidelity? Rest assured the Phaser II PXi is approved by Pantone and features TekColor™ color matching.

A screaming 24 MHz RISC processor and 6 Mb of memory make the Phaser II PXi the fastest color printer on the market. Really.

So you have this great idea. One that'll win an account. Break a sales record. Or simply make you look like a genius. Don't blow it with a color printer that won't do your brainwork justice.

Get the new Phaser II PXi, a thermal wax printer that works simultaneously with Macs, PCs and workstations. It can generate 16.7 million colors at 300 dpi, and it's cost-effective.

To see the quality of its output first hand, call **1-800-835-6100, Dept. 16J** and we'll send you a free sample.

The new Phaser II PXi. It'll make your ideas look as bright as they should.

Tektronix®
The best and the brightest.

Phaser and TekColor are trademarks of Tektronix, Inc. for color printers and related products. PostScript is a trademark of Adobe Systems Incorporated which is registered in the USA and other countries. Other marks are trademarks or registered trademarks of the manufacturers or marketers of the products with which the marks are associated. France: (1) 69-86-83-92, U.K.: (0628) 52749, Germany: (221) 94669-0, Italy: (2) 8444[illegible], Sweden: (8) 29 21 10, Holland: (2503) 35111, European Operations Center: 44-628-869-299.

Circle 25 on Inquiry Card.

World Radio History

Programs for Drawing, Painting,

Many of the graphics packages import and export a bewildering variety of graphics file formats. Check which file formats you normally use before selecting a package. The maximum colors a package can display are limited by the available hardware for DOS computers and the Macintosh, and by the Windows configuration. (● = yes; ○ = no)

Product	Company	Price	Platform	Import Files
ABC Flowcharter 1.13	Roykore, Inc.	$296	Windows	None
AccuDraw for WordPerfect 2.1	AccuSoft Corp.	$195	DOS	WPG, CGM, PIC, DXF, GEM CUT, IMG, HPGL, PCX, TIFF
Adobe Illustrator 3.0.1	Adobe Systems, Inc.	$595	Macintosh	Illustrator 88/1.1, EPSF
Aldus FreeHand 3.0	Aldus Corp.	$595	Macintosh	EPS, PICT, TIFF
Aldus FreeHand 3.0	Aldus Corp.	$595	Windows	EPS, AI, BMP, CGM, DRW, GRF HPGL, PCX, PIC, PLT, PNT, XLC
Arts & Letters Apprentice 1.0	Computer Support Corp.	$169	Windows	TIFF, WMF, PIC, DIA, ASCII
CA-Cricket Graph 1.3.1	Computer Assoc. International, Inc.	$129	Windows	ASCII, DIF, SYLK, WK1, WK2, WK3 Cricket Graph for Mac
CA-Cricket Graph 1.3.2	Computer Assoc. International, Inc.	$129	Macintosh	ASCII, DIF, PICT, JWKS, SYLK WK1, WK2, WK3, WKS
Canvas 3.0	Deneba Software	$399	Macintosh	CGM, DXF, EPSF, IGES, PICT, TIFF, MacPaint, Illustrator 88/1.1, Ultrapaint
Color It 1.0	MicroFrontier	$119.95	Macintosh	GIFF, TIFF, PICT, MacPaint, Photoshop
CorelDraw 2.01L	Corel Systems Corp.	$695	Windows	BMP, CGM, DXF, EPS, GEM, PCX PCT, PIF, HPGL, PIC, PICT, TIFF
DeltaGraph Professional 2.0	DeltaPoint	$295	Macintosh	WKS, Excel, SYLK, ASCII, PICT, EPSF, Cricket Graph, Trapeze, QuickTime Movie
Designer 3.1	Micrografx, Inc.	$695	Windows	MGX_DRAW, MGX_PICT, PICT BMP, SYLK, ASCII
Dr. Halo IV Imaging Pak 1.0	Media Cybernetics, Inc.	$140	DOS	TIFF, TGA, PCX, IMG, HALO CUT
Express Presenter 1.0	Power Up Software Corp.	$199.95	DOS	ASCII, CGM, PIC, TIFF, WK1, WKS
Graph-in-the-Box Executive 1.14	New England Software, Inc.	$299.95	DOS	DIF, CGM, HPGL, EPS, PIC
Graphicway 1.0	Tilcon Software, Ltd.	$495	Windows	PCX, TIFF, WKS, DBF, DIF ASCII, RIPCAM
GraphMaster 1.31	Visual Business Systems	$295	Macintosh	WKS, Excel, SYLK, ASC, EPSF, PICT
Harvard Draw for Windows 1.0	Software Publishing Corp.	$595	Windows	CHT, SYM, DRW, EPS, CH3, SY3, DXF CGM, AI, WMF, BMP, PCX, TIFF
Instant ORGcharting 1.0	Roykore, Inc.	$195	Windows	ASCII, WMF
MacDraw Pro 1.0	Claris Corp.	$399	Macintosh	EPSF, TIFF, ASCII, PICT, MacDraw
Mass-11 Draw 6.1	Microsystems Engineering Corp.	$695	DOS	PIC, Mac PICT, CGM, HPGL, MDL, TEK
Michael's Draw 1.0	Event One	$149	Macintosh	EPSF, PICT, MacPaint
Painter 1.0	Fractal Design	$299	Macintosh	PICT, RIFF, TIFF, Photoshop
Painter 1.0	Fractal Design	$299	Windows	PICT, RIFF,TIFF,Photoshop
PC Paintbrush IV Plus 2.0	ZSoft, Inc.	$240	DOS	PCX, TIFF
Publisher's Paintbrush 2.0	ZSoft, Inc.	$495	Windows	BMP, GIF, MSP, PCX RAW, TGA, TIFF
Splash	Spinnaker Software Corp.	$39.95	DOS	TIFF
Windows Draw 3.0	Micrografx, Inc.	$149.95	Windows	DRW, GRF, PCX, PIC, TIFF ASCII, WMF, AI, EPS, CGM GEM, Mac PICT, WPG

World Radio History

Charting, and Graphing

Export Files	Maximum Colors	Maximum Fonts	Undo Command	Rotate/ Flip	Color Separation	Video Support	Output Devices
WME	Windows	Windows	●	○	○	Windows	Win
PNTG, PPIC, DXF, MSP CUT, IMG, HPGL, PCX, TIFF	16	3	●	●	○	Super VGA	Only through WordPerfect
Illustrator 88/1.1, EPSF	16.7 million	Macintosh	●	●	○	Macintosh	Mac, PostScript
EPS, PICT, TIFF	Macintosh	Macintosh	●	●	●	Macintosh	Mac
EPS, AI, BMP, CGM, DRW, GRF HPGL, PCX, PIC, PLT, PNT, XLC	Windows	Windows	●	●	●	Windows	Win
EPS, CGM, TIFF, SCD, WMF, WPG, CSP	Windows	Windows	●	●	○	Windows	Win
ASCII, DIF, SYLK , WK1, WK2, WK3, Cricket Graph for Mac	Windows	Windows	○	○	○	Windows	Win
ASCII, DIF, PICT, JWKS, SYLK WK1, WK2, WK3, WKS	Macintosh	Macintosh	●	○	○	Macintosh	Mac, slide service
CGM, DXF, EPSF, IGES, PICT, TIFF, MacPaint, Illustrator 88/1.1, Ultrapaint	Macintosh	Macintosh	●	●	●	Macintosh	Mac, PostScript
GIFF, TIFF, PICT, MacPaint, Photoshop	Macintosh	Macintosh	●	●	○	Macintosh	Mac, Postscript
BMP, CGM, DXF, EPS, GEM, PCX PCT, PIF, HPGL, PIC, PICT, TIFF	Windows	Windows	●	●	●	Windows	Win
PICT, EPSF, ASCII, Illustrator 88/1.1	Macintosh	Macintosh	●	●	○	Macintosh	Mac, PostScript, film recorder
DRW, TIFF, CGM, WMF, DXF, GEM HPGL, PCX, EPS, PICT1&2	Windows	41	●	●	○	Windows (Super VGA)	Win
TIFF, TGA, PCX, IMG Halo CUT, MSP, BMP	16.7 million	45	●	●	○	Super VGA	Color/B&W printers
ASCII, CGM, PIC, TIFF, WK1, WKS	256	16	●	○	○	Super VGA	Color/B&W printers
DIF, CGM, HPGL, EPS, PIC	15	10	●	●	○	VGA	Color/B&W printers, plotters
PCX, TIFF, HPGL, EPS, WKS DBF, DIF, ASCII, RIPCAM	256	18	●	●	○	Windows	Win
ASCII, SYLK, PICT, Illustrator 88/1.1	Macintosh	Macintosh	●	●	○	Macintosh	Mac
EPS, CH3, SY3, DXF, CGM, AI, WMF BMP, PCX, TIFF, PIC, SCD, LL	Windows	Windows	●	●	○	Windows, TIGA	Win, film recorders
ASCII, WMF	Windows	Windows	●	○	○	Windows	Win
EPSF, PICT	Macintosh	Macintosh	●	●	○	Macintosh	Mac, PostScript Film recorders
DRW, CGM, ILF	3.6 million	2	●	●	○	Super VGA	Printers, plotters, film recorders
EPSF, PICT	Macintosh	Macintosh	●	●	○	Macintosh	Mac, PostScript
PICT, RIFF, TIFF, Photoshop	Macintosh	Macintosh	●	○	○	Macintosh	Mac, PostScript
PICT, RIFF, TIFF, Photoshop	Windows	Windows	●	○	○	Windows	Win, PostScript
PCX, TIFF	256	25	●	●	○	VGA	Color/B&W printers, plotters
PCX, BMP, EPS GIFF, TGA, TIFF	Windows	15	●	●	○	Windows	Win
TIFF	256	13	●	●	○	VGA	Color/B&W printers
DRW, EPS, HPGL, PCX, PIC PS, TIFF, WMF, AI, CGM GEM, Mac PICT, WPG	Windows	Windows	●	●	○	Windows	Win

World Radio History

LARGER DISPLAY AREA FOR
BIGGER IMAGES



BRIGHTER SCREENS FOR
SHARP, CRISP IMAGES

NON-INTERLACED, FLICKER-FREE
DISPLAY FOR LESS EYE STRAIN

WISHES DO COME TRUE. And at MAG Innovision™ our new MX-Series color monitors are making a number of wishes come true. These advanced displays are great for all types of applications, particularly Microsoft® Windows.

4 MODELS TO CHOOSE FROM. With a variety of sizes and tubes to select from, there's an MX display just right for you. The MX15F and MX17F make use of the latest flat square tube technology to offer distortion-free images, while the MX14S and MX17S utilize proven Trinitron® tubes.

WISHES
GRANTED.

LARGER DISPLAY AREA. Every MX-Series monitor uses advanced overscan technology to provide an edge-to-edge active display area that dwarfs displays of comparable size by as much as 36 percent!

HIGH-RESOLUTION. MX monitors offer the highest resolution you can find in any display of comparable size. In fact, at 1280 x 1024 non-interlaced, the MX15F displays four times the information available with standard VGA. That means more windows on the screen...more information...more productivity!

BUILT-IN MICROPROCESSOR. Each MX-Series display has its own microprocessor that can adjust the display format automatically to work with almost any of the available video standards. So whether you're

World Radio History

BUILT-IN MICROPROCESSOR FOR AUTOMATIC CONFIGURATION



HIGH-RESOLUTION FOR MORE WORK SPACE

changing a video mode or upgrading a video card, the MX display will adjust automatically. And, if you do make adjustments, you only do it once. An MX display never forgets.

SHARPER, BRIGHTER IMAGES. By incorporating an Invar Shadow Mask into the MX15F and MX17F, we've achieved 30 percent more brightness without sacrificing sharp, crisp focus. And when combined with our high-resolution and fast-refresh rate, that 30 percent more brightness truly creates an image to wish for.

LISTEN TO THE EXPERTS. Don't just take our word for it. We're partial. Read *PC Magazine*'s "Editors' Choice" for July 1991. They said of the MX15F..."clearly the best." Or listen to *PC World* (12/91) rave about the MX17F... "so great that it defies comparison."

WISHES DO COME TRUE. The next time you go window shopping to look at Windows displays check out an MX monitor. For more information on how to make your wishes come true, call us now at 1-800/827-3998, or contact us at our corporate headquarters: 4392 Corporate Center Drive, Los Alamitos, CA 90720. Tel: 714/827-3998. Fax: 714/827 5522.

©1992. MAG Innovision. All rights reserved. MAG Innovision and its logo are trademarks of MAG Innovision. Microsoft and Windows are registered trademarks of Microsoft Corp. Trinitron is a registered trademark of SONY Corp.

MAG INNOVISION

Circle 30 on Inquiry Card (RESELLERS: 31).

World Radio History

A Comparison of Capabilities

Painting and drawing features: All of the graphics packages we looked at had basic tools for image manipulation. Advanced or user customizable tools, such as customizable patterns or modifiable brushes, can give you more professional-looking results. Charting and graphing features: The larger the number of data points and data sets a package can handle, the greater the detail a chart or graph can display. (● = yes; ○ = no; N/A = not applicable.)

	PAINTING AND DRAWING FEATURES							
	Skew	Resize	Gradient Fill	Customizable Patterns	Masking	Modify Brushes	Group/ Ungroup	Graph Types
ABC Flowcharter 1.13								Organization
AccuDraw For Word Perfect 2.1	○	●	○	○	○	○	●	
Adobe Illustrator 3.0.1	●	●	Via Blend tool	●	●	○	●	6
Aldus FreeHand 3.0 (Mac)	●	●	●	●	●	○	●	
Aldus FreeHand 3.0 (Windows)	●	●	●	●	●	○	●	
Arts & Letters Apprentice 1.0	●	●	●	●	○	○	●	5
CA-Cricket Graph 1.3.1								9
CA-Cricket Graph 1.3.2								10
Canvas 3.0	●	●	●	●	○	●	●	
Color It 1.0	●	●	●	●	●	●	○	
CorelDraw 2.01L	●	●	Via Blend tool	●	●	○	●	
DeltaGraph Professional 2.0								17
Designer 3.1								
Dr. Halo IV Imaging Pak 1.0	●	●	●	●	○	●	○	
Express Presenter 1.0								11
Graph-in-the-Box Executive 1.14								12
Graphicway 1.0	●	●	●	●	○	○	●	7
GraphMaster 1.31								13
Harvard Draw for Windows 1.0	●	●	●	●	○	○	●	
Instant ORGcharting 1.0								Organization
MacDraw Pro 1.0	●	●	●	●	○	○	●	
Mass-11 Draw 6.1	●	●	○	●	○	○	●	
Michael's Draw	●	●	●	●	●	○	●	
Painter 1.0 (Mac)	○	○	○	○	●	●	○	
Painter 1.0 (Windows)	○	○	○	○	●	●	○	
PC Paintbrush IV Plus 2.0	○	○	●	●	○	●	●	
Publisher's Paintbrush 2.0								
Splash	○	○	●	○	○	○	○	
Windows Draw 3.0	●	●	●	●	○	○	●	

World Radio History

CHARTING AND GRAPHING FEATURES

Cut/ Paste	Freehand Drawing	Maximum Data Points	Maximum Data Sets	Edit Text	Edit Legends	Math Coprocessor Support
	N/A	N/A	●	●	○	
●	●					●
●	○	N/A	1	●	○	Via SANE
●	●	60	5	●	●	○
●	○	108,000	216,000	●	●	○
●	○	270,000	540,000	●	●	○
●	●	10,000	unlimited	●	●	Via SANE
●	●	270	1440	●	●	○
○	○	1000	1	○	○	○
●	●	2200	12	○	●	○
●	●	10,000	unlimited	●	●	Via SANE
●	●					●
●	○	N/A	N/A	●	●	○
●	●					
●				●		
●	●					●

Super VGA resolution. Micrografx Designer is well suited to handling complex technical drawing and sophisticated images. With its multitude of special-purpose tools, Designer is difficult to learn, but it is a powerful illustration package.

—S. W.



HARVARD DRAW FOR WINDOWS 1.0

Software Publishing's Harvard Draw for Windows is an object-oriented program that gives you a snappy drawing interface with 18 speedy drawing tools. Its support for as many as 99 layers within each illustration (think of each layer as a separate sheet of acetate) makes this a drawing and painting package for the professional artist.

You can work in multiple windows, creating, previewing, and editing full-color images. The package offers 16.7 million user-defined colors with 12 predesigned palettes of 150 colors each, as well as user-defined palettes. Equally important, you can undo up to 16 actions in a row, blend objects, make multiple copies of an object, and cut holes in objects. The program can import and export a wide range of vector and bit-mapped file types. You can call up clip art files and symbols into separate windows, using a thumbnail image to preview them before you go further.

Harvard Draw for Windows takes much of the guesswork out of moving objects. As you move your mouse, a black-and-white outline of the object shows its exact position on-screen. The original color object remains in place until you release the mouse button. Unfortunately, though, every time you move or modify an object, the screen must repaint itself. This is slow on a 386 machine, even for simple images. Be prepared to spend at least an hour loading the 12 program disks onto your hard drive.

—D. E.

World Radio History



MASS-11 DRAW 6.1

Looking at the screen display of Mass-11 Draw 6.1, you might think it was a low-end PC/XT version of a drawing package, but don't let this less-than-pretty picture deceive you. DOS-based Mass-11 Draw actually has enough sophisticated features to interest users who want to create engineering and technical illustrations without investing in a more expensive CAD application.

Mass-11 Draw provides a spline curve tool with several interactive drawing methods, as well as a utility called Tracer for converting scanned TIFF images, paint program images, or bit-mapped images into a drawing file that you then can edit and scale. Drawbridge, an onboard TSR graphic file-translation utility, can handle HPGL, PICT, MDL, and PIC files. Mass-11 Draw lets you use a digitizing tablet to trace artwork for input into the program and reportedly will display the tracing to an accuracy of 0.002 inch. The package includes libraries of clip art and symbols.

A few of the program's features are somewhat unwieldy, however. When you cut and paste objects, they end up positioned in the *center* of the screen—whether or not that's where you want them. And rotating an object to any angle other than 90 degrees or 180 degrees skews the object.

If you need a good library of prepackaged technical clip art and symbols, and a powerful tool for drawing spline curves as well as other basic drawing tools, then Mass-11 Draw will get the job done.

—D. E.



MACDRAW PRO 1.0

In the process of acquiring Pro status, object-based MacDraw Pro has become proficient at handling color, curves, and text. It has the curve-wrangling functions found in PostScript packages such as Aldus FreeHand and Adobe Illustrator. The Bezigon tool—as in *Bézier* and *polygon*—lets you map out a curve by placing points on the page with mouse clicks rather than by pulling on handles as you would with Adobe Illustrator or Aldus FreeHand. If you're one of the humble mortals frustrated by the usual Bézier methodology, you might find this connect-the-dot procedure more to your liking. And if you want to go back and edit a shape, you just pull on a dot or control point, dragging the line where you want the curve to pass.

Not only does it support 24-bit color, MacDraw Pro has good color-mixing capabilities and lets you set up custom, tear-off color palettes. For shading objects, the package provides a palette of 16 preset gradients (directional, circular, or shape burst) or you may easily develop new ones with the program's nicely implemented editor.

The package has the usual pens and tools for generating geometric shapes (e.g., rectangles, ovals, and arcs), as well as a freehand drawing tool. You create text just as you would an object. That means you can apply colors and fill patterns to characters, but you cannot automatically fit text inside a shape or make it conform to a curve. Oddly, System 7 functions are scarce: TrueType support, virtual memory, and the use of aliases.

MacDraw Pro will never get pulled over by the Highway Patrol; gradient fills are especially time-consuming. Even on a Mac II hopped up with a Radius Rocket, a circular fill took 15 to 20 seconds. While color manipulations can tax any system, this program is noticeably slow. Claris itself has acknowledged as much, promising speed

Rasters and Vectors

Computer graphics has evolved into a jungle of file types with no overall standard for what format images are saved in. The methods for creating images, however, fall into just two major classes: vector and raster. Each has special advantages.

Paint packages create raster, or bit-mapped, files by using hardware to define the grid of dots that compose an image. Each dot has a specific color. One big advantage of bit maps is that you can edit each pixel in the array of dots. And because you can manipulate these dots, you can mix them the way an artist might mix paints on a canvas. Developers have learned to do wonders with the bit-mapping concept: Witness the new programs that come close to electronically simulating the properties of real paint. The resolution of these device-dependent image files is limited to that of the display used to create them, and the resolution of the output device determines the final quality of the image.

Vector files are used by programs that generate line-oriented art; CAD packages and technical illustration products typically fall in this category. Vector files are object-oriented and, as such, are composed of a series of instructions—for point-to-point lines or circles, for example—that are placed at specific positions. A shape, pattern, or shading is described by a formula or code and assembled into lists of geometrical abstractions. Vector graphics are device-independent. Object-oriented graphics can be scaled without distortion and can be printed at the highest resolution of the output device. Their object orientation makes vector programs ideal for the precision drawing needed by engineers, architects, designers, and others working on the geometric planes.

World Radio History

How An Unlimited Imagination Thrives On A Limited Budget.

The world's most-persuasive graphics software is now the most-affordable. CA-Cricket Presents is now just $199, and CA-Cricket Graph is only $129.



It's fast, easy and fully integrated. It's CA-Cricket® Presents,™ and it has every feature you need to bring your ideas to life.

CA90s
CA's Computing Architecture For The 90s

A built-in outliner so you can organize your thoughts. Predesigned graphic templates. An electronic light table to edit and re-sequence your presentation. Plus speaker's notes and presentation-quality handouts and transparencies. And as you can see, you can even import graphics and scanned images from a wide variety of file formats including TIFF, CGM, Windows Metafile, Encapsulated PostScript and ASCII Text Files.

Need graphs for the slide show? Switch over to CA-Cricket® Graph.™ It comes with a selection of twelve graph types, plus all the color and fonts you need. With just a few clicks of the mouse, you'll have the charts and graphs that'll make your presentations shine.

So call 1-800-645-3003 today for the location of your nearest dealer.

Now there are no limits to what the mind, or the wallet, can do.

Microsoft Windows

COMPUTER ASSOCIATES®
Software superior by design.

©1991 Computer Associates International, Inc., 711 Stewart Avenue, Garden City, NY 11530-4787. All trade names referenced are the trademarks or registered trademarks of their respective manufacturer.

Circle 11 on Inquiry Card.

World Radio History

fixes in an upgrade already in the works.

For the person just getting into computer graphics, MacDraw Pro is a good choice. It's easy to learn and use and you can get sharp results without hauling yourself up the steep learning curve of a PostScript package. But before you join on, be aware that you'll need at least 4 MB of memory to burn—and a fairly stout Mac.

For users who need to produce professional-looking images but have little artistic ability, MacDraw Pro provides a strong alternative to Adobe Illustrator and Aldus FreeHand.

—D. B.

MICHAEL'S DRAW 1.0

Michael's Draw, an object-based drawing program with an unusual name, is a straightforward package for generating line-oriented artwork and twiddling text with special effects. The package has the standard tools for drawing geometric shapes, polygons, and lines. A nice complement of reshaping functions let you skew objects, shear them, and add perspective. A handy Copy tool automatically replicates a selected object, which can save you repeated trips to the copy/paste menu while you're attempting to clone a particular element.

To create complex drawings, the program relies on layering and "script" commands. The procedure, which involves creating scripted images by compiling a montage of layers into a single picture, requires careful reading of the manual.

The program also offers a considerable number of tools for manipulating text. It's easy to wrap text around a shape, have it follow the curve of a line, or flow a block of type into a particular shape. You can add color to text and achieve smooth gradations of color between the first and last letters. Although not as sophisticated as most desktop publishing programs, Michael's Draw has good typographic controls. A well-designed

Impressive any way you look at it.

Our Still Video Imaging Kits let you convert objects into digitized images, ready for use on Mac, PC and Windows programs like PageMaker,™ Ventura,™ Photoshop,™ Persuasion,™ MediaMaker™ and HyperCard.™

Impressed? Call 1-800-221-3333 ext. 313 for dealer locations and a free brochure.

Canon
STILL VIDEO

© 1991 Canon U.S.A., Inc.
One Canon Plaza, Lake Success, NY 11042

Brand and Product names are trademarks of their respective holders.

Circle 10 on Inquiry Card

World Radio History

WARNING! FAST WINDOWS AHEAD

Fasten your seat belt and snap in the new Hercules Graphics Station GOLD!

Windows *acceleration* plus:

- 32,768 colors
- Graphics processor
- High resolution
- High refresh rates
- VRAM
- DRAM (optional)

$495

Hercules Graphics Station GOLD

High-speed, true color Windows . . . and much more!

Call 1-800-532-0600 for details.

© Copyright 1991 Hercules Computer Technology, Inc., 921 Parker Street, Berkeley, CA 94710. 510 540 6000. Hercules is a registered trademark and Hercules Graphics Station GOLD is a trademark of Hercules Computer Technology, Inc. All other product names are trademarks of their respective owners, who are not associated with Hercules.

Circle 15 on Inquiry Card.

World Class Windows Performance.

Hercules

World Radio History

GRAPHIC TOOLS LIBRARY

GIGABASE: Interactive program with GUI. Add images to your existing database or create image database interactively. Image display, browse, print, store. Document management system. Set database views, relation, filters. Image view, scroll, zoom, compare, catalog and add memos to documents, photos, faxes, blue prints or large drawings. B/W and color images. Various image formats and compression. Fast access. Network compatible. List $295 yours for $240.

MEGAVDI: Graphics and image linkable functions. Draw, merge, clean and edit large drawings, scanned B/W, greyscale and color images. High resolution draw or overlay on image (lines, arcs, polygons, outline scalable text, splines etc.) in bitmap up to 64 MB is size with selectable pixel depth and aspect. Write or overlay text using H.P. compatible laser soft fonts. EMS, XMS. SCANNER INTERFACE. Scan part or full page B/W, greyscale or color (3 & 24bit) images from your program. Image pan, scroll, rotate(any angle), scale, zoom. Scale and print. Import TGA, GIF, RAW, RLC, PCX or TIFF (CCITT, GROUP 3, LZW, PACKBITS, RGB) images for processing. Dithering. Convert color and greyscale images to B/W. HP-GL and PaintJet. Pre-view & Print. Data Compression. Image Database. Scan & Fill. JUST USE IT. GROUP 4 optionally available. Dual Page (1600x1280) Monitor support. 'C' and C++, MS QuickBasic & Basic, CLIPPER. Herc to Super 1024X768X256. List $1195 your price $950. VISA/MC/AMEX/Check/COD/GPO

NOVA INC.
2500 W. Higgins Road, #1144
Hoffman Estates, IL 60195
708-882-4111
DOWN LOAD
DEMO'S
FAX: 708-882-4173
BBS: 708-882-4175

Fitness is feeling GREAT!

Let's Be Sure Our Children Grow Up Smart And Fit.

We know our children won't get very far in the world without a good, working knowledge of the "3 R's." That's why school is such an important part of their lives. But there's another part of their education that's just as important to their future — physical education.

The healthy hearts they develop now will go a long way toward helping them grow into healthy adults. And the good fitness habits they learn can stay with them for a lifetime. So let's encourage our children to exercise their minds. But let's be sure they do the same for their bodies.



The President's Council on Physical Fitness and Sports

BUSINESS GRAPHICS

dialog box makes it easy to adjust the spacing between characters.

In keeping with its individualistic moniker, Michael's Draw has an individualistic interface. That interface is intuitive enough, but it sometimes departs from the conventions of other Mac drawing programs. The differences are subtle—the use of heavy frames around selected items, for example—but getting used to the program's look and feel can take a while.

This is a capable package that's more than adequate for producing heavily geometric designs and generating text with special effects. Even though Michael's Draw doesn't really do anything unique, it's fairly priced, isn't a resource hog, and is easy to learn and use.

—D. B.

WINDOWS DRAW 1.0

Micrografx Designer has received most of the attention, but the company's low-end drawing program, Windows Draw, has a number of fine qualities: It is intuitive, easy to use, and smart. This Windows-based package comes with more than 2600 vector-based clip art images, which you can reshape, customize, move, and rotate with ease.

Running in 24-bit color graphics mode, Windows Draw offers 16 million colors, from which you may select a 64-color palette. You can create your own bit-mapped fill pattern by editing magnified pixels; your editing changes are visible on-screen immediately.

The rotation tool is ingenious. You establish a focal point for the rotation by positioning the cursor near the object and clicking; then you use the mouse to rotate the cursor—left or right—until the object is in the correct position. Special effects include slanting, color blending, stretching, and the ability to wrap text around objects and apply custom gradient styles.

To know instantly the function of each icon or to name a color, you simply

World Radio History



It's Time To Think About America's Biggest Business Coverup.

Today's business is covered in paper. It's piled on desks, lost in files and burying good ideas alive. That's why we created WordScan™ and WordScan Plus for Windows. The award-winning Optical Character Recognition technology that eliminates the slow process of manually typing documents into your PC. WordScan converts any document into text that can be read by word processing, desktop publishing and spreadsheet programs (no typist can equal 1200 words per minute or our industry leading accuracy). So you can integrate the information into your own work, ready in moments for revisions, retrieval and E-mail. Call us for details.

CALERA
RECOGNITION SYSTEMS

For A FREE Full-Working Evaluation Copy Of WordScan Plus And The Nearest Dealer Location Call (800) 544-7051

Calera Recognition Systems 475 Potrero Ave., Sunnyvale, CA 94086 Outside USA (408) 720-0999 FAX (408) 720-1330 © 1992 Calera Recognition Systems.
Calera® is a registered trademark and WordScan™ is a trademark of Calera Recognition Systems, Inc. All other products and brands are property of their respective trademark holders. Offer valid in USA only.

Circle 9 on Inquiry Card.

Computers and Communications

Circle 20 on Inquiry Card.

World Radio History

BUSINESS GRAPHICS



PAINTER 1.0

Working with this amazing paint program for the Mac and Windows seems almost like working with the real thing. Fractal Design has developed software that comes close to replicating the feel of working with a variety of traditional artistic media. The toolbox includes everything you'd find in a well-equipped studio: a selection of brushes, colored pencils, chalks, charcoals, calligraphy pens, felt-tipped pens, crayons, and an airbrush.

More significant, the tools generally work the way their nonelectronic counterparts do. If you take the pencil, say, and make a quick stroke, you get a light line on the screen. Bear down on a pastel chalk, and you get a broad smudge. Rub a yellow felt tip pen against black ink and the yellow gets "dirty." Each tool can be adjusted to provide different effects. You can dilute colors or blur an image by dropping "water" on it. This 24-bit paint program employs the HSV (hue, saturation, value) color system and an easy-to-use color wheel for choosing colors. As you apply more color to a region, it gets darker and denser—exactly what you'd expect in real life. Because their tools are pressure sensitive, both versions of Painter are best used with a pen and tablet (I used a Wacom digitizer). You can use a mouse, but drawing with a brick doesn't do this package justice.

The work space allows you to simulate painting or drawing on different types of paper and illustration board, offering you a wide range of grains and textures from which to choose. The paper you select determines, for instance, how a brush or other tool lays down paint or ink.

The tools are all reasonably responsive, particularly if you've got an accelerated Mac. Sometimes, though, you can end up a few steps ahead of the screen; even on a Mac with a Radius Rocket, the screen was a few seconds behind what I was doing on the tablet. The package doesn't include tools for altering the appearance of text.

You have to work with Painter to really appreciate it. Although it's geared toward experienced artists, even people who haven't picked up a paintbrush since grade school are impressed by the way it simulates traditional tools. Businesses that want unique, eye-catching graphics ought to put this in the hands of their designers. But beware: Productivity might drop, as users are inclined to get caught up exploring this remarkable electronic art studio. At $299, it's worth every penny. Painter is too cool for words.

—D. B.

PC PAINTBRUSH IV PLUS 2.0

DOS-based PC Paintbrush IV Plus, the latest version of an old standard, is a painting and image-editing program. The $240 package can work with both PCX and TIFF files and supports 8-bit color images.

PC Paintbrush's principal strength is image enhancement. It provides seven special-effects tools that control blending, smudging, gradient fill, tiling, tinting, brightness and contrast. These tools can be used to change all or part of a graphic image, and you may enhance an image using outlining and shadowing. Or you may reduce a graphic element by as much as 25 percent or enlarge it by as much as 400 percent. PC Paintbrush's repertoire also includes the ability to overlay images and the ability to zoom in and out to provide detailed editing of graphic elements.

PC Paintbrush is optimized for use with a long list of scanners, both stand-alone and hand-held. You can control a scanner from the file menu and capture black-and-white or color images. The scanner setup options include settings for brightness, contrast, image type, resolution, and scaling. The program defaults to a 4- by 4-inch size, but you can enlarge or reduce this. Unfortunately, it is very difficult to paste two images together if you have to use multiple scans of a large image.

This a good, basic picture-editing program. But its limitations are evident when compared to one of the newer Windows packages, such as ZSoft's own PhotoFinish. Still, PC Paintbrush IV Plus is easy to use, and if you follow the tutorial, you'll be drawing and painting in no time.

—S. W.

PUBLISHER'S PAINTBRUSH 2.0

Publisher's Paintbrush 2.0, ZSoft's Windows-based big brother to PC Paintbrush IV Plus, is an expanded painting and image-editing package. This $495 update now supports 24-bit color files and can display 256 shades of gray and 16.7 million colors. Version 2.0 supports a variety of scanners as well as several devices used for color calibration.

The package makes more intelligent use of Windows than did previous versions. By supporting the Multiple Document Interface, the program lets you open multiple graphic-image files and reduce them to icons when you don't need them open on-screen. The initial screen display shows a toolbox of 42 tools, which may be grouped into 24 primary icons with pull-down secondary icons. You can rearrange the location of the tools on the screen to suit your needs. If you think the brush width and color palettes take too much screen space, you may move, fold, or hide them. If you have a particular set of tools you prefer to work with, you can save that combination of tools as a personal workspace.

The package's standard drawing tools are extremely powerful. ZSoft supports both its own proprietary fonts and URW outlines. You can enter and edit text in a dialog box. Publisher's Paintbrush has very strong import/export capabilities, but it relies heavily on the older 8-bit PCX format.

Publishers Paintbrush also is optimized for use with scanners. It is compatible with a long list of scanners, both stand-alone and hand-held models. A complete installation requires 7 MB of hard disk space. Publisher's Paintbrush provides advanced graphic image editing capabilities for PC users running Windows.

—S.W.

SPLASH

Splash from Spinnaker Software is small, quick, inexpensive, useful, and a delight to use. Although definitely not a

World Radio History



STANFORD GRAPHICS FOR WINDOWS

Finally...presentation graphics with numerical clout!

Does your presentation software give you all beauty and no brains? Where is the substance behind those pretty pictures? What if your presentation program had enough data-handling muscle to meet the needs of business *and* statistical *and* scientific users?

Presenting Stanford Graphics for Windows, the first graphics package to offer both state-of-the-art presentation features and powerful analysis capabilities.

With on-screen curve fitting, formula solving, statistics, and data manipulation, Stanford Graphics advances both the art and science of technical presentations.

Circle 32 on Inquiry Card.

"Stanford Graphics offers the best of both worlds. It combines top-notch presentation features with unprecedented technical sophistication. We were greatly impressed."
—Infoworld, Sept. 16, 1991

STANFORD GRAPHICS
PRESENTATION & ANALYSIS

All this and Windows too. Stanford Graphics takes full advantage of the latest in Windows 3.0 and 3.1 technology, with sophisticated DDE, OLE, and TrueType font support.

Stanford Graphics for Windows: Presentation and Analysis.

Finally, form *and* substance.

3-D VISIONS
Call Toll Free for Details
1-800-729-4723
2780 Skypark Drive, Torrance, CA 90505
Tel:(310) 325-1339 FAX:(310) 325-1505

World Radio History

high-powered graphics program, this VGA-only package is just right for touching up and annotating TIFF files from other programs.

Useful features include an easily changeable 256-color palette and the ability to digitize signals from a Digital Vision ComputerEyes video digitizer. Shortcomings include a user interface that beeps when you perform a function properly and a limited zoom capability. The zoom function has only two sizes: normal and zoomed. When you zoom in, you get a close-up look at a portion of the larger image.

If you are on a tight budget, don't do a lot of drawing, or have children who like to draw, Splash is well worth exploring. The $39.95 price simply cannot be beat.

—R. C.

CHARTING AND GRAPHING

Charts and graphs are the mainstays of business graphics. Any serious enterprise needs to produce them at some time, for use in annual reports, business plans, promotional materials, internal financial documents, and presentations. Although many of the popular spreadsheet programs are quite astute at generating good-looking graphs, sometimes the situation calls for something more sophisticated or more creative. Also, not everyone is a spreadsheet user. Whether you need to generate charts and graphs from raw data or from cells imported from a spreadsheet package, there's a wide choice of programs that can make your visual information look professional and appealing. Mac users have an advantage here in that the better charting tools currently run on that machine. Obviously, the Mac has become a serious business computer.

Get a hold of the best value in LAN power protection for just $169 suggested list price

Blackouts, brownouts, sags... Your data and hardware are vulnerable to problems that surge suppressors and power directors are just not equipped to handle.

Now there's a complete Uninterruptible Power Supply solution to suit any budget. The Back-UPS™ 250 is reliable protection for LAN nodes, 386SX machines, 286, small PS/2 systems, and internetworking hardware such as routers, bridges, gateways and hubs.

From the largest server to the smallest router, the Back-UPS Series will increase your productivity by providing a cost-effective solution to power problems. Call for your free power protection handbook.

The NEW Back-UPS 250 offers even more cost-effective protection for LAN nodes (typical runtime for a 386SX system is 10 minutes)

Computer Reseller News Editors' Choice

- Full-time surge protection and line filtering
- Models from 250 to 1200 Volt-Amps, many with LAN interface for automatic-shutdown of Novell, LAN Manager, LAN Server, LANtastic, Banyan, SCO Unix, SunOS, AIX etc.
- UL, CSA and Novell approved with a 2 year warranty
- 230V models available
- Ask about PowerChute® UPS monitoring software and Novell-compatible UPS monitoring boards

Reader's Choice

	Model	Application	List
NEW!	Back-UPS 250	386SX, 286, XT, AT, internet hardware, POS	$169
NEW!	Back-UPS 400	Desktop 386, 486 systems, 286 servers	$249
NEW!	Back-UPS 450	Tower 386, 486 systems, servers	$329
NEW!	Back-UPS 600	Heavily configured systems, CAD/CAM workstations	$449
	Back-UPS 800RT	Multiple systems, longer runtime applications	$899
	Back-UPS 1200VX	Multiple systems, LAN hubs, small minis, telecom equipment	$1199

The Back-UPS™ by American Power Conversion

800-800-4APC, Dpt. A2



ABC FLOWCHARTER 1.13

As a Windows-based diagramming and charting program, Roykore's ABC Flowcharter provides a means of tracking procedural flow. The program's ability to link charts with chart shapes lets you create complex, hierarchical flowcharts, which you navigate by double-clicking on a chart icon and displaying the linked chart. A unique navigational grid above the vertical scroll bar moves the window image in each of the compass directions.

Flowcharter takes advantage of the Windows environment by providing complete control of most display options. You can control color, line width and style, shadowing, fill colors and patterns, and text format. The program's Fit Shape feature automatically adjusts the symbol size to display all the text. Unfortunately, the text is not contoured to the symbol shape, and text does not fit well within nonrectangular symbols. Circles and triangles, for instance, often are displayed with text extending beyond the borders.

Since Flowcharter supports Windows 2.11 as well as 3.0, it does not use the

Circle 42 on Inquiry Card

World Radio History

Make the Smart Choice in LaserJet PostScript Language Emulation Cartridges

	Pacific Data Products		Hewlett-Packard
	PacificPage PE™	PacificPage XL™	PostScript Cartridge
Suggested list price including 2 MB memory	$579★	$899	$1085
Time to output Ventura Scoop	2 minutes 23 seconds	39 seconds	2 minutes 54 seconds
60-day Money-back guarantee	Yes	Yes	No
PostScript to PCL switching	Yes	Yes	No
Upgrade program	Yes	Yes	No
Warranty	Lifetime	Lifetime	One year

★ Suggested list price of PacificPage P•E cartridge without a 2 MB memory board is only $399.

"PacificPage swiftly and accurately renders some test EPS files that other interpreters distort, and had no trouble with any of the large and complex images I used for testing."

"An Intel i960™ RISC processor on the accelerator board helps the PacificPage XL print graphics more than six times as fast as the HP PostScript Cartridge"

Edward Mendelson
PC Magazine, (June 25, 1991)

Don't settle for less just to buy the Hewlett-Packard name. Ask for PacificPage PostScript® language emulation solutions from Pacific Data Products. You'll get a lot more, for a lot less.

Each PacificPage product for LaserJet® II, IIP, IIP Plus, IID*, III, IIID, and IIIP printers is guaranteed to be completely compatible with all of your PostScript output. If you can create it, PacificPage can print it. If not, we'll give you your money back.

Choose from PacificPage PE or PacificPage II (ver. 5.0), our fastest stand-alone cartridges ever. Or PacificPage PE/XL and II/XL which combine the PacificPage cartridges with a RISC-based accelerator board. Just slip the board into the LaserJet memory slot and you'll experience an incredible increase in printing speed. If you purchase one of the PacificPage cartridges alone and find that your printing applications demand even greater speed, simply upgrade to the XL version.

Why not get more for less? Buy a PacificPage cartridge and save more than $500 over Hewlett-Packard. Or, save close to $200 over Hewlett-Packard with an XL version and amaze yourself with its speed. Make the smart choice. Choose PacificPage.

For more information call your nearest dealer or contact Pacific Data Products, 9125 Rehco Road, San Diego, CA 92121, USA. **(619) 597-4607**, Fax (619) 552-0889.

PACIFIC DATA PRODUCTS

*The XL versions of PacificPage are not compatible with the LaserJet model IID. Prices listed are manufacturer's suggested retail list price as of 2-4-92. Quotes reprinted from PC Magazine June 25, 1991. © 1991, Ziff Communications Company. PacificPage II, PacificPage P•E, PacificPage II /XL, and PacificPage PE/XL are trademarks of Pacific Data Products, Inc. PostScript is a registered trademark of Adobe Systems Incorporated. HP and LaserJet are registered trademarks of Hewlett-Packard Company. i960 is a trademark of Intel Corporation. PhoenixPage is a registered trademark of Phoenix Technologies Ltd. © 1987, 1988 Phoenix Technologies Ltd. © 1992 Pacific Data Products, Inc. EUROPEAN OFFICES: Geneva Tel (41) 22 41 26 50, Fax (41) 22 41 06 82, France Tel (33) 1 39 23 20 00, Fax (33) 1 39 63 31 20, U.K. Tel (44) 42 231414, Fax (44) 442 23 65 40

PhoenixPage

World Radio History

standard Windows help interface. The custom help interface is confusing because the index is arranged in topical rather than alphabetical order. Looking for answers to a particular question requires a lot of manual scanning. Another significant drawback is that, when I ran it in 1024 by 768 graphics mode, Flowcharter repeatedly lost pieces of symbols. The edges of the symbols weren't always drawn. This problem did not appear in standard 640 by 480 graphics mode.

Except for the improperly drawn symbols, the $295 ABC Flowcharter performed smoothly and well. It felt comfortable to use and interaction was intuitive.

—R.C.



CA-CRICKET GRAPH

CA-Cricket Graph from Computer Associates International is a chart-creation and presentation package for both Microsoft Windows and the Macintosh (versions 1.3.1 and 1.3.2, respectively). You enter data in a spreadsheet before converting it into a chart. The spreadsheet function has limited high-end computational capabilities. Unlike normal spreadsheets that allow formulae to be associated with a single cell, Cricket Graph's calculations consist of taking the values in one column, performing a calculation, and placing the results in another column. In addition to simple mathematical calculations, Cricket also supports advanced functions such as logarithms, exponential powers, and sine/cosine. Logarithmic and polar graph formats are supported, as well.

Once you enter all the data, creating a graph is quick and simple. After selecting the type of graph to create, you select your *x* and *y* axes from a dialog box and the graph is displayed. All the default graph layouts are aesthetically pleasing. Cricket allows all aspects of the displayed charts to be manipulated: colors, hatch patterns, fonts, and so on. The Windows version of the package comes with its own set of 11 high-quality display fonts. In addition to changing colors and styles, you may move and resize each graph element. One of the nicest features is that Cricket Graph lets you move slices of pie charts around for emphasis by simply clicking and dragging on the slice.

One of Cricket's drawbacks is its failure to interactively link the spreadsheet and the displayed graph. Changing the spreadsheet data does not change the graph. Another problem is the program's execution speed under Windows. Although the graph drawing speed on the Macintosh was quite comfortable, the response time under Windows was much slower, even on a 20-MHz 486SX.

If your main requirement is creating nice looking graphs, and you really don't need the power (or expense) of a spreadsheet, then the $129 CA-Cricket Graph is an affordable solution.

—R. C.



DELTAGRAPH PROFESSIONAL 2.0

DeltaPoint's excellent charting program for the Mac will help you generate good-looking, colorful graphs with little hassle. You can enter the data using the program's own columns-and-rows worksheet, which comes up when you open the program, or import data from your usual spreadsheet. Select the data, click on the Plot icon, pick the type of chart you want, then click a button to produce a chart in a separate window. You then can work directly on the chart sheet to change the way it looks. Each element (bar, line, text, and so on) is an object, so you just double-click anything you want to change. Needless to say, this setup makes it very easy to manipulate anything within a chart.

DeltaGraph Pro can generate just about any type of chart you'd want—from standard business graphs to scientific graphs. All told, the package offers 38 varieties, including 10 three-dimensional types and some esoteric kinds such as polar and spider charts. The program lets you have multiple windows associated with each data sheet, so you can have a bunch of different graphs of the same material up on the screen, if you're unsure which graph is most appropriate.

DeltaGraph Professional's color capabilities are considerable. With the shading functions and some other effects, you can design visually sophisticated graphical and textual charts. A set of drawing tools enables you to annotate graphs; another collection of tools lets you set up slide shows.

DeltaGraph Pro takes full advantage of System 7, including Publish and Subscribe. Special hooks are provided to Excel, so you can establish active links between spreadsheet files and DeltaGraph charts. Excel users who'd like a more sophisticated graphing tool than Excel provides should check out the full-featured charting of DeltaGraph Pro.

At $295, DeltaGraph Pro is a good deal. Any functions it's missing are too obscure to concern most business graphers. Best of all, it's easy to use. And the results look good enough to make even a chart full of declining revenues seem less depressing.

—D. B.

EXPRESS PRESENTER 1.0

Power Up Software's Express Presenter charting package provides a fast and efficient way to create 35mm slides and on-screen presentations. Express Presenter can handle 13 chart types that range from outlines and bulleted lists of information to bar, pie, and line charts.

The charts fall into three categories: data, graphical, and annotated. In data mode, you enter information into predefined fields such as title, subtitle, and bullet. Graphic mode automatically translates the data into a presentation-quality screen according to the rules stored in definable style sheets. Annotate modem permits you to place additional text, graphics, and clip art on a slide, and you can overlay charts on each other. Groups of slides may be gathered into slide shows for real-time presentations.

If you've ever felt embarrassed by presentations with misspellings, then you'll love the built-in spelling checker. Unfortunately, you cannot spell-check an entire set of slides with one command. You must check each slide individually.

Express Presenter sells for $199.95 and

World Radio History

THE BIG 3





WORDS **GRAPHICS** **NUMBERS**

For the fast-paced business world of the 90's, you need to use the best possible tools in every aspect of communication. A combination of three key applications will drive your message home: words to tell the story, graphics to create impact, numbers to fill in the details. Windows gives you the freedom to work easily with the best in each category and use an all-star team. CorelDRAW, with over 40 international 1st place awards, is the logical choice to add graphics to your words and numbers. It's the most versatile, powerful and the easiest to use. And today, the impact of graphics is a must to get your message across.

CorelDRAW — the graphics choice!

- **MOST VERSATILE** — Dress up any document. Watch your project go from the ordinary to the spectacular using CorelDRAW's special effects.
- **EASIEST TO USE** — Just point and click. CorelDRAW does the rest. It's fast and it's fun! No wonder it's the world's #1 seller.
- **BEST TYPE CONTROL** — Over 150 fully scalable outline fonts can be altered in any way. Kern visually, extrude, envelope, apply perspective, or curve text. Nobody else comes close!
- **BEST CLIPART** — Choose from over 4,000 images and symbols. Use it 'as is' or as elements in your own designs. "Publish" readers voted it "Best Clipart"!

Available for Windows, OS/2, Unix and CD-ROM!

COREL
1-800-836-DRAW
FAX: (613) 728-9176
CDN TEL: (613) 728-8200

Circle 12 on Inquiry Card.

World Radio History

arrives with several hundred useful clip art images arranged in four files. Only one of these four files may be used at a time. Oddly, to switch from one clip art group to another, you must first quit the program and start it up again, selecting the clip art file you want to look at and loading it. But this is the only awkward feature in an otherwise easy-to-use program.

—R. C.



GRAPH-IN-THE-BOX EXECUTIVE 1.14

Graph-in-the-Box Executive for DOS is a TSR program that lets you capture numerical data from a screen display within another program and use that data to create as many as 15 different types of graphs. The TSR occupies only 10 KB of memory when inactive.

Graph-in-the-Box is simple to operate. After you run the Graph program, you run a DOS application—a spreadsheet, for example—and then invoke the graphing TSR to capture a portion of the screen. Then you quit your DOS application and use the program's Graph module to quickly and easily create a graph.

One of the first PC graphing tools, Graph-in-the-Box isn't as sophisticated as some high-end packages now on the market, but it does allow you to capture data from a wide variety of DOS programs. The $299 program requires 1 MB of disk space for a complete installation. New England Software also sells a Windows and a network version of the product.

—S. W.

GRAPHMASTER 1.31

GraphMaster, Visual Business Systems' charting program for the Macintosh, is similar to DeltaGraph Pro in that it has a big selection of graph types, uses a spreadsheet-like form for entering data, is very flexible at manipulating data, uses 24 bits of color, and can produce charts that look really good. You can choose from 13 basic chart types (each of which has several variants), including the usual bar/column styles and some statistical/scientific types, such as polar graphs and histograms. Most of them can be represented in 3-D format.

The big difference between the two products lies in the way they operate. DeltaGraph Pro—for me, at least—is a bit more graceful. For example, with DeltaGraph, if you want to try out different types of charts for the same data, you just click on the Plot button and the program automatically opens up a new window for that new chart. With GraphMaster, you must open up a new page before plotting your graph; otherwise, the new chart gets plunked down on top of the one already on the screen. That doesn't present insurmountable obstacles, but it would be nice if GraphMaster got rid of the extra step.

When it comes to working on a chart, though, GraphMaster shines. Besides letting you easily change any element—once you get used to the method of selecting individual elements—the program provides a few spiffy features: gradient backgrounds, color shades, and pictograms (images based on PICT or EPS drawings). You'll even find a set of object-based drawing tools. In fact, it's so easy to customize a chart that it's hard to leave well enough alone.

GraphMaster has numerous data-manipulation functions, including sorting and transposing, and it comes with its own language for developing formulas. The program maintains links between the data window and the related chart; if you make a change to the data, the graph is updated automatically. GraphMaster also can establish a link to data in an Excel spreadsheet. With version 1.3, it fully supports System 7, including Publish and Subscribe, Data Access Language queries, and AppleEvents.

Despite its sometimes unusual procedures, this is an excellent tool that can generate just about any kind of presentation-quality chart or graph a business would need. At $295, it's a good buy.

—D. B.

INSTANT ORGCHARTING 1.0

Instant ORGcharting, another charting program from Roykore Inc., is exactly what its name implies—a method of creating presentation-quality organizational charts in record time. Although it is similar in some ways to the company's ABC Flowcharting product, Instant ORGcharting has a single purpose. This $195 package manages all layout and positioning details for you, while still providing a wealth of options. And, if you don't like any of the nine default layouts, you may manually adjust them.

Each box on the organizational chart has a set of fields associated with it. You can add, delete, and rename these fields at will. Fields can be defined and displayed box by box or you can display an entire chart. Each organizational box may have both a bit-mapped picture and a note box, which are displayed automatically when you select a symbol. Although the documentation and examples are all centered around business/personnel charts, this product is suitable for diagramming any structured information, including hierarchical parts lists.

One excellent feature is the package's ability to import and export ASCII text files to create and edit organizational charts. This feature allows information to be quickly extracted from databases.

Instant ORGcharting allows only a single organizational chart to be open at a time. Its ability to link multiple charts into a hierarchical relationship is a major shortcoming. Although sufficient to create an organizational chart for BYTE's editorial department, a chart covering all of McGraw-Hill would be unwieldy.

Instant ORGcharting is fast and it's simple. An excellent choice for anyone who builds organizational charts more than once.

—R. C.

Taking Care of Business Graphics

Remember the childhood excitement of opening a new box of crayons? All those colors to choose from. All those nice, sharp points to work with. The prospect of opening up a new business graphics package can evoke a similar sort of excitement. Too often, though, that excitement is tempered by the fear that you might choose the wrong package.

We can't tell you what to buy, but we can offer a few straightforward guidelines on selecting the appropriate *type* of business graphics program: Buy an object-based drawing package for creating precise, line-oriented artwork; a painting package for free-form illustration or photo touch-ups; and a charting program for producing graphs (although drawing programs such as Adobe Illustrator also are very good at this).

Graphics software, like art, is highly

World Radio History



CTX Monitors: Touching the World

Immortality. We each, in our own way, strive to leave our mark. Our own individual contribution to the planet.

CTX is helping you leave a lasting impression. By creating a brilliant line of monitors with unsurpassed crispness and quality, CTX is enhancing your vision.

CTX's 14″ VGA products range from the non-interlaced low radiation Super VGA to Standard VGA and Monochrome. CTX monitors offer IBM and Macintosh compatibility, handy up-front controls, non-glare screens, detachable tilt/swivel bases and universal power supplies . . . plus reputable nationwide servicing and affordable pricing.

Recently added to CTX's new product line are large screen 15″, 17″, and 21″ monitors, featuring flat screen technology and programmable screen controls. Now you know that CTX is your link to the future.

Let a CTX monitor bring your own personal greatness into view. Contact your nearest CTX dealer today. OEM accounts are also welcome.

CTX INTERNATIONAL
20530 Earlgate Street
Walnut, CA 91789
714/595-6146
Fax 714/595-6293

See us at COMDEX/Spring '92 Sands, Booth #432

CTX SOUTH
6090-F Northbelt Parkway
Norcross, GA 30071
404/729-8909
Fax 404/729-8805

CTX EAST
146 Division Place
Hackensack, NJ 07601
201/646-0707
Fax 201/646-1998

CTX MIDWEST
500 Park Blvd., Suite 425
Itasca, IL 60143
708/285-0202
Fax 708/285-0212

CTX OEM
1445 MacArthur Dr.
Carrolton, TX 75007
214/416-9610
Fax 214/245-7447

© 1991 CTX International, Inc. All rights reserved.
All trademarks, products or services are trademarks or registered trademarks of their respective owners.

Circle 13 on Inquiry Card (RESELLERS: 14).

World Radio History

subjective. Each of us has our favorites, based on what a program can do and how it does it. Professional artists tend to prefer Adobe Illustrator, Aldus FreeHand, and CorelDraw. For those less artistically inclined, the market offers a range of easy-to-use packages—such as Harvard Draw for Windows and Windows Draw—that produce good-looking images.

In the realm of painting, the very capable and inexpensive Splash deserves mention. For painting originals or retouching scanned images on the Mac, fun-to-use, bargain-priced Color It is remarkable. On the Windows side, Publisher's Paintbrush is comparable as an image editor, but it doesn't have the fluid feel of Color It. If you want to produce images that look as if you've lifted them off an easel or drawing table, Painter is a masterpiece. If you're going to work on technical as well as free-form illustrations, check out Canvas 3.0, which can handle either type of art. For charting and graphing, DeltaGraph Professional and GraphMaster both are winners on the Mac. If you're running Windows, CA-Cricket Graph looks like the best choice for right now.

None of these packages will give you the skill or aesthetic sense of DaVinci, but they can compensate for such basic artistic shortcomings as the inability to draw a straight line. And they can save artists a great deal of designing time. No matter what your business graphics requirements, you'll find plenty of powerful software to satisfy them, but before you settle on a particular program, get a test drive to make sure it can do what you need done. The ultimate buying decision, like your choice of which crayon to use first, really is up to you. ■

Stan Wszola, a BYTE Lab testing editor, is a veteran DOS user. David L. Edwards is a consulting editor for the BYTE Lab. Raymond GA Côté is continuing his 15-year love affair with computers as tools and toys. He has extensive experience as a software developer and designer of interpretive languages and user interfaces. Tom Thompson is a BYTE senior editor at large. He holds a B.S.E.E. from Memphis State University and is a certified Mac developer. D. Barker, an art school dropout, is the BYTE Lab editor handling applications software reviews. You can reach them on BIX as "stan," "dedwards," "rgacote," "tom_thompson," and "dbarker," respectively.

COMPANY INFORMATION

Accusoft Corp.
160 East Main St.
Westboro, MA 01581
(800) 525-3577
Circle 1105 on Inquiry Card.

Adobe Systems, Inc.
1625 Charleston Rd.
P.O. Box 7900
Mountain View, CA 94039
(415) 961-4400
fax: (415) 961-3769
Circle 1106 on Inquiry Card.

Aldus Corp.
411 First Ave. S.
Seattle, WA 98104
(206) 622-5500
fax: (206) 343-4240
Circle 1107 on Inquiry Card.

Claris Corp.
5201 Patrick Henry Dr.
Santa Clara, CA 95052
(408) 987-7000
fax: (408) 987-4400
Circle 1108 on Inquiry Card.

Computer Associates International, Inc.
711 Stewart Ave.
Garden City, NY 11530
(516) 227-3300
fax: (516) 227-3937
Circle 1109 on Inquiry Card.

Computer Support Corp.
15926 Midway Rd.
Dallas, TX 75244
(214) 661-5429
Circle 1110 on Inquiry Card.

Corel Systems Corp.
The Corel Building
1600 Carling Ave.
Ottawa, Ontario K1Z 8R7
(613) 728-8200
fax: (613) 761-9219
Circle 1111 on Inquiry Card.

DeltaPoint, Inc.
2 Harris Court, Suite B-1
Monterey, CA 93940
(408) 648-4000
fax: (408) 648-4020
Circle 1112 on Inquiry Card.

Deneba Software
3305 Norhtwest 74th Ave.
Miami, FL 33122
(305) 594-6965
fax: (305) 477-5794
Circle 1113 on Inquiry Card.

Event One
222 Del Norte Ave.
Sunnyvale, CA 94086
(408) 734-4358
Circle 1114 on Inquiry Card.

Fractal Design Corp.
101 Madeline Dr., Suite 204
Aptos, CA 95003
(408) 688-8800
Circle 1115 on Inquiry Card.

Media Cybernetics, Inc.
8484 Georgia Ave.
Silver Springs, MD 20910
(301) 495-3305
fax: (301) 495-5964
Circle 1116 on Inquiry Card.

MicroFrontier, Inc.
3401 101st St., Suite E
Des Moines, IA 50322
(515) 270-8109
fax: (515) 278-6828
Circle 1117 on Inquiry Card.

Micrografx, Inc.
1303 Arapaho Rd.
Richardson, TX 75081
(214) 234-1769
fax: (214) 234-2410
Circle 1118 on Inquiry Card.

Microsystems Engineering Corp.
2400 West Hassell Rd.,
Suite 400
Hoffman Estates, IL 60195F
(708) 882-0111
fax: (708) 882-9397
Circle 1119 on Inquiry Card.

New England Software, Inc.
Greenwich Office Park 3
Greenwich, CT 06831
(203) 625-0062
Circle 1120 on Inquiry Card.

Power Up Software Corp.
2929 Campus Dr.
San Mateo, CA 94403
(415) 345-5900
Circle 1121 on Inquiry Card.

Roykore, Inc.
2215 Filbert St.
San Francisco, CA 94123-3414
(415) 563-9175
fax: (415) 563-0836
Circle 1122 on Inquiry Card.

Software Publishing Corp.
3165 Kifer Rd.
Santa Clara, CA 95051
(408) 986-8000
Circle 1123 on Inquiry Card.

Spinnaker Software Corp.
201 Broadway
Cambridge, MA 02139
(617) 494-1200
Circle 1124 on Inquiry Card.

Tilcon Software, Ltd.
38 Antares, Suite 300
Nepean, Ontario
Canada K2E 7V2
(613) 226-3917
fax: (613) 226-3631
Circle 1125 on Inquiry Card.

Visual Business Systems
380 Interstate N., Suite 190
Atlanta, GA 30339
(404) 956-0325
fax: (404) 988-0009
Circle 1126 on Inquiry Card.

ZSoft, Inc.
450 Franklin Rd., Suite 100
Marietta, GA 30067
(404) 428-0008
fax: (404) 427-1150
Circle 1127 on Inquiry Card.

World Radio History



If you need statistical software, this is a statistic you should know.

SYSTAT is rated #1 by Software Digest®. In fact, SYSTAT is the only statistical analysis package to receive top honors from InfoWorld, PC Magazine and PC Week. According to Software Digest: "It is the only program that successfully blends robust features, good usability and performance, and many areas of uncommon strength from analytical graphs to powerful programming."

SYSTAT. The statistics speak for themselves.

For more information call or write: SYSTAT, Inc. 1800 Sherman Avenue, Evanston, IL 60201-3793 Tel. 708.864.5670 Fax: 708.492.3567

SYSTAT®

For international representatives call: Australia 61.3.8661766, **Canada** 416.424.1700, **Denmark** 45.64.406575, **Finland** 358.0.6923800. **France** 33.1.40935000, **Germany** 49.61.265950 (DOS), 49.30.310423 (Mac), **Italy** 39.587.213640, **Japan** 81.33.5902311, **New Zealand** 64.71.562675, **Norway** 47.3.892240, **Sweden** 46.7.6076207, **Switzerland** 41.31.416611, **The Netherlands** 31.340.266336, **UK** London 44.81.6926636.

For IBM/compatible information circle 23;

©1991 SYSTAT, Inc. Software Digest is a registered trademark of NSTL

World Radio History

For Macintosh information, circle 24 on Inquiry Card

How Can Northgate® Offer You A 386SX™/16 Color System Plus Expert Support For Only $1699?

Like Stonehenge, Some Phenomena May Never Be Explained.

Mankind has a long, fascinating history of combining ingenuity and dedication to building items that can only be described as phenomenal. Like Northgate's high-performance 386SX/16 system.

Created from the ground up, this modern wonder takes powerful 386SX performance to new levels with its impressive engineering, support and value. Take a look:

- 386SX/16MHz processor
- 2MB RAM; expands to 16MB
- 52MB IDE hard drive with 17ms seek time
- 1.2MB 5.25" and 1.44MB 3.5" floppy drives
- Space-saving 5-bay desktop case
- Six 16-bit expansion card slots
- 14" SVGA monitor
- Exclusive *OmniKey*® keyboard
- MS-DOS® 5.0
- DiagSoft™ QA Plus™ system diagnostic/performance software
- FCC Class B Certified

But what's really phenomenal... you also get 24-hour 7-day-a-week toll-free technical support, a limited one year parts and labor warranty with on-site hardware service from NCR® (second and third year plans available), and overnight shipment of replacement parts at our expense during the

©Copyright Northgate Computer 1992. All rights reserved. Northgate, OmniKey and the Northgate "N" logo are U.S. trademarks or registered U.S. trademarks of Northgate Computer Systems. 80386SX is a U.S. trademark of Intel. MS-DOS is a trademark of Microsoft Corporation. All other products and brand names are U.S. trademarks and registered U.S. trademarks of their respective companies. Specifications subject to change without notice. Northgate reserves the right to substitute components of equal or greater quality or performance. All items subject to availability. Offer good in the U.S. and Canada only. Prices shown are in U.S. dollars and do not include shipping and handling or appropriate sales taxes. We support the ethical use of software. To report

World Radio History

Rising up from Salisbury Plain in England, Stonehenge is a mystery. Theories about its creation include a primitive "duplication" of Roman architecture to an observatory for tracking the movement of stars. Even more intriguing is how the ancient craftsmen could move the massive blocks, stand them up and balance another stone on top of the pillars. And how were they able to perfectly align the stones so the sun would shine through particular columns during equinoxes? These mysteries may never be solved.



intel inside

warranty period. When coupled with our 30-day money back guarantee, it's clear you have nothing to lose. And a phenomenal computing solution to gain.

Northgate 386SX/16 **$1699**
*Lease as low as $62.86/per month**

Northgate 386SX/20 **$1799**
*Lease as low as $66.56/per month**

Call for a free Decision-Maker's Kit, complete pricing and custom configuration information.
800-345-8709

Major corporations, volume purchasers and government agencies call National Business Accounts: 800-545-6059

Charge it to your VISA, MasterCard, Discover, American Express or Northgate Big 'N' card.

NORTHGATE COMPUTER SYSTEMS, INC.
7075 Flying Cloud Drive, Eden Prairie, MN 55344

CODE B3604

software copyright violations, call the Software Publishers Association's Anti-Piracy Hotline at 1-800-388-PIRA. *Monthly lease payments are based on a 36-month standard, fair market value, open-ended lease. 12-60 month leasing options available for qualified businesses.

World Radio History



TAKE THE "LOCAL" OUT OF YOUR AREA'S NETWORK.

Today's demands to share business information, resources and technologies mean that networks can no longer afford to be local. With LANMODEM™ from Microtest, there is no reason to limit the area of your network. ⚡ **LANMODEM opens the door to the outside world.** As an intelligent network modem, LANMODEM gives authorized users transparent access to, from and between Novell™ LANs. And with the external serial port, a second modem can be attached to allow multiple users to dial-in and dial-out simultaneously. ⚡ **There's a universe of possibilities for LANMODEM.** Sales people can dial-in to upload today's orders or download timely account data to their laptop PC. Employees can dial-out to access bulletin boards, on-line information services and even other LANs. Service technicians can perform remote support and maintenance. Remote users can even run applications like spreadsheets and databases without remote control software—using LANMODEM's FastLink™ direct IPX feature. ⚡ **The down-to-earth benefits of LANMODEM.** *Cost effective:* LANMODEM is an affordable network solution that delivers 9600 baud v.42bis communications and up to 57.6K bps via the external serial port. *Compatibility:* Supports Ethernet™ (thin, thick and 10BASE-T), ARCNET™ and even 4/16 Mbps token ring. LANMODEM is also compatible with most network communications software, including popular remote control packages. *Innovative hardware/software design:* Security and utility software make management and installation easy. Plus Flash ROM allows LANMODEM to be upgraded instantly, without disconnecting it from the LAN. ⚡ **Now there's no reason to limit the area of your network.** For more information on "what's in" on dialing-in and out of your LAN call Microtest at 1-800-LAN-9675.

Microtest
Innovative LAN Solutions
800-526-9675

All product names are trademarks or registered trademarks of their respective companies.

Copyright 1991 Microtest, Inc.

Circle 91 on Inquiry Card (RESELLERS: 92).

World Radio History

SOFTWARE

LAN Manager 2.1 Opens the Gates

JON UDELL

Wide-area connectivity, solid Macintosh support, and client-side NetWare integration top the list of improvements that make the new version of LAN Manager the most impressive ever. Despite continuing confusion over the changing roles of DOS, Windows, and OS/2, Microsoft's network strategy is on target and should now begin to pay off. What's the strategy? Quite simply, to tear down barriers to Windows-oriented client/server computing.



Simultaneous NetWare/LAN Manager connectivity; browsing (top) NetWare volumes or (bottom) LAN Manager volumes.

Tapping into TCP/IP

The TCP/IP protocol included with LAN Manager 2.1 is one key strategic move. Although I'm connected to a LAN Manager server as I write these words, there's no NetBEUI stack on my DOS/Windows machine—I'm using TCP/IP. The same transport code that carries files to the server carries `icmp` packets to BYTE's Unix workstations when I type `ping`. Microsoft doesn't ship, but plans to offer as a separate product, additional TCP/IP utilities such as `telnet` and `ftp`. If you need PC-to-Unix connectivity, you will love not having to burden DOS with an extra protocol to get it. Even if you don't do Unix, though, LAN Manager's ability to ride TCP/IP networks places serious long-haul connectivity within your reach.

LAN Manager 2.1 also comes with libraries that implement Berkeley Standard Distribution sockets for both DOS and OS/2. Although an SNMP agent that monitors a LAN Manager server is the only shipping Microsoft component that uses sockets, I welcome the implicit endorsement of an alternative to named pipes. Kudos to Microsoft for encouraging the development of client/server applications without mandating how they are built.

Remote Access Done Right

Remote access to a LAN can work two ways. From a modem-connected remote PC, you can either capture the screen and keyboard of a LAN workstation (remote control) or drive a true network connection through the phone line. Remote control can be very useful for training and for those aspects of network management that involve "visiting" LAN workstations. However, it isn't really the right tool for remote database access, although it's often put to that task to compensate for non-client/server architectures.

LAN Manager's new Remote Access Service, by contrast, shines brightest in client/server applications. Like Unix SLIP (serial-line Internet Protocol) and Shiva's NetModem/E, it makes a serial port masquerade as a network adapter. You just load up another NDIS protocol, AsyBEUI, which stands for "asynchronous NetBEUI." Then you can dial up a LAN Manager server running AsyBEUI as one of its protocols and `net use` its drives and printers just as you would on an Ethernet connection. The LAN Manager server can accept asynchronous connections through its COM ports or by way of a multiport adapter (several popular models are supported). Both DOS and OS/2 clients can dial into the server's Remote Access Service.

Naturally, unless you've got a pair of screaming modems in the circuit, simple file- and print-sharing activities move at a snail's pace. But client/server applications may hardly mind the slow link. I ran the Windows-based administrative tool that comes with the latest release of SQL Server from my home DOS/Windows machine against a LAN Manager server at work. Because relatively small squirts of data passed between client and server—commands, acknowledgments, query results—the setup was very usable even over a 2400-bps connection.

There were two glitches. First, although you can have two simultaneous network connections, serial and Ethernet, LAN Manager's `net send` command didn't work in that situation. It reported a network adapter error. A Microsoft representative explained that many NetBIOS applications (although of those shipped with LAN Manager itself, only `net send`) become confused when they see two adapters. Evidently, the NetBIOS software base has some catching up to do. Second, I couldn't get DOS and Windows to do useful work during AsyBEUI transfers—the protocol processing yields virtually no cycles to other tasks.

Remote-access utilities include `rasphone`, a character-mode dialing program that you use to make and break connections, and `rasadmin`, a graphical

World Radio History

A Message To Our Subscribers

From time to time we make the BYTE subscriber list available to other companies who wish to send our subscribers material about their products. We take great care to screen these companies, choosing only those who are reputable, and whose products, services or information we feel would be of interest to you. Direct mail is an efficient medium for presenting the latest personal computer goods and services to our subscribers.

Many BYTE subscribers appreciate this controlled use of our mailing list, and look forward to finding information of interest to them in the mail. Used are our subscribers' names and addresses only (no other information we may have is ever given).

While we believe the distribution of this information is of benefit to our subscribers, we firmly respect the wishes of any subscriber who does not want to receive such promotional literature. Should you wish to restrict the use of your name, simply send your request to the following address.

BYTE Magazine
Attn: Subscriber Service
P.O. Box 555
Hightstown, NJ 08520

administrative tool (for both Windows and Presentation Manager) that controls ports, users, and connections. Using `rasadmin` over a home-to-work connection, I activated the callback feature, and the next time I dialed in, the server called me back.

BYTE ACTION SUMMARY

- **WHAT MICROSOFT LAN MANAGER 2.1 IS**
  The latest version of Microsoft's OS/2-based network operating system.
- **LIKES**
  TCP/IP and the Remote Access Service put wide-area client/server computing within reach. Macintosh and NetWare connectivity broaden LAN Manager's appeal immensely.
- **DISLIKES**
  The uncertain status of the underlying operating system, a Microsoft version of OS/2, makes life difficult for developers who want to write server applications today.
- **HARDWARE REQUIREMENTS**
  Server: 286 or higher; 9 MB of RAM recommended.
  OS/2 workstation: 286 or higher; 4.5 MB of RAM recommended.
  DOS workstation: 8086 or higher; 640 KB of RAM and extended/expanded memory recommended.
- **RECOMMENDATIONS**
  Use it alone, or in conjunction with NetWare, as a foundation for Windows-oriented client/server computing.
- **PRICES**
  Server software with 10-user license, $1995
  Unlimited user pack, $5495
  Macintosh services, $995
  Remote Access Service, $1995
  Visual Basic toolkit, $135
- **FOR MORE INFORMATION**
  Microsoft Corp.
  1 Microsoft Way
  Redmond, WA 98052
  (800) 426-9400
  (206) 882-8080

  Circle 1224 on Inquiry Card.

Living with NetWare

Thanks to one more new NDIS protocol, DOS clients can connect simultaneously to LAN Manager and NetWare servers. When you install LAN Manager's new NetWare-connectivity feature, the setup program prompts for your SHGEN (or WSGEN) disk and builds an NDIS-compliant IPX.COM. Now you can load the NetWare and LAN Manager shells at the same time—a wonderfully convenient, if somewhat ungainly, arrangement. While I would rather see Microsoft and Novell cross-support SMB and NetWare Core Protocol in their servers, LAN Manager's client-side NetWare connectivity is a laudable step in the right direction.

What puts it a cut above other dual-shell solutions I've tried is the superb Windows integration. A new Windows network driver, DUALNET.DRV, sorts out access to the two flavors of network resources. When you select Connect to Network Drive in the File Manager, for example, the driver asks you to choose between LAN Manager and NetWare. Running Windows 3.1, I connected to drives on both servers and then used drag-and-drop to move files back and forth between them.

The same LAN Manager/NetWare choice appears when you select Printers in the Control Panel. I routed LPT1 through a NetWare queue to a LaserJet and LPT2 through a LAN Manager queue to a LaserWriter (on an AppleTalk network, actually), and then I monitored both queues in Print Manager.

All this juicy interoperability takes a predictable toll on DOS and Windows. Loading both shells brought free conventional memory down to about 470 KB. Windows had to load half a dozen VxDs to support the two networks in enhanced mode. I could unload either network shell, but I had to quit Windows first. When I restarted Windows minus one or the other of the shells, it still expected to see both and so complained about the missing one—although it ran fine. And, of course, I could only unload in the reverse order of loading; so, to switch from LAN Manager plus NetWare to NetWare alone, I had to unload two shells and then reload one. Ultimately, though, LAN Manager's NetWare-connectivity feature rises above the peculiarities of DOS and Windows. It's incredibly useful.

LAN Manager for Macintosh

The new Macintosh services, formerly available from 3Com but, thankfully,

World Radio History

now a standard option, worked flawlessly. Installation was a snap, in part because I didn't make the server a *seed router* and so didn't have to define AppleTalk zones and network numbers. My Ethernet-connected LAN Manager server talked to BYTE's AppleTalk LAN by way of a Cayman Systems GatorBox. Alternatively, I could have installed a LocalTalk adapter in the server and had LAN Manager do the Ethernet/LocalTalk routing. (Note that NetWare-style internal routing, never a feature of LAN Manager, still is not; you can't, for example, join token-ring and Ethernet segments at the server to create a single logical network.) The Mac services support a maximum of 50 users; that's a hard limit, related to the availability of threads in OS/2 1.x.

The file-sharing service, MacFile, works with existing LAN Manager user accounts, so there's no administrative overhead there. You do have to explicitly share out volumes. Permissions and filenames map across the cultural chasm pretty much as you'd expect, and there's one nice enhancement that NetWare for Macintosh doesn't provide. LAN Manager maintains a list of DOS file extensions and a mapping from these to Macintosh Type and Creator strings. So when I copied a .DBF file and a .TXT file to the server, Mac clients immediately saw these as FoxBase+ and Microsoft Word documents. You can use the `macadmin` utility to change the mappings if, for example, you want Mac folks to see .TXT files as MindWrite documents instead. The same tool can also monitor active shares, which is handy.

The MacPrint service can export LAN Manager–connected printers to the Mac population, link PC users to AppleTalk-connected printers, and interpose queuing between Mac users and their own printers. Figuring out how to do all this can be confusing, in part because you have to make OS/2 and LAN Manager agree on printer and queue definitions. Eventually, I got everything to work. MacPrint caches LaserPrep files so Mac users needn't retransmit them, and it can "capture" AppleTalk printers so you can ensure spooled access and centralize job control.

Installation Central

Remote installation is an intriguing but frustrating feature of LAN Manager 2.1. You install the workstation software at the server and create a bootstrap disk. You boot a workstation from the disk, and it connects to the server and pulls the necessary files across the network.

But Microsoft failed to parameterize the installation so you can specify your version of DOS, your network adapter, and your adapter settings on the fly. Instead, the company recommends that you set up one directory on the server for each combination of these variables.

Visible Seams

The role of OS/2 remains problematic. To spare you the trouble of hunting for a compatible version of OS/2 to put underneath LAN Manager, Microsoft now includes a modified version of OS/2 1.3. Thanks to the LADDR (Layered Device Driver Architecture) extensions in this version, LAN Manager (and the new version of Sytos Plus bundled with it) works with a healthy variety of SCSI adapters.

Yet thick irony surrounds these welcome developments. With IBM leading the OS/2 charge and Microsoft advancing on the Windows NT front, it's hard to take Microsoft OS/2 1.3 seriously as a platform for the server parts of client/server applications.

OS/2's role confusion affects LAN Manager's client-side offerings as well. For historical reasons, OS/2 workstations have a number of advantages over DOS workstations in LAN Manager networks. For example, OS/2 clients can use server modem pools and can manage servers remotely; DOS clients can't. Yet sexy new features, like NetWare connectivity and over-the-network installation, aren't made available to OS/2 clients; they're for DOS/Windows clients only.

Utilities are another anomaly. The company whose strategy is "Windows, Windows, Windows" continues to lean on an awful lot of character-mode DOS utilities. Only `rasadmin` is a Windows program—and also an OS/2 program, by the way, thanks to the Windows Libraries for OS/2. This despite Microsoft's offering of a Visual Basic toolkit that encapsulates the LAN Manager application programming interface, to simplify development of Windows-based LAN Manager utilities.

Does Microsoft's shifting platform emphasis cast doubt on the future of LAN Manager? In principle, Windows NT should slide neatly under LAN Manager, but only time will tell. Meanwhile, I'm quite pleased with the 2.1 product. Key strategic advances—TCP/IP, remote access, Mac services, and NetWare connectivity—should make every savvy network integrator sit up and take notice. ■

Jon Udell is a BYTE senior technical editor at large. You can reach him on BIX as "judell."

Circle 79 on Inquiry Card.

Rack & Desk PC/AT Chassis

Integrand's new Chassis/System is not another IBM mechanical and electrical clone. An entirely fresh packaging design approach has been taken using modular construction. At present, over 40 optional stock modules allow you to customize our standard chassis to nearly any requirement. Integrand offers high quality, advanced design hardware along with applications and technical support *all at prices competitive with imports.* Why settle for less?



Rack & Desk Models
Accepts PC, XT, AT Motherboards and Passive Backplanes
Doesn't Look Like IBM
Rugged, Modular Construction
Excellent Air Flow & Cooling
Optional Card Cage Fan
Designed to meet FCC
204 Watt Supply, UL Recognized
145W & 85W also available
Reasonably Priced

Now Available
Passive Backplanes

INTEGRAND
RESEARCH CORP.

Call or write for descriptive brochure and prices:
8620 Roosevelt Ave. • Visalia, CA 93291
209/651-1203
TELEX 5106012830 (INTEGRAND UD)
FAX 209/651-1353
We accept Bank Americard/VISA and MasterCard

IBM, PC, XT, AT trademarks of International Business Machines.
Drives and computer boards not included.

World Radio History

HARDWARE

New MultiSyncs Prove That Flatter Is Better

ALAN JOCH

Although NEC's MultiSync sales have traditionally led the multiscanning-monitor market, consumers are benefiting from a wave of monitors that offer larger screens, higher noninterlaced resolutions, faster refresh rates, and flatter displays than many of NEC's products. Sony's flat-panel Trinitron displays and Nanao's innovative FlexScan series, for example, have challenged the MultiSync's stature.

NEC's response is the new FG line, which updates the MultiSync line with new sizes, crisper displays, and innovative features such as a built-in color calibrator.

The Line

The FG line will replace NEC's existing MultiSync 3DS, 4DS, and 5D. The two new 15-inch FGs, the $949 4FG and the stripped-down $799 3FGx, began shipping late last year. At press time, two larger-screen versions came to market: the 17-inch 5FG and a 21-inch 6FG. Both the $1699 5FG and the $3499 6FG display up to 1280 by 1024 pixels at 74 Hz noninterlaced.

All the FGs sport flat-square displays, which, while not flat panels like Sony's Trinitron tube, present realistic images and text with little distortion. The microprocessor control panels on the FGs let you easily size and position the display area and save your settings in memory. NEC's unique integrated color-calibration system (on all but the 3FGx) allows you to match screen colors to those of your printer or service-bureau output. Each FG complies with Sweden's MPRII ELF and VLF emissions standards, according to NEC.

Testing the 4FG

I tested the 15-inch 4FG, whose price and sharp display promise to make this model the most popular in the FG line for Windows- and Macintosh-based business applications. The 4FG offers the standard check-off items for business monitors. It has a 0.28-mm dot pitch, and it supports VGA, Super VGA, 8514/A, noninterlaced 1024- by 768-pixel display, and XGA modes. With the optional $20 interface adapter, the 4FG supports Mac II and LC users.

The 4FG's maximum resolution of 1024 by 768 pixels will serve most business users today, but given the rapid introductions of higher-resolution and relatively low-cost graphics cards that run at 1280 by 1024 pixels, the 4FG could soon run out of headroom. Those who require the higher resolution must look to the larger 5FG or 6FG and their substantial increase in price.

When displaying its maximum resolution, the 4FG supports either 60 Hz or 70 Hz in noninterlaced mode. The monitor supports 72 Hz when running 1024 by 768 pixels in interlaced mode or 800 by 600 pixels and VGA resolutions.

The front-panel controls are in easy reach and make it a breeze to resize and position the display. Included in the panel is a degauss button that you press to clear stray magnetic fields. When you switch to color mode, the same controls let you adjust the display colors to add or subtract percentages of red, green, and blue. You can select and save into memory up to three color-level combinations to match specific color models or service-bureau output. A sync switch on the panel lets you select the monitor for use with PCs or Macs.

The 4FG presents a bright, high-contrast display (thanks in part to an Invar shadow mask) that I found easy to read even after hours of editing manuscripts. The 15-inch display was large enough to work comfortably in Windows. I noticed no flicker even when I ran it at 1024 by 768 pixels. Windows icons, while small, remained easily discernible in the highest resolution.

I found the optional monitor lens ($79) to be practically a necessity. The contrast that makes the display so appealing lessens considerably without the lens. Likewise, glare is a problem without the lens (background reflections existed even when the lens was in place). Overall, however, I prefer the deep black, glare and all, in the 4FG to the antiglare, flat-black coating on a MultiSync 3D in the BYTE Lab.

NEC deserves credit for designing a bevel around the outside of the display that lets you slip the lens onto the monitor. Unlike most covers of this sort, the MultiSync lens looks like an integral part of the overall unit and not something slapped on as an afterthought.

Close examination of the screen revealed some pincushioning: waviness and bowing of vertical lines. This was most evident when a window abutted the corner of the display. The FGs provide

An optional slip-on lens reduces glare and improves contrast in the MultiSync 4FG's already-sharp display.

World Radio History

Circle 90 on Inquiry Card.

BYTE ACTION SUMMARY

- **WHAT THE MULTISYNC 4FG IS**
  A 15-inch, flat-square display for PCs and Macintoshes.
- **LIKES**
  Crisp, high-contrast display; integrated color calibrator.
- **DISLIKES**
  Slight but noticeable wavy lines (pincushioning) when running Windows; maximum resolution of 1024 by 768 pixels.
- **RECOMMENDATIONS**
  For general business applications that don't require higher than 1024-by 768-pixel resolution, the 4FG is a solid choice for displaying crisp colors and text.
- **PRICE**
  $1028 as tested with optional ($79) monitor lens
- **FOR MORE INFORMATION**
  NEC Technologies, Inc.
  1255 Michael Dr.
  Wood Dale, IL 60191
  (708) 860-9500
  fax: (800) 366-0476

  Circle 1222 on Inquiry Card.

adjustments within the color-calibration mode to increase or decrease pincushioning, and I found these controls to be generally effective. However, the outside edges of the Windows screens remained wavy to some degree no matter how much I adjusted the controls. In practice, though, this distortion didn't affect my work. In addition, the light background of Windows helped reveal a hot spot in the center of the display: The middle of the screen was noticeably brighter than at the edges.

I evaluated the MultiSync 4FG with the optional lens using Sonera's DisplayMate software, which provides a series of test screens to determine display quality. For comparison, I ran the same tests on an NEC MultiSync 3D, a 14-inch display, and Sony's new CPD-1604S, a 16-inch Trinitron monitor priced at $1700 (for a complete review of the CPD-1604S and dozens of other high-resolution monitors, see the BYTE Lab Product Report on monitors coming in May). My test platform consisted of a Tangent 320s 20-MHz 386SX with ATI Technologies' Graphics Ultra graphics board (a 1-MB video RAM accelerator that runs ATI's Mach 8 coprocessor, an 8514/A clone).

The DisplayMate test screens highlighted some of the flaws I noticed when working with the monitor. But overall, the display proved to have accurate screen uniformity and almost no geometric distortion, and it was on target with color registers. I noticed no ghosting and only slight persistence with the monitor. It passed DisplayMate's pincushioning test, probably because the test screen background is black and the test lines are white. As I've mentioned, when the display is pushed harder to reproduce black lines on a white background, distortion crops up.

I note all this for the record, but my overall satisfaction with the 4FG is high, especially considering its $949 price. The Sony CPD-1604S didn't exhibit wavy pincushion lines, and its crisp display breezed through the DisplayMate tests. But for the money, the 4FG is an impressive monitor. It offers a nice compromise for those who want better performance and a larger display than 14-inch monitors but balk at the prices of the finest 16-inch and larger monitors. As I've noted, the maximum resolution of 1024 by 768 pixels is part of that compromise.

If you're a GUI-centric business user looking to enjoy what today's multiscanning monitors have to offer, the MultiSync 4FG is a sound choice. ■

Alan Joch is a senior technical editor and director of the BYTE Lab. You can contact him on BIX as "ajoch."

Gain speed in your problem solving and confidence in your answers with Maple V...



3-D Tube Plot created with Maple V.

The symbolic math software for engineering, science, and education professionals.

Maple, developed at the University of Waterloo, is today's most complete symbolic math package, and it's now available from MathSoft, the makers of Mathcad. Maple's comprehensive library of over 2,000 built-in functions and easy-to-use interactive environment delivers a maximum strength program in a surprisingly uncomplicated package.

- **Provides power and flexibility.** You won't believe that something so powerful runs on everything from supercomputers to computers with as little as 1MB of memory. And Maple's flexibility makes it easy to share files across all platforms. It's completely programmable... and Maple's user interface supports natural mathematical calculations, so you can request an infinite variety of computations and graph your output in two or three dimensions.
- **Use for a wide range of applications.** Maple is ideal for a wide range of applications, including helicopter blade design, VLSI design, chemistry, satellite guidance systems, econometrics, electrical engineering, and applied mathematics — to name just a few. Maple frees you from the "bookkeeping" of complex calculations and lets you concentrate on modeling and problem solving.

Call us toll-free at 800-628-4223 or use this coupon to request more information on Maple.

In Massachusetts call 617-577-1017 or fax this coupon to 617-577-8829.

[ ] Yes! Tell me more about Maple.

Name_____
Title_____
Company or institution_____
Address_____
City_____ State_____ Zip_____
Phone (____) _____

Mail this coupon to:
MathSoft, Inc.
201 Broadway
Cambridge, MA 02139
USA

B95 Maple

World Radio History

NATURAL

For Results that

Monument Valley, Arizona

Fans, Enclosures and Components

Books

Integrated Circuits and RAM Modules

Jameco Tool Kits



Graphics Cards



Floppy Disk Drives

MasterCard VISA

Please refer to Mail Key 1 when ordering

Terms: Prices are subject to change without notice. Items subject to availability and prior sale. Complete list of terms/warranties is available upon request.

World Radio History

RESOURCE

are Monumental

Announcing Jameco ServiceDirect™
Computer Repair and Support
1·800·831·8020

JAMECO ServiceDirect UPTIME



Get Your Free Jameco Catalog Today. Call Our 24-Hour Hotline 1·800·831·4242



Buy exactly what you want, when you want it, at competitive prices – with complete confidence in performance. Monumental results are yours with one phone call to Jameco, your natural electronic and computer product resource for over 18 years.

A wide product selection, expert technical phone support and information exchange assure that you find exactly what you want. Our 24-hour toll-free direct or fax ordering team stands ready. Most items are in stock. Same-day shipping is standard and one-day delivery always an option. Our large inventory and efficient operation mean consistently competitive prices. And our quality-tested products are warranted and backed by a 30-day full refund guarantee.

Shop on your schedule: from your office, lab or home. Just open our catalog, it's your resource for products and services whether your setting is in the home, at school or in business. Call our toll-free number to obtain your free catalog.

Discover our commitment to your convenience and satisfaction. Make your next electronic and computer product purchase directly from Jameco. See why so many people, year after year, continue to naturally choose Jameco electronics.

Motherboards, Computer Cases,
Keyboards, Power Supplies and Monitors

Circle 82 on Inquiry Card.

JAMECO®
ELECTRONIC COMPONENTS
COMPUTER PRODUCTS

1355 Shoreway Road, Belmont, CA 94002
Sales: 1·800·831·4242
Technical Support: 1·800·831·0084
Outside US: 415·592·8097
FAX: 1·800·237·6948

All trademarks are registered trademarks of their respective companies. © 4/92 Jameco Electronic Components/Computer Products

World Radio History

486-B²T

486/860 Speed... Microway Quality.

Microway has engineered four distinctive black tower systems. The **486-B²T** is designed for high-end users. It comes standard with American 486 motherboards and power supplies, yet has a reasonable starting price of $2,195. A broad range of options can be installed including high speed and capacity hard disks, intelligent serial controllers, tape back-up units, high end graphics adapters and our *Number Smasher-860*. These systems are ideal for configuring Novell or UNIX file servers, multiuser systems, and workstations for graphics, CAD and scientific uses. The **486-B²T** comes with dual fans, *Across the Board*™ Cooling and American industrial grade power supplies. All systems are thoroughly tested, burned in and include the best technical support in the industry, which we've provided since 1982.

Number Smasher-860

The key to attaining workstation performance is Microway's 40MHz *Number Smasher-860*. It features a four-way interleaved 64-bit memory system that runs at 160 megabytes/sec. The *Number Smasher's* i860 has been clocked at 80 megaflops doing matrix multiplies, 67 megaflops doing FFTs and 11.8 Double Precision Linpack Megaflops on large arrays—ten times the speed of a 486 and twice the speed of a Cray 1F! One happy user recently reported that his "Baby Cray" was happily humming away saving him thousands of dollars per month in 3090 rentals. The *Number Smasher* comes with the finest i860 compilers on the market, your choice of Microway's NDP™ FORTRAN, C|C++ or Pascal.

Call or write today for more information on Microway's new black tower systems.

Circle 93 on Inquiry Card.

Microway®

Technology You Can Count On

Corporate Headquarters, Box 79, Kingston, MA 02364 USA • TEL 508-746-7341 • FAX 508-746-4678 • U.K./Europe 081-541-5466
France 01 43 2 69593 • Germany 069-75-2023 • Holland 40 836455 • Italy 02-74.90.749 • Japan 0474 23 1322 • Norway 6-892020

World Radio History

HARDWARE AND SOFTWARE

Video Goes Digital with Fluency

TOM YAGER



Fluency's VideoPad application records, plays, and edits video clips. Programmers can use FluentStreams library functions to build digital video into their own programs.

Many of us who track the rapid growth of multimedia technology share a common view of the future: Video will enjoy widespread use as a data type. This will stem partly from the undeniable appeal of viewing moving video on your computer's display. But the practical benefits of tagging E-mail, database records, and documents with video clips far outweigh the "gee-whiz" value.

To bolster this view, a new generation of multimedia technology is emerging out of earlier, more primitive attempts at turning moving video into digital data files. With Fluency, Fluent Machines is among the first companies to package one of these new digital-video technologies for broad use. Fluency is a combination of PC hardware and software that lets you capture moving video images in real time and store them in files on your hard drive. You can play back that video with perfectly synchronized audio in a window on your PC's monitor.

Most significant is FluentStreams, the software component that enables developers to easily build digital video into applications. For nondevelopers, Fluency offers a glimpse of how digital video can be integrated into general desktop applications.

Most of Fluent Machines' work in digital video focuses on software and standards, but since no other company was shipping digital-video hardware late in 1991, Fluent Machines created the VSA-1000. This first-pass hardware was constructed to give eager developers a jump on creating digital-video applications.

The VSA-1000 has some pretty impressive specifications: real-time capture and playback of moving video and synchronized audio at a variety of bit rates (ranging roughly from 384 Kbps to 2 Mbps); image compression through an on-board C-Cube JPEG chip; the ability to simultaneously display live incoming video and captured video playback in separate windows; digital "zooming" of live and captured video (up to 300 percent); and pass-through of a standard VGA signal.

Since the VSA-1000 is planned for obsolescence, I won't dwell on its shortcomings. It does, however, illustrate that digital video has some way to go before everyone will want it. The minimum requirements for a Fluency host system are 8 MB of memory, a 25-MHz 386, and *three* empty slots. One of the VSA-1000 boards has a daughtercard that juts out far enough to obscure the neighboring slot. No matter how you slice it, you're talking about a big system. The new boards in development are reportedly trimmer, less demanding, and much easier to install.

Future hardware likely to be supported by FluentStreams includes other JPEG boards, and these are likely to behave much like the VSA-1000. Other standards, like MPEG and Intel ActionMedia II, use compression schemes that preclude certain capabilities (like quick random access). So while FluentStreams will adjust to any digital video hardware, its capabilities are inevitably tied to those of the hardware being used.

Down by the Video Stream

I installed the Fluency hardware and software in a Tandy 4033 LX Multimedia, a 33-MHz 386 system with MPC-compatible CD-ROM and audio gear. I connected the video and audio outputs from an NEC PC-VCR (a computer-controllable Super VHS VCR) to the VSA-1000's input jacks.

The real heart of Fluency is FluentStreams. This is a scheme for manipulating digital-video hardware and video and audio files, and a foundation for digital-video applications. It is hardware-independent, so it will adapt to whatever hardware becomes popular. Several vendors have already agreed to make FluentStreams part of their digital-video solutions. The software is also geared to work with playback-only systems. Inexpensive full-motion video playback hardware is expected to hit the streets soon from a variety of sources.

FluentStreams will also adapt itself well to the coming software-only playback (digital-video playback without hardware assistance) and the transmission and storage of video clips through networks. Developers who write to FluentStreams may have the best chance of having their applications run on these, and other, future systems.

For the developer, FluentStreams takes the shape of a digital-video application programming interface that offers precise control over capture and playback, live video (video-in-a-window), and digitized audio. FluentStreams supports not only playback of digital-video clips, but editing of them as well. The FluentStreams API is based on the concept of Digital Video Objects—windows in Microsoft Windows that understand how to deal with video and audio. As far as Windows programs are concerned, DVOs are full-fledged windows; they can be manipulated using regular Windows calls and referenced through ordinary window handles.

FluentStreams defines three flavors of DVOs that cover what most digital-video applications might need: an analog input object that displays external (live) video

World Radio History

in a scalable window with audio pass-through; an audio stream object that can record and play digitized audio files; and an audio/video stream object that manipulates digitized audio and video. You can work with DVOs at a simple level. Playing back an audio/video stream involves four DVO calls: `DvoCreateAudioVideo`, `DvoShow`, `DvoLoad`, and `DvoPlayForward`. This simple sequence creates the DVO audio/video object, shows the window associated with it, loads a stream from disk, and plays it. Even the `DvoLoad` call is optional, since the stream filename can be specified with the `DvoCreateAudioVideo` call.

BYTE ACTION SUMMARY

- **WHAT FLUENCY IS**
  A developer's kit consisting of the VSA-1000 digital-video capture and playback boards, FluentStreams/Digital Video Object programming libraries, and a handful of applications.
- **LIKES**
  Very well designed programming interface that includes precise video editing; consideration (through varying bit rates) for storage types covering the range from hard drives to CD-ROMs and networks.
- **DISLIKES**
  Same as with all digital video: diminished image quality (compared to videotape or laser disc); extreme system and storage requirements.
- **RECOMMENDATIONS**
  Developers intending to market digital-video applications should consider writing to FluentStreams; the Fluency package will give you everything you need to get started.
- **PRICE**
  VSA-1000, $3995
  FluentStreams, $495
- **FOR MORE INFORMATION**
  Fluent Machines, Inc.
  1881 Worcester Rd.
  Framingham, MA 01701
  (508) 626-2144
  fax: (508) 820-1106
  Circle 1221 on Inquiry Card.

Making the Cut

Once you open a video/audio or video stream, you can use DVO functions to edit the stream's contents as easily as if they were text. You can select a portion of a stream, down to an individual video frame, and cut or copy it to the Windows Clipboard. You can then paste that clip to another location in the stream, where it can either replace or add to data already there. After you've applied a series of edits, you can save the finished result to a stream file.

When you mark part of a video stream for editing, or position the playback pointer, the DVO calls expect frame addresses. These represent the number of frames, at 30 frames per second, preceding the location you wish to represent. This scheme is compatible with that used by most laser disc players, and it converts easily to and from other reference methods, including SMPTE time code. As a result, applications that expect to communicate with external laser disc players and other video gear can be easily converted to work instead with DVOs.

Practically Speaking

There are two ways to put Fluency, and products like it, to work. The simplest way is to use the applications provided by the vendor. In this case, Fluent Machines includes several useful programs, the best of which is called VideoPad (see the screen). This Windows program can play, capture, and edit video/audio clips and offers control over most of the VSA-1000's capabilities, including capture bit rates. At every rate, FluentStreams keeps the audio locked to the video and keeps the motion as smooth as the level of detail will permit.

I also wrote a small custom application using the FluentStreams library. To save time, I wrote it in OpenScript, the programming language behind Asymetrix's ToolBook. The original program opened a live video window (using New Media Graphics' Super Video Windows card) and placed buttons under it that sent positioning and playback commands to my PC-VCR. Each graphical button was tied to a different scene on the tape, which the PC-VCR located by frame number. The drawback to this original application was that, even though the PC-VCR is particularly responsive, it took several seconds to shuttle the tape from scene to scene.

It took less than an hour to replace the PC-VCR and Super Video Windows calls with rough FluentStreams equivalents. I used VideoPad to create a single stream file that included all the taped segments. I then converted the button code to play predefined segments in that loaded stream. After the initial overhead of opening and loading the stream file, response time proved to be significantly better than that of the original external-video version of my application.

That's not to say there weren't drawbacks, but they have nothing to do with FluentStreams. Most of the problems related to image quality. The original application took advantage of the PC-VCR's high-quality Super VHS output and displayed it in a large window; the video looked good even at 640 by 480 pixels. Moving to digital video, even at the highest bit rate and in a smaller window, resulted in a huge step down in image quality. While it served well for "talking heads" and other trivial subjects, it fell apart when the image included complex visuals like handwriting and detailed graphics.

Issues like these aside, writing a FluentStreams application using ToolBook proved easy enough to be enjoyable. Programming in C, or any other language that can tie into Windows dynamic link libraries, should not prove much more difficult. Fluent Machines has packaged so much functionality into a handful of calls that digital-video applications are a snap to create.

So Many Questions

Should you go with analog (external, videotape-based) or digital? Analog is inexpensive and universally viewable, and it delivers a very high quality image. Today's digital solution is more expensive, has lower quality, and requires specialized hardware and software (not to mention lots of storage), but it offers near-immediate access and very precise control.

Is it difficult to build digital video into applications? The answer, thanks to Fluent Machines, is a boisterous *no*. The company's dealings with others venturing into the digital-video realm make FluentStreams a name to watch. As digital video, which is still in its infancy, grows to take on better image quality and storage efficiency, I expect FluentStreams to keep pace. So even though digital video has a long way to go before it's ready for the average desktop, you can start building today the video-capable applications that users will want tomorrow. ■

Tom Yager is a technical editor and director of the BYTE Multimedia Lab. You can contact him on BIX as "tyager" or through the Internet at tyager@bytepb.byte.com.

World Radio History

SYSTEM

Local Bus Fuels PowerMate's Graphics Response

STEVE APIKI



High-quality, high-speed graphics is the hallmark of the PowerMate 386/33i, shown here with an optional NEC 4FG monitor.

Even the simplest application you'll find on a software dealer's shelf today will likely sport a GUI. Graphics make software more attractive and easier to use. Unfortunately, interactive graphics can also demand enough resources to choke otherwise capable systems. As applications have grown more graphical, they've required faster, more expensive systems to supply minimum acceptable performance.

The NEC PowerMate series marries high-performance graphics with midrange systems to create highly usable, general-purpose graphics machines. The PowerMate 386/33i is an excellent example of this design philosophy. Its graphics performance is solid, and screen updates in Windows and other graphics applications are snappy. This system *feels* faster than it really is. High-speed graphics hardware shortens response time enough to make the PowerMate, with modest processing power and a modest price, seem like a real screamer.

Graphic Improvement

The PowerMate's graphics system is a local-bus video design. In this arrangement, the video subsystem is not hooked to the standard peripheral (ISA) bus; instead, it's wired directly to the CPU bus, which it shares with cache memory and the cache controller. When the CPU reads or writes video memory, it does so on the 33-MHz clock of the processor bus, not on the 8-MHz cycles of the ISA bus. Obviously, this greatly enhances video performance. NEC claims that the PowerMate can save up to an additional 200 nanoseconds per video access by avoiding the synchronizing delays imposed by the ISA bus.

Local-bus technology has been the focus of industry attention of late, with the Video Electronics Standards Association recently recommending a local-bus standard and several manufacturers developing local-bus architectures. But NEC takes a proprietary approach to local-bus technology in the PowerMate, preferring to hard-wire video to the CPU bus and tweak for performance rather than design for expandability and third-party upgrades.

ACTION SUMMARY

WHAT THE NEC POWERMATE 386/33I IS
The PowerMate 386/33i is the first Intel-based system to take advantage of local-bus video processing.

LIKES
Video performance is outstanding. When coupled with a MultiSync 4FG monitor, the 386/33i also provides excellent image quality.

DISLIKES
The PowerMate 386/33i's underpowered processing system makes it only an average performer overall.

RECOMMENDATIONS
The PowerMate 386/33i is best for image-intensive applications, but aggressive pricing also makes it a good choice for general Windows or DOS use.

PRICE
$4208 (as tested)

FOR MORE INFORMATION
NEC Technologies, Inc.
1414 Massachusetts Ave.
Boxborough, MA 01719
(508) 264-8000
fax: (508) 264-8673
Circle 1223 on Inquiry Card.

My test system included a 33-MHz 386DX processor with a 32-KB cache; 4 MB of 80-ns RAM; a 60-MB 16-millisecond IDE hard drive; a 1.44-MB floppy drive; integrated (1-MB) Super VGA video; a MultiSync 4FG monitor; four 16-bit slots; one serial port; one parallel port; one PS/2 mouse port; headphone and microphone jacks; a 101-key keyboard; MS-DOS 5.0; and Windows 3.0.

continued

World Radio History



Except for the conventional benchmarks, all results are indexed, and higher numbers indicate better performance. For each index in the DOS and Windows tests, a Compaq Deskpro 386/33L running Compaq DOS 5.0 and Windows 3.0 = 1. For each index in the Unix tests, a Sun Sparcstation IPC = 1. The overall index is the average index of the individual tests.

The BYTE low-level benchmark suite identifies relative performance at the hardware level, breaking down performance by system component. The results of these tests can help you to identify the relative performance of a given subsystem and to determine where performance bottlenecks may lie. For a complete description of these tests, see "BYTE's New Benchmarks: New Looks, New Numbers," August 1990 BYTE. The BYTE low-level benchmarks, version 2.2, are available in the byte.bmarks conference on BIX, or you can contact BYTE directly.

BYTE's application performance suite measures the performance you can expect to see running a given application category under a given operating environment. We test under two environments, DOS 5.0 and Windows 3.0. We test six application categories for each environment, running test scripts using the following programs: Word Processing: WordPerfect 5.0 and Lotus Ami Pro 2.0; Spreadsheet: Lotus 1-2-3 release 3.1+ and Microsoft Excel 3.0a; Database: Software Publishing Superbase 4 1.3 and Ashton-Tate dBase IV; Development: Borland Turbo Pascal for Windows and Microsoft C 6.0; Scientific/Engineering: MathSoft MathCAD for Windows 3.0, MathWorks MatLab 3.5k, and Computing Resource Center Biturbo Stata 2.1; CAD: Autodesk AutoCAD release 11, and Desktop Publishing: Aldus PageMaker 4.0. The data files and test scripts are available from BYTE.

Our Unix tests show relative performance for double-precision arithmetic, the Dhrystone 2 benchmark, spawning a process (execl()), file copy throughput (in 5 seconds), pipe-based context switching, and running a shell script with eight concurrent scripts running. Unix benchmarks are available on Usenet, from Demolink, in the listings area on BIX, or on disk.

CONVENTIONAL BENCHMARKS

	LINPACK (single) (MFLOPS)	Dhrystones (Dhry./sec.)
NEC PowerMate 386/33i	0.32	14725.3
Compaq Deskpro 386/33L	0.32	14724.3

BYTE's low-level video benchmarks (see the figure) illustrate the speed of the PowerMate 386/33i's local bus. These benchmarks are not measurements of raw memory-access speed; they also include BIOS operations and times for calculating pixel placement. The PowerMate 386/33i proved about 25 percent faster than a Compaq Deskpro 386/33L on these tests, which is a good representation of the real graphics performance improvement you can expect.

But while graphics performance was excellent, the PowerMate turned in only average numbers overall, performing at about the level of the Compaq Deskpro 386/33 on our DOS and Windows application tests. To be fair, our Windows benchmarks run in 16-color mode, and the PowerMate would undoubtedly have more of an advantage at 256 colors. Unix benchmarks showed that the PowerMate is a capable Unix workstation. Still, CPU tests revealed a noticeable bottleneck in

World Radio History

the system; the PowerMate's limited 32-KB cache made it significantly slower than the Deskpro at raw memory-access tests.

Good Looks, Too

Speed is not the PowerMate 386/33i's only graphics-system innovation. When it is paired with an NEC MultiSync FG-series monitor, the PowerMate automatically sets itself for the highest supported resolution and refresh rates. The built-in video system comes with 512 KB of RAM and supports noninterlaced, 70-Hz resolutions of up to 1024 by 768 pixels at 16 colors. You can upgrade to 1 MB of video RAM (VRAM); this gives you 256 colors at 1024 by 768 pixels and pushes the maximum 16-color resolution up to 1280 by 1024 pixels interlaced.

My review unit included 1 MB of VRAM and a MultiSync 4FG monitor. In 1024- by 768-pixel Windows, the view is just stunning. The 4FG handles 70-Hz refresh for a steady, beautifully clear and bright picture. (For a review of the 4FG, see "New MultiSyncs Prove That Flatter Is Better" on page 262.)

Take the monitor off the system, twist a clip on the back of the system unit, and the case pops off readily. It goes back on just as easily. While I don't usually get excited about well-designed cases, the PowerMate deserves recognition in this area. The drive and mounting bays snap out without tools, and motherboard-mounted components are easily accessible. Adding a coprocessor or upgrading memory (to 64 MB) is just a few minutes' work.

The PowerMate 386/33i has other nice touches: Although it is not designed as an expandable system, the PowerMate provides BIOS in flash memory so that BIOS updates can be downloaded from a floppy disk. Together with the easily disassembled case, this feature makes minor upgrades trivial. It also has headphone and microphone jacks, and Windows comes preinstalled on the system.

Its advanced video features, however, are what set it apart. Supercharged video and a $3249 price ($4208 with the 4FG monitor and 1-MB video upgrade) make this system an excellent choice for Windows or any application where interactive graphics is important. As more and more applications join that category, the PowerMate 386/33i and systems like it become even better selections. ■

Steve Apiki is a BYTE technical editor with a B.S.E.E. from Rensselaer Polytechnic Institute. You can contact him on BIX as "apiki."

Order BYTE Program Listings on Disk!



BYTE listings are available on disk if you want to compile or read the complete source code listings of programs. Disks include any Software Corner programs available for the format you have chosen. BYTE listings are available from December 1985 to the present at the prices stated on the order form.

For direct ordering call TOLL-FREE: 800-258-5485. New Hampshire residents call: 603-924-9281 M–F, 8:30am to 4:30pm, Eastern Time for credit card orders only. Subscription Customer Service: 800-232-BYTE.

ORDER FORM: to place your order, complete the information below, and mail to: BYTE on Disk, One Phoenix Mill Lane, P.O. Box 809 Peterborough, NH 03458-0809. Please complete in full.

Name _____

Address _____

City _____

State _____ Zip _____

County or Parish _____ Country _____

Credit Card # _____ Exp. Date _____

Signature _____ Date _____

Please allow 6–12 weeks for delivery.

APRIL

5-1/4 Inch:	3-1/2 Inch:
☐ IBM PC	☐ Apple Macintosh ☐ IBM PS/2
IN USA/Single Month	
☐ BYTE listings $13	☐ BYTE Listings $14
IN USA/Annual Subscription	
☐ BYTE Listings $110	☐ BYTE Listings $120
OUTSIDE USA/Single Month	
☐ BYTE Listings $17	☐ BYTE Listings $18
OUTSIDE USA/Annual Subscription	
☐ BYTE Listings $140	☐ BYTE Listings $150

*Please indicate the issue date below. If you are beginning an annual subscription, note the starting issue.

BYTE Program Listings
Month _____
Year _____

☐ Check enclosed
☐ MasterCard
☐ VISA
☐ U.S. funds enclosed. (If ordering from outside the U.S., please remit in U.S. funds drawn on U.S. bank. Thank you.)

BYTE

World Radio History

REVIEWER'S NOTEBOOK

NCR 3447 Serves Up Unix

The February Solutions Focus compared high-performance file servers from Compaq, Advanced Logic Research, Tricord, Tangent, and Dell. Each included a built-in drive array for very high disk throughput and increased immunity to data loss.

Just after that review was completed, NCR delivered its own built-in drive array. We tested it in NCR's 3447 workgroup server, a 50-MHz 486-based Micro Channel system. Although the 3447 can support up to four 486 processors, we tested it in a single-processor configuration with a 128-KB second-level cache. Our test system also included 16 MB of RAM, an NCR Micro Channel Ethernet adapter, a SCSI controller, and a VGA graphics system. With the 2.1-gigabyte array bundled in (which accounts for $27,500 of the price), this super server sells for $45,085.

NCR's 3447 50-MHz processor and high-speed drive array place it among the fastest Unix file servers we've tested to date.

NCR's drive array is a RAID (redundant arrays of inexpensive disks) level 5 system that can be set up for highest performance or to provide redundancy for data protection (for an explanation of RAID, see "File Servers Face Off," February BYTE). The array that we tested consisted of five 670-MB Seagate SCSI drives configured for RAID level 0 (striping only). We ran our tests under NCR's Unix System V release 4.

The table shows the results of BYTE's Unix network server tests for NCR's 3447, Compaq's Systempro, and Tangent's Multi-Server. When comparing results, keep in mind that the Compaq and Tangent systems are 33-MHz 486-based machines, which we tested with arrays of four, not five, drives.

The 3447's random I/O performance was outstanding. On sequential tests, where fast processor performance matters less than drive controller throughput, the 3447 performed only at the same level as Tangent's fast Multi-Server. But for the majority of operations, this first 50-MHz 486 server we've tested earns the title of fastest server we've seen.

BYTE UNIX NETWORK BENCHMARK RESULTS

NCR's 3447 outruns some of the fastest competitors available.

	Compaq Systempro	Tangent Multi-Server	NCR 3447
Random I/O with transmissions (Kbps)			
One node	284	335	476
Three nodes	140	173	313
Six nodes	61	95	198
Sequential I/O with transmissions (Kbps)			
One node	226	240	249
Three nodes	86	124	116
Six nodes	42	61	55

Connect Printers Without Wires

Although it debuted in North America at 1991's Spring Comdex, Infralink, by the company of the same name, didn't receive FCC Class B approval until late last year. Now ready for prime time, Infralink generally delivers on its promise of quick and wireless connections among PCs and printers.

Infralinks use the parallel port to connect to PCs and printers. When you send a print command, the two devices pass the file using infrared light, broadcasted rather than sent as a direct beam. This, in theory, reduces problems associated with line-of-sight obstructions. According to the company, up to eight PCs and printers as far as 230 feet apart can communicate using Infralink.

The company claims that at distances of up to 23 feet, Infralink will work without any special orientation of the modules. Our tests bore this out: At roughly 20 feet we could establish almost instantaneous connections, although we sometimes had to twist the receiving module around in the air. At 40 feet, across four rows of cubicles, we were never able to successfully send a print message. Infralink says that at that distance, the sending modules should be wall mounted and angled in the direction of the receiving unit.

For those who can't bear the cost and effort of rewiring connections, Infralink is a possible alternative. However, each module costs $320. So the minimum price of $640 to get one printer and one PC talking would make us explore some more conventional print sharer avenues before we took the plunge into wireless communications. ■

Reviewer's Notebook provides new information—including version updates, new test data, long-term usage reports, and reader feedback—on products and product categories.

ITEMS DISCUSSED

Infralink ..... $320 per unit
Infralink of America, Inc.
1925 North Lynn St., Suite 703
Arlington, VA 22209
(703) 522-4412
Circle 1225 on Inquiry Card.

NCR 3447 .....$45,085
NCR Corp.
Workstation Products Division
1700 South Patterson Blvd.
Dayton, OH 45479
(800) 225-5627
(513) 445-6160
Circle 1226 on Inquiry Card.

World Radio History

release
3.1 shipping

CSS:STATISTICA



CSS/3™ Complete Statistical System with over 1,000 presentation-quality graphs fully integrated with all procedures and on-screen graph customization ■ The largest selection of statistics in a single system: in-depth, comprehensive implementations of: *Exploratory techniques; multi-way tables with banners; nonparametrics; distribution fitting; multiple regression; general nonlinear estimation; logit/probit analysis; general ANCOVA/MANCOVA; stepwise discriminant analysis; log-linear analysis; factor analysis; cluster analysis; multidimensional scaling; canonical correlation; item analysis/reliability; survival analysis; time series modeling; forecasting; lags analysis; quality control; process analysis; experimental design (with Taguchi);* and much more ■ Manuals with comprehensive introductions to each procedure and examples ■ Integrated Stats Advisor expert system ■ Extensive data management facilities (powerful spreadsheet with formulas; relational merge; data verification; flexible programming language) ■ Optimized (plain English menus/mouse) user interface: even complex analyses require just few self-explanatory selections (CSS can be run without manual; Quick Start booklet explains all basic conventions) ■ Macros, batch commands also supported ■ All output displayed in Scrollsheets™ (dynamic tables with pop-up windows and instant graphs) ■ Extremely large analysis designs (e.g., correlation matrices up to 32,000x32,000) ■ Unlimited size of files; extended precision; unmatched speed (Assembler, C) ■ Exchanges data (and graphics) with many applications (incl. Excel®, Lotus 3®, dBASE IV®, SPSS®) ■ Highest resolution output on practically all printers (incl. HP, Postscript), plotters, recorders, typesetters ■ IBM compatibles, 640k or more ■ Price: **$595.**

Quick CSS™ Subset of CSS/3: all basic statistical modules (incl. data management) and the full, presentation-quality graphics capabilities of CSS/3 ■ Price: **$295.**

CSS:GRAPHICS™ A comprehensive graphics/charting system with data management ■ All graphics capabilities of CSS/3 and, in addition, extended on-screen drawing, 19 scalable fonts, special effects, icons, maps, multi-graphics management ■ Hundreds of types of graphs ■ Interactive rotation and interactive cross-sections of 3D graphs ■ Extensive selection of tools for graphical exploration of data; fitting; smoothing; spectral planes; overlaying; layered compressions; marked subsets ■ Unique multivariate (e.g., 4D) graphs ■ Facilities to custom-design new graphs and add them permanently to menu ■ Import/export of graphs and data, 15 formats ■ Optimized (menu/mouse) user interface: even complex graphs require few keystrokes: all graphs on this page can be produced from raw data in less than 20 minutes ■ Macros, batch commands also supported ■ Unlimited size of files ■ Highest resolution output on all hardware (see CSS/3) ■ IBM compatibles, 640k or more ■ CSS:GRAPHICS is included in CSS:STATISTICA (available separately for **$495).**

Megafile Manager™ Comprehensive analytic data base management system ■ Unlimited size of files (up to 32,000 fields or 8 MB per record) ■ Megafile Manager is included in CSS/3 and CSS:STATISTICA (separately: **$295).**

CSS:STATISTICA™ A fully integrated system that combines all the capabilities of CSS/3 and CSS:GRAPHICS into a single extremely comprehensive data analysis system ■ Price: **$795.**

Domestic sh/h $7 per product; 14-day money back guarantee.

Circle 124 for DOS. Circle 125 for MAC.

StatSoft™

2325 E. 13th St. • Tulsa, OK 74104 • (918) 583-4149
Fax: (918) 583-4376

STATISTICA/Mac™ A CSS-compatible, comprehensive data analysis and graphics system designed for the Macintosh ■ Large selection of statistical methods fully integrated with presentation-quality graphics (incl. EDA, multiplots, a wide selection of interactively rotatable 3D graphs; MacDraw-style tools) ■ Unlimited size of files ■ Exchanges data with Excel and other applications ■ Price: **$495.**

Quick CSS Mac™ A subset of STATISTICA/Mac: all basic statistical modules and the full, presentation-quality graphics capabilities of STATISTICA/Mac ■ Price: **$295.**

Overseas Offices: StatSoft of Europe (Hamburg, FRG), ph: 040/4200347, fax: 040/4911310; **StatSoft UK** (London, UK), ph: 0462/482822, fax: 0462/482855; **StatSoft Pacific** (Melbourne, Australia), ph: 613-866-1766, fax: 613-866-3318; **StatSoft Canada-CCO** (Ontario), ph: 416-849-0737, fax: 416-849-0918. Available from: CORPORATE SOFTWARE and other Authorized Representatives Worldwide: Holland: Lemax BV 02065-98701; France: VERSION US (1) 40590913; Sweden: AkademiData 018-240035; Spain: ADDLINK, SRL; ph: 34-3-459-0722.

CSS, CSS/3, CSS:GRAPHICS, Megafile Manager, Quick CSS, STATISTICA, StatSoft, dBase IV, Excel, Lotus, MacDraw, Macintosh, Postscript are trademarks of their respective companies; SPSS is a registered trademark of SPSS, Inc

World Radio History

The Programmer's Shop™

RoboHELP™
by Blue Sky Software

Automatic Windows help authoring tool that makes creating Windows Help Systems as easy as point and click. RoboHELP features a customizable visual tool palette. Generates source code for context sensitive help, hypertext links, cross references, etc. RoboHELP takes care of generating complex, precisely formatted RTF, HPJ & H file(s). It is no longer necessary to know Windows programming or the Windows Help Compiler to develop a complete Help System.

LIST: $495 **PS** Price: **$479**

FastFaxts 2001-001

HALO Image File Format Library by Media Cybernetics

Instant file support for your applications

Add image file reading and writing to your applications with the HALO Image File Format Library. Makes your application instantly compatible with hundreds of graphics and imaging products. Offers complete support for TIFF (Tagged Image File Format), PCX (PC Paintbrush), BMP (Windows Bitmap), and CUT (Dr. HALO). Works with Borland C++, Turbo C, Turbo C++, and Microsoft C.

DOS		Windows	
LIST:	$249	LIST:	$349
PS Price:	**$199**	**PS** Price:	**$279**

FastFaxts 86-073

Rappôrt The Unix/DOS Bridge
by Tundra Software

Unlike terminal emulators, Rappôrt puts your PC in direct menu-driven contact with a Unix host, without asking you to remember a thing. All function and cursor keys work exactly as you would expect. And, if you wish to transfer a file, simply press Alt-Spacebar. Rappôrt displays both the DOS and Unix directories. Then use Rappôrt to navigate directories, highlight the file you want, and press enter.

LIST: $249 **PS** Price: **$229**

FastFaxts 1975-001

Janus/Ada x86 Compiler
by R. R. Software

Janus/Ada for DOS: the power and reliability of Ada, priced for everybody! You get a full implementation of the Ada standard – compiler, linker, royalty-free runtime libraries, multiple memory models, environment, tools, even an Ada tutorial. And R.R. Software supports you with 11 years of Ada experience and know-how. Now's the time for you to use Janus/Ada.

LIST: $99 **PS**Price:**$95**

FastFaxts 586-002

386 DEVELOPMENT

	LIST	PS
386 Max 6.$	100	$89
386 DOS Extender SDK	495	479
Blue MAX	125	109
DESQview 386	220	189
High C 386/486	795	749
QEMM 386	100	75
SVS C3/ANSI C Comp.	1195	325
WATCOM C8.5 386	795	639
C Code Builder	695	579

ASSEMBLY

MS MASM	150	105
Spontaneous Assembly	199	159

BASIC & ADD-ONS

BAS-C Commercial	955	925
dB/LIB Professional	189	179
Microsoft BASIC PDS	495	349
MS QuickBASIC V4.5	99	69
QuickPak Prof. V4.0	199	189

C LANGUAGE COMPILERS

Instant C	495	479
Quick C	99	69
Microsoft C/C++ Dev.Sys.	495	349
Watcom C 8.5	495	439

CASE & PROTOTYPERS

Demo II V3.0	249	239
EasyCase Plus	495	449
G-Base Professional	799	699
Instant Replay Prof.	795	769
Layout	300	239
Show Partner F/X	395	295

COMMUNICATIONS ADD-ONS

Blast PC Plus	295	250
C Asynch Manager 3.0	219	189
Essential COMM	329	249
Greenleaf Comm Library	359	309
Procomm Plus	119	99
QuickComm	149	129

DBMS

CLARION Prof. Dev.V2.1	845	475
Clipper 5.01	795	570
dBASE IV	795	549
dBMAN V	295	219
dBXL	249	169
FilePro Plus	699	669
FoxPro 2.0	795	499
Paradox V3.5	795	555
QuickSilver	599	399
R:BASE 3.1	795	645

DBMS CODE GENERATORS

DataBoss	695	649
Genifer	395	289
Pro-C w/Workbench	795	735
UI2 Developer's Release	595	449

DBMS TOOLS & LIBRARIES

Artful Two	295	285
Accsys for dBASE	395	349
B-Tree Dictionary	149	139
CLEAR + for dBASE	200	179
CodeBase 4.5	395	349
Comet Multiport	169	149
Comm Tools for Clipper	299	269

The PKWARE Data Compression Library
by PKWARE

The PKWARE Data Compression Library allows software developers to add data compression technology to applications. The application program controls all data I/O, allowing data to be compressed or extracted to any device or area of memory. Only 35K of memory is needed to compress data, and only 12K is needed to extract data. Compatible with MSC, BC++, TC, TP 6.0, Clipper, Basic 4.5,7.1, ASM.

LIST: $295 **PS** Price: **$275**

FastFaxts 3043-011



PRO-C
by PRO-C Limited

PRO-C is a complete C source code application generator that produces commented, fully documented, error-free C code. PRO-C Workbench (included) allows users to customize their applications. Features include: screen, report, menu and batch update modules; interfaces to many database formats. (PRO-TREE and Btrieve 5.0 file managers are included); segmented keys; relational capabilities; mouse support; and password protection.

LIST: $795 **PS** Price: **$99**

FastFaxts 1243-002 *(offer exp. 4/30/92)*

THE PROGRAMMER'S SHOP 1-800-421-8006

World Radio History

We give developers what they need...

- Tools to automate every aspect of the development cycle – over 5,000 in all
- FREE pre-sales technical support



WindowsMAKER™ Professional
by Blue Sky Software™

Considered the easiest and fastest way to create MS-Windows applications in C/C++. Generate the Windows .EXE w/complete source & production files (no royalties). Just Point & Click to define the Windows user interface. Lets you animate your design to instantly test look & feel and make changes on the fly without needing to compile. Custom code is preserved during code regeneration. The leading development tool for Microsoft Windows. Highly Recommended.

LIST: $995 **PS** Price: **$895**
FastFaxts 2001-006



WATCOM C/386
by WATCOM

Develop and debug 32-bit applications for extended DOS, Windows and OS/2 2.0. Includes royalty-free 32-bit DOS extender, true 32-bit Windows GUI Application Kit, our fast, tight, and reliable 32-bit Code Optimizer, licensed Microsoft Windows SDK Components, an interactive Source-Level Debugger, an Execution Profiler and More! *Now includes OS/2 2.0 Support.*

LIST: $795 **PS** Price: **$639**
FastFaxts 1044-020

Clipper 5.01
by Nantucket Corp.

Clipper's open architecture lends unprecedented freedom to application development. Its language is fully extensible with user-defined functions and new user-defined commands. You can extend the language with routines written in Clipper itself, or integrate code from other languages like C, Assembler, dBASE® and Pascal. Develop applications larger than available memory, without defining overlays. Clipper's compiler generates stand-alone, executable files for cost-free, unrestricted distribution.

LIST: $795 **PS** Price: **$570**
FastFaxts 1139-003



DataBoss 3.5
by Kedwell Software

DataBoss 3.5 is a complete environment for developing relational database applications and generating Pascal or C/C++ source code. DataBoss has a powerful WYSIWYG report designer and true context-sensitive help throughout. "PC Week" reviewed DataBoss as the most complete database creation system around for the PC.

LIST: $695 **PS** Price: **$649**
FastFaxts 5277-001

dBX/dBport w/source	1000	895
dGE 4.1	295	279
dSalvage Professional	200	195
Essential B-tree w/source	199	149
Faircom c-tree Plus	595	495
FLIPPER Graphics Lib.	295	279
FUNCky.LIB	249	239
Nantucket Tools II	695	499
Net Lib	299	269
Novell BTrieve	595	479
Pro Clip	99	95
R&R for dBASE & Comp.	249	229
R&R Code Generator	199	159
Scrimage	149	139

DEBUGGERS/ DISASSEMBLERS

Dis/Doc Professional	250	229
Multiscope for DOS	179	99
Periscope I/OK	495	459
Periscope IV	Varies	
Sourcer 486 w/BIOS pre-proc.	170	149
Turbo Debugger & Tools	150	119

DEVELOPMENT TOOLS

AllClear	300	259
ASMFLOW Prof.	200	179
Blinker	299	279
dANALYST Gold	495	100
C-DOC	189	179
Charge	75	69
CLEAR+ for C	200	179
Codan	395	349
Install	250	219
INSTALIT w/source	249	229
MKS Toolkit	249	229
Optlink	150	139
PC-Lint	139	115
PVCS Config. Builder	250	219
PVCS Version Manager	600	529
.RTLINK Plus	495	419
.RTPatch	495	419
Sourcerer's Appr. Prof.	499	459

EDITORS

BRIEF	249	Call
BrieFor C++	129	119
dBrief	129	119
Epsilon	250	229
KEDIT	150	139
PVCS Profes. Editor	300	249
SPF/PC	295	249
SpeedEdit	295	265
Vedit +	185	159

GRAPHICS

Essential Graphics Chart	399	349
GFX Graphics Library	150	139
GraphiC	465	419
graphics-Menu	249	229
GSS Graphics Dev't Tlkt.	795	699
GX Effects w/Source	399	369
GX Text w/Source	299	289
HALO Professional	395	319
MetaWINDOW/PLUS	395	349
PCX Programmer's Tlkt.	249	229
QuickPix	495	479
Victor w/source	295	279

THE PROGRAMMER'S SHOP 1-800-421-8006

All prices subject to change. International prices will vary.

National Accounts : 800-446-1185 ***FastFaxts*: 617-740-0025**

World Radio History

And MORE!...



Agility/VB
by Apex Software

Revolutionary Visual Basic database engine. Set-oriented function calls for fast and easy development. Built-in query-by-example (QBE) search facilities. Graphical tool provided to define complex file relationships. Automated conversion to and from Visual Basic data types. Full dBase III+, Iv database, index, and memo support. Native file format for variable record length and structure. *Special introductory price: $99*

LIST: $99 **PS** Price: $99

FastFaxts 1327-005

SpeedEdit
by Bradford Business Systems

SpeedEdit is a professional level text editor available for Windows 3.0, X-Windows Motif, & X-Windows OpenLook as a true Windows application. Also available are DOS, OS/2, SunOS, SCO Unix & Xenix, Interactive Unix, ATT Unix, HP-UX, MPE & MPE-XL character versions. Includes user customization; DDE; regular expressions; language sensitivity; keyboard macros; multiple file access; compilation & testing from within. Call for Unix, MPE & multi-user pricing.

LIST: $295 **PS** Price: **$265**

FastFaxts 2835-004



DR DOS
by Digital Research

Single -user single tasking DOS compatible operating system for 8086/286/386/486. Features MemoryMAX to move OS, TSR's buffers, drivers above 640K, file transfer utility, file viewer, partitions up to 512Mb, disk cache, full-screen editor, command line history, password protection. Multi-user version available.

LIST: $99 **Special Price:$59**
(offer exp. 4/30/92)

FastFaxts 1907-029

SVS C3 ANSI C, Pascal, or FORTRAN-77
by Silicon Valley Software

Only from the Programmer's Shop! ANSI compliant, optimizing, 32-bit compilers; DPMI-compliant, royalty-free DOS extender; source level debugger; utilities. Supports "flat model" code. Linker, librarian, make, i387 emulation, W31/4167 support. Interoperable languages!

	LIST	**PS** Price
ANSI C	$1195	$325
Pascal	$1195	$325
FORTRAN	$1495	$395

FastFaxts 1958-048 (C), 1958-049 (FORTRAN), 1958-050 (Pascal)

OBJECT-ORIENTED/C++

	LIST	PS
BORLAND C++	*$495*	*$379*
C++ Science & Engineer	1000	895
M++	295	279
Math.h++	100	95
POET/DOS	399	379
Smalltalk/V	125	85
Tools.h++ w/Source	299	279

OTHER PRODUCTS

Alpha RPL Companion Ugrade	99	99
Carbon Copy	199	179
Disk Dupe Pro	179	159
Fast!	99	89
FastBack Plus	189	159
Flow Charting 3	250	199
HEADROOM	130	89
HiJaak	199	149
LapLink Pro	150	115
Link & Locate ++ - Ext.	479	399
Mace Utilities 1990	149	99
MCapture	99	98
Norton Anti-Virus	129	119
Norton Utilities 6.0	179	149
pcANYWHERE IV	179	159
PC Tools Deluxe 7.1	179	149
PC-KWIK Power Pak	130	95
QuickNet	199	195
Remote2	195	139
Speak2Me	99	98
SpinRite II	89	79
Turbo EMS	100	89

PASCAL

MetaWare Prof. Pascal	495	480
Microsoft Pascal	300	199
Quick Pascal	99	69
Pascal ASYNCH Mgr.	175	159
Turbo Pascal 6.0	150	109
Turbo Professional	135	119

TEXT SCREEN ADD-ONS

C Worthy w/Source	649	549
MEWEL Window System	295	279
Vitamin C	395	369
VC Screen - painter	149	139
Vermont Views w/ source	890	819

WINDOWS & OS/2

ACTOR Professional 4.0	495	449
After Dark for Windows	50	39
BRIEF for OS/2	249	Call
Case: PM (for C or C++)	1995	1899
Case: W Corporate Vers.	995	969
Class Manager	399	379
dBFAST/Windows	550	399
DialogCoder	549	539
Graphics Server SDK	495	455
KnowledgePro Windows	549	395
MS Windows V3.0	149	119
MS Windows SDK V3.0	500	365
Multiscope Windows Deb.	379	315
Objectrieve/Windows	395	379
ObjectVision by Borland	150	129
POET/Windows	499	469
Quadbase-SQL for Win.	995	949
Quick C for Windows	199	149
Realizer	395	269
Smalltalk/V	500	399
ToolBook	395	349
Visual BASIC	199	165
WindowsMaker Prof.	995	895

Mach[TEN]
by Tenon Intersystems

A Smaller, Simpler UNIX! Mach[TEN] turns your Macintosh into a fully featured Berkeley 4.3BSD Unix workstation. Mach[TEN] includes the full TCP suite of protocols, NFS, UUCP, and r-series. Unix multi-tasking lets you run multiple Macintosh applications along with multiple Unix applications. All with the friendly Macintosh "point & click" interface. Built on a Carnegie Mellon Mach foundation. Turns every Macintosh into an open system. Macintosh Classic thru MacIIfx; 4MB; 40MB disk.

	LIST	PS
Mach[TEN] Workstation	$595	$475
Development System Option	$395	$325

FastFaxts 4622-001 (Work station)
FastFaxts 4622-008 (Dev. Option)

HiJaak Release 2.1
by Inset Systems Inc.

HiJaak 2.1 is a graphics conversion and screen capture utility that translates more than 43 graphics file formats such as GEM, PICT I&II, CGM, DRW, HPGL, PIC, DSF, PCS, MAC, TIF, and supports more than 25 group 3 fax device formats. 5K pop-up provides capture function of both text and graphics screens, including Windows 3.0 screens.

LIST: $199 **PS** Price: **$149**

FastFaxts 1085-003

THE PROGRAMMER'S SHOP 1-800-421-8006

World Radio History

- DOS, Windows, OS/2 and UNIX tools – for every major language
- FREE, comprehensive buyers guides
- Instant, on-line product literature with *FastFaxts!*
- International Support –

THE PROGRAMMER'S SHOP :

DEUTSCHLAND
Telefon: 0231/1768-0
Telefax: 0231/1768-16

ITALIA
Telefono: 02-48.01.11.11
Telefax: 02-48.01.11.07

International prices will vary



dCLIP 2.50
by DONNAY Software Designs

Winner of DMBS Magazine's 1991 Readers Choice Award for Best Clipper Tool. A complete Turbo-like and Dot-Prompt-style inter-active development environment for Clipper 5.01 and S87. With dCLIP you can develop Clipper applications without linking. Includes complete Database Management System and 700 tutorial programs. A library of functions (with source code) lets you build any dCLIP feature (including dot-prompt) into Clipper applications.

LIST: $349 **PS** Price: **$325**

FastFaxts 1684-001

Intel 386/486
C Code Builder
by Intel Corporation

Open Intel's new 386/486 C Code Builder™ Kit. And tear into the increased memory and performance of 32-bit DOS protected mode. Inside, you'll find everything you need to develop 32-bit applications. That means you get a Microsoft and ANSI compatible C Compiler and Libraries, Linker, Librarian, Make Utility, and Source Level Debugger. We've even included a DOS Extender that's DPMI-compliant. Compliancy that enables easy migration to Windows from Microsoft. No royalties to pay.

LIST: $695 **PS** Price: **$579**

FastFaxts 2799-028

dBFast
for Windows
by
Computer
Associates

dBFast provides a migration path to Windows for dBASE, Clipper and FoxBase applications. With extensive Windows support applications, you can utilize Windows objects such as push buttons and check boxes. Graphical images can be stored in the database for use with visual applications such as personnel databases. A single user version of dBFast meets the needs of the individual, while a multi-user version provides the data sharing capabilities required by information groups and corporate work groups. Support for Novell, LANManager, Token Ring and other NetBIOS compatible systems is available. Full support for Dynamic Link Libraries (DLL) and Dynamic Data Exchange (DDE) provide integration with other Windows applications and support for external routines, such as C programs. Computer Associates is proud to deliver a complete dBASE compatible development environment under Windows.

LIST: $550 **Special PS** Price: **$399**

FastFaxts 998-006

offer expires 4/30/92



What is FastFaxts?

Access literature on any of our products via FAX machine. **FREE!**

Call: 617-740-0025 from any fax phone!

Follow the voice computer's instructions and enter your product's code number. Then await your instant print out of product literature.

THE PROGRAMMER'S SHOP

MEMBER DIRECT MARKETING ASSOCIATION

1-800-421-8006 National Accounts 800-446-1185

BY492

90 Industrial Park Road, Hingham, MA 02043 • Canada 800-446-3846 • Mass. 617-740-2510 • FAX: 617-749-2018
Credit card orders processed only when product is shipped. All prices subject to change. International prices will vary.

World Radio History

FrameMaker.

The richest blend in document publishing.

▼ *FrameMaker 3.0 with conditional text running on a Macintosh.*

◀ *FrameMaker 3.0 running under the X Window system on SCO Open Desktop on a 386/486 PC.*

▲ *FrameMaker 3.0 on a SPARCstation under Sun's OPEN LOOK interface.*

▶ *FrameMaker 3.0 under the NeXTStep interface on this NeXTstation Color.*

Frame Technology® has a unique formula for publishing everything from simple memos to long, structured documents: FrameMaker.®

▶ FrameMaker blends into one integrated, easy-to-use program all the essentials of publishing: Authoring, editing, graphics, page layout, and production. Even math equations and hypertext.

▶ And FrameMaker 3.0 blends in new robust and exclusive features. Like conditional text capabilities to help you generate and maintain multiple versions of a single document. And an integrated, multipage table editor.

▶ FrameMaker is the perfect complement to all your hardware, because it runs on more platforms than any other publishing program. Including Apollo, Macintosh,® DEC, HP, IBM, NeXT, Sun, 386- or 486-PCs running SCO Open Desktop, and a host of other UNIX platforms—with complete file compatibility. So your workgroups not only share files, but also their skills and expertise.

▶ For a taste of FrameMaker 3.0, call 1-800-U4-FRAME Ext. 987 for more information and the name of your nearest reseller. And start brewing your own blend of publishing.

Frame™

Copyright © 1991 Frame Technology Corporation. International customers please call (408) 433-3311. FrameMaker and Frame Technology are registered trademarks, Frame and the Frame logo are trademarks of Frame Technology Corporation. Macintosh is a registered trademark of Apple Computer, Inc. All other trademarks or registered trademarks are the property of their respective holders.

Circle 71 on Inquiry Card.

World Radio History

TOM THOMPSON

MAC PROGRAMMING REVEALED

Programming the Macintosh is not as difficult as rumor has it. Here's how.

The BYTE Lab showed all the telltale signs of a typical late-night programming project. A pyramid of Diet Coke cans had been erected on the lab bench next to the environmental test chamber. The floor was littered with marked-up laser-printed listings and a medley of candy bar wrappers, while a CD player blasted out licks from a Donna Summer disco album. None of these details mattered at the moment. What did matter was the behavior of the sleeping PowerBook 140, sitting under the waiting servos of Thumper II, BYTE's battery-life testing mechanism for notebook computers.

Two bleary-eyed people stared at the testing apparatus: me and Howard Eglowstein, BYTE Lab testing editor and Thumper's creator. Howard had used Thumper to run battery-life tests on the platoon of PC notebooks arranged in neat formation on an adjacent lab bench. I was there to implement the Macintosh version of the support code that had to run on the PowerBooks during their tests. This support code periodically writes to the hard disk to simulate user operations and transmits status reports to Thumper's host computer via a serial cable.

I had started the project on the preceding afternoon and completed the code during the wee hours of the night, but there was still the question of whether the program could function reliably for the many hours the test would run. So far, 5 hours had passed without a glitch. On schedule, a servo whirred, and a rod tapped the notebook's Return key. With an understated pop, the PowerBook's screen came to life, its hard disk hummed, and a message appeared on the host PC's screen. We both breathed a sign of relief.

Somebody wandered in, and, spotting the debris, asked what was going on. I explained that the Mac notebook battery-life tests were under way. When asked how difficult it had been to write the Mac code, my explanation was, "With the exception of some problems with the serial port, it was just a matter of cutting and pasting old stuff into the shape of a battery-check program."

Sound absurd? Admittedly, I wasn't writing a complex application like Wingz, but a lot of Mac programming is like that. To a novice Mac programmer, that raises the question, "Where does old stuff come from?" The old stuff comes from the bits and pieces of code you cobbled together trying to get the Mac to do something—anything—in the first place. These first fumbling steps are the hardest, because there's a lot you have to understand about the Mac environment before you can write a line of code. But it's not impossible, especially if you place limits on what the program should accomplish while you gain an understanding of the computer. What I'll try to do here is show you working code fragments that explain some Mac fundamentals and give you something to start out with in your own programming attempts. But I'll

ILLUSTRATION: EARL KELENY © 1992

World Radio History

Listing 1: *A Mac application that writes "Hello world" in a window.*

```
/* Hello world example */
#include <Types.h>
#include <QuickDraw.h>
#include <Windows.h>
#include <Fonts.h>
#include <Memory.h>
#include <Menus.h>
#include <Dialogs.h>
#include <Events.h>
#include <OSEvents.h>
#include <THINK.h>

#define NIL             0L
#define IN_FRONT        -1
#define IS_VISIBLE    true   /* Window will be visible when drawn
                                (for debug) */
#define NO_GOAWAY     false  /* Window lacks a go-away box */
#define STACK_SIZE    20000

void main()
{
WindowPtr  thisWindow;
Rect       windowRect = {40, 40, 60, 120};

/* Set up application's heap and stack */
   SetApplLimit(((Ptr) ApplicZone() + STACK_SIZE));
   MaxApplZone();

/* Make sure we've got some master pointers */
   MoreMasters();
   MoreMasters();
   MoreMasters();

/* Set up the Mac */
   InitGraf(&qd.thePort);
   InitFonts();
   FlushEvents(everyEvent, 0);
   InitWindows();
   InitMenus();
   TEInit();
   InitDialogs(0L);

/* Make our window */
   if ((thisWindow = NewWindow(NIL, &windowRect, "\pHello", IS_VISIBLE,
         noGrowDocProc, (WindowPtr) IN_FRONT, NO_GOAWAY, NIL)) != NIL)
     {
     SetPort(thisWindow);
     MoveTo(5, 10);
     DrawString("\pHello world");
     InitCursor();                    /* Get rid of wristwatch cursor */
     do                               /* Sit in a tight loop... */
       {
       ;
       }
     while (!Button());              /* ...until mouse is clicked */
     DisposeWindow(thisWindow);     /* Discard storage for window object*/
     } /* end if thisWindow != NIL */
   else
     SysBeep(30);
} /* end main() */
```

start by dispelling some common Mac misconceptions.

A Change of Interface

Rumors have always run rampant that the Mac is hard to program and that it takes hundreds of lines of code to write out the message "Hello world." Interestingly, as Windows 3.0 becomes more popular, the same grumbling can be heard about it as well.

The first myth—that it's hard to program—came about because the Mac, in making things easy for the end user, makes more demands on the programmer. This is because the Mac (and Windows) has an event-driven GUI. The user interacts with the computer by creating events—mouse-clicks, menu selections, and key presses—that the application must respond to. That complicates things for the programmer, who has to anticipate all sorts of user actions at any time. It's not like in DOS or command-line interface–based Unix applications, where you steer users by prompting them for information in a specific order.

To manage this event-driven interface, the programmer implements an *event loop*, which is a chunk of code that polls for events and dispatches them to the appropriate handler code. As you might expect, for sophisticated applications, the event loop and its handler code can be very large, since the loop must field a variety of events and provide reasonable default settings if the user doesn't happen to give them. This also happens to fuel the second myth—those hundreds of lines of code I mentioned earlier.

If you were to implement a full-blown event-driven interface for a "Hello world" application, then this myth would become reality. But look at the matter practically, where you just generate the message itself. Listing 1 is a complete Mac application, written in Symantec's Think C 5.0, that places "Hello world" in a window. As you can see, you only have to write 48 lines of actual C code (excluding comments) to accomplish this. Obviously, the header files supply numerous "hidden" lines of definition code (for a total of 5345 lines, according to the compiler), but that's not the point: You only had to write 48 lines.

By itself, this example doesn't do much: It lacks that event loop I've been talking about. The example shown in all the C primers doesn't do much, either. However, both serve as a starting point for programming basics. Listing 1 illustrates the fundamental operations required to initialize the Mac's graphical environment, open a window, wait for a user action, and then quit cleanly. The Mac's firmware routines, called the Mac *Toolbox*, are used extensively even in this simple program.

Looking more closely, you can see that the Hello application first divvies up the memory partition given to it by the Process Manager (System 7.0) or MultiFinder (System 6.0.x), using the Toolbox call `SetApplLimit()`. This adjusts the application's heap (program area) size, which in turn gives more or less of the memory partition to the application's stack. The default stack size is 8 KB (it varies according to the type of Mac hardware and the Mac OS version number). This size is normally adequate, especially for my example. However, I put the `SetApplLimit()` call there, because if you make heavy use of recursive functions that eat up the stack, you'll want to be aware of it.

Next, you initialize the various Mac Managers. (A Manager is a collection of related Toolbox functions. For example,

World Radio History

NOTICE

WE'VE BEEN ASKED TO MAKE IT VERY CLEAR THAT
THERE'S A WHALE OF A DIFFERENCE BETWEEN QNX® AND UNIX®.

WE'RE GLAD TO OBLIGE.

EVEN THOUGH THE QNX REALTIME OPERATING SYSTEM IS *NOT* BASED ON UNIX SOURCE CODE, WE CAN UNDERSTAND HOW SOME DEVELOPERS MIGHT CONFUSE THE TWO. AFTER ALL, QNX FOLLOWS THE LATEST IEEE POSIX 1003.1 AND 1003.2 OPEN SYSTEMS STANDARDS, SO YOU GET THE SAME API AND UTILITY SET FOUND IN MANY UNIX SYSTEMS.

BUT LOOK BENEATH THE SURFACE AND YOU'LL SEE TWO FUNDAMENTALLY DISTINCT ARCHITECTURES. A MONOLITHIC OS ON THE ONE HAND, A MICROKERNEL OS ON THE OTHER. THEY'RE DIFFERENT SPECIES ALTOGETHER, AS DIFFERENT AS A WHALE AND A SCHOOL OF DOLPHINS.

ARCHITECTURE YOU CAN BUILD ON

QNX'S MODULAR, MICROKERNEL ARCHITECTURE GIVES YOU REMARKABLE FLEXIBILITY. OS SERVICES ARE PROVIDED BY A TEAM OF COOPERATING PROCESSES RATHER THAN BY A MASSIVE MONOLITHIC KERNEL. THE RESULT? YOU CAN STRIP QNX DOWN TO A ROM-ABLE EMBEDDED SYSTEM. OR BUILD IT UP TO A VAST NETWORK AND HARNESS THE POWER OF HUNDREDS OF CPUS.

OUR PRICING IS MODULAR TOO, SO YOU'RE NOT FORCED TO PAY FOR WHAT YOU DON'T NEED.

REALTIME PERFORMANCE YOU CAN COUNT ON

NEED THE SPEED OF A FAST, REALTIME EXECUTIVE? QNX CLOCKS IN AT 16 µSEC PER CONTEXT SWITCH ON A 33 MHZ 80486. BUT QNX DOESN'T STOP THERE. WITH ITS PRIORITY-DRIVEN, PREEMPTIVE SCHEDULING, YOU CAN BUILD *REAL* REALTIME SOLUTIONS.

DISTRIBUTED PROCESSING YOU CAN BET ON

QNX CAN TRANSFORM A BUNCH OF ISOLATED MACHINES INTO A SEAMLESS SUPERCOMPUTER, ORCHESTRATING HUNDREDS OF CPUS WITH ITS NETWORK-WIDE IPC. YOU'RE IN COMPLETE CONTROL OF ALL RESOURCES AT ANY POINT, FROM THE PLANT FLOOR RIGHT UP TO YOUR DESKTOP.

SUPPORT YOU CAN DEPEND ON

DURING THE LAST TEN YEARS, WE'VE EARNED A REPUTATION FOR OUTSTANDING TECHNICAL SUPPORT. WE OFFER EVERYTHING FROM 24-HOUR ONLINE CONFERENCING TO ONSITE CONSULTING, SO YOU CAN EASILY REACH THE PEOPLE WHO MAKE UP THE QNX DEVELOPMENT TEAM. THEIR EXPERTISE CAN HELP YOU KEEP YOUR DEVELOPMENT PROJECTS RIGHT ON COURSE.

TO FIND OUT HOW YOUR APPLICATIONS CAN THRIVE IN THE QNX ENVIRONMENT, CALL 1-800-363-9001, (EXT. 101).

QNX®

REALTIME OPERATING SYSTEM

Circle 113 on Inquiry Card.

QUANTUM SOFTWARE SYSTEMS LTD.
175 TERRENCE MATTHEWS CRESCENT
KANATA, ONTARIO, CANADA
K2M 1W8
TEL: 613-591-0931
FAX: 613-591-3579

ARCHITECTURE MAKES THE DIFFERENCE

QNX IS A REGISTERED TRADEMARK OF QUANTUM SOFTWARE SYSTEMS LTD. UNIX IS A REGISTERED TRADEMARK OF UNIX SYSTEM LABORATORIES, INC. ©QUANTUM SOFTWARE SYSTEMS LTD. 1991

World Radio History



Screen 1: *Using ResEdit to create a dialog box that displays four values. The digits 0 through 3 will be replaced with value strings at run time. Both the DLOG and DITL resources have an ID of 400.*



Screen 2: *The dialog box used to obtain a choice from the user. A mouse-click on either button supplies an item value to the program. All other events are ignored. Note that this dialog box isn't initially visible; the code displays it later.*

Listing 2: *A diagnostic function that displays the contents of four suspect variables in a dialog box. Note that the ID number (400) used by* `GetNewDialog()` *matches the DLOG resource ID built in screen 1.*

```
#include <Types.h>
#include <QuickDraw.h>
#include <Windows.h>
#include <Dialogs.h>

#define DIAGNOSTIC_DIALOG  400
#define NIL                0L
#define IN_FRONT           -1

void Report_It(long var1, long var2, long var3, long var4)
{
unsigned char  item1Str[10], item2Str[10], item3Str[10], item4Str[10];
short          item;
GrafPtr        oldPort;
DialogPtr      timeDialog;

   NumToString(var1, item1Str);
   NumToString(var2, item2Str);
   NumToString(var3, item3Str);
   NumToString(var4, item4Str);
   ParamText(item1Str, item2Str, item3Str, item4Str);
   timeDialog = GetNewDialog(DIAGNOSTIC_DIALOG,NIL,(WindowPtr)IN_FRONT);
   GetPort(&oldPort);
   SetPort(timeDialog);
   DrawDialog(timeDialog);
   ModalDialog(NIL, &item);
   SetPort(oldPort);
   DisposDialog(timeDialog);
) /* end Report_It() */
```

the Window Manager deals with the manipulation of windows on the screen.) Then you create a window in which to place your message, using the Window Manager call `NewWindow()`. The important thing to note here is the error-checking performed in case the `NewWindow()` call fails: You beep and abort the operation. Next, you tell the Mac OS to make your window the active graphics port using `SetPort()`. (If you don't do this, you may write your message to the Desktop or another window and thus damage the windowing environment.) Finally, you write the string "Hello world" to the window and then hang around waiting for a mouse-click using `Button()`. When you get one, you clean up after yourself and exit.

The linear execution thread of this sample program is identical to that of a DOS or Unix program. Having praised the event-driven design, now I will say something heretical: There's nothing wrong with doing things this way on the Mac. This linear sequence eliminates a lot of messy details while you are learning how the various Managers operate. It's also ideal in certain situations, such as implementing a quick problem-solving hack. I've written a few utilities this way because I only needed to elicit one or two responses from a user to accomplish a task, as you'll see later. If you ever want to write a commercial product (or a great utility), however, you'll need to implement a complete event loop to provide a flexible and friendly interface for the user. For now, I'll stick with the keep-it-simple approach.

Get the Message Out—Carefully

One of the nice things about C is that if you encounter a programming problem, you can slap some strategically placed `printf()` statements in the code to dump the values of suspect variables to the screen. Both Think C and Apple's MPW C support the standard C libraries, so you can use console I/O functions to write to the Mac's screen, and file I/O functions to handle disk files.

You're discouraged from mixing these standard I/O functions with Toolbox calls, and for good reason. Say that you've made a window and you are having problems with the text appearing in it. In an attempt to spot problems, you use a `printf()` function to examine some control variables. What you're really going to see is a bomb box, because the console I/O function will attempt to initialize the Window Manager for its own use, which in turn stomps all over the graphical environment you already set up. Result: The Mac crashes and burns.

This problem applies to other I/O functions, too: If you're using the `fwrite()` function to write to the hard disk, then avoid using Mac File Manager calls at all costs. The trick is to prevent conflicts between what you're actually doing and what the standard I/O functions intend to do. What this means is that you want to use a careful mix of nonconflicting Mac Toolbox calls and standard I/O functions to get the job done.

ResEdit to the Rescue

Back to that troublesome window example. If you can't use `printf()`, then how do you examine the variable data, short of dropping into a debugger? Since you're using the Mac Toolbox already, go an extra step and use the Dialog Manager to display the values. You create a dialog box using ResEdit, Apple's resource editor. Diagnostic code that you write then converts the target variable values to strings and places these strings in the dialog box.

ResEdit is available from the Apple Programmers and Developers Association for about $25. It is also bundled with some development software, such as Think C

World Radio History

SELECT 5 BOOKS for only $4.95

Values to $174.75





881654P $29.95
Counts as 2



9339 $32.95



15038P $28.95
Counts as 2



3280 $36.95

3490 $29.95

3279 $36.95
Counts as 2

857574 $24.95



3620P $24.95

3989P $18.95

3823 $29.95

3762P $22.95

3875 $36.95

3803 $32.95

3418P $26.95

053614 $49.95
Counts as 2



3860P $24.95

3921P $22.95
Counts as 2

3828 $29.95

4132 $29.95
Counts as 2

3049P $27.95
Counts as 2

3628 $26.95



9409 $34.95
Counts as 2



2951P $19.95

3382P $29.95
Counts as 2

3679P $22.95



881255P $24.95

3915 $36.95
Counts as 2

3916 $36.95
Counts as 2



3649P $24.95

10041P $29.95



881622P $17.95

3744 $34.95

3944P $16.95

881691P $39.95
Counts as 2



881700P $29.95
Counts as 2

4089 $29.95

881746P $24.95



881748P $29.95
Counts as 2

The Computer Book Club℠

with the BYTE Book Club

▼▽▼▽▼▽▼▽▼ Membership Benefits ▼▽▼▽▼▽▼▽▼

The Computer Book Club and the BYTE Book Club have joined forces to bring you the largest selection of business and personal computing titles available today.

- **Big Savings** In addition to this introductory offer, you keep saving substantially with members' prices of up to 50% off the publishers' prices.
- **Bonus Books** Starting immediately, you will be eligible for our Bonus Book Plan, with savings of up to 80% off publishers' prices.
- **Club News Bulletins** 15 times per year you will receive the Book Club News, describing all the current selections—mains, alternates, extras—plus bonus offers and special sales, with scores of titles to choose from.
- **Automatic Order.** If you want the Main Selection, do nothing and it will be sent to you automatically. If you prefer another selection, or no book at all, simply indicate your choice on the reply form provided. You will have at least 10 days to decide. We guarantee return postage on books received due to late mail delivery of the News. As a member, you agree to purchase at least 3 books within the next 2 years and may resign at any time thereafter.
- **Ironclad No-Risk Guarantee** If not satisfied with your books, return them within 10 days without obligation!
- **Exceptional Quality** All books are quality publishers' editions especially selected by our Editorial Board.

BY492

All books are hardcover unless number is followed by a "P" for paperback.
A shipping/handling charge and sales tax will be added to all orders. (Publishers' Prices Shown)
If card is missing, use this address to join:

©1992 THE COMPUTER BOOK CLUB, Blue Ridge Summit, PA 17294-0820

World Radio History

Listing 3: *A code fragment that sets up a dialog box and then polls for mouse-clicks on items within it. A hit on the appropriate item executes code located in the switch statement. The case constants DISABLE_CACHE and ENABLE_CACHE correspond to the numbered dialog items shown in screen 2.*

```
#define BUTTON_OFF           0
#define BUTTON_ON            1
#define CACHE_DIALOG_ID    400
#define DISABLE_CACHE        2
#define ENABLE_CACHE         3
#define NIL                 0L
#define ON_MASK    0x80008000L
#define ON         0x80008000L  /* Both caches are on (bits set) */

void main()
{
unsigned char cacheContents[20];
unsigned long cacheRegister;
short         itemHit;
short         item, itemType;
Rect          itemBox;
Handle        itemHandle;
DialogPtr     theDialog;

/* Initialize the Mac; see listing 1 */
   theDialog = GetNewDialog(CACHE_DIALOG_ID, 0L, (WindowPtr) -1L);
   asm 68030{
      MOVEC  CACR, D0            ;Copy cache-control register
      MOVE.L D0, cacheRegister   ;Save copy in our variable
      } /* end asm */

   if ((cacheRegister & ON_MASK) == ON) /* 68040 caches enabled? */
      {                          /* Yep; highlight dialog's on button */
      GetDItem(theDialog, ENABLE_CACHE, &itemType, &itemHandle, &itemBox);
      SetCtlValue((ControlHandle) itemHandle, BUTTON_ON);
      GetDItem(theDialog, DISABLE_CACHE, &itemType,
          &itemHandle, &itemBox);
      SetCtlValue((ControlHandle) itemHandle, BUTTON_OFF);
      } /* end if == ON */
    else                     /* Nope. They're off; highlight off button */
      {
      GetDItem(theDialog, DISABLE_CACHE, &itemType,
          &itemHandle, &itemBox);
      SetCtlValue((ControlHandle) itemHandle, BUTTON_ON);
      GetDItem(theDialog, ENABLE_CACHE, &itemType, &itemHandle, &itemBox);
      SetCtlValue((ControlHandle) itemHandle, BUTTON_OFF);
      } /* end else */
   ShowWindow(theDialog);
   DrawDialog(theDialog);
   do /* Handle events */
     {
     ModalDialog(0L, &itemHit);
     switch (itemHit)
       {
       case ENABLE_CACHE:  /* itemHit = 1 */
       asm 68030{
         MOVE.L #ON, D0
         MOVEC  D0, CACR
         } /* end asm */
         ;
       break;
       case DISABLE_CACHE:  /* itemHit  = 2 */
       asm 68030{
         DC.W  0xF4F8  ;CPUSHA BC  - Flush both caches
         MOVEQ #0, D0
         MOVEC D0, CACR
         } /* end asm */
         ;
       break;
       default:
       break;
       } /* end switch */
    } /* end do */
    while ((itemHit < ENABLE_CACHE) && (itemHit > DISABLE_CACHE));
    DisposDialog(theDialog);
} /* end main */
```

5.0. ResEdit has evolved over time to the point where the latest version (2.1.1) makes creating most resources just a matter of pointing and clicking.

Start by using ResEdit to create a new resource of type DLOG and sketching out a window of the desired size. Double-clicking on this window calls up the dialog items (DITL) editor. Now you add static text boxes to display the desired variables, as shown in screen 1. The "caret digit" string in these text boxes tells the Dialog Manager to substitute a string for this position in the window. Be sure to make the OK Button dialog item 1. By default, the Dialog Manager assumes that item 1 is the OK button, which means that you can dismiss the dialog box by pressing the Return key after you've looked at the values. You'll notice that a DITL resource is automatically created when you complete the dialog box design.

Finally, save the resources in a file. For Think C, my support-code project file was named Battery Check. If you name the resource file `BatteryCheck.rsrc`, Think C automatically loads these resources when you test-launch the Mac program. This is very convenient when your program is still in the early stages and you might have to revise the dialog box layout. Once you've completed the resource and code design, you have the Think C compiler create a stand-alone Mac application, where it copies these resources into the application file.

Listing 2 shows the C code that implements the rest of the diagnostic function. This routine takes the four values passed to it and converts them into strings using the Toolbox call `NumToString()`. `ParamText()` then places these strings in the corresponding locations in the dialog box. That is, `ParamText()`'s first argument gets placed at `^0` in the dialog box, the second one is placed at `^1`, and so on. Next, the code has the Dialog Manager create the dialog box (`GetNewDialog()`), set the graphics port, and draw the dialog box's contents. `ModalDialog()` looks for a mouse-click or a key press. When it receives one, it exits, the current graphics port is restored, and you clean up. While this diagnostic function isn't quite as convenient as `printf()`, once you get the resource and diagnostic function code working, it's very handy for debugging work.

A Two-Way Dialog

So far, so good. I've covered how to get a simple Mac application up and running, create windows, and display information using the Dialog Manager. Now, how do you get responses from the user? If you've got the hang of the Dialog Manager, this

World Radio History

Your interface doesn't have to be a straitjacket.

LIANT OPEN SYSTEMS PROGRAMMING TOOLS

C-scape is the most flexible user interface package for text or graphics-based applications.

All too often user interface management systems force you to program with your hands tied. You do things their way or not at all.

C-scape sets you free. It provides powerful features - scrolling windows, mouse support, menus, text editors, help, data entry, etc. - yet lets you tie your own functionality to these objects without touching the underlying code.

What's more, C-scape's object-oriented architecture makes it easy to integrate with any other C library. So you aren't locked into one solution.



...and on character-based terminals...

Unlike many other screen managers, C-scape is a true windowing environment. Which makes it powerful enough to tackle the most demanding user interface requirements.

C-scape is also so easy to use you can affordably build elegant new interfaces even for simple applications and databases.

Prototyping and code generation are no problem. C-scape's Look & Feel interactive screen designer lets you create full featured screens, test them, and then automatically generate complete C source code or binary screen files.

Applications built with C-scape can run on PC's...

C-scape applications port without modification across DOS, extended DOS, OS/2, UNIX, AIX, the X Window System, QNX and VMS.

And since C-scape supports text and graphics simultaneously, it's a smart choice for users who want to add graphics to existing text applications.

See for yourself why thousands of programmers worldwide use C-scape. Call for a copy today. And escape the interface straitjacket.

...and under the X Window System.

Liant is the world's leading supplier of open systems programming tools, languages, and libraries. Call for your free Liant product catalogue.

30 DAY MONEY BACK GUARANTEE. CALL FOR FREE DEMO 1-800-662-9866.

LIANT

In Europe, call our Berlin office at 030-391-5045. Training and international support available.

Liant logo type, C-scape and Look & Feel are trademarks of Liant Software Corp. Other trademarks belong to their respective companies. Copyright © 1991 by Liant Software Corporation, 959 Concord St., Framingham, MA 01701. 508-872-8700, FAX: 508-626-2221.

Circle 150 on Inquiry Card (RESELLERS: 151).

World Radio History

turns out to be surprisingly easy. The key is understanding the behavior of the just-mentioned `ModalDialog()`. This call presents its namesake, a modal dialog box.

Modal dialog boxes are called such because the Mac is placed into a single mode: No other user events are allowed. If you click outside of such a dialog box, the Mac just beeps at you. You use modal dialog boxes in situations where the user *must* make a choice or supply information that the application requires before it can proceed. When you click on a button or other object in the dialog box, `ModalDialog()` returns the item number of the object that was clicked on.

This behavior has important implications that you can exploit. First, to lock out all other events, `ModalDialog()` implements a sort of mini-event loop that discards all events except those having to do with its window. Second, it returns a dialog item value that you can use in a C `switch` statement to control the execution of your Mac application. By a careful arrangement of buttons, descriptive text, and item numbers for the objects in your dialog box, you can politely prompt the user as to what he or she should do, and then respond to it.

Here's a real example of putting a modal dialog box to work. A while ago, I was involved with running the Mac benchmark test suite on the Mac Quadra 900. Unfortunately, several of these applications crashed on the Quadra, due to side effects caused by the 68040 processor's caches running in the copyback mode. While Apple provides a Cache Control cdev to turn the 68040 caches off or on, you have to reboot the computer for the change to take effect. As fast as the Quadra is, I didn't want to wait for it to restart every time I had to change the operating mode of the caches—not with all the applications I had to run. Looking at a Motorola manual, I discovered instructions that would change the bits in the 68040's cache-control register, which in turn would switch the processor caches on or off.

For this either-or situation, the application design is simple. Screen 2 shows the interface I used: a dialog box with two radio buttons. Listing 3 shows the code that dealt with the interface and handled the job. After first initializing the Mac, I then created a hidden dialog box. Using Think C's in-line assembly feature, I used assembly code that examined the contents of the 68040's cache-control register. This information helps determine whether the caches are on or not, since I might have turned them off previously. The appropriate radio button—on or off—is highlighted to reflect the cache's current status. With the dialog box set up, I used `ShowWindow()` and `DrawDialog()` to make the dialog box visible and draw the dialog items.

The code then called `ModalDialog()` to look for user events. When this call returned, I passed the item value to a `switch` statement. (If the item number isn't either of the radio buttons, the value is thrown away and `ModalDialog()` is called again.) Once I hit a radio button, I executed the corresponding code in the `switch`. I used more in-line assembly code to modify the contents of the cache-control register, exit the loop, and dispose of the dialog box. To flush the 68040 caches before disabling them, I had to manually generate the `CPUSHA BC` instruction that performs this operation.

Amazingly, the code worked the first time. I could disable and enable the caches on the fly and rapidly complete the benchmark tests. I could get away with using these privileged `MOVEC` instructions be-

Some of the most enlightening articles in a magazine never make it to the table of contents.

Open to the table of contents in any publication and you can find some insightful stories. You'll also find some missing. Because the advertising isn't there.

Advertising is important. It's informative. It lets you know your options. And helps you to make decisions.

Like which car to buy. Which airline to fly. And what to serve for dinner.

So, next time you open a magazine, read it. From cover to cover.

Because what's on the back cover, may be just as important as what's on the front.

ADVERTISING.
Without it you wouldn't know.

AAF
AMERICAN ADVERTISING FEDERATION

World Radio History

cause the Mac OS normally runs in the supervisor mode on the Quadra. (It runs in user mode only when virtual memory is active, so the page-faulting mechanism can operate. In this case, I can't control the caches at all.) Not until two weeks later did I find out that by holding the Option key down while using the Cache Control cdev, you could switch the caches on and off the same way. Oh, well...

A Skeleton in the Closet

If you're wondering if the `do` loop and `ModalDialog()` and `switch` statements constitute a rudimentary event loop, you're correct. Obviously, an actual event loop is more complex than this and makes use of other Toolbox calls to capture user events, but if you've grasped the fundamental concept here, then writing a real Mac application is just a matter of filling in the details—a lot of details, to be sure, but it's a manageable task once you've mastered the basics.

Research some of these basics, such as handling menus. If you are stumped on some aspect of Mac programming, be sure to investigate the on-line services or BBSes for snippets of working Mac code. Or, if you know a Mac programmer, ask him or her for information: More often than not, the programmer will be glad to share. Also, lay your hands on the programming texts mentioned in the bibliography.

Writing a full-blown Mac application, event loop and all, is a lengthy process. You may be interested to learn that most of the experts keep a code "skeleton" handy for ready use. This skeleton implements the event loop, menu, and basic file operations. Creating a new Mac application becomes just a matter of fleshing out the code skeleton with task-specific code.

More often than not, even the task-specific code is cut and pasted from other source code files. For example, I have a lot of code files that do useful things, such as displaying a continuous line count in a dialog box, building a hierarchical menu, or initializing a serial port. When it came time to write the battery-life support code, I hauled out a code skeleton that I've developed over the years and began cutting and pasting. Naturally, some detail work required new code. This wasn't too difficult a task, because I could focus all my efforts on writing the new code and trust the old code to take care of the rest.

As I said at the beginning of this article, Mac programming requires diligent work because there are so many details to handle, such as hundreds of Mac Toolbox calls and dozens of data structures. Nevertheless, if you start small and keep your first programming projects simple, you can eventually understand it all—or, at the very least, write a set of files that remembers the details for you. ■

BIBLIOGRAPHY

Knaster, Scott. *How to Write Macintosh Software*. Hasbrouck Heights, NJ: Hayden Book Co., 1986.

Mark, Dave. *Macintosh C Programming Primer: Mastering the Toolbox Using Think C*, vol. 2. Reading, MA: Addison-Wesley, 1990.

Mark, Dave, and Cartwright Reed. *Macintosh Programming Primer: Inside the Toolbox Using THINK's LightspeedC*, vol. 1. Reading, MA: Addison-Wesley, 1989.

Tom Thompson is a BYTE senior technical editor at large. He has a B.S.E.E. from Memphis State University. You can contact him on BIX as "tom_thompson" or on AppleLink as "T.THOMPSON."

The Source for open systems programming.

If you want to create applications that are portable and hardware independent, come to The Source.

Our new catalogue offers the broadest scope of high performance programming tools, libraries and industry-standard languages available for open systems.

And all it takes to get it free is a simple phone call.

True portability for your applications.

Anything created on one machine with our products can usually be transferred intact to virtually any other machine - from PCs to supercomputers.

Which makes vendor-independence, off-loading, down-sizing, and heterogeneous networked environments now all possible.

One stop shopping.

We offer the C-scape screen designer and C-library, RM/COBOL compilers and tools, the FIGARO+ high performance graphics tool kit, UNIX languages such as LPI C++ and LPI FORTRAN. And much more.

So come to The Source.

And leave yourself open for the future.

CALL FOR YOUR FREE CATALOGUE 1-800-662-9866

LIANT



Our free software catalogue has all the products you need to make open computing a reality.

Liant logo type, LPI language logos, RM/COBOL and FIGARO+ are trademarks of Liant Software Corp. Other trademarks belong to their respective companies. Copyright © 1991 by Liant Software Corporation, 9[illegible] Concord St., Framingham, MA 01701. 508-872-8700, FAX: 508-626-2221.

Circle 146 on Inquiry Card (RESELLERS: 147).

World Radio History

How Can Northgate® Put A Loaded 486™/33 EISA System To Work For You For Only $4699?

Like The Easter Island Statues, Some Phenomena May Never Be Explained.

Visitors to Easter Island are awestruck by the statues that greet them. This same sense of awe is experienced by people who see how much performance Elegance™ 486/33 EISA gives them for such a low price.

Elegance 486/33 EISA lets you quickly tackle scientific analysis, software development, 3D CAD/CAM/CAE, complex financial modeling plus database and network management. This unsurpassed power results from Northgate's phenomenal engineering that features:

- 80486/33 MHz processor
- 8MB of rapid 32-bit DRAM
- 128K SRAM cache
- 200 MB IDE hard drive
- 1.2MB 5.25" and 1.44MB 3.5" floppy drives
- Eight 32-bit EISA bus slots (six bus master, two slave)
- Vertical Power Case with room for eight external half-height devices
- 14" SVGA 1024 x 768 color monitor with high-speed video card
- Exclusive, award-winning *OmniKey*® keyboard
- MS-DOS® 3.3, 4.01 or 5.0
- Microsoft® Windows™ 3.0
- Microsoft Mouse
- DiagSoft™ QA Plus™ system diagnostic/performance software

©Copyright Northgate Computer Systems, Inc 1992 All rights reserved Northgate, Elegance, OmniKey and the Northgate 'N' logo are U S trademarks or registered U S trademarks of Northgate Computer Systems 80486 is a registered U S trademark of Intel Microsoft, MS-DOS and Windows are trademarks of Microsoft Corp All other products and brand names are U S trademarks and registered U S trademarks of their respective companies Specifications subject to change without notice Northgate reserves the right to substitute components of equal or greater quality or performance All items subject to availability Offer good only in the U S and Canada Prices are in U S dollars and do not include shipping and handling or appropriate sales taxes.

World Radio History

Along the shores of Easter Island, isolated in the Pacific, a row of statues reveals the past of an ancient civilization shrouded in mystery. Some historians speculate that these figures were symbols of worship. Others believe they represent ancestors long deceased. Who they were and how the ancient craftsmen moved them to their positions without heavy machinery, are long-kept secrets that history books have failed to unlock.

intel inside

You can also count on toll-free telephone technical support 24 hours a day, 7 days a week; a limited one-year parts/labor warranty with overnight shipment of replacement parts at our expense; and on-site hardware service from NCR® (second and third year plans available), plus a 30 day money-back guarantee.

For a truly phenomenal computing experience, order today.

Elegance 486e/33 MHz $4699

*Lease as low as $160.71/mo.**

Call for a free Decision-Maker's Kit, complete pricing and custom configuration information.

800-345-8709

Major corporations, volume purchasers and government agencies call National Business Accounts: 800-545-6059

Charge it to your VISA, MasterCard, Discover, American Express or Northgate Big 'N' card.

NORTHGATE COMPUTER SYSTEMS, INC.

7075 Flying Cloud Drive, Eden Prairie, MN 55344

CODE B3504

We support the ethical use of software. To report software copyright violations, call the Software Publishers Association's Anti-Piracy Hotline at 1-800-388-PIRE. *Monthly lease payments are based on a 36 month standard fair market value open-ended lease. 12-60 month leasing options available for qualified businesses.

World Radio History



System Architect kicks into overdrive: Today's Price/Performance CASE Leader Now Offers Schema Generation.

Now you can build applications even faster with System Architect's new database Schema Generator. And System Architect is so easy to use, even beginners will be productive in no time.

NEW: Schema Generator.

Translate entity models, captured in our encyclopedia, into schema for DB2, Oracle, INGRES, SQL Server, RDB, Progress, Paradox, SQL Base, AS400 (SQL), XDB, Sybase, and Informix. Generate data definitions for C or COBOL programs. And create Windows user dialogue panels.

NEW: Screen Painter. (Call for availability.)

Develop screens for Windows, Presentation Manager, or character-based applications. The screens you create are then linked to our encyclopedia.



Paint GUI screens.

Multiple Methodology Support.

Work with such methodologies as DeMarco/Yourdon, Gane & Sarson, Ward & Mellor (real-time), Entity Relation diagrams, Decomposition diagrams, Object Oriented Design (optional), State Transition diagrams, Flow Charts and SSADM.

Integrated Data Dictionary/ Encyclopedia.

Customize your own data dictionary/ encyclopedia, and get multi-user support with and without a network.

Advanced Features.

Take advantage of normalization, rules & balancing, requirements traceability, a network version, import/export capabilities, custom reporting, an extendable data dictionary, auto leveling, CRUD Matrices, and automated documentation (enhanced 2167A -- call for availability).



Generate schema from entity diagrams.

A Proven CASE Product.

IEEE Software Magazine called System Architect "a useful, well-planned, affordable CASE tool." CASE Trends found System Architect "to be extremely easy to use. . . . with many features that are completely lacking in higher priced competitors." Toshiba said "System Architect stood out from many other prospects." And System Builder called System Architect "truly a price/performance leader."



View data models, DFDs, and structure charts simultaneously.

Works under Windows 3 or OS/2 Presentation Manager.

You get full functionality in each environment.

Affordable.

System Architect costs from one half to one fifth the price of comparable CASE products.

FOR THE REAL-WORLD CASE SOLUTION, CALL (212) 571-3434 TODAY.*

POPKIN
Software & Systems Inc.
11 Park Place, NY, NY 10007
Tel: (212) 571-3434
Fax: (212) 571-3436

MICROSOFT WINDOWS
Version 3.0 Compatible Product

SystemArchitect™

Supporting IBM's AD/Cycle

System Architect logo is a trademark of Popkin Software & Systems Incorporated. Other product names used herein are for identification purposes only and may be trademarks of their respective companies. Specifications subject to change without notice at the sole discretion of the company. Product delivery subject to availability.

*Worldwide sales: Italy 39-49-8700366; Germany 49-(0)6151-82077; Sweden 46-8-(0)626-8100; Benelux: 31-(0)3406-65530; England 44-(0)926-881186; Elsewhere 1(212)571-3434

Circle 108 on Inquiry Card.

World Radio History

NICHOLAS BARAN

WIRELESS NETWORKING

New technologies and standards portend the era of mobile computing

One of the most promising and widely discussed technologies of this decade is the wireless network. The idea of computers communicating through radio waves or infrared links is compelling and opens up a wide range of possible new applications for computers. Wireless networks can facilitate warehouse inventory-taking, cooperative learning in the classroom, and countless other tasks that can benefit from mobile networked computing. It's also a key enabling technology for pen- or notepad-based computing systems. But while there is much excitement and enthusiasm about wireless networks, the technology is still in its infancy (much like pen-based computing), and it must overcome a variety of technical and regulatory hurdles before it becomes a major component in today's computer systems. In this article, I'll take a look at the primary types of wireless technologies and their current status.

It is not realistic to expect wireless networks to replace unshielded twisted-pair and other hard-wired networks. Cable offers much higher data transmission speeds than are possible with wireless technology and will continue to do so for the foreseeable future. While most wireless networks offer maximum speeds of about 2 Mbps (many systems, as I will discuss later, are considerably slower than that), UTP systems operate at a minimum of 10 Mbps and are expected to reach speeds of 100 Mbps in the next two years. Fiber-optic (Fiber Distributed Data Interface, or FDDI) cable systems will achieve even faster transmission rates, while wireless networks will reach maximum speeds of only 10 Mbps. Clearly, wireless systems cannot compete with wired networks with regard to performance.

Wireless systems will, however, nicely complement wired networks. According to Ken Biba of Xircom (a network hardware vendor mainly known for its pocket LAN adapters), "wireless will solve your last 10 to 50 meters." In other words, a wired network can serve as a primary, or backbone, system, with a wireless network providing additional mobility.

The Long and Short of It

There are two broad categories of wireless networks: long-distance and short-distance. Long-distance networks are designed to transmit data within a metropolitan area or across a country and are characterized by relatively low data transmission rates, in the 4.8- to 19.2-Kbps range. Short-distance wireless networks are primarily in-building networks with speeds ranging from 230 Kbps to 2 Mbps.

The two primary types of long-distance networks are public and private packet-switched radio networks and cellular-circuit-switched telephone networks. Cellular telephone networks are an expensive means of transmitting data. Cellular modems are much more expensive

ILLUSTRATION: MARTY BRAUN © 1992

World Radio History



The components of the Photonics infrared transceiver. The transceiver directs the beam of light to a passive surface, such as the room's ceiling, where the light transmission can be picked up by another transceiver.

than conventional modems, since they require special circuitry to handle the loss of the signal when the circuit is handed off or switched from one base station to another. This signal loss is not a problem for voice communications because the switch delay, which usually lasts a few hundred milliseconds, is not noticeable to the speakers. But it can play havoc with data.

There are many other drawbacks of cellular data transmission: phone-usage charges can easily add up; cellular transmissions are easily intercepted, which makes data security an issue; interference and transmission errors are a major concern; cellular data transmissions must compete for cellular lines that are already jammed with cellular voice transmissions; and transmission speeds are slow. All these drawbacks make cellular data communication appropriate only for small file transfers or perhaps for short database queries to a host computer. Nevertheless, advances in data compression, data security, and error-checking algorithms will make cellular networks a viable option in some situations. Cellular modems will certainly play a role in wireless fax transmission.

The other major long-distance network option is the public packet-switched radio network. Packet-switched networks do not have the signal-loss problems that plague circuit-switched networks because the architecture is designed to support packets of data rather than voice communications. Note that private packet-switched networks, such as those used by public safety departments, government agencies, and electric utilities, use the same technology as the public variety but on restricted RF bands using an organization's own computer systems.

Public Radio Networks

The public radio network market has two major players: ARDIS, a joint venture of Motorola and IBM, and RAM Mobile Data, a company that uses the Mobitex mobile data network system developed by the Swedish company Ericsson AB. This system is widely used in Europe.

These public radio networks provide a series of radio channels in major metropolitan areas that are licensed by the FCC and are available for a fee to be used as long-distance networks. The user pays a monthly fee for air time and use of the mobile data equipment. The network company (e.g., ARDIS or RAM Mobile Data) provides the network infrastructure, which includes area network controllers and base stations, fault-tolerant computer systems, and so forth. Both these systems support the X.25 packet-switching standard as well as their own proprietary frame-relay packets. (For more on frame-relay packets, see the State of the Art section in the July 1991 BYTE.)

These public radio networks are fully documented according to the Open Systems Interconnection reference model (see "Remote Connections," July 1991 BYTE, for a complete description of the seven network layers that make up the OSI reference model). Both ARDIS and the Mobitex system specify the lower three network layers (i.e., physical, data link, and network) and provide flexibility in the application layers, allowing custom software and applications development. A small company called RF Data (Hinsdale, IL) has developed a data-compression routine for use on these public networks. Hardware developers also provide peripherals for use with public networks. For example, IBM has developed its PCradio for use with ARDIS and other Motorola-based public and private networks. The PCradio is a hand-held device with an 80C186 microprocessor running DOS, a built-in radio/fax/modem, an IC memory card slot, and 640 KB of RAM.

These public networks operate in the 800- to 900-MHz frequency range. ARDIS offers a data transmission speed of 4.8 Kbps, while Mobitex operates at 8 Kbps. Motorola recently introduced a new version of its public radio network technology that operates at 19.2 Kbps in the U.S. (and at 9.6 Kbps in Europe due to a narrower frequency band). The ARDIS system will eventually migrate to this new Motorola network technology.

Public radio networks such as ARDIS and Mobitex will play a significant role in the LAN market, particularly for large corporations with widespread field-service activities. For example, Otis Elevator uses the ARDIS system for its field-service organization. But, as with cellular technology, these networks are limited by their low data transfer rates and are not practical for large file transfers. They are appropriate only for two-way messaging, short-duration transactions, and small file transfers.

World Radio History

WIRELESS NETWORKING TECHNOLOGIES

A comparison of wireless network media. (Table courtesy of Photonics Corp.)

	Public networks	In-building microwave	Cellular modems	Spread-spectrum	Infrared
Speed	4.8–9.6 Kbps	10 Mbps	2.4–16.8 Kbps	0.23–2.0 Mbps	0.23–10 Mbps
Range	Wide area	Building	Wide area	20–100 meters	20–200 meters
Cost per node	$100/mo.*	Unknown	$100/mo.*	$300–$1400	$250–$300

* Monthly charges vary according to usage (these examples are at the low end).

Wireless LANs

Wireless LANs differ from conventional wired networks primarily in the physical and data-link layers of the OSI reference model. The physical layer simply describes the method by which the bits of data are transferred from one node to another. The data-link layer (also called the media access control, or MAC, layer) describes how those data bits are packaged and error-checked. The higher layers generally conform to existing network protocols or use bridges, routers, or gateways to connect to them.

The two methods of implementing the physical layer in a wireless LAN are radio frequency and infrared light transmission. Infrared systems are primarily limited to a single room, since the receiver and transmitter must be able to see each other. There are, however, infrared building-to-building networks in which the transceivers are placed in windows of adjacent buildings.

RF transmissions have one major disadvantage: government regulations over the use of radio frequencies. Currently, there are no RF bands in the U.S. for the exclusive use of wireless LANs other than narrow-frequency bands licensed by private companies (e.g., Motorola or RAM Mobile Data) for commercial applications. The same situation is true for the rest of the world, and, to make matters worse, there are no international standards for RF data transmissions. Therefore, different countries have different regulations and allocate the same frequency bands for different uses. However, efforts are under way to establish an international standard for RF transmissions.

Infrared does not have this problem and is, therefore, an attractive alternative to RF wireless LANs. The principle of infrared data communication has existed for many years. In the late 1970s, Hewlett-Packard introduced its HP-41 calculator, which used an infrared transmitter to operate a portable thermal printer. HP, as well as other manufacturers, uses infrared communications in calculators and other electronic devices. Of course, infrared is used in remote controllers for TVs, VCRs, and stereos. The same principle used in these devices also applies to the use of infrared communication on a wireless LAN: The infrared light is beamed from one transceiver to another, and the light transmission is encoded and decoded at the sending and receiving ends into a protocol compatible with existing network protocols.

The pioneer in the development of infrared networking is Richard Allen, who founded Photonics Corp. in 1985 and developed an infrared transceiver. The first version of this transceiver, developed for end users, directed the infrared beam of light to a passive surface in the room—usually the ceiling—where another transceiver could pick it up. Multiple network nodes can be installed in a single room by using a limited passive area for each transceiver.

To set up a room with infrared transceivers, you simply aim the transceivers at a common spot on the ceiling. A green light on the transceiver illuminates when the alignment is correct. See the figure for an illustration of the Photonics transceiver. To date, Photonics has only developed an AppleTalk/LocalTalk version of this transceiver, called Photolink, that operates at 230 Kbps. The system has a range of up to 200 meters.

Photonics has also developed a miniaturized version of the transceiver for use as an OEM product in laptops and notebooks. This version uses the principle of diffused infrared light, in which the beam of light is diffused throughout the entire room and picked up by other computers or terminals containing infrared transceivers. In addition, Photonics is working on an Ethernet version of its portable transceiver and claims the unit has transmission speeds of up to 1 Mbps.

Prices for the transceiver in OEM quantities start at $20. This makes it an affordable add-on for pen-based or other portable systems.

While Photonics is currently the main player in the infrared market, you can expect other companies to make some moves. BICC Communications (Auburn, MA) has developed a Token Ring–based infrared transceiver that requires you to install a central transmitter in the room. The IEEE 802.11 wireless networking group is currently working on a standard MAC layer for infrared networks.

RF Wireless LANs

In 1985, the FCC allowed unlicensed operation of devices using less than 1 watt of power in three frequency bands: 902 to 928 MHz, 2400 to 2483.5 MHz, and 5725 to 5850 MHz. These frequency bands, called ISM bands, had previously been limited to licensed industrial, scientific, and medical instruments. Network vendors therefore began developing devices for networking within those frequency bands.

Unlike licensed frequency bands, such as those used by ARDIS and Mobitex, ISM bands are open to everybody. To minimize interference, FCC regulations stipulate that a signal transmission technique called *spread-spectrum modulation*, which has a maximum transmitter power of 1 W, must be used within the ISM band. This technique has been used for military applications for many years. The basic idea of spread-spectrum modulation is to take a conventional narrow-band signal and distribute its energy over a much wider frequency domain. Thus, the average energy density is far lower in the spread-spectrum equivalent of the original narrow-band signal. In military applications, the objective is to reduce the energy density below the ambient noise level so that the signal is undetectable. The idea in commercial radio networks is to be able to receive and send signals with minimal interference.

There are two techniques used for distributing the conventional narrow-band signal into a spread-spectrum equivalent: direct sequencing and frequency hopping. In the direct-sequence method, the incoming bit stream is multiplied by a

World Radio History

higher-frequency signal based on a predetermined spreading function. The original data stream can then be recovered at the receiving end by correlating it with the known spreading function. This technique requires a computationally powerful device, such as a digital signal processor, to correlate the incoming signal. Currently, the fastest spread-spectrum device is the NCR WaveLAN spread-spectrum radio, which uses direct sequencing at a speed of 2 Mbps. Current technology allows a range of about 100 meters.

Frequency hopping is a technique in which the receiving and transmitting devices move synchronously in a predetermined pattern from one frequency to another, both hopping at the same time and in the same predetermined sequence. As in the direct-sequence method, the data must be reconstructed based on the frequency-hopping pattern.

While spread-spectrum modulation is a viable method for wireless networking, the current allocation of ISM bands is proving inadequate due to the competition with other devices in these bands. For example, the higher ISM bandwidths (2.4 and 5.8 gigahertz) have microwave ovens to contend with.

Many proponents of various wireless approaches like to point out that competing wireless approaches have big security problems. But, according to Xircom's Ken Biba, security is more of a red herring. Most, if not all, network vendors in the wireless field use some form of data encryption. In spread-spectrum applications, the spread-spectrum function itself is a form of data security. And, as Biba points out, hard-wired Ethernet cables make excellent antennas. In other words, security is probably not any more of a problem with wireless networks than it is with other methods of data communication.

The Data-PCS

The inadequacies of ISM bands have prompted Apple to petition the FCC to establish a dedicated frequency bandwidth for data transmissions, called the Data-PCS (for personal communications service). Apple has requested the FCC to allocate 40 MHz within the 1850- to 1990-MHz bandwidth strictly for data communications. According to the petition, "an allocation of 40 MHz is sufficient to permit several Data-PCS networks operating at rates of up to 10 Mbps, for example, to coexist in the same geographic area today, as well as to motivate technological innovations that can lead to higher data rates in the future."

Apple's petition states that the company performed extensive testing of the current ISM bands using spread-spectrum modulation and found that "there is a strong likelihood of unpredictable, essentially uncontrollable, interference in the ISM bands." Apple's extensive testing also indicated that the 1850- to 1990-MHz frequency band provides the optimum propagation characteristics for data communications.

According to the Apple proposal, the dedicated bandwidth would conform to "Part 15" rules, or, in other words, would continue to require spread-spectrum devices to have a transmitter power of under 1 W. The petition further requests that the FCC require data to be transmitted on the Data-PCS in "packetized form." This requirement is already met by all major network protocols. In addition, Apple's petition requests that manufacturers should have the right to maintain proprietary encryption schemes for data transmitted via the Data-PCS.

The petition also asks that the FCC release 10-MHz increments for the Data-PCS in two-year intervals starting this year. Thus, it will be a slow process before a full-fledged dedicated data radio LAN will be fully functional.

In-Building Microwave

In the meantime, alternatives to unlicensed spread-spectrum modulation are available from private companies such as Motorola, which recently introduced its first wireless in-building network that supports Ethernet LANs at 10 Mbps. Called Altair (not to be confused with the old Altair microcomputer), the system uses a centrally located control module that can support up to 32 Ethernet devices within an office area of approximately 5000 square feet. The Ethernet devices are connected to a user module located on the desktop and transmit data using conventional frequency modulation at 18 gigahertz to and from the control module. While the Altair system provides a wireless solution for the desktop office environment, it does not address the need for *mobile* wireless communications, which spread-spectrum radio and the Photonics portable infrared transceiver do provide.

In the European market, Olivetti has introduced a wireless LAN based on the Digital European Cordless Telecommunication standard. DECT uses a star topology in which each device in the star transmits to the server at a speed of 1 Mbps. The exact frequency range of the DECT LAN has not yet been specified, but it will be in the microwave frequency range using conventional FM, probably around 18 gigahertz. More specific details are expected early this year.

Wireless LANs and Mobile Computing

The table summarizes the different types of wireless networks discussed in this article. As I mentioned earlier, wireless networks will be a key component in mobile notebook and pen-based computer systems. In fact, without wireless networking, much of the utility of a pen-based system is lost. The idea of working in the field with an electronic notepad from which you can query a host database or transmit a fax to the home office is a crucial concept in the pen-based computing model.

Several issues must be considered in the development of wireless network environments. From a software perspective, wireless networks require a different approach than wired networks. In particular, network connectivity can be easily interrupted in a wireless network if, for example, the wireless user walks outside of the range of the radio or infrared signal. Therefore, network software for wireless systems must provide methods for seamlessly detaching and reconnecting to the network without crashing either the network or the remote node. Ideally, the network would be able to interrupt a data transmission and pick up where it left off when the network was reconnected.

Go Corp.'s PenPoint operating system has addressed this problem in its wired networks by incorporating a feature called "detachable networking." By unplugging the network cable, the PenPoint user automatically suspends network operations. Presumably, the same approach would work for wireless systems. Nevertheless, it's unknown how the network server would respond to these interruptions.

Regardless of the technical challenges that face wireless networking, all will be for naught unless the regulatory challenges are overcome. The FCC must allocate a dedicated frequency band for data communications. As Apple's proposal points out, the current shared usage of ISM bands is simply too unreliable for data communications. In addition, international standards must also be established, allowing U.S. and foreign vendors to be able to design internationally supported wireless network systems. Hopefully, the IEEE 802.11 committee and its foreign counterparts will be able to establish working standards in the near future. In any event, the next few years should deliver some exciting new developments in the field of wireless networking. ■

Nicholas Baran is a consulting editor for BYTE and coeditor of Pen-Based Computing *(Sandpoint, ID). He can be reached on BIX as "nickbaran."*

World Radio History

Choose Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist

Now! NRI training assures your success in three of today's fastest-growing PC career fields

Businesses everywhere promise solid employment prospects for people with the skills to create software for a Windows environment, troubleshoot and service PCs, or evaluate, recommend, and use vital PC software applications. Now, you can prepare for success in today's hottest PC careers with your choice of NRI's three innovative new courses – Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist.



1 Get in on today's hottest programming opportunities

Jobs for software developers are booming in the '90's, according to the Bureau of Labor Statistics. And PC experts agree: To create the new software applications required for today's complex computer environments, you need design expertise plus hands-on experience with C++ programming.

Now you can take advantage of today's hottest programming opportunities with NRI's new training — Programming in C++ with Windows. Only NRI shows you how to combine the power of object-oriented C++ with the new freedom and ease of Windows to create in-demand software for business, industry, or personal use.

Get hands-on training with a 386sx-based mini-tower computer system

With NRI, you get hands-on training with a 386sx-based mini-tower computer — yours to train with and keep! Only NRI gives you practical experience with this fully IBM PC/AT-compatible computer system, complete with VGA color monitor, enhanced keyboard and mouse, 40 meg IDE hard drive, and a full meg of RAM.

This state-of-the-art computer system gives you all the memory, speed, and power you need to develop the kind of quality software programs today's employers and consumers demand. But that's just part of your NRI training...

Master object-oriented programming using Turbo C++ for Windows®

NRI's Discovery Learning Method takes you step-by-step from computer basics to advanced programming in C++, today's hottest object-oriented programming language. As you work with Borland Turbo C++ for Windows, you discover for yourself how this in-demand language allows you the freedom to write real-world applications that rival software produced by top-paid design teams — from stand-alone graphics and word processing packages to spreadsheets, text editors, database managers, and more! But that's still not all...

Learn to program for the exciting visual environment of Windows®

With NRI training you take command of today's newest design techniques as you master programming skills for Windows — using both C++ and the built-in functions and routines of your Microsoft Windows software.

As you actually build your own software application, you develop hands-on experience with Windows' easy-to-use features — including graphics, memory management, multitasking, data exchange, and more!

Soon you're ready to use your computer and know-how to create fast, functional programs — complete with on-screen graphics, custom cursors, images, icons, and all the other Windows features you need to build high-performance software that meets today's competitive business needs.

Send for your FREE NRI catalog today!

See other side for two more ways NRI can give you the computer know-how you need for success. →

SEND TODAY FOR YOUR FREE CATALOG!

NRI Schools
McGraw-Hill Continuing Education Center
4401 Connecticut Avenue, NW, Washington, DC 20008

YES! Send me the FREE catalog I've checked and show me how NRI can give me the state-of-the-art computer training I need for advancement, extra income, even a business of my own.

- ☑ Check one FREE catalog only
- ❑ **Programming in C++ with Windows**
- ❑ **PC Troubleshooter**
- ❑ **PC Applications Specialist**

Other computer career training:
- ❑ Computer Programming
- ❑ Desktop Publishing and Design
- ❑ Bookkeeping and Accounting

Name _____ Age _____

Address _____

City _____ State _____ Zip _____

Accredited Member, National Home Study Council 4536-042

World Radio History

NRI training gives you two more exciting opportunities to make money with your computer



No matter which course you choose — PC Troubleshooter or PC Applications Specialist — your training includes a powerful IBM PC/AT-compatible computer system and valuable software you keep!

2 Earn good money as a PC Troubleshooter

There's no doubt about it: Businesses spend billions of dollars on personal computers each year — *even more* on PC service and support. That means big opportunity for computer pros who can troubleshoot today's PCs —people with the hands-on training it takes to diagnose system failures, replace damaged chips, retrieve lost data, or troubleshoot faulty disk drives and circuit boards.

Now with NRI, you can master the skills you need to make money as a PC troubleshooter and cash in on big opportunities in this top-paying career field.

AT-compatible computer, diagnostic hardware and software included

NRI's step-by-step lessons and unique hands-on Discovery Learning projects show you how to localize PC problems, identify faulty components, recommend system configurations, and replace the damaged parts that cause PC system failures — plus much more!

Best of all, you get hands-on experience with a powerful AT-compatible computer, 40 meg IDE hard drive, and professional diagnostic hardware and software — all included in your course. Using PC Tools, an invaluable diagnostic software package, you get a hands-on understanding of the special utilities that make correcting software and data problems easy and profitable — everything from hard disk backup to data recovery, disk and file management, even virus and memory loss protection. But that's not all...

Rounding out your training, you get professional troubleshooting experience using your Ultra-X R.A.C.E.R. plug-in diagnostic card and QuickTech menu-driven software to test the system RAM and uncover the problems that can occur with PC motherboards and peripheral adapters.

By the time you complete your course, you have the skills and the software you need to make money as a PC troubleshooter. Send for your FREE NRI catalog today!

3 Become today's in-demand PC Applications Specialist

Organizations everywhere are paying top dollar for computer pros who can use word processing, database management, spreadsheet, and data communications software. In fact, today's PC-driven business world has given rise to a *new* breed of computer professional: the PC applications specialist.

Now, you can become this sought-after expert — on the job or in a business of your own. Only NRI gives you a powerful computer system plus the hands-on experience you need to succeed.

Train with and keep an AT-compatible computer system and Microsoft®Works™

Even if you've never worked with computers before, with NRI you master the real-world skills you need to make good money as a PC applications specialist. Easy, step-by-step lessons and hands-on training with a powerful AT-compatible computer system, MS-DOS, and Microsoft Works software – all included in your course – give you the important computer skills behind today's most in-demand business applications.

With NRI, you train at home and at a comfortable pace, always supported by your experienced NRI instructor. Step by easy step you learn not one or two, but *four* essential PC applications. Using your computer and Microsoft Works software, you master word processing, database management, spreadsheets, and data communications with confidence and ease. You even learn to install and use your mouse for quick-click access to the menu commands that save you time and effort when working with today's business applications.

Get the skills, the computer, and the software you need to start a money-making new career as a PC applications specialist. Send for your FREE NRI catalog today!

FREE catalog tells more!

Get all the facts about NRI training in your choice of three high-growth computer fields: Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist. If the card is missing, write to NRI Schools, McGraw-Hill Continuing Education Center, 4401 Connecticut Avenue, NW, Washington, DC 20008.

SEND TODAY FOR YOUR FREE CATALOG!

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS MAIL PERMIT NO. 10008 WASHINGTON, D.C.

POSTAGE WILL BE PAID BY ADDRESSEE

NRI SCHOOLS
McGRAW-HILL CONTINUING EDUCATION CENTER
4401 CONNECTICUT AVENUE, NW
WASHINGTON, DC 20078-3543

World Radio History

BATCH-FILE TOOLKIT

I feature three DOS enhancers this month: Need, Get, and Ask. Each adds significant features to the batch-file programs you write. If, like me, you stopped writing DOS batch files long ago out of boredom and frustration, you may find that these utilities rekindle your interest in batch-file programming.

These batch-file enhancers extend the capabilities of DOS

A Friendly Environment

Need, which includes Avoid and Sniff, ensures a friendly hardware and software environment. You can use these three programs to see if Desqview is running; to determine if there's sufficient conventional, extended, or expanded memory; to determine if the CPU is a 386 or higher; or to check for a host of similar conditions. Need includes numerous hardware and software tests to determine if a machine meets all your requirements.

You tell Need what you want. It tests the computer's configuration and sets DOS's ERRORLEVEL variable to 0 if all is OK or to 1 if one or more of the conditions you specified could not be met. You can check the ERRORLEVEL inside the batch file and decide if your batch file should continue, abort, or alert the user.

Avoid is the opposite of Need; it helps you avoid certain hardware/software combinations. Finally, Sniff will return configuration information that you can read.

What DOS Leaves Out

Get supplements the DOS batch-file commands. It turns batch-file programming into macro-language programming. Like Need, Get queries the hardware and software configurations of a system. However, Get also prompts for input and sets system parameters. This utility can ask questions, get disk and file information, get hardware or software information, do screen output, and toggle system settings.

Get's command-line parameters let you get and put strings; set screen color and video mode; and get the DOS version, file size, free disk space, disk size, current directory, and volume label.

Typically, Get sets an environment variable that you can test after Get completes. For example, you might code the following

```
GET N "Answer yes or no: "
IF "%GET%"=="N" goto NO
IF "%GET%"=="Y" goto YES
```

to get a yes or no answer from the person running your batch program.

Just Ask

Use Ask to get multiple-choice answers to questions you submit to the user. Ask puts a string in the master environment containing the user's answer, and you can easily test the string to know what to do next in your batch-file program. You can even use Ask to build menus inside batch programs. You might use Ask to determine which program to launch, or to force a compiler or linker to use a certain set of options or libraries.

You can use Roedy Green's Need, Avoid, and Sniff for free, but you must pay the $15 registration fee to get the assembly language source code. Get is a $15 shareware program developed by Bob Stephan. Ask, written by Jay Vanderbilt, is free. ■

UNIX/Ben Smith

Noninteractive Unix

Computing implies automation. But since the advent of interactive programs, where users control the program as it runs, the ability of a program to run noninteractively (i.e., in batch mode) has sometimes been neglected by programmers. This trend has even infected the Unix software world, where traditionalists have usually ensured that their programs (e.g., `mailx`) can run both interactively and in batch mode.

To patch some of these holes that liberal-minded developers have created, Don Libes developed `expect`. This utility program performs programmed dialogue with those trendy, user-interactive programs that haven't been designed for use in a world of automation. This is a public domain program. Libes, who works for the National Institute of Standards and Technology, is the coauthor of *Life with UNIX: A Guide for Everyone* (Prentice-Hall, 1988).

MAC/Tom Thompson

Solving Virus Crimes

A computer virus is one of those subjects you'd rather not hear about—until one "roaches" your Mac's hard drive, taking the day's work with it. Worse, like their biological counterparts, new viral strains appear that bypass protective detection software that's only familiar with existing viruses.

Virus Detective 5.0 by Jeffrey Shulman is a $40 shareware desk accessory that scans hard drives and floppy disks for viruses. What's important about Virus Detective is its programmability: You can type in new code signatures so that Virus Detective will recognize new viruses. Virus Detective can read text files with new code signatures. Thus, an update is often only a matter of logging onto an on-line service and downloading the latest signature file. Virus Detective's programmability ends the arms race between the virus creator and victim once and for all—not a bad bargain.

Editor's note: *Software Corner highlights public domain, freeware, and shareware programs. The programs are available on BIX (in the sw.corner conference), from Demolink, and on disk. See "Program Listings" on page 5 for details. We solicit contributions and pay $50 for any program we use. Write to: Software Corner, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458.*

hands full learning the Windows application programming interface (API), as explicated in the Software Development Kit. I'll try to remedy this.

Standard mode and enhanced mode have quite different DOS extenders. Standard mode works in the protected-address segmented 16-bit mode of a 286 CPU; extended mode sets up 386 virtual machine environments underneath a paged 32-bit virtual machine manager (VMM). Standard mode is really pretty simple; enhanced mode is not simple at all.

Virtual Concepts

What is a virtual machine? Imagine you are a program. You think you have control of a computer, but you don't: The operating system has simulated a computer to fool you. You can't affect programs running in other VMs; you can't even tell they're there.

The enhanced-mode Windows implementation of a VM has a memory partition (i.e., an area to save processor registers) and a control block (i.e., data structures to implement virtualization of the other aspects of a PC, such as ports, I/O controllers, DMA controllers, video interfaces, and interrupt tables). In other words, a VM maintains a complete description of the state of an application and lets a program execute as though it were running on a 386 in real mode.

An ordinary real-mode program will be fooled by a VM. A somewhat more so-

compatible with DPMI. But the major DOS-extender vendors—Phar Lap Software, Rational Systems, and Ergo Computing—have updated their products to work with DPMI.

The system VM is automatically creat-

Things your mother never told you about Windows

World Radio History

write VxDs, you need to write 32-bit programs; 32-bit versions of Microsoft Macro Assembler and Link come with the DDK for that purpose. Windows comes with VxDs for the screen, keyboard, mouse, and serial ports, as well as virtualization support for lower-level hardware.

VM Details

When enhanced mode starts up, VMM and the virtual devices specified in SYSTEM.INI load. The VMM and all the VxDs initialize, the system VM is created and initialized, and, finally, the shell VxD executes Windows. The shell VxD calls V86MMGR services to set up VMs. To start a DOS VM, it uses `V86MMGR_Allocate_V86_Pages` to allocate memory pages for the VM's base memory and map them into the VM. Then it uses `V86MMGR_Set_EMS_XMS_Limits` to allocate memory pages for EMS and Extended Memory Specification and connect those pages to the code that handles EMS and XMS interrupts.

A value of 0 for the minimum and maximum size (normally set in a program information file) will disable access to EMS or XMS services; a value of -1 will set no limit. For instance, setting EMS memory for a FoxPro application to a minimum of 1024 and a maximum of -1 means that the database will see as much expanded memory as possible, at least 1 MB, or the application won't run.

What about having multiple DOS VMs?

continued

WHY SOFTWARE COMPANIES ARE CHOOSING HARDLOCK™



Developers Say. . .

"Since the Hardlock uses an algorithmic response chip, I am assured of the highest level of protection. Also, the optional programmable memory means I can keep custom configurations in Hardlock rather than in a file. I can protect my .EXE or .COM files directly and/or incorporate Glenco's high level language interface routines into my software. And, I feel confident I'll have Glenco's support if I use other programming languages."

Accountants Say. . .

"Hardlock provides our company with a healthier bottom line. Since our software can't be copied, our revenue has steadily increased. The unique programming board allows us to program the Hardlock in seconds. This ensures optimum delivery schedules from Glenco and a lower inventory cost for us. Hardlock's field programmable feature means a single Hardlock can protect more than one product."



HANDS ON/BEYOND DOS

In its V86-mode memory map, each VM has its own local set of interrupt vectors, its own display memory, and its own local application code and data. Each also has a map to global memory regions that hold MS-DOS and the loaded DOS device drivers, any network and TSR program code loaded before Windows starts, a portion of Windows/386, and the system ROM. All the above run at privilege ring 3 (the lowest level).

The protected-mode portion of a VM runs at privilege ring 1, 2, or 3. Every VM also has a control block and a client stack at privilege ring 0 (the highest level). The control block contains, among other things, data used by the system VxDs to maintain the state of, for example, the physical hardware across all VMs.

The enhanced-mode Windows VMM has a two-level scheduler that preemptively allocates time among the VMs. The primary level of the scheduler scans the execution priority of all VMs and lets the VM with the highest priority run. The secondary level is the time slicer, which dynamically alters the execution priorities of VMs based on the current time and their foreground and background time-slice priorities.

A VM lets a program execute as though it were running on a 386 in real mode.

When application code in a VM issues a software interrupt or causes a protection fault, the 386 protection mechanism causes a privilege-ring transition. Control transfers to the VMM, which, in turn, dispatches the interrupt to the appropriate VxD. If your program issues a DOS call (e.g., INT 21h), the software interrupt will cause a privilege-ring transition. Instead of directly executing the DOS function, the program flips into the VMM, which makes sure that the DOS function is allowed before it passes control to DOS.

There's much more to enhanced mode, but that's the gist of it. You can find out more from the DDK and by poking around with an enhanced-mode debugger (e.g., Soft-Ice for Windows).

Class Libraries, Redux

My collection of class libraries for Windows continues to grow, with something old—Glockenspiel's CommonView 3.0—and something new—the Microsoft Foundation Classes (MFC). CommonView, which is distributed in the U.S. by ImageSoft, supports Borland C++ as well as Glockenspiel's own C++ translator coupled with Microsoft C 6.0ax. It targets Windows, Presentation Manager, and OSF/Motif in a portable way. CommonView's classes cover the user (i.e., window and dialog-box management) and GDI (i.e., graphics) parts of Windows fairly well. Borland's ObjectWindows covers the user but not the GDI. CommonView comes with container classes and a memory management dynamic link library.

MFC, which ships with Microsoft C/C++ 7.0 for Windows, covers most of the Windows API, including hard parts like Multiple Document Interface and Object Linking and Embedding. MFC has container classes that can also be used in DOS applications, but its main purpose is to encapsulate the Windows C interface. You want portability? It's portable only as far as the Windows API is portable, but the Windows API could go places you'd never have expected. Stay tuned.

MFC is a thin layer. There's relatively little overhead and relatively little abstraction. The MFC sample applications seem as quick as their C counterparts. At the same time, many of the MFC classes were designed specifically to be extended by inheritance, which makes MFC a better building block than less-extensible application frameworks.

Anything with a handle in Windows becomes an object in MFC—an object with almost the same name as its API counterpart. What's the main thing with a handle in the GDI? A device context. How do you draw in a window in MFC? You construct an item of class CDC and then use its member functions: `CDC::MoveTo`, `CDC::LineTo`, `CDC::TextOut`, and so on. Do you have to use the classes? No; it's OK to mix in your old C code. I think I'm going to like MFC.

Nasty and Nice Surprises

I mentioned in a previous column that I was producing the final pages of my book with Word for Windows 2.0. I was able to produce perfectly acceptable individual pages with WinWord, but I couldn't get facing pages to align at the top and bottom to save my life.

Fine, I thought. I'll just flow the book into PageMaker. After all, I'd tested for this possible exigency with Word 1.1. Microsoft wouldn't dare break such an essential function in a new version.

Wrong. PageMaker 4.0 can't import WinWord 2.0 format, nor can it import WinWord 2.0 Rich Text Format output. I tried sending RTF to the Mac. I was able to get Mac PageMaker to read the files only by first opening and saving them from MacWord. My text came across, but none of my illustrations survived the process.

As it happened, there was a copy of Image-In-Color in my pile of things to examine. It produces TIFF files acceptable to Mac PageMaker. I copied all the bit maps out of my WinWord files, saved them as BMP files (using the Image2 application from my book), and then converted each BMP file to TIFF with Image-In-Color.

Happy ending: The book got to the printer complete with all its illustrations, albeit a few weeks later than I had hoped. My apologies to anyone who scoured bookstores looking for a copy of it in early January. ■

Martin Heller develops software and writes about computers, despite a Ph.D. in physics and despite having worked, literally, as a rocket scientist. He is the author of Advanced Windows Programming *(Wiley, 1992).*

Your questions and comments are welcome. Write to: Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458.

ITEMS DISCUSSED

Glockenspiel's CommonView 3.0.....$499
ImageSoft, Inc.
(516) 767-2233
Circle 1146 on Inquiry Card.

Image-In-Color.....$495
Image-In, Inc.
(612) 888-3633
Circle 1147 on Inquiry Card.

Microsoft C/C++ 7.0 for Windows.....$495
Windows 3.0 Software Development Kit.....$500
Microsoft Corp.
(206) 882-8080
Circle 1148 on Inquiry Card.

Soft-Ice for Windows.....$386
Nu-Mega Technologies, Inc.
(603) 888-2386
Circle 1149 on Inquiry Card.

World Radio History

ASK BYTE

Video Downsizing

I want to obtain a high-performance PC on a moderate budget. These systems often include 1024- by 768-pixel monitors that are compatible with standard VGA but not with older video graphics standards (e.g., MDA, CGA, and EGA). I am interested in a video adapter capable of displaying these older video modes.

Do video controllers supplied with high-resolution monitors typically support the older standards? If so, could I simply unhook the high-resolution monitor, configure the video software drivers to older modes, and plug in another monitor?

Thomas A. Williams
Waterford, MI

ATI Technologies (3761 Victoria Park Ave., Scarborough, Ontario, Canada M1W 3S2, (416) 756-0718; fax (416) 756-0720) has just the video adapter for you. While many high-resolution video boards let you run EGA- or CGA-mode programs on your VGA monitor, they do not give you dual connectors so that you can attach an EGA or a CGA monitor. The ATI VGAWonder XL gives you 15-pin (analog) and nine-pin (digital) video connections and a mouse port as well. The board supports resolutions of up to 1024 by 768 pixels, as well as VGA, MDA, EGA, and CGA modes. ATI's suggested list price is $399 with 1 MB of video RAM, but you can find it for considerably less.

Many clone vendors will build a system to your specifications and will be happy to substitute the VGAWonder XL for their standard video board.—Stanford Diehl

Windows Environment Revisited

In the October 1991 Ask BYTE, Paul M. Smith brought up a common problem in the DOS community: Running a batch file that sets an environment variable in a DOS window produces an "Out of environment space" error message. The cause of this problem and the fix, however, have little to do with the `windir` variable produced by Windows 3.0.

When started, Windows inherits an environment equal to the parent's current environment. This includes the variable set and the size currently used. Setting an environment size in CONFIG.SYS (e.g., `SHELL=C:\COMMAND.COM /P /E:256`) is the first step. This gives the initial environment a size of 256 bytes. The environment can grow to 256 bytes, but once you start a program, its inherited environment size is limited to what is currently used. The only fix is to add the `/E:256` switch to the COMMAND.COM in Windows.

If you open a DOS window or start a batch file without a program information file (PIF), change the command line under program item properties to `C:\COMMAND.COM /E:256 [/C batchfile.bat]`.

If you use a PIF, set the program filename to `COMMAND.COM` and change the optional parameters to `/E:256 [/C batchfile.bat]`.

Both options start up COMMAND.COM with an initial environment size of 256 bytes. You can change the environment size to any value between 160 and 32,768.

This problem is inherent in nearly all programs that have a shell to DOS or DOS window function (Desqview somehow avoids it). The fix is the same in all cases (provided that the program lets you change the shell/window command). It would be nice if developers would check for the initial environment size setting and use it in their shell/window function.

Here's one little memory-squeezing tip: When loading TSR programs in your AUTOEXEC.BAT file, do so before setting an environment variable (e.g., PATH or APPEND). Because a TSR also inherits the current environment, keeping it as small as possible saves a few precious bytes of memory. The exceptions are those "intelligent" TSRs that release the unneeded environment back to the memory pool.

Kevin J. Burkholder
Spring City, PA

The Working Font

I use Adobe Type Manager and a Qume ScripTen PostScript printer. I have 13 fonts to use with ATM. I wanted to add more fonts using the WFN Boss utility included with CorelDraw 2.0. The utility converts fonts from Corel format to Adobe Type 1 format.

I converted many fonts with WFN Boss. When I used ATM to add these new typefaces, it did so perfectly. But when I tried to print a PageMaker file, all the fonts I had converted printed in Courier. How can I use the fonts converted by WFN Boss to work with other Windows applications?

Jean Lauzier
Val-Brillant, Quebec, Canada

Corel has made improvements to the WFN Boss utility in CorelDraw 2.01. Register your software if you haven't done so and ask for the upgrade.

It also sounds like you have not made some necessary modifications to your WIN.INI file. ATM assumes that typefaces are resident in your PostScript printer. Thus, it does not automatically download them for you. You must do it manually from the WIN.INI file. Load the WIN.INI file into your word processor and find the section where Windows lists the information on your PostScript fonts. The section will begin with the header `[PostScript,LPT1]` *or something similar. You will want to edit the lines beginning with* `softfontX=` *to include the typefaces you have created. The lines will show a path to only the .PFM files. Go to the end of the line, insert a comma, and add a path to the .PFB files. The final result will look something like the following:*

```
softfont9=c:\psfonts\pfm\newfont.pfm,
c:\psfonts\newfont.pfb
```

Also, try using ATM's PSDOWN utility to automatically download the font to your printer. PSDOWN flushes

World Radio History

the font from your printer's memory after each print job. If you don't use it, you'll have to reset your printer after each job to free up memory.—Stanford Diehl

High-Resolution BASICs

I recently purchased a 25-MHz 386 computer with a Super VGA card (1024 by 768 pixels) and DOS 5.0. I wanted the higher resolution to program some graphics and animation. I want to work in BASIC and access this high resolution. So far, I have been unable to find out how to do this.

I am able to program in 640- by 480-pixel resolution. I can set the high-resolution mode in DOS (with the display card's DMODE utility), but BASIC sets it back to the lower resolution. Is it possible to have BASIC access the higher-resolution modes?

R. A. Fischer
Sun Lakes, AZ

It's a funny thing about standards—just when you get used to one, someone changes it. Versions of BASIC (and libraries for most other languages) usually support only the modes defined by IBM. That means 16 colors in 640- by 480-pixel mode or 256 colors in 320- by 200-pixel mode. There is a relatively small number of de facto Super VGA standards. The Tseng Laboratories 3000 and 4000 chip sets are popular among manufacturers, as are the sets used by Paradise, ATI Technologies, and Video Seven. To access the higher-resolution modes, you need a replacement graphics library that supports your video card.

You might contact Genus Microprogramming (2900 Wilcrest, Suite 145, Houston, TX 77042, (800) 227-0918 or (713) 870-0737; fax (713) 870-0288) and ask about its GX Effects library ($199). It links into Microsoft QuickBasic 4.x or BASIC PDS 7.x and gives you sprite animation, sound, music playback, Sound Blaster file playback, and many other features. You might also want Genus's $249 PCX Programmer's Toolkit if you're working with .PCX files.

The current versions of both Genus products support the Trident, Paradise, ATI, and Video Seven cards in 800- by 600-pixel display modes, and cards based on the Tseng Labs 4000 in 1024- by 768-pixel mode. New versions (possibly available by the time you read this) will support all these cards and the Video Electronics Standards Association specification in 1024- by 768-pixel mode.—Howard Eglowstein

Resolving Conflict

If Cliff Millward's ScanJet/video board conflict is like mine (Ask BYTE, December 1991), he can cure the problem by changing video boards. When I added a ScanJet Plus a few years ago, my Paradise VGA Plus 16 from Western Digital Imaging would no longer work in 16-bit mode. According to Hewlett-Packard and WDI, the video and scanner interface boards compete for the same memory area. I replaced the Paradise board with an Orchid Technology ProDesigner Plus, which runs in 16-bit mode and politely avoids trampling scanner memory.

I have just replaced the ProDesigner Plus with an Orchid Fahrenheit 1280, and it runs correctly in 16-bit mode with the ScanJet Plus active. I suspect that Orchid's popularity with the graphics crowd, who are likely to use a scanner, caused the firm to design its boards this way. (Contact Orchid Technology, Inc., 45365 Northport Loop W, Fremont, CA 94538, (800) 767-2443 or (510) 683-0300; fax (510) 490-9312.)

David Ellis
Torrance, CA

CNS on the Move

In the August 1991 Beyond DOS, Martin Heller discussed CNS's C++/Views software. I have been unable to locate the company.

Stacey Wohleber
Huntsville, AL

CNS has moved. Its new address is 1250 Park Rd., Chanhassen, MN 55317, (800) 843-2978 or (612) 474-7600; fax (612) 474-6737.—Raymond GA Côté

CPU Upgrade Issues

I have an IBM PS/2 Model 50 Z. I want to upgrade my system to a 386 processor, but I have found some problems in doing so. In Chile, we do not have as much information about products coming to market.

IBM of Chile has an Aox card to upgrade my system, but it is very expensive. The 25-MHz MicroMaster 386 sells for $2000. I know there must be other cards. Can you provide me with the names of manufacturers? I would also appreciate references to any articles published on this topic.

Julio Rodiño Durán
Santiago, Chile

Installing upgrade boards into 286 systems is complicated and expensive. Do so only if you are an experienced user. BYTE has not evaluated any 386DX upgrade boards, but we have covered 386SX upgrade boards (see "SX Upgrade Boards: Not for the Fainthearted," April 1991 BYTE). We also covered two SX upgrade boards in the October 1991 Reviewer's Notebook. One of them was the SX/Now, a product for the Model 50 Z from Kingston Technology Corp. (17600 Newhope St., Fountain Valley, CA 92708, (714) 435-2600; fax (714) 435-2699). The 25-MHz SX/Now upgrade sells for $625.

As you mentioned, Aox (486 Totten Pond Rd., Waltham, MA 02154, (617) 890-4402; fax (617) 890-8445) offers the 25-MHz upgrade for your system. It has a list price of $1549. You should also consider 20-MHz versions from both of these companies. You'll give up some performance but save money.—Stanford Diehl ■

The BYTE Lab welcomes your questions. Address correspondence to Ask BYTE, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458. You can also send BIX mail c/o "editors."

We read every letter, but due to the volume of mail received, we cannot guarantee a response. We edit all letters for clarity and brevity. Letters appear in BYTE about four months after we receive them.

World Radio History

Being online never felt so fine.

Join the online network with personality. The most interesting conferences. 10,000 programs you can download for your own use. All the most popular services.

Two membership plans: $6 an hour or $1 an hour with the 20/20 Advantage.

Join us online, the water's fine.

Circle 61 on Inquiry Card.

Free Membership

Dial by modem,

1-800-365-4636

Press return. At password, type RB22

DELPHI

Voice, 1-800-695-4005
617-491-3393

World Radio History

WHEN YOU NEED SOLUTIONS, NOT JUST ANOTHER BOARD!

Let a Quatech Sales Engineer show you the value of quality, service and support.

COMMUNICATION

Quatech produces a full line of serial and parallel adapters for PS/2, PC-XT, AT and compatible systems available in RS-232, RS-422, RS-485 and Current Loop. Selectable addresses and interrupt capabilities are featured in our multi-port/user, SDLC, HDLC, and X.25 adapters. Software and 16550 UARTS are available.

DATA ACQUISITION

Quatech has developed a full line of data acquisition products for the IBM AT and compatibles. These high performance, low cost boards provide analog-to-digital, digital-to-analog, and digital input/output functions. A/D and D/A converters are equipped with 8, 12, or 16 bit resolution, and sampling rates up to 1 MHz.

1-800-553-1170

QUATECH

Made in U.S.A.

Corporate office: (216) 434-3154, FAX (216) 434-1409, 662 Wolf Ledges Pkwy, Akron, OH 44311 U.S.A. International: Australia/Interworld Electronics 03-563-7066, Canada (Western)/Interworld VCR 604-984-4171, England/Diamond Point International 634-722-390, Finland/Lab Hitech OY 358-0-804-2522, France/Elexo 33-1-69302880, Germany/Jupiter Electronic Systems 06181/75041, Israel/RCM Ltd. 972-03-5447885, Italy/N.C.S. Computer Italia 0331/ 770-016, Netherlands/ACAL Auriema 040-816565 Korea/Sam Boo Enterprise Co. 02-678-7457. IBM PC-XT, AT and PS/2 are registered trademarks of IBM Corp.

Circle 205 on Inquiry Card.

World Radio History

BYTE BUYER'S GUIDE

Your direct source for buying software, hardware and accessories from knowledgeable and service-oriented dealers.



	Page
Mail Order The latest offerings from vendors supplying products of all leading manufacturers at extremely competitive prices.	304
Hardware/Software Showcase This new, *categorized* four-color display section makes it easy to find Hardware and Software products from a wide variety of manufacturers and suppliers.	340
Buyer's Mart From Accessories to Laptops to Word Processors, you can easily find the dealers you are looking for in this directory of products and services.	350

World Radio History

Get A Lode Of This.

Our Three-Way Guarantee Just Got Better.

The LodeStar Three-Way Personal Guarantee has always been one of the industry's most comprehensive. But now it just got better. Introducing The LodeStar Five-Way Personal Guarantee. Now, every LodeStar system is covered five ways to insure your complete satisfaction. And that should take a lode off you mind.

1. MONEY BACK GUARANTEE.
If you change your mind-for any reason-simply return your LodeStar system to us in original condition within 30 days of your receipt andwe'll refund your money.

2. FREE LIFETIME TECHNICAL SUPPORT.
For as long as you own your system, we'll give you FAST, FREE unlimited technical advice and guidance from our expert staff. This includes any support needed to upgrade or modify your system.

3. FREE LIFETIME LABOR SUPPORT.
Although you will probably never need it, for as long as you own your system, it will be protected by our 100% labor warranty.

4. FREE 2-YEAR PARTS WARRANTY.
For a full two years after purchase, your LodeStar computer will be covered by our 100% parts warranty, with fast turn around on any replacements.

5. FREE 1-YEAR ON-SITE SERVICE.
For a full one year after purchase, you'll have the added security of our coast-to-coast FREE on-site service.

Moduless Upgradeables

Carry A Greater Lode In The Future

Easy and inexpensive upgrades are built right into your LodeStar Starflex computer. Unlike conventional modular upgradeable systems from other Companies, you can upgrade your LodeStar Starflex system at a fraction of the cost-all the way from 386DX to 486SX or 486DX, at any clock speed.
Thanks to our unique non-proprietary Moduless Upgrade design, LodeStar Starflex systems can be upgraded by simply plugging in the new chip and oscillator that comes in their inexpensive upgrade kit. Another bright idea from LodeStar-It's just that simple !

Every LodeStar computer is fully loaded with value. This includes unsurpassed quality throughout. To make certain of this, every system is individually pretested and burned-in for 72 hours prior to shipment. And of course, we stand behind our quality with our comprehensive Five-Way Personal Guarantee. You will see this quality all the way from our StarView SVGA Non-Interlaced Monitors with flicker-free image, to our own StarKey extended keyboards. And we pack in even extra value by pre-loading MS DOS 5.0 & Windows 3.0, as well as a Hi-Res 400 DPI serial mouse on every system. And our systems can be upgraded to include optional cache, RAM, more hard disk capacity, larger monitor, and a host of other enhancements you may require. Add it all together - stellar performance, brilliant quality, and guarantee that outshines all others - and you've got LodeStar.

World Radio History

WIRELESS NETWORKING TECHNOLOGIES

A comparison of wireless network media. (Table courtesy of Photonics Corp.)

	Public networks	In-building microwave	Cellular modems	Spread-spectrum	Infrared
Speed	4.8–9.6 Kbps	10 Mbps	2.4–16.8 Kbps	0.23–2.0 Mbps	0.23–10 Mbps
Range	Wide area	Building	Wide area	20–100 meters	20–200 meters
Cost per node	$100/mo.*	Unknown	$100/mo.*	$300–$1400	$250–$300

* Monthly charges vary according to usage (these examples are at the low end).

Wireless LANs

Wireless LANs differ from conventional wired networks primarily in the physical and data-link layers of the OSI reference model. The physical layer simply describes the method by which the bits of data are transferred from one node to another. The data-link layer (also called the media access control, or MAC, layer) describes how those data bits are packaged and error-checked. The higher layers generally conform to existing network protocols or use bridges, routers, or gateways to connect to them.

The two methods of implementing the physical layer in a wireless LAN are radio frequency and infrared light transmission. Infrared systems are primarily limited to a single room, since the receiver and transmitter must be able to see each other. There are, however, infrared building-to-building networks in which the transceivers are placed in windows of adjacent buildings.

RF transmissions have one major disadvantage: government regulations over the use of radio frequencies. Currently, there are no RF bands in the U.S. for the exclusive use of wireless LANs other than narrow-frequency bands licensed by private companies (e.g., Motorola or RAM Mobile Data) for commercial applications. The same situation is true for the rest of the world, and, to make matters worse, there are no international standards for RF data transmissions. Therefore, different countries have different regulations and allocate the same frequency bands for different uses. However, efforts are under way to establish an international standard for RF transmissions.

Infrared does not have this problem and is, therefore, an attractive alternative to RF wireless LANs. The principle of infrared data communication has existed for many years. In the late 1970s, Hewlett-Packard introduced its HP-41 calculator, which used an infrared transmitter to operate a portable thermal printer. HP, as well as other manufacturers, uses infrared communications in calculators and other electronic devices. Of course, infrared is used in remote controllers for TVs, VCRs, and stereos. The same principle used in these devices also applies to the use of infrared communication on a wireless LAN: The infrared light is beamed from one transceiver to another, and the light transmission is encoded and decoded at the sending and receiving ends into a protocol compatible with existing network protocols.

The pioneer in the development of infrared networking is Richard Allen, who founded Photonics Corp. in 1985 and developed an infrared transceiver. The first version of this transceiver, developed for end users, directed the infrared beam of light to a passive surface in the room—usually the ceiling—where another transceiver could pick it up. Multiple network nodes can be installed in a single room by using a limited passive area for each transceiver.

To set up a room with infrared transceivers, you simply aim the transceivers at a common spot on the ceiling. A green light on the transceiver illuminates when the alignment is correct. See the figure for an illustration of the Photonics transceiver. To date, Photonics has only developed an AppleTalk/LocalTalk version of this transceiver, called Photolink, that operates at 230 Kbps. The system has a range of up to 200 meters.

Photonics has also developed a miniaturized version of the transceiver for use as an OEM product in laptops and notebooks. This version uses the principle of diffused infrared light, in which the beam of light is diffused throughout the entire room and picked up by other computers or terminals containing infrared transceivers. In addition, Photonics is working on an Ethernet version of its portable transceiver and claims the unit has transmission speeds of up to 1 Mbps.

Prices for the transceiver in OEM quantities start at $20. This makes it an affordable add-on for pen-based or other portable systems.

While Photonics is currently the main player in the infrared market, you can expect other companies to make some moves. BICC Communications (Auburn, MA) has developed a Token Ring–based infrared transceiver that requires you to install a central transmitter in the room. The IEEE 802.11 wireless networking group is currently working on a standard MAC layer for infrared networks.

RF Wireless LANs

In 1985, the FCC allowed unlicensed operation of devices using less than 1 watt of power in three frequency bands: 902 to 928 MHz, 2400 to 2483.5 MHz, and 5725 to 5850 MHz. These frequency bands, called ISM bands, had previously been limited to licensed industrial, scientific, and medical instruments. Network vendors therefore began developing devices for networking within those frequency bands.

Unlike licensed frequency bands, such as those used by ARDIS and Mobitex, ISM bands are open to everybody. To minimize interference, FCC regulations stipulate that a signal transmission technique called *spread-spectrum modulation*, which has a maximum transmitter power of 1 W, must be used within the ISM band. This technique has been used for military applications for many years. The basic idea of spread-spectrum modulation is to take a conventional narrow-band signal and distribute its energy over a much wider frequency domain. Thus, the average energy density is far lower in the spread-spectrum equivalent of the original narrow-band signal. In military applications, the objective is to reduce the energy density below the ambient noise level so that the signal is undetectable. The idea in commercial radio networks is to be able to receive and send signals with minimal interference.

There are two techniques used for distributing the conventional narrow-band signal into a spread-spectrum equivalent: direct sequencing and frequency hopping. In the direct-sequence method, the incoming bit stream is multiplied by a

World Radio History

higher-frequency signal based on a predetermined spreading function. The original data stream can then be recovered at the receiving end by correlating it with the known spreading function. This technique requires a computationally powerful device, such as a digital signal processor, to correlate the incoming signal. Currently, the fastest spread-spectrum device is the NCR WaveLAN spread-spectrum radio, which uses direct sequencing at a speed of 2 Mbps. Current technology allows a range of about 100 meters.

Frequency hopping is a technique in which the receiving and transmitting devices move synchronously in a predetermined pattern from one frequency to another, both hopping at the same time and in the same predetermined sequence. As in the direct-sequence method, the data must be reconstructed based on the frequency-hopping pattern.

While spread-spectrum modulation is a viable method for wireless networking, the current allocation of ISM bands is proving inadequate due to the competition with other devices in these bands. For example, the higher ISM bandwidths (2.4 and 5.8 gigahertz) have microwave ovens to contend with.

Many proponents of various wireless approaches like to point out that competing wireless approaches have big security problems. But, according to Xircom's Ken Biba, security is more of a red herring. Most, if not all, network vendors in the wireless field use some form of data encryption. In spread-spectrum applications, the spread-spectrum function itself is a form of data security. And, as Biba points out, hard-wired Ethernet cables make excellent antennas. In other words, security is probably not any more of a problem with wireless networks than it is with other methods of data communication.

The Data-PCS

The inadequacies of ISM bands have prompted Apple to petition the FCC to establish a dedicated frequency bandwidth for data transmissions, called the Data-PCS (for personal communications service). Apple has requested the FCC to allocate 40 MHz within the 1850- to 1990-MHz bandwidth strictly for data communications. According to the petition, "an allocation of 40 MHz is sufficient to permit several Data-PCS networks operating at rates of up to 10 Mbps, for example, to coexist in the same geographic area today, as well as to motivate technological innovations that can lead to higher data rates in the future."

Apple's petition states that the company performed extensive testing of the current ISM bands using spread-spectrum modulation and found that "there is a strong likelihood of unpredictable, essentially uncontrollable, interference in the ISM bands." Apple's extensive testing also indicated that the 1850- to 1990-MHz frequency band provides the optimum propagation characteristics for data communications.

According to the Apple proposal, the dedicated bandwidth would conform to "Part 15" rules, or, in other words, would continue to require spread-spectrum devices to have a transmitter power of under 1 W. The petition further requests that the FCC require data to be transmitted on the Data-PCS in "packetized form." This requirement is already met by all major network protocols. In addition, Apple's petition requests that manufacturers should have the right to maintain proprietary encryption schemes for data transmitted via the Data-PCS.

The petition also asks that the FCC release 10-MHz increments for the Data-PCS in two-year intervals starting this year. Thus, it will be a slow process before a full-fledged dedicated data radio LAN will be fully functional.

In-Building Microwave

In the meantime, alternatives to unlicensed spread-spectrum modulation are available from private companies such as Motorola, which recently introduced its first wireless in-building network that supports Ethernet LANs at 10 Mbps. Called Altair (not to be confused with the old Altair microcomputer), the system uses a centrally located control module that can support up to 32 Ethernet devices within an office area of approximately 5000 square feet. The Ethernet devices are connected to a user module located on the desktop and transmit data using conventional frequency modulation at 18 gigahertz to and from the control module. While the Altair system provides a wireless solution for the desktop office environment, it does not address the need for *mobile* wireless communications, which spread-spectrum radio and the Photonics portable infrared transceiver do provide.

In the European market, Olivetti has introduced a wireless LAN based on the Digital European Cordless Telecommunication standard. DECT uses a star topology in which each device in the star transmits to the server at a speed of 1 Mbps. The exact frequency range of the DECT LAN has not yet been specified, but it will be in the microwave frequency range using conventional FM, probably around 18 gigahertz. More specific details are expected early this year.

Wireless LANs and Mobile Computing

The table summarizes the different types of wireless networks discussed in this article. As I mentioned earlier, wireless networks will be a key component in mobile notebook and pen-based computer systems. In fact, without wireless networking, much of the utility of a pen-based system is lost. The idea of working in the field with an electronic notepad from which you can query a host database or transmit a fax to the home office is a crucial concept in the pen-based computing model.

Several issues must be considered in the development of wireless network environments. From a software perspective, wireless networks require a different approach than wired networks. In particular, network connectivity can be easily interrupted in a wireless network if, for example, the wireless user walks outside of the range of the radio or infrared signal. Therefore, network software for wireless systems must provide methods for seamlessly detaching and reconnecting to the network without crashing either the network or the remote node. Ideally, the network would be able to interrupt a data transmission and pick up where it left off when the network was reconnected.

Go Corp.'s PenPoint operating system has addressed this problem in its wired networks by incorporating a feature called "detachable networking." By unplugging the network cable, the PenPoint user automatically suspends network operations. Presumably, the same approach would work for wireless systems. Nevertheless, it's unknown how the network server would respond to these interruptions.

Regardless of the technical challenges that face wireless networking, all will be for naught unless the regulatory challenges are overcome. The FCC must allocate a dedicated frequency band for data communications. As Apple's proposal points out, the current shared usage of ISM bands is simply too unreliable for data communications. In addition, international standards must also be established, allowing U.S. and foreign vendors to be able to design internationally supported wireless network systems. Hopefully, the IEEE 802.11 committee and its foreign counterparts will be able to establish working standards in the near future. In any event, the next few years should deliver some exciting new developments in the field of wireless networking. ■

Nicholas Baran is a consulting editor for BYTE and coeditor of Pen-Based Computing *(Sandpoint, ID). He can be reached on BIX as "nickbaran."*

World Radio History

Choose Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist

Now! NRI training assures your success in three of today's fastest-growing PC career fields

Businesses everywhere promise solid employment prospects for people with the skills to create software for a Windows environment, troubleshoot and service PCs, or evaluate, recommend, and use vital PC software applications. Now, you can prepare for success in today's hottest PC careers with your choice of NRI's three innovative new courses – Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist.

1 Get in on today's hottest programming opportunities

Jobs for software developers are booming in the '90's, according to the Bureau of Labor Statistics. And PC experts agree: To create the new software applications required for today's complex computer environments, you need design expertise plus hands-on experience with C++ programming.

Now you can take advantage of today's hottest programming opportunities with NRI's new training — Programming in C++ with Windows. Only NRI shows you how to combine the power of object-oriented C++ with the new freedom and ease of Windows to create in-demand software for business, industry, or personal use.

Get hands-on training with a 386sx-based mini-tower computer system

With NRI, you get hands-on training with a 386sx-based mini-tower computer — yours to train with and keep! Only NRI gives you practical experience with this fully IBM PC/AT-compatible computer system, complete with VGA color monitor, enhanced keyboard and mouse, 40 meg IDE hard drive, and a full meg of RAM.

This state-of-the-art computer system gives you all the memory, speed, and power you need to develop the kind of quality software programs today's employers and consumers demand. But that's just part of your NRI training...

Master object-oriented programming using Turbo C++ for Windows®

NRI's Discovery Learning Method takes you step-by-step from computer basics to advanced programming in C++, today's hottest object-oriented programming language. As you work with Borland Turbo C++ for Windows, you discover for yourself how this in-demand language allows you the freedom to write real-world applications that rival software produced by top-paid design teams — from stand-alone graphics and word processing packages to spreadsheets, text editors, database managers, and more! But that's still not all...

Learn to program for the exciting visual environment of Windows®

With NRI training you take command of today's newest design techniques as you master programming skills for Windows — using both C++ and the built-in functions and routines of your Microsoft Windows software.

As you actually build your own software application, you develop hands-on experience with Windows' easy-to-use features — including graphics, memory management, multitasking, data exchange, and more!

Soon you're ready to use your computer and know-how to create fast, functional programs — complete with on-screen graphics, custom cursors, images, icons, and all the other Windows features you need to build high-performance software that meets today's competitive business needs.

Send for your FREE NRI catalog today!

See other side for two more ways NRI can give you the computer know-how you need for success. →

SEND TODAY FOR YOUR FREE CATALOG!

NRI Schools
McGraw-Hill Continuing Education Center
4401 Connecticut Avenue, NW, Washington, DC 20008

YES! Send me the FREE catalog I've checked and show me how NRI can give me the state-of-the-art computer training I need for advancement, extra income, even a business of my own.

☑ Check one FREE catalog only
- ❑ **Programming in C++ with Windows**
- ❑ **PC Troubleshooter**
- ❑ **PC Applications Specialist**

Other computer career training:
- ❑ Computer Programming
- ❑ Desktop Publishing and Design
- ❑ Bookkeeping and Accounting

Name _____ Age _____

Address _____

City _____ State _____ Zip _____

Accredited Member, National Home Study Council 4536-042

World Radio History

NRI training gives you two more exciting opportunities to make money with your computer



No matter which course you choose — PC Troubleshooter or PC Applications Specialist — your training includes a powerful IBM PC/AT-compatible computer system and valuable software you keep!

2 Earn good money as a PC Troubleshooter

There's no doubt about it: Businesses spend billions of dollars on personal computers each year — *even more* on PC service and support. That means big opportunity for computer pros who can troubleshoot today's PCs —people with the hands-on training it takes to diagnose system failures, replace damaged chips, retrieve lost data, or troubleshoot faulty disk drives and circuit boards.

Now with NRI, you can master the skills you need to make money as a PC troubleshooter and cash in on big opportunities in this top-paying career field.

AT-compatible computer, diagnostic hardware and software included

NRI's step-by-step lessons and unique hands-on Discovery Learning projects show you how to localize PC problems, identify faulty components, recommend system configurations, and replace the damaged parts that cause PC system failures — plus much more!

Best of all, you get hands-on experience with a powerful AT-compatible computer, 40 meg IDE hard drive, and professional diagnostic hardware and software — all included in your course. Using PC Tools, an invaluable diagnostic software package, you get a hands-on understanding of the special utilities that make correcting software and data problems easy and profitable — everything from hard disk backup to data recovery, disk and file management, even virus and memory loss protection. But that's not all...

Rounding out your training, you get professional troubleshooting experience using your Ultra-X R.A.C.E.R. plug-in diagnostic card and QuickTech menu-driven software to test the system RAM and uncover the problems that can occur with PC motherboards and peripheral adapters.

By the time you complete your course, you have the skills and the software you need to make money as a PC troubleshooter. Send for your FREE NRI catalog today!

3 Become today's in-demand PC Applications Specialist

Organizations everywhere are paying top dollar for computer pros who can use word processing, database management, spreadsheet, and data communications software. In fact, today's PC-driven business world has given rise to a *new* breed of computer professional: the PC applications specialist.

Now, you can become this sought-after expert — on the job or in a business of your own. Only NRI gives you a powerful computer system plus the hands-on experience you need to succeed.

Train with and keep an AT-compatible computer system and Microsoft®Works™

Even if you've never worked with computers before, with NRI you master the real-world skills you need to make good money as a PC applications specialist. Easy, step-by-step lessons and hands-on training with a powerful AT-compatible computer system, MS-DOS, and Microsoft Works software – all included in your course – give you the important computer skills behind today's most in-demand business applications.

With NRI, you train at home and at a comfortable pace, always supported by your experienced NRI instructor. Step by easy step you learn not one or two, but *four* essential PC applications. Using your computer and Microsoft Works software, you master word processing, database management, spreadsheets, and data communications with confidence and ease. You even learn to install and use your mouse for quick-click access to the menu commands that save you time and effort when working with today's business applications.

Get the skills, the computer, and the software you need to start a money-making new career as a PC applications specialist. Send for your FREE NRI catalog today!

FREE catalog tells more!

Get all the facts about NRI training in your choice of three high-growth computer fields: Programming in C++ with Windows, PC Troubleshooter, or PC Applications Specialist. If the card is missing, write to NRI Schools, McGraw-Hill Continuing Education Center, 4401 Connecticut Avenue, NW, Washington, DC 20008.

SEND TODAY FOR YOUR FREE CATALOG!

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS MAIL PERMIT NO. 10008 WASHINGTON, D.C.

POSTAGE WILL BE PAID BY ADDRESSEE

NRI SCHOOLS
McGRAW-HILL CONTINUING EDUCATION CENTER
4401 CONNECTICUT AVENUE, NW
WASHINGTON, DC 20078-3543

World Radio History

BARRY NANCE

BATCH-FILE TOOLKIT

I feature three DOS enhancers this month: Need, Get, and Ask. Each adds significant features to the batch-file programs you write. If, like me, you stopped writing DOS batch files long ago out of boredom and frustration, you may find that these utilities rekindle your interest in batch-file programming.

These batch-file enhancers extend the capabilities of DOS

A Friendly Environment

Need, which includes Avoid and Sniff, ensures a friendly hardware and software environment. You can use these three programs to see if Desqview is running; to determine if there's sufficient conventional, extended, or expanded memory; to determine if the CPU is a 386 or higher; or to check for a host of similar conditions. Need includes numerous hardware and software tests to determine if a machine meets all your requirements.

You tell Need what you want. It tests the computer's configuration and sets DOS's ERRORLEVEL variable to 0 if all is OK or to 1 if one or more of the conditions you specified could not be met. You can check the ERRORLEVEL inside the batch file and decide if your batch file should continue, abort, or alert the user.

Avoid is the opposite of Need; it helps you avoid certain hardware/software combinations. Finally, Sniff will return configuration information that you can read.

What DOS Leaves Out

Get supplements the DOS batch-file commands. It turns batch-file programming into macro-language programming. Like Need, Get queries the hardware and software configurations of a system. However, Get also prompts for input and sets system parameters. This utility can ask questions, get disk and file information, get hardware or software information, do screen output, and toggle system settings.

Get's command-line parameters let you get and put strings; set screen color and video mode; and get the DOS version, file size, free disk space, disk size, current directory, and volume label.

Typically, Get sets an environment variable that you can test after Get completes. For example, you might code the following

```
GET N "Answer yes or no: "
IF "%GET%"=="N" goto NO
IF "%GET%"=="Y" goto YES
```

to get a yes or no answer from the person running your batch program.

Just Ask

Use Ask to get multiple-choice answers to questions you submit to the user. Ask puts a string in the master environment containing the user's answer, and you can easily test the string to know what to do next in your batch-file program. You can even use Ask to build menus inside batch programs. You might use Ask to determine which program to launch, or to force a compiler or linker to use a certain set of options or libraries.

You can use Roedy Green's Need, Avoid, and Sniff for free, but you must pay the $15 registration fee to get the assembly language source code. Get is a $15 shareware program developed by Bob Stephan. Ask, written by Jay Vanderbilt, is free. ■

UNIX/Ben Smith

Noninteractive Unix

Computing implies automation. But since the advent of interactive programs, where users control the program as it runs, the ability of a program to run noninteractively (i.e., in batch mode) has sometimes been neglected by programmers. This trend has even infected the Unix software world, where traditionalists have usually ensured that their programs (e.g., `mailx`) can run both interactively and in batch mode.

To patch some of these holes that liberal-minded developers have created, Don Libes developed `expect`. This utility program performs programmed dialogue with those trendy, user-interactive programs that haven't been designed for use in a world of automation. This is a public domain program. Libes, who works for the National Institute of Standards and Technology, is the coauthor of *Life with UNIX: A Guide for Everyone* (Prentice-Hall, 1988).

MAC/Tom Thompson

Solving Virus Crimes

A computer virus is one of those subjects you'd rather not hear about—until one "roaches" your Mac's hard drive, taking the day's work with it. Worse, like their biological counterparts, new viral strains appear that bypass protective detection software that's only familiar with existing viruses.

Virus Detective 5.0 by Jeffrey Shulman is a $40 shareware desk accessory that scans hard drives and floppy disks for viruses. What's important about Virus Detective is its programmability: You can type in new code signatures so that Virus Detective will recognize new viruses. Virus Detective can read text files with new code signatures. Thus, an update is often only a matter of logging onto an on-line service and downloading the latest signature file. Virus Detective's programmability ends the arms race between the virus creator and victim once and for all—not a bad bargain.

Editor's note: *Software Corner highlights public domain, freeware, and shareware programs. The programs are available on BIX (in the sw.corner conference), from Demolink, and on disk. See "Program Listings" on page 5 for details. We solicit contributions and pay $50 for any program we use. Write to: Software Corner, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458.*

World Radio History

WHY SOFTWARE COMPANIES ARE CHOOSING HARDLOCK™



Developers Say. . .

"Since the Hardlock uses an algorithmic response chip, I am assured of the highest level of protection. Also, the optional programmable memory means I can keep custom configurations in Hardlock rather than in a file. I can protect my .EXE or .COM files directly and/or incorporate Glenco's high level language interface routines into my software. And, I feel confident I'll have Glenco's support if I use other programming languages."

Accountants Say. . .



"Hardlock provides our company with a healthier bottom line. Since our software can't be copied, our revenue has steadily increased. The unique programming board allows us to program the Hardlock in seconds. This ensures optimum delivery schedules from Glenco and a lower inventory cost for us. Hardlock's field programmable feature means a single Hardlock can protect more than one product."

Actual size shown.

Hardlock — programmable, algorithmic response and memory option — all in one

End Users Say. . .

"Hardlock allows me to backup my software investment. I just plugged Hardlock into the printer card, connected the printer cable, and forgot about it. Since Hardlock doesn't require a battery, I am assured of reliability and no down time.

HARDLOCK™ The Preferred Protection System!

GLENCO ENGINEERING INC.

SERVING THE SOFTWARE INDUSTRY SINCE 1979

270 Lexington Drive
Buffalo Grove, Illinois 60089-6930
(708) 808-0300 FAX 808-0313
1-800-562-2543

See us at COMDEX Booth #W2946 **1-800-562-2543**

H A R D L O C K

For a distributor in Europe contact, FAST Electronic GmbH 49-89-539800-20 FAX 49-89-539800-40

For International information circle 74, For End-User information circle 75 on Inquiry Card.

World Radio History

MARTIN HELLER

INSIDE 386 ENHANCED MODE

Windows is divided into three parts: the kernel, the user, and the Graphics Device Interface (GDI). Although that's the basic architecture, there is more to heaven and earth than is dreamt of in this philosophy. Windows also acts as a DOS extender (DOSX) to work in protected mode.

Most Windows programmers are unfamiliar with DOSX because its documentation is in the Windows Device Driver Kit (DDK). Most programmers have their hands full learning the Windows application programming interface (API), as explicated in the Software Development Kit. I'll try to remedy this.

Standard mode and enhanced mode have quite different DOS extenders. Standard mode works in the protected-address segmented 16-bit mode of a 286 CPU; extended mode sets up 386 virtual machine environments underneath a paged 32-bit virtual machine manager (VMM). Standard mode is really pretty simple; enhanced mode is not simple at all.

Virtual Concepts

What is a virtual machine? Imagine you are a program. You think you have control of a computer, but you don't: The operating system has simulated a computer to fool you. You can't affect programs running in other VMs; you can't even tell they're there.

The enhanced-mode Windows implementation of a VM has a memory partition (i.e., an area to save processor registers) and a control block (i.e., data structures to implement virtualization of the other aspects of a PC, such as ports, I/O controllers, DMA controllers, video interfaces, and interrupt tables). In other words, a VM maintains a complete description of the state of an application and lets a program execute as though it were running on a 386 in real mode.

An ordinary real-mode program will be fooled by a VM. A somewhat more sophisticated program will detect that it is running under enhanced-mode Windows using an INT 2F hexadecimal service and, perhaps, modify its behavior to allow for better multitasking. The most sophisticated programs know they are running in a VM and can take advantage of it, using INT 33h services to access the DOS Protected Mode Interface and INT 2Fh services to access other enhanced-mode services. With DPMI, an application can even go into protected mode.

Not every extended-DOS application is compatible with DPMI. But the major DOS-extender vendors—Phar Lap Software, Rational Systems, and Ergo Computing—have updated their products to work with DPMI.

The system VM is automatically created when enhanced mode initializes. It always has a protected-mode portion that is used to run the Windows desktop. Yes, that's right: What you think of as Windows is running in a VM. The Windows desktop, too, is fooled into thinking it has the whole machine, when it is just the first of many VMs.

Things your mother never told you about Windows



Below all the VMs is a VMM, which takes care of allocating memory, CPU time, and peripherals. The VMM and the virtual device drivers (VxDs) run in one flat-model 32-bit memory segment. To write VxDs, you need to write 32-bit programs; 32-bit versions of Microsoft Macro Assembler and Link come with the DDK for that purpose. Windows comes with VxDs for the screen, keyboard, mouse, and serial ports, as well as virtualization support for lower-level hardware.

VM Details

When enhanced mode starts up, VMM and the virtual devices specified in SYSTEM.INI load. The VMM and all the VxDs initialize, the system VM is created and initialized, and, finally, the shell VxD executes Windows. The shell VxD calls V86MMGR services to set up VMs. To start a DOS VM, it uses `V86MMGR_Allocate_V86_Pages` to allocate memory pages for the VM's base memory and map them into the VM. Then it uses `V86MMGR_Set_EMS_XMS_Limits` to allocate memory pages for EMS and Extended Memory Specification and connect those pages to the code that handles EMS and XMS interrupts.

A value of 0 for the minimum and maximum size (normally set in a program information file) will disable access to EMS or XMS services; a value of -1 will set no limit. For instance, setting EMS memory for a FoxPro application to a minimum of 1024 and a maximum of -1 means that the database will see as much expanded memory as possible, at least 1 MB, or the application won't run.

What about having multiple DOS VMs?

continued

ILLUSTRATION: VICKI GULLICKSON © 1992

World Radio History

In its V86-mode memory map, each VM has its own local set of interrupt vectors, its own display memory, and its own local application code and data. Each also has a map to global memory regions that hold MS-DOS and the loaded DOS device drivers, any network and TSR program code loaded before Windows starts, a portion of Windows/386, and the system ROM. All the above run at privilege ring 3 (the lowest level).

The protected-mode portion of a VM runs at privilege ring 1, 2, or 3. Every VM also has a control block and a client stack at privilege ring 0 (the highest level). The control block contains, among other things, data used by the system VxDs to maintain the state of, for example, the physical hardware across all VMs.

The enhanced-mode Windows VMM has a two-level scheduler that preemptively allocates time among the VMs. The primary level of the scheduler scans the execution priority of all VMs and lets the VM with the highest priority run. The secondary level is the time slicer, which dynamically alters the execution priorities of VMs based on the current time and their foreground and background time-slice priorities.

A VM lets a program execute as though it were running on a 386 in real mode.

When application code in a VM issues a software interrupt or causes a protection fault, the 386 protection mechanism causes a privilege-ring transition. Control transfers to the VMM, which, in turn, dispatches the interrupt to the appropriate VxD. If your program issues a DOS call (e.g., INT 21h), the software interrupt will cause a privilege-ring transition. Instead of directly executing the DOS function, the program flips into the VMM, which makes sure that the DOS function is allowed before it passes control to DOS.

There's much more to enhanced mode, but that's the gist of it. You can find out more from the DDK and by poking around with an enhanced-mode debugger (e.g., Soft-Ice for Windows).

Class Libraries, Redux

My collection of class libraries for Windows continues to grow, with something old—Glockenspiel's CommonView 3.0—and something new—the Microsoft Foundation Classes (MFC). CommonView, which is distributed in the U.S. by ImageSoft, supports Borland C++ as well as Glockenspiel's own C++ translator coupled with Microsoft C 6.0ax. It targets Windows, Presentation Manager, and OSF/Motif in a portable way. CommonView's classes cover the user (i.e., window and dialog-box management) and GDI (i.e., graphics) parts of Windows fairly well. Borland's ObjectWindows covers the user but not the GDI. CommonView comes with container classes and a memory management dynamic link library.

MFC, which ships with Microsoft C/C++ 7.0 for Windows, covers most of the Windows API, including hard parts like Multiple Document Interface and Object Linking and Embedding. MFC has container classes that can also be used in DOS applications, but its main purpose is to encapsulate the Windows C interface. You want portability? It's portable only as far as the Windows API is portable, but the Windows API could go places you'd never have expected. Stay tuned.

MFC is a thin layer. There's relatively little overhead and relatively little abstraction. The MFC sample applications seem as quick as their C counterparts. At the same time, many of the MFC classes were designed specifically to be extended by inheritance, which makes MFC a better building block than less-extensible application frameworks.

Anything with a handle in Windows becomes an object in MFC—an object with almost the same name as its API counterpart. What's the main thing with a handle in the GDI? A device context. How do you draw in a window in MFC? You construct an item of class CDC and then use its member functions: `CDC::MoveTo`, `CDC::LineTo`, `CDC::TextOut`, and so on. Do you have to use the classes? No; it's OK to mix in your old C code. I think I'm going to like MFC.

Nasty and Nice Surprises

I mentioned in a previous column that I was producing the final pages of my book with Word for Windows 2.0. I was able to produce perfectly acceptable individual pages with WinWord, but I couldn't get facing pages to align at the top and bottom to save my life.

Fine, I thought. I'll just flow the book into PageMaker. After all, I'd tested for this possible exigency with Word 1.1. Microsoft wouldn't dare break such an essential function in a new version.

Wrong. PageMaker 4.0 can't import WinWord 2.0 format, nor can it import WinWord 2.0 Rich Text Format output. I tried sending RTF to the Mac. I was able to get Mac PageMaker to read the files only by first opening and saving them from MacWord. My text came across, but none of my illustrations survived the process.

As it happened, there was a copy of Image-In-Color in my pile of things to examine. It produces TIFF files acceptable to Mac PageMaker. I copied all the bit maps out of my WinWord files, saved them as BMP files (using the Image2 application from my book), and then converted each BMP file to TIFF with Image-In-Color.

Happy ending: The book got to the printer complete with all its illustrations, albeit a few weeks later than I had hoped. My apologies to anyone who scoured bookstores looking for a copy of it in early January. ■

Martin Heller develops software and writes about computers, despite a Ph.D. in physics and despite having worked, literally, as a rocket scientist. He is the author of Advanced Windows Programming *(Wiley, 1992).*

Your questions and comments are welcome. Write to: Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458.

ITEMS DISCUSSED

Glockenspiel's CommonView 3.0.....$499
ImageSoft, Inc.
(516) 767-2233
Circle 1146 on Inquiry Card.

Image-In-Color.....$495
Image-In, Inc.
(612) 888-3633
Circle 1147 on Inquiry Card.

Microsoft C/C++ 7.0 for Windows.....$495
Windows 3.0 Software Development Kit.....$500
Microsoft Corp.
(206) 882-8080
Circle 1148 on Inquiry Card.

Soft-Ice for Windows.....$386
Nu-Mega Technologies, Inc.
(603) 888-2386
Circle 1149 on Inquiry Card.

World Radio History

ASK BYTE

Video Downsizing

I want to obtain a high-performance PC on a moderate budget. These systems often include 1024- by 768-pixel monitors that are compatible with standard VGA but not with older video graphics standards (e.g., MDA, CGA, and EGA). I am interested in a video adapter capable of displaying these older video modes.

Do video controllers supplied with high-resolution monitors typically support the older standards? If so, could I simply unhook the high-resolution monitor, configure the video software drivers to older modes, and plug in another monitor?

Thomas A. Williams
Waterford, MI

ATI Technologies (3761 Victoria Park Ave., Scarborough, Ontario, Canada M1W 3S2, (416) 756-0718; fax (416) 756-0720) has just the video adapter for you. While many high-resolution video boards let you run EGA- or CGA-mode programs on your VGA monitor, they do not give you dual connectors so that you can attach an EGA or a CGA monitor. The ATI VGAWonder XL gives you 15-pin (analog) and nine-pin (digital) video connections and a mouse port as well. The board supports resolutions of up to 1024 by 768 pixels, as well as VGA, MDA, EGA, and CGA modes. ATI's suggested list price is $399 with 1 MB of video RAM, but you can find it for considerably less.

Many clone vendors will build a system to your specifications and will be happy to substitute the VGAWonder XL for their standard video board.—Stanford Diehl

Windows Environment Revisited

In the October 1991 Ask BYTE, Paul M. Smith brought up a common problem in the DOS community: Running a batch file that sets an environment variable in a DOS window produces an "Out of environment space" error message. The cause of this problem and the fix, however, have little to do with the `windir` variable produced by Windows 3.0.

When started, Windows inherits an environment equal to the parent's current environment. This includes the variable set and the size currently used. Setting an environment size in CONFIG.SYS (e.g., `SHELL=C:\COMMAND.COM /P /E:256`) is the first step. This gives the initial environment a size of 256 bytes. The environment can grow to 256 bytes, but once you start a program, its inherited environment size is limited to what is currently used. The only fix is to add the `/E:256` switch to the COMMAND.COM in Windows.

If you open a DOS window or start a batch file without a program information file (PIF), change the command line under program item properties to `C:\COMMAND.COM /E:256 [/C batchfile.bat]`.

If you use a PIF, set the program filename to `COMMAND.COM` and change the optional parameters to `/E:256 [/C batchfile.bat]`.

Both options start up COMMAND.COM with an initial environment size of 256 bytes. You can change the environment size to any value between 160 and 32,768.

This problem is inherent in nearly all programs that have a shell to DOS or DOS window function (Desqview somehow avoids it). The fix is the same in all cases (provided that the program lets you change the shell/window command). It would be nice if developers would check for the initial environment size setting and use it in their shell/window function.

Here's one little memory-squeezing tip: When loading TSR programs in your AUTOEXEC.BAT file, do so before setting an environment variable (e.g., PATH or APPEND). Because a TSR also inherits the current environment, keeping it as small as possible saves a few precious bytes of memory. The exceptions are those "intelligent" TSRs that release the unneeded environment back to the memory pool.

Kevin J. Burkholder
Spring City, PA

The Working Font

I use Adobe Type Manager and a Qume ScripTen PostScript printer. I have 13 fonts to use with ATM. I wanted to add more fonts using the WFN Boss utility included with CorelDraw 2.0. The utility converts fonts from Corel format to Adobe Type 1 format.

I converted many fonts with WFN Boss. When I used ATM to add these new typefaces, it did so perfectly. But when I tried to print a PageMaker file, all the fonts I had converted printed in Courier. How can I use the fonts converted by WFN Boss to work with other Windows applications?

Jean Lauzier
Val-Brillant, Quebec, Canada

Corel has made improvements to the WFN Boss utility in CorelDraw 2.01. Register your software if you haven't done so and ask for the upgrade.

It also sounds like you have not made some necessary modifications to your WIN.INI file. ATM assumes that typefaces are resident in your PostScript printer. Thus, it does not automatically download them for you. You must do it manually from the WIN.INI file. Load the WIN.INI file into your word processor and find the section where Windows lists the information on your PostScript fonts. The section will begin with the header `[PostScript,LPT1]` *or something similar. You will want to edit the lines beginning with* `softfontX=` *to include the typefaces you have created. The lines will show a path to only the .PFM files. Go to the end of the line, insert a comma, and add a path to the .PFB files. The final result will look something like the following:*

```
softfont9=c:\psfonts\pfm\newfont.pfm,
c:\psfonts\newfont.pfb
```

Also, try using ATM's PSDOWN utility to automatically download the font to your printer. PSDOWN flushes

World Radio History

the font from your printer's memory after each print job. If you don't use it, you'll have to reset your printer after each job to free up memory.—Stanford Diehl

High-Resolution BASICs

I recently purchased a 25-MHz 386 computer with a Super VGA card (1024 by 768 pixels) and DOS 5.0. I wanted the higher resolution to program some graphics and animation. I want to work in BASIC and access this high resolution. So far, I have been unable to find out how to do this.

I am able to program in 640- by 480-pixel resolution. I can set the high-resolution mode in DOS (with the display card's DMODE utility), but BASIC sets it back to the lower resolution. Is it possible to have BASIC access the higher-resolution modes?

R. A. Fischer
Sun Lakes, AZ

It's a funny thing about standards—just when you get used to one, someone changes it. Versions of BASIC (and libraries for most other languages) usually support only the modes defined by IBM. That means 16 colors in 640- by 480-pixel mode or 256 colors in 320- by 200-pixel mode. There is a relatively small number of de facto Super VGA standards. The Tseng Laboratories 3000 and 4000 chip sets are popular among manufacturers, as are the sets used by Paradise, ATI Technologies, and Video Seven. To access the higher-resolution modes, you need a replacement graphics library that supports your video card.

You might contact Genus Microprogramming (2900 Wilcrest, Suite 145, Houston, TX 77042, (800) 227-0918 or (713) 870-0737; fax (713) 870-0288) and ask about its GX Effects library ($199). It links into Microsoft QuickBasic 4.x or BASIC PDS 7.x and gives you sprite animation, sound, music playback, Sound Blaster file playback, and many other features. You might also want Genus's $249 PCX Programmer's Toolkit if you're working with .PCX files.

The current versions of both Genus products support the Trident, Paradise, ATI, and Video Seven cards in 800- by 600-pixel display modes, and cards based on the Tseng Labs 4000 in 1024- by 768-pixel mode. New versions (possibly available by the time you read this) will support all these cards and the Video Electronics Standards Association specification in 1024- by 768-pixel mode.—Howard Eglowstein

Resolving Conflict

If Cliff Millward's ScanJet/video board conflict is like mine (Ask BYTE, December 1991), he can cure the problem by changing video boards. When I added a ScanJet Plus a few years ago, my Paradise VGA Plus 16 from Western Digital Imaging would no longer work in 16-bit mode. According to Hewlett-Packard and WDI, the video and scanner interface boards compete for the same memory area. I replaced the Paradise board with an Orchid Technology ProDesigner Plus, which runs in 16-bit mode and politely avoids trampling scanner memory.

I have just replaced the ProDesigner Plus with an Orchid Fahrenheit 1280, and it runs correctly in 16-bit mode with the ScanJet Plus active. I suspect that Orchid's popularity with the graphics crowd, who are likely to use a scanner, caused the firm to design its boards this way. (Contact Orchid Technology, Inc., 45365 Northport Loop W, Fremont, CA 94538, (800) 767-2443 or (510) 683-0300; fax (510) 490-9312.)

David Ellis
Torrance, CA

CNS on the Move

In the August 1991 Beyond DOS, Martin Heller discussed CNS's C++/Views software. I have been unable to locate the company.

Stacey Wohleber
Huntsville, AL

CNS has moved. Its new address is 1250 Park Rd., Chanhassen, MN 55317, (800) 843-2978 or (612) 474-7600; fax (612) 474-6737.—Raymond GA Côté

CPU Upgrade Issues

I have an IBM PS/2 Model 50 Z. I want to upgrade my system to a 386 processor, but I have found some problems in doing so. In Chile, we do not have as much information about products coming to market.

IBM of Chile has an Aox card to upgrade my system, but it is very expensive. The 25-MHz MicroMaster 386 sells for $2000. I know there must be other cards. Can you provide me with the names of manufacturers? I would also appreciate references to any articles published on this topic.

Julio Rodiño Durán
Santiago, Chile

Installing upgrade boards into 286 systems is complicated and expensive. Do so only if you are an experienced user. BYTE has not evaluated any 386DX upgrade boards, but we have covered 386SX upgrade boards (see "SX Upgrade Boards: Not for the Fainthearted," April 1991 BYTE). We also covered two SX upgrade boards in the October 1991 Reviewer's Notebook. One of them was the SX/Now, a product for the Model 50 Z from Kingston Technology Corp. (17600 Newhope St., Fountain Valley, CA 92708, (714) 435-2600; fax (714) 435-2699). The 25-MHz SX/Now upgrade sells for $625.

As you mentioned, Aox (486 Totten Pond Rd., Waltham, MA 02154, (617) 890-4402; fax (617) 890-8445) offers the 25-MHz upgrade for your system. It has a list price of $1549. You should also consider 20-MHz versions from both of these companies. You'll give up some performance but save money.—Stanford Diehl ■

The BYTE Lab welcomes your questions. Address correspondence to Ask BYTE, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458. You can also send BIX mail c/o "editors."

We read every letter, but due to the volume of mail received, we cannot guarantee a response. We edit all letters for clarity and brevity. Letters appear in BYTE about four months after we receive them.

World Radio History

Being online never felt so fine.

Join the online network with personality. The most interesting conferences. 10,000 programs you can download for your own use. All the most popular services.

Two membership plans: $6 an hour or $1 an hour with the 20/20 Advantage.

Join us online, the water's fine.

Circle 61 on Inquiry Card.

Free Membership

Dial by modem,

1-800-365-4636

Press return. At password, type RB22

DELPHI

Voice, 1-800-695-4005
617-491-3393

World Radio History

WHEN YOU NEED SOLUTIONS, NOT JUST ANOTHER BOARD!

Let a Quatech Sales Engineer show you the value of quality, service and support.

COMMUNICATION

Quatech produces a full line of serial and parallel adapters for PS/2, PC-XT, AT and compatible systems available in RS-232, RS-422, RS-485 and Current Loop. Selectable addresses and interrupt capabilities are featured in our multi-port/user, SDLC, HDLC, and X.25 adapters. Software and 16550 UARTS are available.

DATA ACQUISITION

Quatech has developed a full line of data acquisition products for the IBM AT and compatibles. These high performance, low cost boards provide analog-to-digital, digital-to-analog, and digital input/output functions. A/D and D/A converters are equipped with 8, 12, or 16 bit resolution, and sampling rates up to 1 MHz.

1-800-553-1170

QUATECH

Made in U.S.A.

Corporate office: (216) 434-3154, FAX (216) 434-1409, 662 Wolf Ledges Pkwy, Akron, OH 44311 U.S.A. International: Australia/Interworld Electronics 03-563-7066, Canada (Western)/Interworld VCR 604-984-4171, England/Diamond Point International 634-722-390, Finland/Lab Hitech OY 358-0-804-2522, France/Elexo 33-1-69302880, Germany/Jupiter Electronic Systems 06181/75041, Israel/RCM Ltd. 972-03-5447885, Italy/N.C.S. Computer Italia 0331/ 770-016, Netherlands/ACAL Auriema 040-816565 Korea/Sam Boo Enterprise Co. 02-678-7457. IBM PC-XT, AT and PS/2 are registered trademarks of IBM Corp.

Circle 205 on Inquiry Card.

World Radio History



BYTE BUYER'S GUIDE

Your direct source for buying software, hardware and accessories from knowledgeable and service-oriented dealers.

	Page
Mail Order The latest offerings from vendors supplying products of all leading manufacturers at extremely competitive prices.	304
Hardware/Software Showcase This new, *categorized* four-color display section makes it easy to find Hardware and Software products from a wide variety of manufacturers and suppliers.	340
Buyer's Mart From Accessories to Laptops to Word Processors, you can easily find the dealers you are looking for in this directory of products and services.	350

World Radio History

Get A Lode Of This.

Our Three-Way Guarantee Just Got Better.

The LodeStar Three-Way Personal Guarantee has always been one of the industry's most comprehensive. But now it just got better. Introducing The LodeStar Five-Way Personal Guarantee. Now, every LodeStar system is covered five ways to insure your complete satisfaction. And that should take a lode off you mind.

1. MONEY BACK GUARANTEE.
If you change your mind-for any reason-simply return your LodeStar system to us in original condition within 30 days of your receipt andwe'll refund your money

2. FREE LIFETIME TECHNICAL SUPPORT.
For as long as you own your system, we'll give you FAST, FREE unlimited technical advice and guidance from our expert staff. This includes any support needed to upgrade or modify your system.

3. FREE LIFETIME LABOR SUPPORT.
Although you will probably never need it, for as long as you own your system, it will be protected by our 100% labor warranty.

4. FREE 2-YEAR PARTS WARRANTY.
For a full two years after purchase, your LodeStar computer will be covered by our 100% parts warranty, with fast turn around on any replacements.

5. FREE 1-YEAR ON-SITE SERVICE..
For a full one year after purchase, you'll have the added security of our coast-to-coast FREE on-site service.

Moduless Upgradeables

Carry A Greater Lode In The Future

Easy and inexpensive upgrades are built right into your LodeStar Starflex computer. Unlike conventional modular upgradeable systems from other Companies, you can upgrade your LodeStar Starflex system at a fraction of the cost-all the way from 386DX to 486SX or 486DX, at any clock speed.
Thanks to our unique non-proprietary Moduless Upgrade design, LodeStar Starflex systems can be upgraded by simply plugging in the new chip and oscillator that comes in their inexpensive upgrade kit. Another bright idea from LodeStar-It's just that simple !

Every LodeStar computer is fully loaded with value. This includes unsurpassed quality throughout. To make certain of this, every system is individually pre-tested and burned-in for 72 hours prior to shipment. And of course, we stand behind our quality with our comprehensive Five-Way Personal Guarantee. You will see this quality all the way from our StarView SVGA Non-Interlaced Monitors with flicker-free image, to our own StarKey extended keyboards. And we pack in even extra value by pre-loading MS DOS 5.0 & Windows 3.0, as well as a Hi-Res 400 DPI serial mouse on every system. And our systems can be upgraded to include optional cache, RAM, more hard disk capacity, larger monitor, and a host of other enhancements you may require. Add it all together - stellar performance, brilliant quality, and guarantee that outshines all others - and you've got LodeStar.

World Radio History

LodeStar 386-40C
$ 1759

AMD 80386/40 Processor
64K Cache RAM (Expandable to 256K)
4MB RAM (Expandable to 32MB) 60ns
125 MB IDE Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Non-Interlaced Color card
14" StarView 1024 NI SVGA Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse
Desktop CPU case (Verticals optional)

StarFlex 386-40 Cache
Upgradable Series
$ 1899

Upgradable to 486SX-20, 486-33/50.

LodeStar 386SX-25
$ 1199

Intel/AMD 80386SX 25 Processor
2MB RAM & 42 MB Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Color card
14" StarView 1024 x 768 Color Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse
Desktop CPU case (Verticals optional)

LodeStar 386SX-16
$ 1159

LodeStar 386-33C
$ 1699

Intel 80386/33 Processor
64K Cache RAM (Expandable to 256K)
4MB RAM (Expandable to 32MB) 60ns
125 MB IDE Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Non-Interlaced Color card
14" StarView 1024 NI SVGA Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse
Desktop CPU case (Verticals optional)

StarFlex 386-33 Cache
Upgradable Series
$ 1849

Upgradable to 40 Mhz & 486SX-20,486-33/50

LodeStar 486-50C
$ 2679

Intel 80486/50 Processor w/ 8K Internal
Cache & Built-in Math Coprocessor
2 x 32 Bit Local Bus Expansion Slots
64K Cache RAM (Expandable to 256K)
4MB RAM (Expandable to 32MB) 60ns
125 MB IDE Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Non-Interlaced Color card
14" StarView 1024 NI SVGA Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse
Vertical or desktop Case

486-50 CADstation
$ 4179

8 MB RAM & 210 MB Hard Drive
17" SVGA Color Monitor.
32 Bit Local Bus SVGA Color Card
(w/1 MB RAM & Provide 32,768 Colors)

LodeStar 386-25
$ 1529

Intel 80386/25 Processor
4MB RAM (Expandable to 32MB) 60ns
85 MB IDE Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Non-Interlaced Color card
14" StarView 1024 NI SVGA Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse

Desktop CPU case (Verticals optional)

StarFlex 386-25 Cache
Upgradable Series
$ 1729

64K Cache RAM (Expandable to 256k)
Upgradable to 33/40 Mhz & 486SX 20, 486-33/50.

LodeStar 486-33C
$ 2079

Intel 80486/33 Processor w/ 8K Internal
Cache & Built-in Math Coprocessor
2 x 32 Bit Local Bus Expansion Slots
64K Cache RAM (Expandable to 256K)
4MB RAM (Expandable to 32MB) 60ns
125 MB IDE Hard Drive w/Cache
Teac 1.2MB 5.25" & 1.44MB 3.5" Drives
1 MB SVGA Non-Interlaced Color card
14" StarView 1024 NI SVGA Monitor
(VESA Std for 72 Hz Flicker-Free Display)
2 Serial, 1 parallel, & 1 Game Port
MS DOS 5.0 & MS Window 3.0 w/Manual
Starkey 102 Keyboard
Hi-Res Serial Mouse
Mid Vertical or Desktop Case

486-33 WINstation
$ 2859

8 MB RAM & 210 MB HD.
32 Bit Local Bus SVGA Color Card
(1 MB RAM & Provide 32,768 Colors)

Circle 217 on Inquiry Card.

**Mid & Full Verticals may be additional on some systems.*

1.800.875.7568

PC Sources

- Warranty -
"One of the most conspicuous things that differentiate LodeStar from its competitors is extensive warranty support."

- Craftsmanship -
Layout is excellent . . . Wonderfully uncramped sight that greets you when you open the case with LodeStar's tower, you don't have to fight a mass of tangled cables and jagged edges."

- Technical Support -
"As a further test of technical support, I deliberately destroyed . . . I then gave the system and a phone to an inexperienced friend. A LodeStar technician competently took her through the process . . ."

- Prompt Response -
"When I called with a question . . . I was immediately connected to a knowledgeable technician."

- Summary -
"The combination of high performance, low price and one year of free on-site services makes LodeStar 486 an attractive buy."
- PC Sources 1992

LodeStar COMPUTER

18539 East Gale Ave.
City of Industry,
California, 91748
Tel: 1.818.810 3818
Tech Support:
1.800.875.7569
Fax: 1.818.810.5928

GOVERNMENT, SCHOOLS AND CORPORATE PURCHASE ORDERS WELCOME. All prices and specifications subject to change without notice. 3 Year Parts Warranty applies to entire product only. Money Back Guarantee does not include shipping & handling, and all returns must be shipped pre-paid in original packaging. Please call for current offers. Prices subject to change without notice. Photography is for illustration only. All trademarks of their respective companies.

World Radio History

Get the WORX!

WORX Computers- Highest Quality and the Features you want at an Affordable Price... That's VALUE!

All WORX computers come with a 30-day satisfaction guarantee and 1-year warranty including parts and labor. To order call: 1-800-639-2185

Desktop or Mini-Tower same price; Full Tower add $149.; 300Watt power supply add $49.; 2nd cooling fan and temp. alarm add $49. Std. power supply is 200/250Watt.

SX HEADQUARTERS:

WORX 386sx/16

1MB RAM/40MB hard drv
51/4" TEAC Floppy
16-Bit VGA w/256k
VGA Color Monitor
Keytronic Keyboard
MS-DOS 5.0
$995.

WORX 386sx/25

same as sx16 w/2MB RAM
80MB hard drv, 16-Bit VGA
w/512k and 1024I, .28 dot
VGA Color Monitor
$1295.

Add MS-Windows and a mouse for only... $99.
Add a TEAC 3.5"... $79.
Add a 2400-Baud internal modem... $79.
Add a 9600/2400-Baud int. FAX Modem... $149.

33MHz POWERHOUSES!

64k cache
WORX 386/33-64c

2MB RAM/120MB hard drv
Both TEAC Floppies
16-Bit VGA w/512k
1024I, .28 dot VGA Color
Keytronic Keyboard
MS-DOS 5.0, MS-Windows
Mouse
$1795.
128k cache add... $50.
256k cache add... $100.

256k cache
WORX 486/33-256c

4MB RAM/120MB hard drv
Both TEAC Floppies
16-Bit VGA w/1MB
1024NI, .28 dot VGA Color
Keytronic Keyboard
MS-DOS 5.0, MS-Windows
Mouse
$2395.

NEW!

WORX 486/50-256c

4MB RAM/200MB hard drv
256k cache RAM
Both TEAC Floppies
16-Bit VGA w/1MB
1024NI, .28 dot VGA Color
Keytronic Keyboard
MS-DOS 5.0, Windows
Mouse
$2995.
8MB RAM add... $200.

Call for custom configurations.

Also available... PS/2 CPU and Memory Upgrades; Networking Hardware and Software; Memory Expansion for HP Workstations.

Call today for memory boards for your HP/Apollo workstation.

100% HP compatible
Full 5-Year warranty

Also available...
COUNTER/TIMER, DIGITAL TO ANALOG, DIGITAL SIGNAL PROCESSOR, AND MOTION CONTROLLER BOARDS

MODEL	340	360	345/75/80	400	700	330/50/70
4MB	$1595	$1850	$1250	$1250	-	call
8MB	-	$3000	$1695	$1695	-	call
12MB	-	$4150	-	-	-	call
16MB	-	-	$2995	$2995	$3495	call
32MB	-	-	$5995	$5995	$6895	call

Quantity discounts available.

ComputerWORX

469 Elm Street • Biddeford, ME 04005

SALES: *1-800-639-2185*
1-207-284-0291

HOURS: Weekdays 9-9 ET
Saturday 10-6 ET

From a small mill town along the rocky vacation coast of Southern Maine... ComputerWORX manufactures quality computers using the highest quality components available. 1982-1992... Ten years of service. Prices subject to change. Shipping not included.

Circle 223 on Inquiry Card.

World Radio History

BUY HDI

PC MAGAZINE EDITORS' CHOICE June 27, 1989 Mass Storage Mail Order

A RECOGNIZED LEADER!

HARD DRIVES AND PERIPHERALS

NEW LOWER PRICES

WORRY-FREE 30 Day ONE YEAR REPLACEMENT GUARANTEE

FOR THE BEST PRICE, SERVICE & SUPPORT CALL:

800/998-8013

HDI SALES: 602/350-1128
FAX 602/350-1150

NATIONAL ACCOUNTS
Purchase Orders
800/998-8014
FAX 602/350-1180

International: 602/350-1144
FAX 602/350-1188

APO/FPO: 602/350-1145

Order Status: 800/729-4490

TOLL-FREE TECHNICAL SUPPORT

WE SHIP VIA FEDERAL EXPRESS

NEVER A SURCHARGE for VISA, MC or Discover!

Prices and availability subject to change without notice. All items NEW. PO's accepted from qualified buyers-Net 20. APO/FPO orders add $13 shipping. 30 Day Guarantee & 1-Year Replacement Policy may have some restrictions. Shipping is not refundable. All trademarks are the properties of their respective owners. 4.92

Hard Drives International
Insight Distribution Network, Inc.
1912 W. 4th St.
Tempe, AZ 85281

QUANTUM

52MB QULPS52A — IDE
17ms 3.5" 1"H
Bare Drive $209
16 Bit Kit $229

105MB QULPS105A — IDE
17ms 3.5" 1"H
Bare Drive $349
16 Bit Kit $369

210MB QUPRO210A — IDE
15ms 3.5" HH
Bare Drive $649
16 Bit Kit $669

MICROPOLIS

HIGH SPEED
HIGH CAPACITY

340MB MC1664 — ESDI
15ms 5.25" HH
Bare Drive $1099
16 Bit Kit $1199

660MB MC1568/1588 — ESDI SCSI
16ms 5.25" FH
Bare Drive $1499
16 Bit Kit $1699

1034MB HS MC1598 — SCSI
14ms 5.25" FH
Bare Drive $2199
16 Bit Kit $2299

1354MB HS MC1528 — SCSI
14ms 5.25" FH
Bare Drive $2699
16 Bit Kit $2799

Maxtor

80MB MX7080A — IDE
17ms 3.5" 1"H
Bare Drive $279
8 Bit Kit $309
16 Bit Kit $289

120MB MX7120A — IDE
15ms 3.5" 1"H
Bare Drive $389
8 Bit Kit $429
16 Bit Kit $399

210MB MX213A — IDE
15ms 3.5" HH
Bare Drive $599
8 Bit Kit $629
16 Bit Kit $629

340MB MX8380E/S — ESDI SCSI
14.5ms 5.25" FH
Bare Drive $1199
16 Bit Kit $1299

660MB MX8760E/S — ESDI SCSI
16ms 5.25" FH
Bare Drive $1599
16 Bit Kit $1699

Seagate

42MB ST351A — IDE
28ms 3.5" 1"H
Bare Drive $179
8 Bit Kit $209
16 Bit Kit $199

60MB ST277R-1 — IDE
28ms 5.25" HH
Bare Drive $249
8 Bit Kit $299
16 Bit Kit $319

89MB ST3096A — IDE
16ms 3.5" 1"H
Bare Drive $289
16 Bit Kit $299

130MB ST3144A — IDE
16ms 3.5" 1"H
Bare Drive $359
16 Bit Kit $379

IMPRIMIS

210MB ST1239A — IDE
15ms 3.5" HH
Bare Drive $599
16 Bit Kit $619

340MB ST4376N — SCSI
17.5ms 5.25" FH
Bare Drive $1199
16 Bit Kit $1349

660MB ST4766E — ESDI
15.5ms 5.25" FH
Bare Drive $1599
16 Bit Kit $1699

1 GIG!

1050MB ST41200N — SCSI
15ms 5.25" FH
Bare Drive $2099
16 Bit Kit $2249

CONNER

40MB CP3000 — IDE
25ms 3.5" 1"H
Bare Drive $189
8 Bit Kit $219
16 Bit Kit $199

120MB CP30104 — IDE
16ms 3.5" 1"H
Bare Drive $379
8 Bit Kit $419
16 Bit Kit $399

209MB CP3204 — IDE
16ms 3.5" HH
Bare Drive $609
16 Bit Kit $629

ALL BARE DRIVES INCLUDE
All mounting hardware, "Disk Manager" formatting/partitioning software (40MB+), and HDI's Hard Drive Reference Manual with complete installation instructions.

ALL KITS INCLUDE
16-Bit host adaptor hard/floppy "1 to 1" controller or interface card, mounting kit (3.5" kit inc. beige & black bezels), rails, cables, all mounting hardware, "Disk Manager" software (40MB+), and manual.

COMPLETE INSTRUCTIONS - EVERYTHING YOU NEED!

MEMORY

ADD 1MB RAM AS LOW AS $39

SIMM

1MB x9 80ns $49
1MB x8 80ns $39
Add $2 for SIP
MEMORY FOR EVERY SYSTEM!

TAPE BACKUP

Insight

120MB/250MB
Internal Unit $259
External Unit $399
Both Inc. one 80MB tape.
120MB Tape $29

With data compression. Standard QIC 80 attaches to existing floppy controller or dedicated host. 2 - 3MB/min. backup.

CD ROM DRIVES

600MB	Internal	External
INSIGHT	$299	N/A
SONY	$389	$509
CHINON	$399	$519
TOSHIBA	$599	$699

HARD DRIVES International

800/998-8013

PURCHASE ORDERS/NATIONAL ACCOUNTS 800/998-8014

Another Insight Company

HARD DRIVES International

HAB

World Radio History

Smooth Translation At A Scaled Down Price . . . And That's No Fish Tale!

With the LANCAST Twisted-Pair/Coax Translator, incompatibility in your network is a thing of the past.

This unique translation product bridges the gap between Coaxial based Ethernet LANS and the newer generation of IEEE 802.3 10Base-T Twisted-Pair LANS. By translating the signals between the two LAN media types, your network can operate smoothly and efficiently with no loss of network integrity or capability. What's more, we do it at a price that fits your budget.

Smooth translation at a scaled down price of $295.00, it's no wonder that many major computer firms are using the "twister" Translator. Call today for a free product brochure.

The "twister" Translator, Transceivers, Network Interface Cards, Repeaters, and other fine essential connectivity products are now available from LANCAST.

LANCAST
STANDARD HIERARCHICAL NETWORKS

10 Northern Blvd., Unit 5
Amherst, NH 03031
Tel: (800) 752-2768 • (603) 880-1833
Fax: (603) 881-9888

©1992 CASAT Technology Inc.

MADE IN USA.

NetCom-West, Booth 1104
DEXPO Spring, Booth 927
INTEROP Spring, Booth 1630

Circle 198 on Inquiry Card.

World Radio History

NEVADA COMPUTER

APRIL SPECIALS BELOW DEALER COST:

#1.) VGA 14" Monitor $229.00 #2.) Microsoft compatible mouse $19.00 #3.) 2MB memory board expandable to 4MB $99.00 #4.) Monochrome text only interface card $4.00

WORDSTAR 6.0

OR WORDSTAR 2000 REL. 3.5

This is not a misprint! These are the exact same ones selling for over $300.00 from our competitors. We have thousands in stock. These are current versions.

FOR SALE BELOW DISTRIBUTOR COST! LIST $495.00 ea.
(Get 100 pieces for $79.00 ea.)

YOUR CHOICE **99.00** EACH

PS/2 50/60 BOARD

AST ADVANTAGE/2

Comes with CLK expandable to 8Meg using SIMMS. SuperPak utility software.
OK - **49.00** 2MEG - **149.00** 4MEG - **249.00** 8MEG - **449.00**

FAX CARD W/ 2400 BAUD MODEM

Automatic group III digital FAX, background operation, send and receive text, screen images, scan pages,. Hayes compatible, modem built on. FAX 9600/7200/4800/2400. Software, telephone cord.

YOUR COST **99.00**

MODEMS W/MNP Level 5

Fully Hayes compatible, monitor speaker w/ volume control. 2400/300 Baud transmission rate, addressable COM 1,2,3,4, Compatible w/ IBM PC, XT, AT & Compatibles. 2year Warranty. Full Duplex operation, complete with software. Auto dial, Auto answer.

INTERNAL **49.00** EXTERNAL **79.00**

DATA CARTRIDGE TAPE

DC 2000 (40MB) **16.00** DC 300XLP (45MB) **17.00** DC 6150 **24.00**

MONITORS

12" GREEN MONOCHROME
Tilt & Swivel Base.....

14" MONO/TTL AMBER FLAT SCREEN	$99.00
14" VGA 640X480 (.41 Dot)	$247.00
14" VGA 1024X768 (.28 Dot)	$299.00
14" VGA 1024X768 (Non Interlaced)	$349.00
VGA CARD 256K Exp 1MEG	$79.00

PRINTERS & LASERS

Hewlett Packard		Panasonic	
LaserJet IIP Plus	795.00	1124I	275.00
LaserJet IIIP	995.00	1123	199.00
LaserJet III	1495.00	1695	359.00
IIID	2295.00	1624	338.00
IIISI	3495.00	1180I	148.00
Toner	89.00	1654	529.00
Pacific Data 25 in 1	249.00	4420	799.00

DUE TO OUR EXTREMELY LOW PRINTER PRICING, YOU MUST ADD 5% IF NOT PRE-PAID PLUS SHIPPING.

HAND SCANNER

400 DPI X 105MM,.La Palette software for scanning, drawing, editing, painting, and printing. FREE OCR INCLUDED!

YOUR COST $99.00

FLOPPY DRIVES

360K-5¼" **49.00**, 720-3½" **49.00**, 1.2 MEG - **58.00**, 1.44MEG-3½" **58.00**,
Tandon TM100-2, the original IBM Drive **99.00**

200 WATT POWER SUPPLY

Direct AT replacement, UL Appr., 110/220V, 4 Drive Connectors.
200 WATT **39.00** 150 WATT for XT **49.00**

INTEL COPROCESSOR

5 YEAR WARRANTY! Quantity Discounts

8088 BASED MACHINES:	80286 BASED MACHINES:	80386 BASED MACHINES:
8087-5 MHz, **54.00**	80287-6 6MHz **49.00**	80387-16 16MHz **149.00**
8087-2 8MHz **79.00**	80287-8 8MHz **59.00**	80387-20 20MHz **179.00**
8087-1 10MHz **119.00**	80287-10 10MHz **89.00**	80387-25 25MHz **189.00**
	80287-XL **99.00**	80387-33 33MHz **199.00**
		80387-SX16 **124.00**
		80387-SX20 **144.00**
		80487-SX20 **549.00**

CONTROLLERS

IDE HD/Floppy **39.00**, 16 Bit HD & FLOPPY 1:1 **39.00**, 8 Bit HD only **49.00**
FOR FLOPPYS: Super Floppy Controls 1:2, 360K, 720K & 1.44 Drives **49.00**

10 MEG HARD DRIVE

Half height - 80 MSEC - 6 Month Warranty List 149.00
Your Cost **69.00** w/ controller & cable add **$50.00**

20 MEG HARD DRIVE

3½" - 40MSEC - 6 MONTH WARRANTY. W/ 5¼" MOUNTS YOUR COST **99.00**
w/ controler & cable add **$50.00**

Connor, Maxtor, Seagate Hard Drives

PART#	SIZE	ACCESS TIME	INTERFACE	YOUR COST
Nev-20MB	21MB	65MSec	MFM	149.00
Nev-40MBI	44MB	28MSec	IDE	179.00
Nev-40MB	40MB	28MSec	MFM	229.00
Nev-80MBI	80MB	18MSec	IDE	299.00
Nev-80MB	80MB	28MSec	MFM	449.00
Nev-120MBI	120MB	18MSec	IDE	349.00
Nev-210MBI	200MB	18MSec	IDE	599.00
Nev-330MBI	330MB	18MSec	IDE	1,195.00

(All Hard Drives have a 1 Year Warranty)

60 MEG TAPE BACKUP

Mfg. by Wangtec, compatible w/ MS DOS, Novel, SCO Xenix, Pick. Complete w/ controller, cable and manual. **$399.00**

We also carry memory for HP, Epson, WYSE, Silicon Graphics, AT&T, Acer, ALR, Apple, AST, Everex, DEC, SUN, Dell

COMPAQ MEMORY

MODEL	MEMORY ADDED	COMPAQ EQUIV. PART#	YOUR COST
DESKPRO 286	512K KIT	113012-001	59.00
DESKPRO	1MB MODULE	118688-001	59.00
286N, 386N	2MB MODULE	118689-001	128.00
	OK BOARD	118700-001	98.00
386SX/20	4MB MODULE	118690-001	269.00
DESKPRO	1MB BOARD	108069-001	238.00
386/16	2MB BOARD	108069W71	348.00
	1MB KIT	108071-001	119.00
	4MB BOARD	108070-001	498.00
	4MB KIT	108072-001	269.00
DESKPRO	1MB BOARD	113633-001	139.00
386S	4MB BOARD	113634-001	299.00
	1MB MODULE	113646-001	79.00
	4MB MODULE	112534-001	229.00
DESKPRO	1MB MODULE	113131-001	59.00
386/20, 25, 286E	4MB MODULE	113132-001	199.00
DESKPRO	1MB BOARD	113644-001	129.00
386/20E/25E	4MB BOARD	113645-001	328.00
DESKPRO	2MB MODULE	115144-001	128.00
386/33, 486/25/33/33I	8MB MODULE	116561-001	639.00
SYSTEMPRO	32MB MODULE	116568-001	3950.00

PORTABLES

PORTABLE	512K KIT	107331-001	38.00
III	INTFC BD	107808-001	149.00
	EXP BD	107811-001	199.00
	2MB KIT	107332-001	119.00
SLT/286	1MB MODULE	110235-001	129.00
	4MB MODULE	110237-001	458.00
LTE/386S/20	1MB	121125-001	169.00
	4MB	121125-002	419.00
LTE/286	1MB BOARD	117081-001	89.00
	4MB BOARD	117081-003	398.00
PORTABLE	1MB KIT	107651-001	169.00
386/20	INTFC BD	107707-001	88.00
	4MB BOARD	107653-001	479.00
	4MB EXT BRD	107654-001	479.00
SLT/386	1MB MODULE	118303-001	129.00
	2MB MODULE	118304-001	219.00
	4MB MODULE	118305-001	469.00

TOSHIBA MEMORY

TOSHIBA MODEL	MEMORY ADDED	TOSHIBA EQUIV. PART #	YOUR COST
PORTABLE 2000SX	1MEG	PC14-PA8311U	119.00
T1000SE & XE/LE	2MEG	PC14-PA8312U	169.00
T2000/T2000SX	1MEG	PC18-PA8316U	119.00
	2MEG	PC18-PA8317U	179.00
T2000SX/T1000LE	4MEG	PC-PA8314U	329.00
	8MEG	PC14-PA8315U	619.00
T2000SXE/2200SX	2MEG	PC-PA2000U	179.00
	4MEG	PC-PA2001U	329.00
	8MEG	PC-PA2002U	659.00
T1200XE	2MEG	PC13-PA8306U	119.00
T1600	2MEG	PC8-PA8302U	119.00
T3100E	2MEG	1PC9-PA8340U	119.00
T3100SX	2MEG	PC15-PA8308U	119.00
	4MEG	PC15-PA8310U	195.00
T3200	3MEG	PC6-PA7137U	219.00
T3200SX	2MEG	PC12-PA8307U	119.00
	4MEG	PC12-PA8309U	195.00
T3200SXC	2MEG	PC19-PA8318U	129.00
	4MEG	PC19-PA8319U	249.00
PORTABLE T5100	2MEG	PC7-PA8301U	119.00
DESKTOP T8500 or	2MEG	PC10-PA8304U	119.00
PORTABLE T5200 & T5200C	8MEG	PC10-PA8313U	638.00

BOCA MEMORY BOARDS

8088 XT MACHINES - BOCARAM 8 Bit 0-2 MEG BOARD USES 256K D-RAM OK **99.00** 1 Meg **148.00** 2MEG **189.00**

80286 & 386 AT MACHINES - BOCA AT PLUS (BRAT 80) OK-8MEG BD. 4.0 LIM COMPATIBLE. CONVENTIONAL, EXPANDED & EXTENDED MEMORY. SUPPORTS DOS, OS/2, LIM/EMS & EEMS
OK-**99.00** 2MEG-**169.00** 4MEG-**249.00** 8MEG-**389.00**
BRAT 90 - SAME EXCEPT USES SIMMS **129.00**
BOCARAM/2 PLUS
FOR PS2 50, 60, 50Z, 65,70,80,90,95. 0-8MB LIM/EMS 4.0, USES 1MB SIMMS
2MB **219.00** 4MB **309.00** 8MB **489.00**

RAM CHIPS (DIPS)

DESCRIPTION	150NS	120NS	100NS	80NS	70NS
64X1	1.20	1.45	1.65		
64X4	1.95	2.25	2.45	2.95	
256X1	.95	1.05	1.10	1.15	1.95
256X4		3.95	4.45	4.95	5.45
1MEGX1		3.50	3.85	4.10	4.45
1MEGX4				25.00	
4MEGX1				34.00	

IBM PS/2 MEMORY

IBM PS/2 MODEL	MEMORY ADDED	IBM EQUIV. PART#	YOUR COST
PS/1	2MB	N/A	130.00
PS/2 25/286	512K KIT	30F5348	38.00
30 286, 50Z & 55 SX, 65SX	2MB KIT	30F5360	107.00
PS/2 L40SX & N33SX	2MEG	79F10999	138.00
	4MEG	79F11000	228.00
	8MEG	79F11001	448.00
PS/2 50Z & 55SX, 65SX	1MB SIMM	6450603	59.00
	2MB SIMM	6450604	89.00
55SX & 65SX	4MB MODULE	34F2933/87F9977	199.00
50, 50Z, 55SX 860, 65SX	2 8MB BOARD	1497259/6450609	349.00
PS/2	1MB SIMM	6450603	52.00
70 E61 061, 121, P70	2MB SIMM	6450604	89.00
PS/270 A21 A61, B21, B61	2MB SIMM	6450608	98.00
PS/280 041	1MB MODULE	6450375	98.00
PS/280 111, 121, 311, 321	2MB MODULE	6450379	138.00
80 A21 A31, A61	4MB MODULE	6451066	249.00
PS/2 35SX LS & 40SX	8MB	6450129	478.00
PS/2	2 8MB BOARD	6450605 OR	328.00
ALL 70s & 80s	2 1 4MB BOARD	34F3077 OR	358.00
	4 16MB BOARD	34F3011	488.00
90, 95 & P75	2MB	6450902	99.00
Install in pairs	4MB	6450128	298.00
PS/257SX, 90, 95, P-75	8MB	6450130	498.00

HEWLETT PACKARD LASER JET MEMORY

MODEL	MEMORY ADDED	H.P. EQUIV.PART#	YOUR COST
HPII & IID	2MB MODULE	33444B	107.00
	4MB MODULE	33445B	177.00
HP3 & IID	1MB MODULE	33474A/B	98.00
HPIIP	2MB MODULE	33475A/B	117.00
	4MB MODULE	N/A	187.00
HPIII SI	1MB MODULE	N/A	79.00
	4MB MODULE	N/A	239.00

SIMM MODULES

DESCRIPTION	120NS	100NS	80NS	70NS	60NS
256X8	5.00	8.00			
256X9	9.00	14.00	17.00	26.00	29.00
1MEG X 9		39.00	42.00	49.00	64.00
4MEG X 9			149.00	169.00	199.00

Quantity Discounts Available...CALL!!

ORDERS ONLY

800-654-7762

TECHNICAL/CUSTOMER SERVICE/ORDER STATUS:
(702) 294-0204 FAX (702) 294-1168
HOURS: M-F 8:00-6:00 PST, SAT 9:00-3:00 PST

Mfg. part #'s for convenience only Some memory products 3rd party
WE ACCEPT INTERNATIONAL ORDERS
WE ALSO PURCHASE EXCESS INVENTORY! FAX OR CALL.
NO SOFTWARE RETURNS
ALL PRICES FINAL.
Trademarks are registered with their respective Co's 386, 387, 287, SX, are trademarks of Intel Corp

NEVADA COMPUTER

TERMS:
NO SURCHARGE FOR MC/VISA
MC, VISA, AE, COD CASH, NET
Purchase orders from Universities Fortune 1000 & Government Agencies
Personal Checks, COD add $5.00
20% Restocking Fee on refunds within 30 days
No refunds or exchanges after 30 days - WARRANTY ONLY

AD # B-492

VISA MasterCard

PRICES SUBJECT TO CHANGE
SHIPPING UPS (Min $8.25)

684 Wells Road, Boulder City, Nevada 89005

Circle 199 on Inquiry Card.

World Radio History

CAD ONE Custom Built Computers

Signature Series

386/486 Mini Tower

386/486 Full Tower

Computers Built to your Specifications at Competetive Prices!! 12 Month Parts & Labor Warranty

CAD ONE 386sx-25

200 Watt Power Supply
AMI BIOS
VLSI Chipset
AMD Processor
Seven 16 Bit Slots
2MB 80ns SIMM Memory
(Expandable to 16MB)
TEAC 1.2 & 1.44 Floppy
Two serial, One parallel and
One game port
80MB Hard drive
Super VGA Card w/512k
KFC Super VGA monitor
(1024 x 768)
101 Full size keyboard
MS DOS 5.0

System Price $1495.00 *

CAD ONE 386-33

64K CACHE
200 Watt Power Supply
AMI BIOS
OPTI Chipset
INTEL Processor
Eight 16 Bit Slots
4MB 70ns SIMM Memory
(Expandable to 32MB)
TEAC 1.2 & 1.44 Floppy
Two serial, One papallel and
One game port
80MB Hard drive
Super VGA Card w/512k
(1024 x 768)
KFC Super VGA monitor
(1024 x 768)
101 Full size keyboard
MS DOS 5.0

System Price $1895.00 *

CAD ONE 486-33

256K CACHE
200 Watt Power Supply
AMI BIOS
ETEQ Chipset
INTEL Processor
Eight 16 Bit & One 32 Bit Slots
4MB 60ns SIMM Memory
(Expandable to 64MB)
TEAC 1.2 & 1.44 MB Floppy
Two serial, One parallel and
One game port
130MB Hard drive
Super VGA Card w/1MB
(1024 x 768)
KFC Super VGA monitor
(1024 x 768)
101 Full size keyboard
MS DOS 5.0

System Price $2395

OPTIONS FOR ABOVE SYSTEMS

IRWIN ACCUTRAK 250MB TAPE BACKUP W/SOFTWARE	$275.00
IDENTITY INTERNAL 2400 BAUD MODEM W/MNP-5 & SOFTWARE	129.00
CARDINAL INTERNAL TX/RX FAX MODEM W/AUTO DETECT	185.00
IDENTITY INTERNAL 9600 BAUD MODEM V.42 BIS & MNP-5	399.00
PANAMAX MAX4 4 OUTLET SURGE PROTECTOR	69.00

ORDERS 800-524-1006

* Prices and availability subject to change according to market conditions, and without notice!

Circle 218 on Inquiry Card.

World Radio History

CAD ONE Feature Products

MOTHERBOARDS

486-50 MHz	$CALL
486-33 MHz 256k Cache	CALL
486-25 MHz 128k Cache	CALL
386-40 MHz 64k Cache	CALL
368-33 MHz 64k Cache	CALL
386SX-25 MHz	249.00
386SX-16 MHz	215.00
286-16 MHz	125.00

I O CONTROLLERS

Multi I/O IDE HDD/FDD w/ 2S/1P/1G Port	$29.00
IDE HDD FDD Controller	18.00
AT I/O 2S/1P/1G port	18.00
Adaptec 1522 KIT	187.00
Adaptec 1542 KIT Bussmaster	290.00
MFM-AT Controller	77.00

COMMUNICATIONS

MODEMS

Identity Int. 2400 BAUD with software	$ 98.00
Identity Int. 2400 BAUD modem MNP-5 w/software	129.00
Identity Ext. 2400 BAUD with software	120.00
Identity Ext. 2400 BAUD modem MNP-5 w/software	165.00
Identity Int. 9600 BAUD with MNP-5, V.42 BIS	415.00
Identity Ext. 9600 BAUD with MNP-5, V.42 BIS	475.00

FAX MODEMS

Identity Int.TX/RX	$135.00
Adtec Int. TX/RX	135.00
Adtec Int. TX/RX with auto detect voice/fax	189.00
Cardinal Int. TX/RX with MNP-5	195.00
Identity 2400 BAUD POCKET modem MNP-5	189.00

VIDEO

Trident 8900C w/256k	$ 79.00
Trident 8900C w/512k	99.00
Trident 8900C w/1MB	129.00
Oak VGA w/256k	69.00
Oak S-VGA w/512k	89.00
Paradise w/256k	69.00
Paradise w/512k	89.00
Cardinal w/256k	112.00
Cardinal w/512k	149.00
Cardinal w/1MB	185.00
Enhanced-VGA 1280 x 1024 (XGA)	215.00
32k color w/software (ROM)	59.00
CEG Chip w/software	69.00

MONITORS

KFC

14" Super VGA .28 DP 1024 x 768	$334.00
14" Super VGA .39 DP 1024 x 768	285.00
14" Super VGA .28 DP Non-interlaced	370.00
14" Multisync .28 DP	380.00
17" Super VGA	CALL

IDENTITY

14" S-VGA .28 DP	$335.00
14" S-VGA .41 DP	280.00
14" VGA .31 DP	295.00
14" VGA .41 DP	249.00

AOC

14" Super VGA .28 DP	$348.00
14" VGA .31 DP	295.00
14" VGA Mono	135.00

PACKARD BELL

14" S-VGA .28 DP	$355.00
14" S-VGA .39 DP	275.00
14" VGA .39 DP	255.00

DATA TRANSFER

MANUAL DATA SWITCHES
AUTO-DATA SWITCHES
GENDER CHANGERS
NULL MODEM ADAPTORS
PRINT SPOOLERS
PRINT BUFFERS
INTERFACE CONVERTERS
LINE BOOSTERS

WE CARRY A COMPLETE LINE OF CABLES AND ACCESSORIES

Printer cable 6 Ft	$5.50
Printer cable 10 Ft	7.00
Printer cable 15 Ft	13.00
Printer cable 25 Ft	25.00
Printer cable 50 Ft	35.00

NETWORKING

16 Bit ARCNet card	$108.00
8 Bit ARCNet card	65.00
ARCNet 8 port active hub	173.00
ARCNet 4 port passive hub	10.00
16 Bit ETHERNet card	156.00
8 Bit ETHERNet card	138.00
C-NET ARCNet pocket adpt	210.00
C-NET ETHERNet pocket	275.00
3Com Ether Link II 3C503	CALL
3Com Ether Link + 3C505	CALL
3Com Ether Link 16 3C507	CALL

POWER BACKUP and SURGE PROTECTION

Leadman 550VA	$299.00
w/Novell interface	39.00
Leadman 1100VA	599.00
American Power Backup	CALL
Panamax MAX4 Surge	59.00
Panamax MAX6 Surge	69.00
Panamax SUPERMAX	109.00
QVS 6 outlet surge	20.00

STORAGE DEVICES

HARD DRIVES

SEAGATE
WESTERN DIGITAL
MAXTOR
(Call for price & product availability)

FLOPPY DRIVES

TAEC 1.2MB	$69.00
TEAC 1.44MB	69.00
TEAC 2.88MB	125.00
Toshiba 360	79.00
Toshiba 1.2MB	75.00
Toshiba 1.44MB	69.00

TAPE BACKUP

Irwin 120MB Accutrak	$210.00
Irwin 250MB Accutrak	275.00
Irwin 120 External Plus	365.00
Irwin 250 External Plus	445.00
Identity 120/250 Internal	255.00
Identity 120/250 External	375.00

PRINTERS

IBM/Lexmark 9-pin narrow	$CALL
IBM/Lexmark 9-pin wide	CALL
IBM/Lexmark 24-pin narrow	CALL
IBM/Lexmark 24–pin wide	CALL
IBM/Lexmark Laser 5 ppm	CALL
IBM/Lexmark Laser 6 ppm	CALL
IBM/Lexmark Laser 10 ppm	CALL
PANASONIC	CALL
STAR Micronics	CALL

MISC.

Media Vision Thunderboard	$154.00
Pro-Audio Spectrum	355.00
TRAX midi board	139.00
Navstar PC interface	CALL
DRAFIX Windows CAD	595.00
DRAFIX ULTRA 4.0	350.00
ULTRA 386 Upgrade	175.00
DRAFIX QwkStart	119.00

Additional CAD ONE products

PLOTTERS - DIGITIZING TABLETS - MICE - MEMORY PRODUCTS AND UPGRADES - BATTERIES KEYBOARDS - CASES - POWER SUPPLIES - CD ROM DRIVES - MULTIMEDIA BOARDS TOSHIBA COPIERS - FAX MACHINES - TERMINALS - MATH CO PROCESSORS

Prices and availability subject to change according to market conditions, and without notice!
Not responsible for typographical errors. All returns must be in orignal packaging.

Sales 800-524-1006 Fax orders 508-778-1887 Tech support 508-778-1990

CAD ONE COMPUTER DESIGN, Inc.
270 Communication Way #4D
Hyannis, MA 02601
Phone (508) 778-1895
Fax (508) 778-1887

We accept MASTERCARD, VISA No service charge. Sorry , no AMEX or C.O.D.
CHECKS and M.O. WELCOME
Products may be subject to a 20% restocking fee. No returns after 30 days

Business hours: Monday - Friday 9 A.M. to 8 P.M. Saturday 9 A.M. to 5 P.M. Eastern Standard Time

Circle 218 on Inquiry Card.

World Radio History

2 Gb
SCSI Portable DAT
$1499

APS Portable DAT provides these features:

Compact size and a light weight – based on Archive's Python 3.5-inch DAT mechanism, the unit measures 6 x 8 x 2.5 inches and weighs under 4 pounds.

Extremely high capacity – 2.0 Gigabytes on the 90-meter Maxell® DAT cartridge supplied with purchase.

High speed random access to any file on tape.

Uncorrectable error rate of less than 1 in 10^{15} bits.

Four Direct-Drive motors (4DD) eliminate belts and mechanical mode changes.

Toshiba
CD ROM

3301B	579

"Bare" Drive includes Drive, Data Cable, Rails & Extenders

- 8-bit SCSI kit (AIC) add $109
- 16-bit SCSI kit (Adaptec 1520) add $149
- 16-bit SCSI Bus Master kit (Adaptec 1540) add $229
- 16-bit MCA SCSI Kit (Adaptec 1640) add $329
- 32-bit EISA SCSI kit (Adaptec 1740) add $599
- 16-bit IDE Kit add $1
- Many Models available with Floppy Controller

• 30-Day Money-Back Guarantee •
All products carry a 30-day money-back guarantee. Your risk in the transaction is the cost of shipping.

• Disk-for-Disk Replacement Warranty •
Quantum, Maxtor, Syquest and Archive drives carry a two-year "parts & labor" disk-for-disk replacement warranty. WREN, Teac, WangDAT, Conner, Micronics products and Syquest Cartridges carry a one- year "parts & labor" disk-for-disk (board-for-board) replacement warranty.

• Mounting Hardware & Cables Included
• All Hard Drives include rails, extenders and data cables required for standard operation. Board products are populated but without RAM.

• Toll-Free Technical Support •
Toll-Free Technical Support, 9am to 7pm Monday thru Friday, Central Time. As often or for as long as you need.

• Prices & Specifications Subject to Change Without Notice •

Quantum

MB	SCSI	IDE
52	229	199
105	339	319
120	449	Call
240	699	Call

Ask about our full line of Macintosh SCSI hard drives.

Maxtor

MB	SCSI	IDE
120	359	349
213	579	559
340	999	889
535	1549	N\A
760	1649	N\A

Micronics

386SX	ISA 25	259
386DX	ISA 25	419
386DX	ISA/33/Cache	569
486DX	ISA/33/Cache	999
486DX	EISA/33/Cache	1549

SyQuest

MODEL	Bare
SQ-555	399
SQ-5110(88)	609
Dual(ext. 44)	899
Dual(ext. 88)	1449

1-800 235-3707

APS TECHNOLOGIES

2900 S. 291 Hwy
Independence, Mo
64057
(816) 478-8300

M-F 7am–9pm CST
Sat 10am–4pm CST

VISA MasterCard DISCOVER

Visa/MC, Discover No Surcharge AMEX Accepted

International: 1-816 478-8300 FAX: 1-816 478-4596 (24 HRS)
Toll Free UK: 0800-897-545 Toll Free Australia: 0014-800-125-875

World Radio History

From

ONE OF THE BEST SYSTEM MANUFACTURERS IN THE USA

ABTECH 386/25 Mhz w/VGA Color Monitor

$999 special

386DX/25 Mhz Motherboard
386/25 Mhz INTEL CPU
1 MB RAM on board (expandable)
1.2 (5.25") and 1.44 (3.5") MB FD
40 MB IDE HD
Super IDE-I/O Controller
Desktop case w/230 W. P/S
101 Enhanced Keyboard
VGA Color Monitor
VGA Display Card w/256K RAM

The sign of excellence in performance and quality

The assurance of quality conponents in each ABTECH system

The assurance of support and service

One year parts & labor warranty

Other Systems

486/33 Mhz	$1,299
386/33 Mhz	$ 899
386/25 Mhz	$ 799
386SX/20 Mhz	$ 699

STANDARD CONFIGURATION
- Motherboard
- AMI BIOS/ Intel CPU
- 4MB RAM
- 1.2 MB FD (5.25")
- 1.44 MB FD (3.5")
- IDE Ctrl. w/2serial,1 parallel,1 game
- Desktop Case w/200W P.S.
- 101 Enhanced Keyboard

Call for the latest pricing on Hard Drives, Monitors and accessories.

CUSTOM CONFIGURATION AVAILABLE ON ANY SYSTEM

Our elite clients includes:

Office of the US President
Veteran Administration
Jet Propulsion Labs
United Nations
Security Pacific Bank
US Government

General Telephone Co.
University of California, Florida, and Arkansas
NASA
AT&T. . .etc.

Major Institutions in Europe
So. America
Middle East
Eastern Europe
Southeast Asia

Reliable Protection and Convenience

On-Site Service Option

ABTECH FUTURA 433. . . . . .Comtemporary black styling

- 486/33 Mhz Motherboard
- 256K Cache
- 4 MB RAM on board exp. to 64MB
- 1.2 (5.25") and 1.44 (3.5") MB FD
- 120 MB FAST IDE HD
- IDE-I/O Controller
- Medium FUTURA Tower Case 230 W. P/S
- Enhanced FUTURA Keyboard
- SVGA Orchid ProDesigner II display card w/1 MB RAM
- 14" Black Multiscan 1024×768 PROTON® Monitor
- Microsoft compatible FUTURA Mouse
- Microsoft® DOS 5.0 & Windows 3.0
- Free Performer time management software

Black Monitor by ***PROTON***™
WORLD LEADING MANUFACTURER
OF HIGH QUALITY T.V. AND MONITORS

$2,295
Complete

Our trained technicians can provide solutions

TECH SUPPORT

ABTECH systems are designed & manufactured in the USA. . . to ensure reliability.

MADE IN USA

ABTECH 386SX/20 Notebook

Dual Battery (7 hrs.)◆2MB RAM ~ to 8MB◆40MB HD (60MB option)◆VGA LCD/64 gray scales◆Interchange modules ~Fax/modem, voicemail, scanner etc.. 386/25 & 386/33 available.

'91 Buyer's Guide

Byte Outlook 92
Computer Buying World
Computer Shopper

International resellers welcomed

818.575.0007

24 HOURS FAX 818.575.1500

ABTECH INCORPORATED

1431 N. Potrero Ave. Unit B.
S. El Monte, CA 91733
USA

©1991 ABTECH Inc. The brands or names mentioned are trademarks of their repective companies. ABTECH and its logo is a trademark of ABTECH Inc. Shipping, handling and applicable taxes are excluded in prices. Prices are subject to change. The usage of credit cards are subject to surcharge. 30 days money back guarantee.

Circle 176 on Inquiry Card (RESELLERS: 177).

World Radio History

CONTROL UP TO 96 PC FILE SERVERS WITH 1 KEYBOARD AND MONITOR USING...

COMMANDER

by cybex



- No external power
- "One-Touch" selection
- Mix PC, PC/XT, PC/AT and PS/2
- "AutoBoot" Feature boots attached computers without operator intervention after power failure
- Shows PC power status
- Mouse support available

- TTL (MDA, CGA, EGA) up to 600 feet away
- VGA up to 400 feet
- Each unit accommodates from 2 to 8 PCs
- Up to 12 units can be cascaded
- Mounting kit available for 19" rack installation



PC, PC/XT, PC/AT and PS/2 are trademarks of International Business Machines Corp.

Dealer Program Available

Cybex Corporation
2800 H Bob Wallace Ave.
Huntsville, Alabama 35805
(205) 534-0011
Fax (205) 534-0010

See us at
COMDEX/Spring '92
Booth #N141

Circle 188 on Inquiry Card.

World Radio History

Call Our Computer Hotline

ACP-The Superstore that sells Direct

ALL USA ORDER 1-800-FONE-ACP

Hard Drives

Western Digital

High performance "Caviar" series with 1" height, Cache Flow™ and 32K buffer.

AC280	80Mb	1" 3.5" 14ms	IDE	299
AC2120	125Mb	1" 3.5" 14ms	IDE	375
AC2200	200Mb	1" 3.5" 14ms	IDE	589

Maxtor

7080A	80Mb	1" 3.5" 15ms	IDE	279
7120A	120Mb	1" 3.5" 15ms	IDE	388
LXT213A	213Mb	1" 3.5" 15ms	IDE	599
MX1240	1.2Gb	1" 3.5" 15ms	IDE	1995

Panther 1.2Gb$1995 Panther 1.7Gb 2595

Conner Peripherals

30104	120Mb	3.5" 19ms	IDE	389
3204	200Mb	3.5" 16ms	IDE	589

Call for Quantum, Micropolis, Seagate. Also controllers from Ultrastor, Always, WD etc.

Hard Drive Cards

Plus Development

Hard Card IIXL	50Mb	16bit	9ms	298
Hard Card IIXL	105Mb	16bit	9ms	448

Backups

Summit

FREE! Central Point BACKUP Software

SE120	120Mb	Tape Drive	internal	239
SE250	250Mb	Tape Drive	internal	349

Colorado

DJ10	120Mb	Tape Drive	internal	235
DJ20	250Mb	Tape Drive	internal	315
QFA700	700Mb	Tape Drive	internal	779

Syquest

44Mb	Removable	5.25" Drive	Int.	308
88Mb	Removable	5.25" Drive	Int.	469

Dual drive case with power supply 169

Floppy Disk Drives

Toshiba

ND04DG	360K	5.25" HH	PC/XT	59
ND08DEG	1.2Mb	5.25" HH	PC/AT	72
ND3561GR	1.44Mb	3.5" HH	w/AT Kit	72

ACP

360K	5.25"HH	55	1.2Mb	5.25"HH 66
720K	3.5" HH	59	1.44Mb	3.5" HH 67

2.88Mb3.5"HH Call Call for 5.25" Mtg. Kit

Pacific Rim

1.2Mb External for any parallel port 235

1.44Mb External for any parallel port 235

MultiMedia

Sony

PC Magazine Editors' Choice

7205 CD Laser Library w/six CD's 549

Brown-Wagh • Creative Labs

Complete all-in-one MPC compatible upgrade kit includes Panasonic CD Drive, Sound Blaster Pro, five CD's, Microsoft Multimedia Windows, Bookshelf, Hyperglide, Games, drivers, cables, connectors and more.

MultiMedia Kit internal/external 649/799

Sound Blaster Pro 239

MediaVision

Complete MPC upgrade kit with CD Drive

PC MultiMedia Kit int/ext 849/1049

Pro Audio Spectrum Card 299

Input Devices

ACP 3-button Mouse (limited supply) 14.95

CH Products Flightstick 49

Mouseman Combo/Cordless 75/88

Logitech Trackman serial/bus 69/72

Logitech Trackman Portable 104

Logitech Fotoman 599

Microspeed PC-Trac ser/bus 79/89

LOGITECH

188.

Logitech ScanMan 32 w/Catchword

This combo gives you the power to scan and use images and text in any application. Eliminate time wasting re-keying, cutting and pasting text. Get high quality image output with GrayTouch Image Editing software. Scanman 32 plus Catchword $188

Chips and SIMM's

RAM Chips

41256-100	256K RAM	100ns	DIP	1.99
41256-80	256K RAM	80ns	DIP	2.19
414256-80	256Kx4 RAM	80ns	DIP	7.95
1Mb-100	1Mb RAM	100ns	DIP	5.49
1Mb-80	1Mb RAM	80ns	DIP	5.99

Over 20,000,000 IC's in-stock including 7400, LS, ALS, CMOS, Linear all types!

Plus Sockets, Crystals, Connectors and more

SIMM Modules

421000A9B-10	1Mbx9	100ns	SIMM	49.95
421000A9B-80	1Mbx9	80ns	SIMM	54.95
421000A9B-60	1Mbx9	60ns	SIMM	59.95
424000A9B-80	4Mbx9	80ns	SIMM	169
424000A9B-60	4Mbx9	60ns	SIMM	189
41256A9B-80	256Kx9	80ns	SIMM	19.95
41256A9B-60	256Kx9	60ns	SIMM	24.95

Math Coprocessors

AMD

Advanced Micro Devices

Increase the performance of your 286 powered PC/AT

80C287-10 Coprocessor 10MHz 49.95

Intel

8087	5MHz 79	80387DXP 16/33	199
8087-2	8MHz 89	80387SX-16	128
8087-1	10MHz 89	80387SX-20	144
80287XL all 286	89	80487SX-20	499

Cyrix

83D87-16	16MHz 169	83D87-40 40MHz	239
83D87-2020	MHz 175	83S87-SX16	114
83D87-2525	MHz 175	83S87-SX20	129
83D87-3333	MHz 189	83S87-SX25	149

IIT

2C87-8	8MHz 79	2C87-12 12MHz	85
2C87-10	10MHz 85	2C87-20 20MHz	99

Memory Upgrades

Laser Printer Upgrades

HP IIP/IIP+/III/IIID/IIIP	2Mb	124
Okidata OL400	2Mb	148
Okidata OL800/820	2Mb	148
Panasonic 4420/4450I	2Mb	148

Call for other models plus we stock most Laser memory upgrades with 0K RAM

Laptop Upgrades

Apple Powerbook	2Mb	127
AST Executive	1Mb	78
Compaq LTE386s/20	1Mb	178
Everex Tempo/LX/16	2Mb	147
IBM L40SX	2Mb	127
Toshiba T1000SE/LE/XE/2000	2Mb	228
Toshiba T2000SXe	2Mb	228
Toshiba T3300SL/4400SX	2Mb	Call

Call for Zenith, Sharp, TI, and more

Palmtop Upgrades

HP 95LX 2Mb 227 Poquet 1Mb 327

Computer Upgrades

AST Premium 386/25,33,SX16/20	1Mb	68
Compaq DP386/33,486/33,SysPro	2Mb	128
IBM 30-286	#30F5360 2Mb	108
IBM 35,40,55sx,65,70	#6450604 2Mb	118
IBM 90,95,P75	#6450902 2Mb	118

Call for NEC, HP, Zenith, Leading Edge.

Mylex 486

Unleash EISA Power with the Mylex 486-33 Motherboard. Expandable to 32 Mbytes of DRAM. Includes 128k cache 8 EISA slots. Motherboard used in 6-time PC winners of PC Magazine "Editors' Choice"

486MAE-33 $1699

Motherboards

ACP 286-12 half-size board w/0K	89
ACP 386SX-20/25 w/0K	269/299
ACP 386DX-33 64K cache w/0K	449
ACP 386DX-40 64K cache w/0K	499
ACP 486DX-33 256K cache w/0K	899
Orchid 386/40 128K cache w/0K	599

Processor Upgrades

Kingston

SX/Now 20MHz SX upgrade module 379

SX/Now 25MHz SX upgrade module 499

Specify for IBM PS/2 or AT, AST, HP ES286/12

Leading Edge Computers

These Leading Edge Systems include...

- Mouse • 2 Floppy Drives • Enhanced 101 Keyboard
- Quantum Hard Drives • MicroSoft Windows, DOS 5.0 & Works

PLUS your choice 20 months Warranty or 6 months On-Site Service!

COMPUTER	SX-16 PLUS	SX PLUS 20	Minitower 33	486 SX-20
Model #	D3SP2051B	D3S2P2051B	D3MT2101B	D4S2101B
MRP$	1399.00	1599.00	2599.00	2899.00
CPU	80386-SX16	80386SX-20	80386-33	80486SX-20*
Hard Drive	52 Mb	52 Mb	105 Mb	105 MB
RAM	2 MB	2 MB	2 MB	2 MB
Max RAM	16 Mb	16 Mb	64 Mb	64 Mb
Cache RAM	.....	.....	16 Kb	64 Kb
Exp. Slots	4	4	6	8
VIDEO	800x600/256k	800x600/256k	ATI Wonder	ATI Wonder
I/O	2ser/1par/m/k	2ser/1parm/k	2ser/1par/m/k	2ser/1par/m/k
ACP Price	959.	1099.	1899.	1999.

LEADING EDGE®

*486SX supports CPU card upgrades



Note: 2400 Baud Modem with SXPlus20 & 486SX20. FAX/Modem with MiniTower33

386sx-20 MHz Notebook

- 2 Mb RAM exp to 5 Mb
- 60 or 80 Mb Hard Drive
- 1 ser, 1 par, 1 kb, VGA 4.9lbs.
- FREE! DOS 5.0, Windows 3.0, Thumbelina Mouse, Microsoft Works

60 Mb...1799. 80 Mb...1999.

Leading Edge Monitors

CMON.42	CMON.31	CMON.28ADE
640X480 (.42)	640X480 (.31)	1024X768 (.28)
249.*	259.	349.

* 199. with purchase of SX-16 PLUS

Call for price/details on NEW DeskPak Kit with VGA, stand & keyboard for your Notebook.

Expansion Boards

Orchid Technology

RamQuest 16/32 w/0K	228
RamQuest 8/16 w/0K	148

AST Research

SixPak 286 w/0K	108
Cupid 32 w/0K	249

Boca Research

BocaRAM AT Plus w/0K (uses SIMM's)	119
BocaRAM AT Plus I/O w/0K	149

Intel

Above Board 2 Plus w/2Mb	489
Above Board Plus 8 w/2Mb	489

ACP

IDE interface with I/O	59.95
(4)Floppy(2.88Mb) w/IDE adapter	79.95
IDE interface with BIOS ROM	65
Serial interface card	39.95
Serial, parallel, game interface	49.95
2Mb EEMS AT memory board w/0K	99.95

ALL NEW!



Everex

The all new Tempo™ Carrier™ Notebook weighs in at only 5.2lbs. 20MHz i386SX powered with 2Mb RAM and 40 or 80Mb hard drive. New "KeyMouse" integrated pointing device. Plus FREE! Microsoft Windows 3.0, MS-DOS 5.0, Mouse and Carrying Case. Call for ACP Price!

159.

US Robotics

329.

Sportster

the most popular 2400bps modem perfect for all PC communications. Includes special introductory offers for Compuserve© or Prodigy© on-line services.

Sportster/2400 external $159

WorldPort

pocket-size lightweight battery-powered features up to 9600bps throughput and Group III FAX V.42/MNP modem communications.

WorldPort/24 96i/FAX DATA $329

Video Graphics Cards

ATI

Graphics Ultra w/512K & Mouse	549
Graphics Vantage w/512K & Mouse	389
VGA Stereo F/X XL w/1Mb	369
VGA Wonder XL w/1Mb & Mouse	238

Orchid Technology

ProDesigner IIs w/1Mb and RAMDAC	248
Fahrenheit 1280 w/1Mb	365

United Solutions

mage 800 8/16bit 256K 800x600	69
mage 1024 w/512K 1024x768	89
mage Ultra w/1Mb 1024 256 colors	139
image HiColor w/1Mb 1280x1024	159

FAX Boards

Intel

SatisFAXtion Card	389
SatisFAXtion Hand Scanner option	339

Frecom

1-Liner Fax/Modem	169
1-Liner Fax/Modem for Windows	229
FAX96/Modem for Windows	169

Diskettes

Fuji

ACP stocks complete Fuji Diskette line. All with Lifetime guarantee. Box (10) Call for color

5.25"	HD Disks 8.95	DS/DD Disks	4.95
3.5"	HD Disks 14.89	DS Disks	7.99

CITIZEN

Citizen 24-pin Printer

Our hottest selling 24-pin Dot Matrix! 80 column 220cps draft, 72cps letter mode, LCD display and controls, push/pull tractor w/bottom feeder.

GSX140 Printer Call

Color kit optional

ACP April Special Buys

Subject to prior sale

IBM OS/2 Extended v.1.2 (3.5")	99
IBM OS/2 Local Area Network Server version 1.2 (3.5")	75
IBM DisplayWrite 4/2, OS/2 (5.25")	99
1992 IC Master (3 volume set)	149

Call for your copy of our quarterly tabloid "ACP Computer Hotline"

ACP Tech Support Hotline

Fast, Expert advice on Software and Hardware

1-900-680-4832

1st minute FREE, then $2 per minute

Call ACP BBS

1-714-953-9465

Check out our latest special buys!

Advanced Computer Products, Inc.

since 1976

1310 E. Edinger, Santa Ana, CA 92705 • FAX 714-558-1603 • Customer Service 714-558-1356 • Sales 714-558-8813

We accept MC/VISA/AMEX, no surcharges. Your card not charged until we ship. 100% guarantee, defective software replaced immediately, defective hardware repaired or replaced at our discretion. Items subject to change without notice. FedEx shipping available for only $6.95 plus normal ground charges up to 15lbs.

MMC MICRO MARKETING CORP.

Circle 179 on Inquiry Card (RESELLERS: 180).

World Radio History

Save BIG on Computer Products

NO EXTRA CHARGE for credit cards

DRIVES AND BACKUPS

Conner Hard Drives

3000	42MB	3.5" IDE 28ms	$199
3204	209MB	3.5" IDE 19ms	599

Seagate Hard Drives

ST351AX	40MB	IDE 3.5"	199
ST225 KIT	20MB	w/Cont. XT	239
ST238 RLL	30MB	RLL XT w/Cont.	239
ST251-1	40MB	28ms 1/2 HT	249
ST4096	80MB	28ms	489

Micropolis

1355	159MB	ESDI FH 23ms	469
1664	345MB	ESDI FH 18ms	999

Plus Development Hard Drive Cards

Hard Card IIXL 50MB	CALL
Hard Card IIXL 105MB	CALL

Mountain Internal Tape Backups

40/120MB AT	249
80/304MB AT	499

Archive Tape Back-up

40MB Internal XT or AT	249
80MB Internal AT	325

Irwin Tape Back-Up

Accutrak 120MB Internal Drive	179
Accutrak+ 120MB External Drive	309
Accutrak+ 120MB Internal Drive	239
Accutrak+ 250MB Internal Drive	299

Sony CD-ROM

7205 Ext XT/AT w/Laser Library	569

Includes Compton's Family Encyclopedia, Languages of the World, Toolwarks, World Atlas and more.

FLOPPY DRIVES

Toshiba Disk Drive Kits

ND 04D 5.25" 1/2 HT 360K (PC/XT)	$59
ND 08DEG 5.25" 1.2MB (PC/AT)	69
ND 356T 3.5" 1.44MB AT Kit	69

Sony Disk Drives

3.5" 720K (PC/XT/AT)	59
3.5" 1.44MB Slimline Bare	59
3.5" 1.44MB	59

MONITORS

Ponasonic 14" Color 1024 x 768

C1381i (28mm)	$349

Packard Bell 14" Color

8551VG VGA 640 x 480 (.51mm)	199
8539VG VGA 640 x 480 (.39mm)	249
8511SV EVGA 1024 x 768 (28mm)	299
8548SVGL EVGA 1024 x 768 (28mm)	379

Packard Bell Multisync Color (31mm)

8517 SVG 17" 1280 x 1024	999
8520 SVG 20" 1280 x 1024	1499

NEC Multisync Color

2A 14" 800 x 600	399
3FGX 15" 1024 x 768	639
4FG 15" 1024 x 768	775
4DS 16" 1024 x 768	999
5FG 17" 1280 x 1024	1399
5D 20" 1280 x 1024	1899

Sony 14" Color

1304HG 1024 x 768 Multiscan	CALL
1320 640 x 480 VGA	CALL

JOYSTICKS

Etronics Super Shooter Jaystick	$10.99
Etronics Watta Shootah Jaystick	10.99
Gravis Analog Jaystick	31.99

MICE

Etronics Smartee Mouse	$25.00
IMSI Serial/Bus Mouse	39.99
IMSI Pet Mouse	19.99
Logitech Mauseman Cambo	69.99
Logitech First Mouse Serial	39.99
Logitech Trackman Serial	69.99
Logitech Portable Trakman	99.00
Microsaft Ballpoint for Laptops	119.99
Microsaft Serial Mouse w/Wind.	149.99
Microsaft Mouse Serial/Bus	79.99
Mouse System Omnimouse II w/Paint Bus/Ser.	49.99/35.99

DIGITIZERS

Summagraphics Summasketch II	$299.99
Summagraphics Summasketch Professional 18 X 12	599.00
Kurta 12 x 12 XLP Digitizer	249.99
Kurta IS/One 12 x 12 corded or cordless	359.99

SCANNERS

Logitech Scanman 256	$279.99
MouseSystems HandScan w/OCR	149.99
Panasonic Flatbed I,II, and III	CALL
Epson Desktop Color Scanner	1099.00

PACKARD BELL COMPUTERS

Monitor not included

THESE PACKARD BELL SYSTEMS INCLUDE:
• 2 Floppy Drives • Enhanced 101 Keyboard • 2-Button Mouse
• Tutorial • DOS 5.0 • QBasic

PACKARD BELL
America grew up listening to us. It still does.
Not affiliated with any former Bell System entity

1 YEAR ON-SITE WARRANTY

FORCE	$16X	$20X	$20XH	486SX
Processor	80386SX-16	80386SX-20	80386SX-20	80486SX-20
Hard Drive	85MB	100MB	130MB	105MB
Stand. RAM	2MB		4MB	4MB (8K Cache)
Max RAM	5MB		16MB	32MB (128K Cache)
Expansion Slots	3 16-BIT			4 16-BIT
Video Support	800 X 600 (256K) Memory			1024 X 768 (512K)
I/O Ports	1S, 1P, 1M, 1G, 1VGA, 1KB		1S, 1P, 1M, 1G, 1VGA, 1KB	2S, 1P, 1M, 1VGA, 1KB
ELEK-TEK Price	$899	$1099	$1299	$1699

2400B Internal Modem with S20X, S20XH & 486SX. **Windows** with S20X, S20XH & 486SX

Packard Bell 14" Color Monitors

8551VG	8539VG	8511SV
640x480 (.51mm)	640x480 (.39mm)	1024x768 (.28mm)
$199	$245	$299

PB Monitors Warranty 1 yr on-site when purch w/a PB Force system (limit 1 per system) Purch separately carry in or mail-in 1 yr warranty

386SX-20MHz NOTEBOOK COMPUTER

• 80C386SX/20MHz • 2MB RAM exp.8MB • 2400B Int. Modem with send/fax
• 40MB Hard Drive • 3.5" 1.44MB FDD
• Free Carrying Case • 640 x 480 VGA • 1 yr. depot warranty

$1799

MATH COPROCESSORS

Intel Math CoProcessors

8087	(5MHz)	$85
80872	(6/8 MHz)	119
80871	(10MHz)	159
80287XL	(6,8,10MHz) and 80C287 (12MHz)	79.99
80287XLT Campaq LTE/286, and Tandy 2800		79.99
80387SX-25	(SL-25MHz)	145
80387SX	(16MHz)	119.99
80387SX	(20MHz)	129.99
80387	(16, 20, 25, 33MHz)	199
80487SX	(20/25MHz)	459

Cyrix Moth CoProcessors

82S87	(8-20MHz 80286)	75
83D87-16	(16MHz 80386)	155
83D87-20	(20MHz 80386)	155
83D87-25	(25MHz 80386)	155
83D87-33	(33MHz 80386)	165
83D87-40	(40MHz 80386)	199
83S87-16	(16MHz 80386SX)	95
83S87-20	(20MHz 80386SX)	109
33S87-25	(25MHz 80386SX)	119

CHIPS AND SIMMS

256K (all speeds)	CALL
1MB (all speeds)	CALL
Simms Modules (all speeds)	CALL
Sipps (all Speeds)	CALL

ACCELERATOR/UPGRADE BOARDS

Sota

286i/386i Acceleratar	$175/249
Express 386SX 16MHz Upgrade	259
Express 386SX 20MHz Upgrade	279
Express 386SX 25MHz Upgrade	325
I/O - II Drive Controller	89

MEMORY UPGRADES FOR IBM

Legend IBM™ Compatible PS/2 Memory Upgrades

529802	2MB 30-286	$125
529828	2MB 70-E61, 70-121	129
529836	2MB 70-A21	129
551029	2MB Exp. Bd 50Z, 60, 55SX	299

Legend Memory available for Toshiba Laptops, AST, HP, Mac & Others. CALL

BOARDS

Intel Aboveboard

Above Board Plus w/512K/2MB	$249/349
Above Board MC for PS/2	249

Boca Boards

Boca I/O 2 Ser., 1Par.	45
Boca I/O MCA 2 Ser., 1 Par.	99
Boca AT Plus 0K/2MB	109/209
Boca VGA Basic 640 x 480	59
Boca VGA Basic 800 x 600	65
Boca VGA Plus 1024 x 768 512K	79
Boca Super VGA 1024 x 768	119
Boca Super VGA 1024 x 768 high resolution color	129

NETWORKING PRODUCTS

NE1000 8-bit Ethernet	$134.99
NE2000 16-bit Ethernet	169.99
3COM 3C503 EtherlinkII PC/XT/AT	159.99
SMC Arcnet PC-130 8-bit board	99.00
SMC Arcnet PC-130E 8-bit board	119.99
Lantastic 10MBPS Starter Kit	499.00
Lantastic 10MBPS Ethernet Adpt.	219.99
Navell Netware Lite	69.00
Navell Netware Starter Kit	375.00
SMC Arcnet PC 500WS 16-bit bd.	129.99
SMC Arcnet PC 500FS 16-bit bd.	209.99
Xircam Adapters	CALL

TRONICS MODEMS

▲ 100% Hayes Compatible
▲ 2 Year Warranty

2400 Baud Internal w/software	$49
2400 Baud Internal w/V.42 & software	95
2400 Baud External no software	69
2400 Baud External w/V.42 no software	119
NEW 9600 Baud Internal w/V.42 & software	259
NEW 9600 Baud External w/V.42 no software	369

DISKETTES

	ELEK-TEK	maxell.	SONY	3M	Verbatim
3 1/2" DSDD	6.50	7.99	7.50	7.99	7.50
3 1/2" DSHD	12.99	14.99	13.50	14.99	13.50
5 1/4" DSDD	3.99	5.50	4.99	5.99	5.50
5 1/4" DSHD (IBM AT)	7.50	9.99	9.99	9.99	8.99

In addition to the above, we stock preformatted & color diskettes.

3M DATA CARTRIDGES

Regular

DC100A(Mini)	$14.99
DC300XL/P	20.00
DC600A	21.00
DC6150	22.00
DC6250	26.99
DC6320	29.00
DC6525	34.00

DC1000(Mini)	14.50
DC2000(Mini)	14.99
DC2080 (Mini)	19.50
DC2120 (Mini)	20.99
DC1 35G Magnus 2000 Tape Drive Cleaner	36.99 / 19.99

Pre-formatted

DC600 HC/Iotamat™	$25.50
DC6150/Zetamat™	28.00
DC2000/Kappamat™	19.00
DC2000/Thetamat™	19.00
DC2080/Rhomat™	20.99
DC2120/Rhomat™	25.50
DC2120/Ximat™	25.50

Call for Large Quantity Pricing. Call for Wholesale Pricing on 3M Computer Tape.

SOFTWARE

386 Max	$64.99	Money V8.0	99.99
AfterDark for Windows	26.99	MS Excel V3.0 for Windows	299.99
All Type	45.99	ProCam Plus	65.99
Carbon Copy Plus	119.99	Publisher's Power Pak for WordPerfect	45.99
DR DOS	69.99	QEMM 386 V6 w/Manifest	58.99
The Farside Computer Calendar for DOS	49.99	Quicken V5.0	39.99
Fastback Plus V3.0	119.99	Quicken for Windows	28.99
Farmtool Gald V3.0	57.99	Stacker V2.0	84.99
Harvard Graphics Windows	339.99	Tabias Taxcut	39.99
Laplink Pro	89.99	WordPerfect V5.1	235.99
LetterPerfect	129.99	WordPerfect for Windows	279.99
Managing Your		XTREE Gold	93.99

We Stock 2500 Other Software Titles

"Complete Line Of EPSON Panasonic & OKIDATA Dot Matrix & Laser Printers Call For Our Low, Low Prices"

Genuine HEWLETT PACKARD Laser Toner Cartridges

HP92275 - LaserJet IIP/IIP+/IIIP	$59.99
HP92285 - LJ/LJ+/LJ 500+	81.99*
HP92295 - LaserJet II/IID/III/IIID	79.99*
HP92291 - LaserJet IIISi	107.99*

* Quantity Discounts Available

Trays

Lower Cassette IIP/IIP+/IIIP	135
Letter** / Legal Size** IIP/IIP+/IIIP	49 / 59
Envelope Tray ** IIP/IIP+/IIIP	65
Letter / Legal Size II/IID/III/IIID	52 / 60
Envelope Tray II/IID/III/IIID	70
Letter Size IIISi / Legal Size IIISi	95 / 95
Executive Size IIISi	95

** Requires Lower Cassette

Memory Boards

1MB Memory LJ IIP/IIP+/IIIP/III/IIID	149.00
2MB Memory LJ IIP/IIP+/IIIP/III/IIID	249.00
1MB Memory LaserJet IIISi	115.00
256K DeskJet Plus/DeskJet 500	129.00
DeskJet/DeskJet Plus Ink Cartridges	14.50
DeskJet High Capacity Cartridge	23.99

HP LASERJET ENHANCEMENTS

PACIFIC

25-IN-1 Font Cart. II/IIP/IIP+/IIIP/IIICALL	
25-IN-1 Font Cart DeskJet 500/Plus	99
1MB Memory Board IIP/IIP+/III/IIID	99
2MB Memory Board IIP/IIP+/III/IIID	149
Postscript Cart. for IIP/IIP+/IID/III/IIID	349

MODEMS AND FAX BOARDS

Internal

Hayes

2400 Baud with Software	$239
9600 Baud V.42 w/Software	499

Internal Hayes Compatibles (with software)

Practical Peripherals

2400 / 2400 V.42	75 / 169
2400 IBM PS/2	199
9600 V.42	269

External

Hayes (no software incl.)

2400 Baud	279
2400 Baud Packet Edition	119
9600 Baud V.42/V.42 Ultra	499/649
Hayes Optima 2400/9600B Ext.	CALL

External Hayes Compatibles

Practical Peripherals

2400SA / 2400SA V.42	169 / 199
9600SA V.42	299
2400 Pocket Modem	99
2400V.42 Pocket Modem w/send fax	159

Other Hayes Compatibles

Intel 9600 Baud with Software	440
Intel 9600 V.32bis with Software	499
All U.S. Robotics High Speed Models	CALL

Fax Boards

Frecam Fax 96 Board	99
Frecam Fax / Modem	119
Intel SatisFAXtion Fax Board	CALL
Practical Peripherals External 2400 Baud Fax/Modem w/9600 send/receive fax	109
Practical Peripherals Internal 2400 Baud Fax/Modem w/9600 send/receive fax	99
Etronics NEW External 2400 Baud Fax/Modem w/9600 send/receive fax	99
Etronics Internal 2400 Baud Fax Modem w/9600 send/receive fax	85

Write for FREE catalog.

CORPORATE CUSTOMERS INVITED

We offer large bid oppartunities. DUNS # 09-718-0517

OPEN ACCOUNTS Net 30 terms available to D&B accounts rated 2A1 or better, actual freight charges FOB Skokie IL Phone (as above) fax orders to Corporate Accounts 708 677-7168, mail P O 's (as above) to Dept C1132

PREPAID ACCOUNTS Use Visa, MasterCard, check, money order (no cash or c o d s please) When ordering by mail please call in advance for shipping and handling charges Shipments to IL add 7 75% tax Minimum order $15 00

4/92

ET VALUELINE
WHERE MORE THAN JUST THE PRICE IS RIGHT

7350 North Linder Avenue, Skokie, Illinois 60077

800-395-1000 In IL: 708-677-7660

ET Valueline is the telemarketing and mail order department of Elek-Tek, inc.

Prices subject to change; products subject to availability while quantities last. ELEK-TEK is not responsible for printing or typesetting errors.

RETURN POLICY - All sales are final except defectives which will be replaced with identical merchandise only Computers and large peripherals 3 work days after delivery, most small items, 30 calender days, after which manufacturer s warranty applies No returns will be accepted without an RMA number Unauthorized returns and refused shipments subject to 15% restocking charge ALL ELEK TEK MERCHANDISE IS BRAND NEW, FIRST QUALITY AND COMPLETE In no event will ELEK TEK be liable for any damages whether incidental, consequential or otherwise Except as stated herein, no warranties (including fitness for a particular purpose or merchantability) shall apply This does not reduce the benefit of any manufacturer s warranty

BY0421L

Circle 191 on Inquiry Card.

World Radio History

PC DIAGNOSTICS MADE EASY

SPEED TEST YOUR PC

You've seen the *Landmark Speed Rating* advertised by many major PC manufacturers, now you can have your own copy of the **Landmark System Speed Test™**. Accurately measure CPU, math, and video speeds to *make an informed purchasing decision*, determine the best PC for the job or maybe just win some bets in the office on whose PC is *really* faster! Includes the Landmark AT CMOS RAM Setup program to update your system configuration *on-the-fly*. ***CALL for current pricing!***

THE 5 MINUTE SOLUTION TO FLOPPY DRIVE FAILURE

With **AlignIt™** you can *clean, diagnose, and align* your floppy drives in minutes *without* a scope. Patented technology requires only a screwdriver to perform ANSI-accurate alignments (.3 mil).

AlignIt is *ideal for corporate users* with 2 or more PCs because it includes a **"GOLD STANDARD"** feature so you can align all your PCs to the same in-house standard, *guaranteeing that all your floppies are perfectly interchangeable* between PCs.

80% of all floppy drive failures can be fixed with AlignIt. So don't replace your drive, save time and money instead.

Includes dual size floppies, (both high and low density) and no-mess pre-lubricated cleaning diskettes (both sizes) good for 180 uses. Replacements and single drive size versions available. For all PCs and compatibles.
CALL for current pricing!

PC WON'T BOOT? THEN JUST KICKSTART IT!

Don't replace your motherboard, use **KickStart 2™**. When serious hardware problems occur, nothing gets you up and running as fast. KickStart 2 *measures power within 2.5%* on all four voltages, *shows Power-On Self-Test* (POST) failure codes, and features *on-board ROM-based diagnostics* allowing you to *determine and remedy the problem quickly, easily, and inexpensively!*

Built-in serial and parallel I/O *allows for testing via modem*, or simply logging results to a remote terminal, printer or laptop. You can configure your own test routines and store them in KickStart 2's battery backed-up CMOS RAM saving valuable setup time. Includes serial and parallel loopback plugs and Landmark JumpStart™ AT ROM BIOS for testing PCs that don't issue POST codes. KickStart 2 *tests your system regardless of O/S (even UNIX).*

On-board switches, LEDs, and digital displays allow complete control over testing in systems lacking video or disk (ideal for motherboard or system burn-in).

KickStart 2 is the *ultimate SECURITY CARD* too! With both supervisor and user levels of password protection, you can prevent unauthorized use of your PC and accidental running of destructive tests. ***CALL for current pricing!***

"KickStart 2 system diagnostics board helps users check out virtually every aspect of a PC's hardware system... the board is a worthy investment for computer maintenance." David Claiborne, PC Week

HOW TO DEBUG A DEAD PC

Need an *inexpensive solution* for dead or problematic PCs and motherboards? Try **KickStart 1™** or **JumpStart ROM POST™**, two quick and easy to use debugging tools.

KickStart 1 test card shows power status on all four voltages and binary PORT 80 Power-On Self-Test codes. The manual translates error codes for easy failed circuit isolation. ***CALL for current pricing!***

JumpStart ROM POST is a plug-in chip designed to replace your motherboard BIOS for testing purposes. Tests include CPU register and logic, 8087 math coprocessor, 8253 timer, 8237 DMA controller, 8259 interrupt controller, parity error and memory refresh logic, erroneous maskable/non-maskable interrupt detection, display adapter (MDA, CGA, EGA), keyboard, keyboard controller, floppy controller, drive A: read Base memory at normal & slow refresh rates, and POST checksum. Display of motherboard switch configuration. ***CALL for current pricing!***

PROFESSIONAL LEVEL PC TROUBLESHOOTING

Landmark **Service Diagnostics™** is ideal for professionals requiring the *most exhaustive diagnostic* test capabilities. Each module is CPU specific, including PC, XT, AT, 386/486, and PS/2. Since 1981 major manufacturers like Wang, Xerox, Prime, Sony, DEC, NEC, and NCR have relied on Service Diagnostics to tackle their toughest operating problems.

Intended for professional service and repair technicians, Service Diagnostics is also *easy to use* for the novice. Clear, concise on-line help and intuitive menus make finding system problems a breeze. Tests all CPUs, math chips, all memory, floppy, fixed and non-standard disk drives, standard/non-standard printers, system board, video, com ports and all keyboards. Utilities include low-level reformat, log bad sectors, edit bad sector table; the partition editor allows you to set up multiple partitions; *back-up program* transfers hard disk image on unformatted floppies and allows for *restore* after reformat.

Ideal for UNIX and other operating systems, the *self-booting version* doesn't require DOS. The manual offers troubleshooting tips to the component level. Also available in a complete Kit including: all CPU specific software, dual size floppy alignment software (see AlignIt), and PC/XT & AT ROM POSTs. ***PC Magazine Editor's Choice 8/90.***



"Overall, Service Diagnostics: The Kit was the best performer. (You can) locate and identify most of the computer problems you'll ever encounter. If you're running a service department, Service Diagnostics is not an option, it's a necessity." Bill O'Brien, PC Magazine

- Service Diagnostics XT/AT Kit...SAVE $$ CALL NOW •
- Service Diagnostics PS/2 Kit...SAVE $$ CALL NOW •
- XT ROM POST...SAVE $$ CALL NOW •
- AT ROM POST...SAVE $$ CALL NOW •

-- Individual pricing available on all kit components, please inquire --

KickStart 2 is ideal for permanent installation. It eliminates the need for an I/O card, provides remote and on-site diagnostic capabilities for quick repair time and offers a solid hardware based solution to unauthorized access with impenetrable password protection.

SLASH DOWNTIME AND OPERATING PROBLEMS

With **PC Probe™** you'll save time and money when your PC starts acting up. In one easy-to-use package you get *Diagnostics, Virus Protection (for over 700+ known viruses), Benchmarks, Performance Enhancement Utilities, and System Information.* Combined, this arsenal of tools will keep your system up and running at peak performance and remove the mystery about what's inside.

PC Probe diagnostic testing quickly isolates the source of hardware problems, even locating bad RAM chips. It tests system board, RAM, video, keyboard, com ports, floppy drive, hard drive, Ethernet card and more. Run PC Probe tests in batch mode or single pass, *remote* or on-site.

PC Probe allows you to *increase your hard drive data transfer rate* by determining optimum interleave and changing it, *prevent catastrophic data loss* by performing data revitalization, *reformat* the hard drive, *run external programs*, display and edit CMOS RAM on-the-fly, *prevent accidental hard drive data destruction* with passwords, *diagnose problems with device drivers installed.*

The 200 page on-line manual has built-in table of contents, *topic/text search*, and troubleshooting tips. PC Probe comes with dual size floppies and 9 & 25 pin serial/parallel port loopback plugs. For PC XT, AT, 386, 486 and compatibles using DOS 2.0 or higher. ***CALL for current pricing!***

- **Toll-Free Lifetime Tech Support**
- **90 Day Money-Back Guarantee**
- **Federal Express Shipping**

CALL (800) 683-6696

Fax (813) 443-6603 • Voice (813) 443-1331
Dealer Inquiries Welcome

LANDMARK

RESEARCH INTERNATIONAL CORPORATION
First in PC Testing... Since 1981

703 Grand Central Street • Clearwater, Florida 34616

Copyright ©1991. PC Probe, AlignIt, KickStart, JumpStart, ROM POST, and Service Diagnostics are trademarks of Landmark Research International Corp. All Rights Reserved. Other names are trademarks of their associated owners.

Circle 206 on Inquiry Card (RESELLERS: 207).

World Radio History

BUY COMPLETE POWER FOR LESS

SYSTEM SPECIAL
386DX-25
M/B, CPU
Case, P/S
1.44 FDD
Monocard
Monitor
Keyboard

$599

MODEM FAX SPECIAL
S/R/FAX
9600/2400 . . . **$69**

4800 External
Send Fax
Modem **$69**

Sii MICROS 1-800-424-1126

BARE BONES SYSTEMS

288-16 @ $299 386-SX25 @ $444 386-33 @ $599 486-20SX @ $699
386-16 @ $399 386-DX25 @ $549 386-40 @ $699 486-33 @ $899

** All the bare bones systems include: CPU Motherboard, 1 MB Ram, great looking Chasis, 200W P/S, 1.2 or 1.44 MB Drive, 1:1 FD/DH Controller*

386-25 SX
- 1MB Ram
- Power Supply, Chassis
- 40 MB Hard Disk
- 1.2 & 1.44 Floppy Disk
- Keyboard, 101 Keys
- SVGA Card
- 1024 x 768 Monitor, 28 dp

$999

386-25DX
- 1MB Ram
- Power Supply, Chassis
- 40 MB Hard Disk
- 1.2 & 1.44 Floppy Disk
- Keyboard, 101 Keys
- SVGA Card
- 1024 x 768 Monitor, 28 dp

$1099

386-33
- 1MB Ram
- Power Supply Chassis
- 40 MB Hard Disk
- 1.2 & 1.44 Floppy Disk
- Keyboard, 101 Keys
- SVGA Card
- 1024 x 768 Monitor, 28 dp

$1199

486-20SX
- 4 MB Ram
- 100MB Hard Disk
- Case & Power Supply
- Keyboard, 101 Keys
- SVGA Card
- 1024 x 768 Monitor, 28 dp
- 1.2 & 1.44 Floppy Disk

$1499

486-33
- 4 MB Ram
- 100 MB Hard Disk
- Case & Power Supply
- Keyboard, 101 Keys
- SVGA Card
- 1024 x 768 Monitor, 28 dp
- 1.2 & 1.44 Floppy Disk

$1699

MOTHER BOARDS

XT-12	$79
286-12	$89
286-16	$99
286-20	$149
386SX-16	$159
386SX-20	$179
386SX-25	$199
386DX-20*	$129
386DX-25*	$139
386DX-33*	$159
386DX-40*	$179
486SX-20	$439
486DX-33 ISA*	$199
486DX-50*	$399
486DX-33 EISA*	$899

*CPU not included.

MEMORY/SIMMS

4164	$1.25
4464	$1.75
41256	$1.25
44256	$4.50
1 x 1 MEG DRAMS	$4.50
1 x 8 SIMMS	$36
1 x 9 SIMMS	$45
4 x 8 SIMMS	$129
4 x 9 SIMMS	$139

Toshiba, IBM, ALR, AST, Compaq, Macintosh, Zenith Memory Modules Available

MATH CO-PROCESSORS

80287-10	$89
80287-12	$129
80387-16SX	$139
80387-20SX	$159
80387-25SX	$169
80387-20DX	$175
80387-25DX	$175
80387-33DX	$175
80387-40DX	$299

IDE, SCSI, ESDI
HARD DISKS FROM 40 MB TO 1 GB AVAILABLE

OTHER AD-ONS AND PERIPHERALS

Case & Power Supply	$99
Full Tower Case & Power Supply	$169
Mono Monitor	$99
VGA 1024 x 768 .28 dp Monitor	$359
101 Keyboard	$45
IDE Controller	$29
SCSI Controller	$169
SVGA Card 1024 x 768	$99
Mono Card	$29
Tape Back Up 120 MB	$259

WHY BUY FROM Sii?
- One year warranty
- 15 days money back guarantee
- Parts flown by air for replacement
- Quality parts used
- 800 customer service no.
- Last but not least, shop at ALR, AST, COMPAQ, IBM, ZENITH and then call us. We have the best quality service & prices.

ALL TYPES OF HARD DISKS, LAN CARDS, CD-ROM AVAILABLE.

VISA MasterCard

14451 Newport Avenue, Tustin, CA 92680
(714) 731-5489 FAX: (714) 731-1538

PURCHASE ORDERS WELCOME

Prices subject to change without notice. Add 4% for Mastercard or Visa orders. Net terms please add 5% to the total. Shipping and handling charges extra. These are COD prices.

Circle 214 on Inquiry Card (RESELLERS: 215).

World Radio History

ANYONE CAN INSTALL BACKPACK. ANYONE.

It's never been easier to add external mass storage. In fact, if you can plug in a printer, you can install Backpack. Backpack connects to the parallel printer port of any PC compatible or portable *without* interface cards or tools! Backpack is available in 3.5" and 5.25" diskette, QIC 40 (40/120MB) and QIC 80 (80/250MB) tape, as well as hard drive models. Several computers can share one Backpack, so you can back up your work or take it home to another computer. So don't monkey around with difficult-to-install drives. Call for full Backpack information today.



backpack

MicroSolutions
Computer Products

132 W. Lincoln Highway, DeKalb, IL 60115 815-756-3411 FAX 756-2928

Visit us at COMDEX in the North Hall, Booth 665.

Circle 202 on Inquiry Card.

World Radio History

Protects While You Type!

SafeSkin® is the finest keyboard protector in today's marketplace.



Compare these features:

- Remains in place while you use your computer
- Prevents costly repairs and protects delicate electronics from dust, spills, smoke, ashes, staples.
- Wrap around design gives full keyboard protection.
- Anti-glare finish reduces eyestrain.
- Soft, flexible, retains normal keyboard feel.
- Durable, washable high-tech polymer lasts for years.
- More than 800 models. Available for most PC's, laptops, workstations and clone keyboards.

SafeSkin®
KEYBOARD PROTECTOR

Merritt®
COMPUTER PRODUCTS

Circle 200 on Inquiry Card (RESELLERS: 201).

ELEK-TEK® BIZMART Computers • Software • Office Products COMPUTER CITY SUPERCENTER ComputerLand EXPRESS

Also available at Egghead Discount Software.

Dealer and OEM inquiries invited.

In the USA contact: Merritt Computer Products; 5565 Red Bird Center Dr., Ste 150; Dallas, TX 75237; Tel. 214/339-0753; Fax 214/339-1313.
In Europe contact: DEAL B.V.; Van Berckelweg 36; P. O. Box 208; 2200 AE Noordwijk ZH; Holland; Tel. 31-1719-41133; Fax 31-1719-46225.

© 1992 Merritt Computer Products

World Radio History

"POWER BEYOND YOUR DREAMS."

When it comes to offering the highest quality components, blazing-fast performance, friendly service, and unbeatable value, Acma ranks among the best! Just ask the experts at PC Magazine who said Acma offers *"Power Beyond Your Dreams,"* and *"A Solid Value For Your Dollar."* BYTE Magazine applauded Acma for *"Speed And Reliability At An Outstanding Price."* Clearly, if you demand the best, you won't find a better choice than an Acma computer. And we guarantee it with a "No Questions Asked" 45-Day Money-Back guarantee!

PC MAGAZINE
"The Perfect Windows 3.0 Workstation" "Our Favorite Is The Acma"

FEATURES & SERVICES

- 45-Day **"NO QUESTIONS ASKED"** Money-Back Guarantee*
- One-Year Parts And Labor Warranty
- **FREE** One Year On-Site Service In Most U.S. Locations
- **FREE** Lifetime Toll-Free Technical Support (Mon. - Sat.)
- **FREE** 24 hour, 365 days a year, tech-support bulletin board!
- Major credit cards honored (not charged until order ships)
- Net credit terms avaliable for qualified businesses
- Windows 3.0 & DOS 5.0 preloaded **FREE** (except notebook)
- **FREE** Return Shipping Of Replacement Or Repaired Parts**
- **NEW PRODUCTS!** Fax/modem card, $115 » Programmable keyboard, $125 » 1.2GB hard disk drives, Call Today!
- Personal And Business Leasing Plans
- Special GSA And Quantity Discounts
- **SPECIAL!** $1.00 Upgrade Program
- 48 Hour High-Temperature Burn-in

GSA# GS00K91AGS5107
Call Toll-Free 800-456-8809

BEST BUY 486/33i

Intel486™ 33MHz » 8MB RAM » 256K Cache » Teac 1.2MB & 1.44MB FDD » Quantum 210MB IDE HDD w/64K DisCache® buffer (15ms) » caching controller w/4MB » 14" Seiko 1450 SVGA monitor (1024x768) » Orchid Pro-IIs SVGA card w/1MB » 120MB tape backup » 2 serial, 1 parallel, & 1 game port » 101 keyboard » Tower case » Windows 3.0 » DOS 5.0 » Hi-Res Mouse » 1yr. TRW on-site service. **$3,698**

SX/20 NOTEBOOK

Intel386™ SX/20MHz » 1MB RAM upgradeable to 5MB » Teac1.44MB FDD » Conner 40MB IDE HDD » VGA CCFT backlite TSTN type LCD monitor w/16 shades of gray » 1 serial & 1 parallel port » 80 key keyboard » 3 hour battery life » 6.3 lbs. w/battery » carrying case » battery charger » supports external VGA monitor and keyboard. Optional Fax/Modem only $160. Extra batteries $75. **$1,795**

386SX/20MHz

Intel386™ SX/20MHz » 2MB RAM expandable to 8MB » Teac 1.2MB & 1.44MB FDD » Quantum 52MB IDE HDD w/64K DisCache® buffer (17ms) » 14" Hyundai Super VGA monitor (1024x768) » 16-bit VGA card w/512K » 2 serial, 1 parallel & 1 game port » 101 key keyboard » Windows 3.0 » DOS 5.0 » Hi-Res Mouse » 1yr. TRW on-site service. **$1,295**

386/25 & 33MHz

Intel386™ 25 & 33MHz » 4MB RAM expandable to 32 & 64MB » 64K Cache 33MHz » Teac 1.2MB & 1.44MB FDD » Quantum 105MB IDE HDD w/64K DisCache® buffer (17ms) » 14" Super VGA monitor (1024x768) » 16-bit SVGA card w/1MB » 2 serial, 1 parallel, & 1 game port » 101 key keyboard » Windows 3.0 » DOS 5.0 » Hi-Res Mouse » 1yr. TRW on-site service.

25MHz $1,795
33MHz $1,895

486/33MHz EISA

Intel486™ 33MHz » 8MB RAM » 256K Cache » Teac 1.2MB & 1.44MB FDD » Quantum 210MB IDE HDD w/64K DisCache® buffer (15ms) » 15" NEC 4FG Super VGA flat square screen monitor (1024x768) » Orchid Pro-IIs SVGA card w/1MB » 2 serial, 1 parallel, & 1 game port » 101 key keyboard » Windows 3.0 » DOS 5.0 » Hi-Res Mouse » 1yr. TRW on-site service. **$3,895**

Acma COMPUTERS, INC.

ORDER TODAY TOLL-FREE!
800-456-1818
Open 6am-7pm Weekdays and 8am-4pm Saturdays (PST)
International 510-623-1212, 24 Hour Fax 510-623-0818

$1 UPGRADES!

© 1991, Acma Computers, Inc., 48501 Warm Springs Blvd., Fremont, CA 94539 All prices and specifications are subject to change without notice. *The 45-day money-back guarantee covers Acma brand computers with Impression Plus or Hyundai monitors only (software, printers, peripherals, and shipping are not included). All brand names are registered trademarks of their respective companies. **Customer pays shipping to Acma for parts replacement or repair, and Acma pays return shipping to customer. Call today to confirm complete details.

B0492

Circle 178 on Inquiry Card.

World Radio History

The Cream. The Crop.



There are plenty of places to get information in this industry. Too many. But if you want the best quality information, there's only one that rises to the top: BYTE*WEEK*.

BYTE*WEEK* is a weekly newsletter from the same professionals who produce BYTE Magazine. Each week, the most important news and information from the previous week is presented in a readable and concise manner. BYTE*WEEK* offers you what no other publication can: timely news on the rapidly-evolving computer industry as it happens with the interpretation and evaluation that only BYTE's experienced editorial staff can provide.

Subscribe now and take advantage of a special subscription rate of $395 ($495 outside the U.S. and Canada). *Don't miss this opportunity!*

For fastest service, call toll-free **1-800-258-5485** (in N.H., call **603-924-9281**) and charge to a major credit card or we'll bill you.

BYTEWEEK

One Phoenix Mill Lane, Peterborough, NH 03458.

BYTE*WEEK* offers a money-back guarantee if you are not completely satisfied.

Clip Coupon Here

☐ **YES! Sign me up as a subscriber to the Cream of the Crop, BYTE*WEEK* at the special subscription rate of $395 a year for 50 issues ($495 a year outside the U.S. and Canada).**

Name _____
Title _____
Company _____
Mail Address _____
City/State/Zip _____
Business Phone _____

☐ MasterCard ☐ VISA
☐ Check enclosed ☐ Bill me

Card # _____
Exp. _____
Signature _____

BYTEWEEK One Phoenix Mill Lane
Peterborough, NH 03458

World Radio History

H.Co. has America's largest selection of memory!

*And, we'll beat any USA advertised price.**

Laptop Memory

TOSHIBA

	Memory Added	Price
T1000SE, XE,LE	1MBKit	$149.00
&2000SX	2MB Kit	199.00
	4MB Kit	319.00
	8MB Kit	679.00
T1200XE	2MB Kit	119.00
T1600	2MB Kit	119.00
T3100SX	2MB Kit	119.00
	4MB Kit	209.00
T3100	2MB Kit	279.00
T3100e	2MB Kit	119.00
T3200SX	2MB Kit	119.00
	4MB Kit	209.00
T3200SXC	2MB Kit	119.00
	4MB Kit	209.00
T3200	3MB Kit	229.00
T5100	2MB Kit	119.00
T5200, 5200C	2MB Kit	119.00
8500	8MB Kit	429.00

IBM

	Memory Added	Price
L40SX	2MB Mem.	119.00
	4MB Mem.	219.00
	8MB Mem.	449.00

COMPAQ

	Memory Added	Price
PortableIII	2MBKit	129.00
Portable 386/20	1MBKit	179.00
	4MBEXP	459.00
Portable	1MB BD	119.00
LTE286	2MB BD	149.00
	4MB BD	459.00
Portable LTE386S/20	1MB BD	179.00
	4MB BD	359.00
SLT/286	1MB BD	129.00
	4MB BD	429.00
SLT/386	1MB BD	139.00
	2MB BD	219.00
	4MB BD	399.00

NEC

	Memory Added	Price
UltraLite	1MB MD	229.00
286F	4MB MD	599.00
Prospeed	1MB BD	159.00
SX/20	4MB BD	439.00
Prospeed 286	1MB BD	139.00
386SX/16	2MB BD	259.00
	4MB BD	399.00
Prospeed 386	2MB CD	259.00
	8MB CD	999.00

ZENITH

	Memory Added	Price
Supersport SX	2MB ALPHA	$169.00
	2MB BETA	169.00
	2MB EXP	189.00
Slimsport 286e	2MB CD	189.00
	4MB CD	429.00
Turbosport 386e	1MB BD	159.00
	4MB BD	495.00

OTHERS

	Memory Added	Price
AST Executive Notebook	1MB SIMM	79.00
	4MB SIMM	209.00
Sharp PC-6220 Notebook	1MB BD	139.00
Ti Travelmate 2000	1MB BD	129.00
Ti Travelmate 3000	2MB Kit	129.00
Everex Tempi LX	2MB MD	199.00
Panasonic CF-170,270	1MB CD	129.00
Epson NB3S	1MB UPG	159.00
	4MB UPG	399.00

Math Coprocessors

IIT

Part #	Price
2C87-8	$ 79.00
2C87-10	89.00
2C87-12	99.00
2C87-20	109.00
3C87SX-16	139.00
3C87SX-25	159.00
3C87-20	179.00
3C87-25	179.00
3C87-33	189.00
3C87-40	209.00

Cyrix

Part #	Price
82S87-20	$ 99.00
83S87-16	149.00
83S87-20	159.00
83S87-25	169.00
83D87-16	199.00
83D87-20	189.00
83D87-25	189.00
83D87-33	199.00
83D87-40	229.00

intel

Part #	Price
80487SX-20	$509.00
80387-33	219.00
80387-25	219.00
80387-20	219.00
80387-16	219.00
80387SX-20	159.00
80387SX-16	149.00
80287XL	109.00
80287XLT	109.00

PURCHASE ORDERS ACCEPTED
from universities, government & qualified firms!
International orders & FAX orders accepted

DeskTop Memory Upgrades

Apple

	Memory Added	Price
Mac Classic	1-3MB BD	$89.00
	2MB Kit	89.00
Mac IIci,IIsi	1MB Kit	69.00
Mac IIsi	2MB Kit	159.00
Mac Ici,IIsi	4MB Kit	209.00
Mac IIsi	8MB Kit	499.00
Mac IIci,IIsi	16MBKit	629.00
Mac IIfx	4MB Kit	199.00
	16MB Kit	699.00
Mac SE,SE 30, Plus, II, IIcx,IIx	4MB Kit	199.00

AST

	Memory Added	Price
Bravo 486/25	2MB Kit	119.00
	8MB Kit	409.00
Prem 386/SX16 & 20, 25, 33	8MB Kit	409.00
Prem II SX/20	1MB Kit	59.00
SX/16	4MB Kit	219.00
Cupid Exp.	0K BD	269.00
Premium 386C	1MB Kit	59.00
WKST & Bravo Premium	4MB Kit	189.00
Fastram	286 512-2MB BD	289.00
FastramKit 512Upg.		55.00
Premium 386	1MB Kit	59.00
	4MB Kit	249.00

COMPAQ

	Memory Added	Price
DP 386/ 33,486/25,33 & Systemp	2MB MD	$119.00
	8MB MD	395.00
DP 386/ 20e,20 & 25e,25	1MB BD	139.00
	4MB BD	299.00
	1MB MD	89.00
	4MB MD	209.00
DP-386S/ 16	1MB BD	119.00
	4MB BD	299.00
	1MB MD	89.00
	4MB MD	209.00
DP 286N, 386N, & 386SX/20	1MB MD	69.00
	2MB MD	109.00
	4MB MD	249.00
	OK BD	99.00
DP386/16	1 MB BD	279.00
	2 MB BD	599.00
	8 MB BD	899.00

IBM

Works w Model	Price
50Z,55SX,70-EGI, 70-121,P-70	$ 59.00
50Z,55SX,70-EGI, 70-121,P-70	109.00
55SX,65SX,55LS, 34F3077	239.00
70-A21,A61,B21, B61	119.00
30/286	99.00
PS/1	119.00
80-041	79.00
80-111,31	139.00
80-A21,A31,A61	239.00
90,95	259.00
70,80	319.00
50 & 60 Series	299.00
50 & 60	249.00
PS/2 Model 57SX,90,95	8MB MD 499.00

CALL FOR RISC SYSTEM 6000 MEMORY!!

NEC

	Memory Added	Price
P.M SX	1MB BD	189.00
	4MB BD	579.00
Plus	8MB BD	1,099.00
P.M.SX/20	2MBCPU UPG.	189.00
	2MB UPG. & Exp.	269.00
	2MB UPG. Kit	119.00
P.M.SX/16	2-8MB Exp.	249.00
	2MB UPG. Kit	149.00
P.M.386/20	2MB MD	349.00
	8MB MD	999.00
P.M.386/25S	2MB Kit	199.00
	8MB Kit	659.00
P.M.386/25	2MB MD	349.00
	8MB MD	859.00
	8MB Repl BD	1,199.00
P.M.386/33E&486/25E	2MB MD	279.00

ZENITH

	Memory Added	Price
Z-386/20, 25,33,33e	1MB SM	$ 69.00
	2MBSM	129.00
	4MBSM	259.00
Z-386SX, 286-LP+,Z-LS Mastersport SL	2MBSM	119.00
	2MB MD	199.00

WE CARRY MEMORY FOR ALL COMPUTERS AND LASER PRINTERS AT LOWEST PRICES!

Laser Printer Memory

Model	Memory Added	PRICE
H.P.Laserjet IIP, III,IIID,IIIP	1MB Module	$ 85.00
	2MB Module	119.00
	3MB Module	179.00
	4MB Module	209.00
H.P.Laserjet II,IID	1MB Module	85.00
	2MB Module	119.00
	4MB Module	209.00
H.P.Laserjet IIIsi	1MB Module	69.00
	4MB Module	189.00
H.P.Deskjet IBM 4019,4019e	256K Module	109.00
	1MB Module	99.00
	2MB Module	139.00
	3.5MB Module	219.00
OKI Laser 400	1MB Module	109.00
	2MB Module	149.00
OKI Laser 800,820	1MB Module	109.00
	2MB Module	149.00
	4MB Module	199.00
Panasonic 4450	1MB Module	160.00
Panasonic 4420, 4450i	1MB Module	99.00
	2MB Module	149.00
	4MB Module	249.00

Chips/SIMMs

STANDARD SIMMS PART#	PRICE	DRAM PART#	PRICE
256X8-10	$17.00	1X1-80	4.95
256X9-80	15.00	256-80	1.80
1X8-80	43.00	256-70	2.00
1X9-80	43.00	256X4-80	5.00
1X9-70	45.00	4464-80	2.50
4X9-80	169.00	4464-10	2.00
4X8-80	159.00		

KINGSTON

Convert your 286 to a 386

The SX/NOW Works with most:
IBM , AST, Compaq, Epson, HP , NEC, AGI



KINGSTON SX/NOW CPU Upgrades

20 Mhz	345.00
25 Mhz	395.00

All Products 100% Guaranteed!

MasterCard VISA American Express Card

WE NOW CARRY DISCOVER

H.Co. Computer Products
17922 Sky Park Circle #F
Irvine, CA 92714

Orders 1-800-726-2477
Tech Support 1-714-833-3364
Information 1-714-833-3222
FAX 1-714-833-3389
GermanyOffice: ThomasBohlmann
Charlottenburgerufer 18, 1000 Berlin 10
TEL: 030/3410478 FAX: 030/3426310

TERMS:
1. PO's accepted from universities, government agencies & qualified firms.
2. VISA,MC,AMEX,COD,pre-paid & apprived PO's only, please.
3. FAX orders accepted.
4. International orders accepted.
5. 15% Restocking fee on returns within 30 days. No refunds after 30 days
6. No Software returns.

OPEN WEEKENDS

* Any legitimate advertised price from companies with new merchandise actually in stock. Offer excludes Chips and SIMMS. Trademarks are the property of their respective companies. Prices are subject to change. 1992 H.Co. Computer Products.

Circle 194 on Inquiry Card (RESELLERS: 195).

World Radio History

intersys...The Towering Presence

High Performance 486, 386, and 286 Computer Systems

The **Intersys** family of computer system embodies an impressive combination of state-of-the-art design, superb engineering and unparalleled value. The result is the flexibility, compatibility and reliability you expect from a leader in the field.

Whether you need a sophisticated high-end 486 or an entry-level 286 system, there's an **Intersys** out there to suit your needs. Full software compatibility gives you a rich variety of options and ease of network interaction.

Made with pride in the U.S.A., each and every **Intersys** product is backed by a unique 5-year warranty, as well as outstanding field support, both domestically and internationally.

When you demand superior value, when you want built-in American quality...**think Intersys.**



For more information, or to order call: (800) 969-COMP

ISS-1000 The Basic Performer
286/16Mhz, 1Mb RAM, 1.2Mb & 1.44Mb FDD, 40Mb HDD, 14" SVGA Mono Monitor
$845.00

ISS-2000 The Enhanced Performer
386SX/25Mhz, 2Mb RAM, 1.2Mb & 1.44Mb FDD, 80Mb HDD, 14" SVGA Color Multisync Monitor
$1,595.00

ISS-3000 The Optimal Performer
386/33Mhz/64K, 4Mb RAM, 1.2Mb & 1.44Mb FDD, 125Mb HDD, 14" SVGA Multisync Monitor
$2,095.00

ISS-4000 The Premier Performer
486SX/20Mhz/64K, 4Mb RAM, 1.2Mb & 1.44Mb FDD, 200Mb HDD, 14" SVGA Multisync Monitor
$2,395.00

ISS-5000 The Ultimate Performer
486/33Mhz/64K, 8Mb RAM, 1.2Mb & 1.44Mb FDD, 200Mb HDD, 14" SVGA Multisync Monitor
$2,795.00

The Intersys Warranty Seal is your assurance of American quality, backed by a unique five-year guarantee!

intersys inc. 2461 W. 205th St., B103, Torrance, CA 90501, USA TEL: (310) 782-9731, FAX: (310) 782-9815

Circle 196 on Inquiry Card (RESELLERS: 197).

World Radio History

SmartCache™ Plus: the grow-as-you-go approach to SCSI controllers



START WITH THE BEST...
DPT's entry level SmartCache Plus board offers unrivaled price/performance for single-user systems. It features ISA or EISA bus mastering, and universal SCSI disk compatibility for all PC operating systems. SmartDriver software supports SCSI-2 peripherals like tape and optical drives.

NOW ADD CACHING!
Get DPT's award-winning caching technology in a plug-in module! Move up to disk caching speed without investing in a new controller. With an integral 512K cache, the module provides up to 5X performance gains for workstations, power users, and small multiuser systems.

ADD MORE USERS, ADD MORE CACHE!
Plug in a 2 MB or 4 MB memory module and accommodate up to 18 users from a single card slot. Ideal for medium-sized networks or multiuser systems.

HOW ABOUT DISK MIRRORING?
DPT's SmartCache mirroring module provides 100% disk fault tolerance by simultaneously writing all data to a second "mirrored" drive. No more data loss or costly system down-time due to disk failures. And unlike software mirroring schemes, fault tolerance is achieved with no performance penalties.

PLUS STILL MORE CACHE, AND THEN SOME...
Cable over to DPT's 4 MB Cache Expansion Card, then grow your system to 16 MB by adding more plug-in memory modules—enough power for 64-plus users!

DPT has your solution—no matter how you grow. Performance, compatibility and upgradability make SmartCache Plus the only SCSI controller you'll ever need. For details, contact Distributed Processing Technology, 140 Candace Drive, Maitland, FL 32751. Phone (407) 830-5522; FAX (407) 260-5366.

See us at Comdex Spring, Booth #756

DPT

Circle 189 on Inquiry Card (RESELLERS: 190).

World Radio History

16MB TECHNOLOGY NOW!!

ACER 486 SX
32MB



MAC QUADRA 900
16MB

MAC II fx
16MB



COMPAQ SYSTEMPRO
32MB

ALSO AVAILABLE: MAC QUADRA 700 LOW PROFILE 16MB MODULE

OTHER MEMORIES AVAILABLE:
ACER, ALTIMA, AST, CHAPLET, DELL, EPSON, HP, IBM, NEC, PANASONIC, QMS, SAMPO, SHARP, SILICON GRAPHICS, SUN MICROSYSTEMS AND ZENITH.

CALL FOR OUR COMPLETE CATALOG

CitiTronics Inc.

TERMS: C.O.D. CASH, VISA OR MASTERCARD.
COMPANY AND UNIVERSITY P.O.'S ACCEPTED UPON CREDIT APPROVAL.

414 CLOVERLEAF DR., UNIT B, BALDWIN PARK, CA 91706

TEL. (818)855-5688 FAX (818)855-5687

Circle 222 on Inquiry Card.

World Radio History

WHY PAY MORE FOR ADVANCED TECHNOLOGY?

ATronics offers you more for your hard-earned dollar. Highest quality components; customer service and technical support second to no other! Systems designed to avert obsolesence and protect your investment dollar. Motherboards designed with upgradeability in mind.

We've been first since 1985. The very first AT-compatible; the first 486/50 on the market. Dollar for dollar and feature for feature, no competitive system available today can match the ATronics line for technology, quality and value. You owe it to yourself to check our prices. Call us today!

Available as a kit for your existing 3.5" IDE hard disk for just $69.00.

120MB Removable IDE Hard Disk

$425

If you've been looking at Bernoulli or SyQuest for removable media, ATronics can provide a better solution, one that offers the ultimate in unlimited data storage, security, backup and transportability.

- 80MB, 200MB & 300MB IDE drives available
- No special drivers required
- Keylock security
- Completely DOS compatible
- Free padded carrying case

Superior performance from a truly portable and affordable system!

386SX-20MHz Notebook

$1,595

- 20MHz 386SX CPU
- 2MB DRAM, 4MB optional
- 640 X 480 LCD VGA screen, 32 shades of gray
- Dimensions: 8.6"x11"x2", Weight: 6.7 lbs.
- 20MB hard disk standard; 40 & 60MB optional
- 1.44MB floppy disk drive
- Free carrying case
- Other options available at additional cost

Systems Proudly Made in the USA!

ATI-386/33

$1,595

- 33MHz 80386
- 64K cache
- 1MB DRAM
- 120MB IDE hard drive
- 1.44MB or 1.2MB drive
- 1024 X 768 SVGA card
- SVGA monitor (1024 X 768)
- 2 serial and 1 parallel port
- 101 enhanced keyboard
- Baby AT case

ATI-486/33

$2,095

- 33MHz 80486
- 64K cache
- 4MB DRAM
- 120MB IDE hard disk
- 1.44 MB or 1.2MB drive
- 1024 X 768 SVGA card
- SVGA monitor (1024 X 768)
- 2 serial and 1 parallel port
- 101 enhanced keyboard
- Baby AT case

50MHz-486

$2,995

- 50MHz 80486
- 256K cache
- 4MB DRAM
- 120MB IDE hard disk
- 1.44 MB or 1.2MB drive
- 1024 X 768 SVGA card
- SVGA monitor (1024 X 768)
- 2 serial and 1 parallel port
- 101 enhanced keyboard
- Baby AT case

Quality: *U.S. designed and made since 1985.* ***On-Site Service:*** *Available; Unlimited technical phone support included.*

intel inside

ATronics International, Inc.

45635 Northport Loop East
Fremont, CA 94538-6415

Phone: 510-656-8400
Fax: 510-656-8560
Hours: 7 am to 5 pm PST

(OUTSIDE CALIFORNIA ONLY)

1-800-488-7776

Circle 182 on Inquiry Card.

World Radio History

STORM WINDOWS.

33MHz 486 32-Bit Win-Station

- Break-Through 32-Bit Graphics Local-Bus Design
- 256K Super Fast Write-Back Cache RAM
- 8MB RAM (70ns) & Built-in 487 Math Coprocessor
- 1.2MB 5.25" & 1.44MB 3.5" TEAC Floppy Drives
- 210MB 15ms IDE Hard Drive w/ 64K Lookahead Cache
- 32-Bit S3 Graphics Accelerator with 1MB VRAM (Up to 50 times faster than standard SVGA)
- 14" Non-Interlaced .28mm SVGA Color Monitor (VESA Standard for 72Hz Flicker-free Display)
- 2 Serial, 1 Parallel & 1 Game Ports
- Quality 101-Key Keyboard
- Hi-Resolution 400 DPI Serial Mouse
- Free MS-DOS 5.0 & Windows 3.0

$2945

- Above System with 15" Monitor $3155
- Above System with 17" Monitor $3595

33MHz 486 Cache

- 256K Fast Write-Back Cache Memory
- 4MB RAM (70ns) & Built-in 487 Math Coprocessor
- 1.2MB 5.25" & 1.44MB 3.5" TEAC Floppy Drives
- 130MB 15ms MAXTOR IDE Hard Drive w/ 64K Cache
- 16-Bit 1024x768 SVGA Card with 1MB
- 14" Non-Interlaced .28mm SVGA Color Monitor (VESA Standard for 72Hz Flicker-free Display)
- 2 Serial, 1 Parallel & 1 Game Ports
- Quality 101-Key Keyboard
- Hi-Resolution 400 DPI Serial Mouse
- Free MS-DOS 5.0 & Windows 3.0

$2075

33MHz 486 Plus

- Same Configuration as our 486/33 above with
- 8MB RAM (70ns) & Built-in 487 Math Coprocessor
- 210MB 15ms IDE Hard Drive w/ 64K Cache
- 16-Bit 1024x768 SVGA Hi-Color Card with 1MB RAM for 32,768 Colors

$2575

50MHz 486 Plus

Same Configuration as our 486/33 above with

- 8MB RAM (60ns) & Built-in 487 Math Coprocessor
- 210MB 15ms IDE Hard Drive w/ 64K Cache
- 16-Bit 1024x768 SVGA Hi-Color Card with 1MB RAM for 32,768 Colors

$3075

Circle 211 on Inquiry Card (RESELLERS: 212).

33MHz 486 CAD-Station

- 256K Super Fast Write-Back Cache Memory
- 8MB RAM (70ns) & Built-in 487 Math Coprocessor
- 1.2MB 5.25" & 1.44MB 3.5" TEAC Floppy Drives
- 210MB 15ms IDE Hard Drive w/ 64K Lookahead Cache
- 16-Bit ORCHID Fahrenheit 1280™ Card with 1MB (Up to 25 times faster than a standard SVGA Card)
- ORCHID AutoCAD Display List Driver
- 17" Flat Screen Non-Interlaced SVGA Color Monitor (VESA Standard for 72Hz Flicker-free Display)
- 2 Serial, 1 Parallel & 1 Game Ports
- Quality 101-Key Keyboard
- Hi-Resolution 400 DPI Serial Mouse
- Free MS-DOS 5.0 & Windows 3.0

$3395

- 50MHz 486 CAD-Station $3895
- 12x12 Digitizer with 16 Button Cursor $300

40/33MHz 386 Cache

- 64K Fast Write-Back Cache Memory
- 4MB RAM (70ns), Up to 32MB
- 1.2MB 5.25" & 1.44MB 3.5" TEAC Floppy Drives
- 130 MB 15ms MAXTOR IDE Hard Drive w/ 64K Cache
- 16-Bit 1024x768 SVGA Card with 1MB
- 14" Non-Interlaced .28mm SVGA Color Monitor (VESA Standard for 72Hz Flicker-free Display)
- 2 Serial, 1 Parallel & 1 Game Ports
- Quality 101-Key Keyboard
- Hi-Resolution 400 DPI Serial Mouse
- Free MS-DOS 5.0 & Windows 3.0

$1695

25MHz 386sx SVGA

Same Configuration as our 386/33/40 System above except with no cache and

- 2MB RAM (70ns), Up to 8MB
- 85MB 17ms MAXTOR IDE Hard Drive w/ 32K Cache
- 16-Bit 1024x768 SVGA Card with 1MB

$1335

- 25MHz 386sx SVGA as above with 4MB of RAM $1495

1.800.969.2125

International 818.964.6688
Fax 818.964.2492
Hours: 7:00-7:30 Pacific Mon-Fri
9:00-6:00 Pacific Sat
1016-B Lawson Street
City of Industry, California 91748

COMTRADE

"Where Quality is Everything"

WITH LIGHTNING FAST SPEED AND HURRICANE POWER, COMTRADE IS TAKING WINDOWS BY STORM. • WHILE MANY COMPUTERS HAVE ADDED GRAPHICS ACCELERATORS, THEIR REAL-TIME SPEEDS ARE STILL LIMITED BY THEIR 16-BIT AT BUS. • BUT COMTRADE'S 33/486 WIN-STATION USES A REAL 32-BIT LOCAL-BUS VIDEO SLOT TO BYPASS THE AT BUS BOTTLENECK. • THIS ENABLES THE 32-BIT S3 GRAPHICS ACCELERATOR TO CONNECT DIRECTLY TO THE 32-BIT 486 CPU AND RUN AT TRUE CPU CLOCK SPEED—FOR PERFORMANCE UP TO 50 TIMES FASTER THAN STANDARD SVGA! • SINCE NO OTHER COMPUTER CAN MATCH THIS SPEED AT THIS PRICE – IT'S NO WONDER WE'RE BLOWING THE COMPETITION AWAY.



Comtrade 486/32 WIN-Station

ALL COMTRADE COMPUTER SYSTEMS USE THE MOST EFFICIENT WRITE-BACK METHOD TO ENSURE THAT PROGRAMS RUN AT SUPER FAST 25NS CACHE MEMORY 99% OF THE TIME. • COMTRADE 486 SYSTEMS ALSO COME WITH AN INCREDIBLE 256K CACHE WHICH IS SO BIG IT MAKES THE SYSTEM AND VIDEO BIOS CACHEABLE. • AND, COMTRADE STANDS BEHIND ALL THEIR PRODUCTS WITH WARRANTIES TO WEATHER ANY STORM – INCLUDING A TWO YEAR PARTS AND LIFETIME LABOR WARRANTY.

World Radio History

First Source will give you great memories!

IBM MEMORY

PS/1		
2MB	IBM PN N/A	$119
PS/2 30/286, 1497259		
2MB kit	30F5360	$109
PS/2 35SX;LS,40SX,50Z,55SX;LS,65SX;LS,70		
1MB	6450603	$59
2MB	6450604	$119
PS/2 70-A21;A61;821;B61		
2MB	6450608	$129
PS/2 35SX; LS; 40SX; 55SX; 55LS; 65LS; 65SX		
4MB	34F2933	$269
PS/2 35SX; LS, 40SX		
8MB	6450129	$589
PS/2 57SX, 90, 95		
8MB	6450130	$509
PS/2 80-141		
1MB	6450375	$79
PS/2 80-111/311		
2MB	6450379	$139
PS/2 90, 95 and P75 (Install in pairs)		
2MB	6450902	$119
4MB	6450128	$209
Expansion boards for all models 50 and 60		
2-8MB w/2M	1497259	$319
2-16MB w/2M	6450609	$339
Expansion boards for all models 70 and 80		
2-14MB w/2M	34F3077	$349
4-16MB w/4M	34F3011	$459

NEC MEMORY

Powermate SX		
2MB Brd	APC-H855	$499
4MB Brd	APC-H853	$729
Powermate SX Plus		
1-2MB Brd	APC-H850E	$239
4-8MB Brd	APC-852E	$629
Powermate SX/20		
2MB CPU	OP-410-8101	$199
2MB Brd	OP-410-8102	$239
Powermate 386/20		
2MB	APC-H655E	$359
Powermate 386/25		
2MB	APC-H655X	$359
Powermate 386/25S		
2MB Kit	OP-410-5201	$199

HP MEMORY

Vectra QS/16S; 20PC, RS/20PC; 25PC, 20C		
1MB kit	D1540/1640A	$69
4MB kit	D1542/1642A	$199
Vecta 386/16N, 386/20N		
2MB	D2406A	$159
8MB	D2404A	$609
Vectra 486 PC (Install in Pairs)		
1MB	D2150A	$69
4MB	D2151A	$299
Vectra 386/25, 486/25T, 33T (Install in Pairs)		
2MB	D2381A	$129
Vectra 486PC and 386/25 PC		
8MB	D2152A	$549

Please call for any item not listed.

SX/NOW! PROCESSOR UPGRADE

Kingston Technology Corp.'s SX-Now! is the undisputed performance champ.

-PC Magazine October 29, 1991



Don't replace your system...

Upgrade your 286 to a 386SX with Kingston's SX/Now!

SX/Now! 80386SX Processor features:
- ✔ Available in 20 or 25MHz
- ✔ 16K bytes of Cache Memory
- ✔ Onboard High Speed Clock
- ✔ Requires No Expansion Slot
- ✔ 80387SX Co-Processor Socket
- ✔ 5-Year Warranty

Now available for:
- ✔ IBM PS/2 25/286, 30/286, 50, 50Z, 60
- ✔ Original IBM AT
- ✔ AST Premium 286 and Bravo 286
- ✔ Hewlett-Packard ES286/12 & ES/8

Kingston TECHNOLOGY CORPORATION

SX/Now! provides true multitasking and background operation for Windows 3.0, OS/2, and 386 specific software. Improves system performance up to 350%!

SX/Now! 20MHz Accelerator	$439
SX/Now! 25MHz Accelerator	$539

PRINTER MEMORY

Hewlett-Packard LaserJet IIP, III, IIIP, IIID		
2MB	33478B	$125
4MB	33478	$199
Hewlett-Packard LaserJet II and IID		
2MB	33444B	$125
4MB	33445B	$199
Hewlett-Packard DeskJet 500 and Plus		
256K	22477B	$99
IBM Laser 4019 and 4019e		
2MB	1089137	$149
3.5MB	1089675	$219
IBM Laser 4029 All Models		
2MB	1184334	$179
4MB	1184335	$359
Canon LBP-4		
2MB	PN N/A	$249
Brother HL-8, 8E		
2MB	MB-820	$199
Panasonic 4450I and 4420		
2MB	KX-P441	$149
4MB	PN N/A	$239
Toshiba Page Laser 6		
4MB	LSX-NB0100	$219
OkiLaser 400		
1MB	70014701	$99
2MB	OKIPN N/A	$129
Texas Instruments MicroLaser and XL		
1MB	2555739-0001	$79
Epson EPL 6000		
2MB	135401	$149

SIMM / DRAM

SIMMS AND SIPPS		DRAM CHIPS	
4MX9-80	$169	1X1-80	$4.50
1MX9-80	$48	256X4-80	$5.00
256X9-80	$15	256X1-80	$1.80

COMPAQ MEMORY

DeskPro 386-20, 20E and 25		
1MB	113131-001	$89
4MB	113132-001	$219
DeskPro 386S/16		
1MB	113646-001	$89
4MB	112534-001	$219
DeskPro 286N, 386N, 386SX/20, 386/25M, 486/33M, 486s/25M, 486s/16M; SystemPro LT		
2MB	118689-001	$119
4MB	118690-001	$269
DeskPro 386-33, 486-33 and SystemPro		
0K Board	116569-001	$229
2MB	115144-001	$129
8MB	116561-001	$419
DeskPro 386-20e and 25e		
1MB Board	113644-001	$139
4MB Board	113645-001	$309
DeskPro 386S		
1MB Board	113633-001	$139
4MB Board	113634-001	$329

AST MEMORY

Premium 386C, 386-16		
4MB Kit	500510-008	$189
Premium 386, 386-20		
4MB Kit	500510-004	$249
Bravo 386-SX, WS/286, 386		
2MB Kit	500510-002	$99
4MB Kit	500510-008	$189
8MB Kit	500824-001	$389
Premium 386/25;33,Premium II 386SX/16;20		
1MB w/WPB	500780-003	$69
All Premium and Bravo 486 Models		
2MB w/WPB	500718-004	$129
8MB w/WPB	500780-001	$459
Premium II 386SX/20 and 386SX/16		
4MB w/WPB	500780-004	$229

LAPTOP MEMORY

AST		
Executive Notebook	1MB	$79
	4MB	$219
COMPAQ		
Portable LTE386S/20	1MB	$179
	4MB	$379
Portable LTE 286	1MB	$89
	4MB	$219
SLT-286	1MB	$129
	4MB	$449
SLT-386	1MB	$129
	4MB	$399
IBM		
L40SX & N33SX laptop	2MB	$129
	4MB	$219
	8MB	$449
TOSHIBA		
T1000SE/LE/XE, T2000SX	2MB	$229
T1000LE, T2000SX	4MB	$359
	8MB	$789
T2000SXE	2MB	$229
	4MB	$359
	8MB	$789
T1200XE, T1600, T3100E	2MB	$129
T3100SX, T3200SX, SXC	2MB	$129
	4MB	$229
T3200	4MB	$229
T5100	2MB	$129
T5200, T5200C, T8500	2MB	$129
	8MB	$469
NEC		
Powermate Part. SX	2MB	$399
	4MB	$T399
ProSpeed 286, 386SX16	1MB	$129
	4MB	$399
ProSpeed SX20	1MB	$159
	4MB	$449
ZENITH		
MastersPort SL	2MB	$209
MastersPort 386SX	2MB	$209
S.S. SX, 286E, SlimsPort	2MB	$169
SupersPort SX	2MB	$169
SupersPort 286, 286E	1MB kit	$119
SupersPort 286E, SlimsPort	4MB	$449
TurbasPort 386, 386E	1MB	$169

ZENITH MEMORY

Zenith 486/33ET		
4MB Kit	ZA-4200-MZ	$293
16MB Kit	ZA-4200-M8	$1279
Zenith Z-386/20/25/33 and 33E		
1MB	ZA36/3300ME	$69
4MB	ZA3800MK	$299

EXPANSION BOARDS

BocaRam/AT Plus

Up to 8MB for any AT or 16 bit compatible machines running up to 33MHz. Offer all types of memory, provides a maximum of 8MB LIM/EMS 4.0

2MB with DRAM $199

We also stock memory for Acer, ALR, Apple, Arche Technologies, AT&T, Austin, Bondwell, Chinon, Citizen, Commodore, CompuAdd, Data Worlc, Dell, DTK, Everex, Gateway, GRiD, Hyundai, Intel, Leading Edge, Magnavox, Micra Express, Midern, Mips, Mitsubishi, NCR, NeXT, Nortlgate, Olivetti, Packard Bell, PC Brand, Poquet, Samsung, Silican Graphics, Smith Corana, Swan, Tandy, Unisys, Wang, Wyse, Zeos and Others.

Outside the U.S.
1-714-588-9866
Business hours: Monday - Friday 8AM - 5PM

FIRST SOURCE INTERNATIONAL, INC.
"The Only Source for Computer Memory!"
Mail orders to: 36 Argonaut, Suite 140 Aliso Viejo, CA 92656

Fax Line
1-714-588-9872
Fax your orders 24 hours a day, 7 days a week!

1-800-535-5892

Price, Quality, and Support
- Same Day Shipping • Free Technical Support • All Products User Installable • Overnight and Saturday Delivery Available • No Surcharge on Visa, Mastercard, or Discover • APO/FPO/ International Orders Welcome • Purchase Orders Accepted from Government, Universities, and Qualified Firms •

Delivery Guaranteed
Follow your package every step of the way with 3 day International delivery via Federal Express, UPS, or DHL. Fast, inexpensive, dependable delivery anywhere in the world! Information in tracking shipments is available at your request.

Terms and Conditions: All products are third party and manufacturers part numbers are for your convenience. All products carry a full manufacturer's warranty. All products are guaranteed 100% compatible or your money back. All freight charges are non refundable. A 20% restocking fee will be charged on all non-defective returns, unopened, and refused or cancelled orders. All items must be returned within 15 days with original documentation and packaging. Returned Merchandise Authorization number is required. Prices and availability are subject to change without notice. Minimum order of $50. All purchase prices at the time of order are final. First Source International can not be responsible for errors in typography or photography. We will beat any advertised price valid only on identical brands, offer not good for SIMMs or DRAM. All trademarks and registered trademarks are of their respective companies.

BYT04 **Circle 192 on Inquiry Card (RESELLERS: 193).**

World Radio History

STOP & CALL

(800) 831-2888

Hi-Tech USA Monthly Specials

EISA 486-33C $1,398

EISA 486-25C $1,348

ISA 486-50C $1348

ISA 486-33C $798

ISA 486-25C $748

486SX 20 MHz $598

386SX 25 MHz $378

All systems include:
- ▲ Motherboard & CPU
- ▲ 1 MB memory installed (512KB for 286 systems)
- ▲ 1:1 2HD/2FD controller
- ▲ 1.2 MB or 1.44 MB Floppy Drive
- ▲ 2 Serial/1 Parallel ports
- ▲ Enhanced case w/ Power Supply
- ▲ 101-key Enhanced Keyboard

Hard Drive + Video Upgrade	40MB	80MB	120MB	200MB
12" mono + MGP card	$286	$386	$436	$656
14" VGA + VGA card	$456	$556	$606	$826
14" SVGA (1024 x 768) + SVGA Card	$496	$596	$646	$866
14" SVGA (non-inter) + SVGA Card	$606	$706	$756	$976

286-20 $298

386SX 20 MHz $368

286-16 $278

VIDEO OPTIONS

14" SVGA Monitor with 512K card	$ 298
14" VGA Monitor with 16-Bit VGA card	$ 258
NEC 3FGX/4FG/4DS/5D	$ 678/828/998/1888
Sony 1304 HG (1024x768, 0.25)	$ 568
Nanao 9070U/9080i	$ 898/1078
Oak VGA-256k (800x600, 16-bit)	$ 48
Trident 1MB (1024x768x256)	$ 88
Orchid Procesigner IIS with 1MB	$ BEST
Orchid Procesigner IIS w/ Hi-Color	$ BEST
Orchid Fahrenheit 1280	$ BEST
Diamond Speed Star with 1MB	$ 158
Diamond Speed Star Hi-Color	$ 168
Video 7 1024i (512 KB)	$ 188
Video 7, VRAM II (1MB)	$ 348

HARD DISK DRIVES

40mb/28ms (IDE)	$ 198
80mb/18ms (IDE)	$ 298
100mb/16ms (IDE)	$ 318
120mb/16ms (IDE)	$ 348
130mb/15ms (IDE)	$ 358
200mb/16ms (IDE)	$ 568
240mb/15ms (IDE)	$ 598
340mb/15ms (IDE or SCSI)	$ 998
676mb/16ms (ESDI or SCSI)	$ 1398

MISCELLANEOUS

Citizen 200GX (9-pin)	$ 168
Citizen GSX-130/140+ (24-pin)	$ 258/328
Citizen GSX-145 (24-pin)	$ 398
Color option for Citizen printer	$ 48/68
Panasonic Printers	$ Call
Windows 3.0 + Super Mouse II	$ 68
Internal Modem 2400 baud	$ 48
Fax Modem (9600 Fax, 2400 Modem)	$ 88
Logitech Mouseman serial/bus	$ 64.74
Colorado Tape Back-up DJ-10/20	$ 218/278

Free 3-button mouse with a complete system purchase

386SX 16 MHz $348

386-40C 64k cache $538

386-33C 64k cache $518

386-25C 64k cache $498

386-25 $468

286-12 $268

▲ Why Hi-Tech USA! ▲

1. Lifetime toll-free technical support.
2. One year parts, 2 years labor warranty.
3. 30 days satifaction money-back guarntee.*
4. We customize to your requirements.
5. Combinations of the best state-of-the-art components
6. 72 hour burn-in test.
7. World wide shipping.
8. Replacement parts shipped at no cost to you.
9. Superior reputation for service, quality & value.
10. Purchase orders are welcomed and subject to approval.

HI-TECH USA

Terms and Conditions
- ▲ Prices and specifications subject to change without notice
- ▲ * Guarantee will be honored only for IBM incompatibility reasons, covers only Hi-Tech USA brand computers, and excludes computer peripherals software, and shipping charges. All other returns subject to 15% restocking fee. No refunds after 30 days
- ▲ Prices reflect cash discount.
- ▲ All logos and trademarks are registered trademarks of their respective companies

Order Number 1-800-831-2888
Technical & Service 1-800-831-2780
International Orders (408) 262-8688
FAX Orders (408) 262-8772
Hours – M-F: 9:00a.m.-6:30p.m., S: 10:00a.m.-4p.m. (PST)
1562 Centre Point Drive Milpitas, CA 95035

Circle 221 on Inquiry Card.

World Radio History

tote-a-lap

"experts in portable intelligence"



PRICES CONTINUE TO DIVE SO PLEASE CALL FOR OUR MOST CURRENT PRICES

TOSHIBA MEMORY

FOR T1000SE, T1000LE, T1000XE, T2000, T2000SX, T2000SXE, T2200SX, T3300SL, T4400SX

1 MB	$98
1.5MB	$128
2 MB	$158
4 MB	$298
8 MB	$498

TOSHIBA MODEMS ON SALE

2400B INTERNAL MODEM FOR T1000, T1100+, T1200, T1600, T3100, T3100E, T3100SX, T3200SX, T3200SXC, T5100, T5200, AND T5200C — **$78**

LAPTOP/NOTEBOOK SUPER SALE

AST PREMIUM EXEC	386SX/25C	80MB *WITH 8MB RAM*	$4,238
AST PREMIUM EXEC	386SX/25C	60MB *WITH 8MB RAM*	$4,128
AST PREMIUM EXEC	386SX/25	80MB *WITH 8MB RAM*	$2,698
AST PREMIUM EXEC	386SX/25	60MB *WITH 8MB RAM*	$2,448
AST PREMIUM EXEC	386SX/20	60MB *WITH 8MB RAM*	$2,328
AST PREMIUM EXEC	386SX/20	40MB *WITH 8MB RAM*	$2,078
EVEREX TEMPO/LX	386SX/20	60MB *WITH 5MB RAM*	$2,318
EVEREX TEMPO/LX	386SX/20	40MB *WITH 5MB RAM*	$2,148
SHARP PC-6681		80MB *WITH 6MB RAM*	$CALL
SHARP PC-6661		***60MB WITH 6 MB RAM***	***$2,218***
SHARP PC-6781		80MB *WITH 8MB RAM*	$CALL
SHARP PC-6881		80MB *WITH 8MB RAM (COLOR)*	$CALL
TEXAS INSTRUMENTS TM2000		40MB *WITH 3MB RAM*	$1,468
TEXAS INSTRUMENTS TM2000		20MB *WITH 3MB RAM*	$1,158
TEXAS INSTRUMENTS TM3000		WinSX 80MB/*6MB RAM*	$CALL
TEXAS INSTRUMENTS TM3000		WinSX 60MB/*6MB RAM*	$CALL
TEXAS INSTRUMENTS TM3000		80MB *WITH 6MB RAM*	$2,468
TEXAS INSTRUMENTS TM3000		60MB *WITH 6MB RAM*	$2,388
TEXAS INSTRUMENTS TM3000		40MB *WITH 6MB RAM*	$2,328
TEXAS INSTRUMENTS TM3000		20MB *WITH 6MB RAM*	$2,038
ZENITH MASTERSPORT 386SLE		60MB *WITH 8MB RAM*	$3,898
ZENITH MASTERSPORT 386SL		60MB *WITH 8MB RAM*	$3,228
ZENITH MASTERSPORT 386SX		60MB *WITH 4MB RAM*	$2,528

LAPTOP/NOTEBOOK HARD DRIVE UPGRADES

40MB 2.5" HARD DRIVE UPGRADE (MOST BRANDS)	$398
60MB HARD DRIVE UPGRADE (MOST BRANDS)	$498
80MB 2.5" HARD DRIVE UPGRADE (MOST BRANDS)	$598
100MB 3.5" HARD DRIVE UPGRADE (MOST BRANDS)	$498
200MB 3.5" HARD DRIVE UPGRADE (MOST BRANDS)	$748
COMPUADD COMPANION 40MB HARD DRIVE UPGRADE	$548
GRID 1720 60MB HARD DRIVE UPGRADE	$648
PANASONIC CF-270 60MB HARD DRIVE UPGRADE	$648
SHARP PC-6220 40MB HARD DRIVE UPGRADE	$548
TANDY 2810-HD 60MB HARD DRIVE UPGRADE	$648
TEXAS INSTRUMENTS TM2000 40MB HD UPGRADE	$548
EXTERNAL 20MB BATTERY-POWERED HD UPGRADE	$358
EXTERNAL 40MB BATTERY-POWERED HD UPGRADE	$498
EXTERNAL 60MB BATTERY-POWERED HD UPGRADE	$578
EXTERNAL 80MB BATTERY-POWERED HD UPGRADE	$668

NOTE: All hard drive upgrades are supplied with a new BIOS whenever necessary, and come with a full one-year warranty.

UPGRADED TOSHIBA SUPER SALE

T5200C	200MB *WITH 14MB RAM*	$6,188
T5200	200MB *WITH 14MB RAM*	$3,868
T5200	100MB *WITH 14MB RAM*	$3,598
T5100	100MB *WITH 4MB RAM*	$1,978
T5100	40MB *WITH 4MB RAM*	$1,598
T4400SX	80MB LCD *WITH 10MB RAM*	$4,708
T4400SX	80MB GAS PLASMA *WITH 10MB RAM*	$CALL
T3300SL	80MB *WITH 10MB RAM*	$CALL
T3200SXC	120MB *WITH 13MB RAM*	$CALL
T3200SX	120MB *WITH 13MB RAM*	$CALL
T3200SX	40MB *WITH 13MB RAM*	$CALL
T3100SX	80MB *WITH 13MB RAM*	$2,958
T3100SX	40MB *WITH 13MB RAM*	$2,298
T2200SX	80MB *WITH 10MB RAM*	$3,968
T2200SX	60MB *WITH 10MB RAM*	$3,748
T2200SX	40MB *WITH 10MB RAM*	$3,528
T2000SXE	60MB *WITH 10MB RAM*	$2,998
T2000SXE	40MB *WITH 10MB RAM*	$2,758
T2000SX	60MB *WITH 9MB RAM*	$2,778
T2000SX	40MB *WITH 9MB RAM*	$2,558
T2000SX	20MB *WITH 9MB RAM*	$2,448
T1600	40MB *WITH 5MB RAM*	$1,738
T1600	20MB *WITH 5MB RAM*	$1,338
T1200XE	60MB *WITH 5MB RAM*	$CALL
T1200XE	40MB *WITH 5MB RAM*	$1,968
T1200XE	20MB *WITH 5MB RAM*	$1,738

UPGRADE TODAY AND SAVE!

TOSHIBA T1200XE/T5100 2MB UPGRADE...$98

APPLE POWERBOOK 2/4/6MB UPGRADE	$128/$248/$328
APPLE QUADRA 16MB UPGRADE	$698
AST PREMIUM EXEC 1MB/4MB UPGRADE	$48/$168
COMMODORE CLT286/386 2MB UPGRADE	$98
COMPAQ LTE/386s 1MB/4MB UPGRADE	$148/$288
COMPUADD COMPANION/SX 2MB/4MB UPGRADE	$88/$178
EVEREX TEMPO/LX 2MB/4MB UPGRADE	$98/$188
GRID 1720/1750 2MB/4MB UPGRADE	$98/188
HP 95LX PALMTOP 512K/1MB UPGRADE	$188/328
IBM PS2 L40SX 2MB/4MB/8MB UPGRADE	$98/$198/$378
NCR 3125 512K/1MB UPGRADE	$188/328
PANASONIC CF170 1MB UPGRADE	$68
PANASONIC CF270/370 2MB UPGRADE	$98
PANASONIC CF270/370 4MB UPGRADE	$188
POQUET PALMTOP 512K/1MB UPGRADE	$188/328
SANYO MBC-17NB/18NB 2MB/4MB UPGRADE	$98/$188
SHARP PC-6641/TI TM3000 2MB/4MB UPGRADE	$88/$178
TANDY 2810HD/3810HD 2MB/4MB UPGRADE	$98/188
TOSHIBA T3100 & T3100/20 2MB UPGRADE	$268
TOSHIBA T3100SX 4MB UPGRADE (1 SLOT)	$178
TOSHIBA T3200 3MB UPGRADE	$168
TOSHIBA T5200 2MB/8MB UPGRADE	$98/$398
ZENITH MASTERSPORT 386SL/386SX 2MB UPGRADE	$98
ZEOS 286/386SX NOTEBOOK 2MB UPGRADE	$98

WE ARE OFFICIALLY LISTED IN THE TOSHIBA TECHNICAL INFORMATION GUIDE AS THE LEAST EXPENSIVE *RECOGNIZED* MEMORY MANUFACTURER FOR TOSHIBA LAPTOPS/NOTEBOOKS

ALL MEMORY UPGRADES COME WITH A *LIFETIME WARRANTY* & A 48-HOUR EXCHANGE GUARANTEE!

ABSOLUTELY NO SALES TO DOMESTIC RESELLERS

Some prices may reflect cash discounts. Not responsible for typographical errors

3.5" EXTERNAL FLOPPY DRIVE FOR COMPUADD COMPANION SHARP PC-6220 TEXAS INSTRUMENTS TM2000

$198

(while supplies last)

NEW!

60 MB HARD DRIVE UPGRADE FOR GRID 1720 PANASONIC CF-270 TANDY 2810HD

$648

SHARP PC-6220 TI TRAVELMATE TM2000 COMPUADD COMPANION

MEMORY UPGRADE

1MB...$98

2MB...$188

NEW!

40 MB HARD DRIVE UPGRADE FOR SHARP PC6220 TI TRAVELMATE TM2000 COMPUADD COMPANION

$548

SE HABLA ESPANOL

(Pregunte por Hector)

1-800-9-LAPTOP

(1-800-952-7867)

TEL: (415) 578-1901

FAX: (415) 578-1914

tote-a-lap

"experts in portable intelligence"

550 Pilgrim Dr. Suite F • Foster City, CA 94404

All prices subject to change without notice.

Circle 208 on Inquiry Card.

World Radio History



NEW Snap-Master Software: Data Acquisition for Windows

Discover Snap-Master — the only Windows-based data acquisition and analysis software to achieve high-speed, real-time data acquisition with multiple simultaneous A/D boards.

Snap-Master lets you define your own custom instruments using icons and easy-to-understand flow charts. A pre-defined database of sensors is integrated with the data acquisition system.

#HDS 200 Snap-Master Acquisition Module.....**$995**
#HDS 210 Snap-Master Analysis Module.....**$495**

Use modules as an integrated package or stand-alone

Circle 300 on Inquiry Card.

100 MHz PC-Based Scope

CompuScope 250 from **Gage Applied Sciences** is a family of high quality 100 MegaSPS PC/XT-compatible Data Acquisition Cards with advanced oscilloscope software. Features include:

- 100 MHz sampling on one channel or 50 MHz simultaneous sampling on two channels
- 8-bit resolution
- 50 MHz bandwidth
- 32 or 128-KiloByte memory buffer
- Programmable gains
- Store and load setups and signals
- Drivers available in C, Pascal and Basic.

#DSO 250L 100 MHz CompuScope 250 Lite....**$2750**
#DSO 250-32 100 MHz Scope w/32K Buffer.....**$3495**
#DSO 250-128 100 MHz Scope w/128K Buffer.....**$3895**

VGA to your VCR

Tape VGA Animation

Redlake TapeCaster VGA to Video Converter

Redlake's **TapeCaster** converts VGA screen output to video for applications such as animation and creating training tapes. The TapeCaster is extremely easy to use: no base addresses, no interrupts, no software — just plug and play.

- True, precise NTSC or PAL video timing.
- Simultaneous VGA and video display.
- Composite Video & Y-C (SuperVHS) output for use with equipment ranging from an inexpensive VCR to broadcast-quality professional video.

#NTSC 200 TapeCaster – NTSC Video Output **$750**
#PAL 200 TapeCaster – PAL (Europe) Video Out. **$750**
#NTSC 100 NTSC Video Digitizer w/software **$1650**

New GPIB Controllers Support IEEE-488.2 Standard



The new IEEE-488.2 standard has made it easier than ever to program and control GPIB devices. Manufactured by **National Instruments**, these boards allow you to control and gather data from up to 15 devices with IEEE-488 interfaces. Our **AT GPIB** and **Micro-Channel** controllers support data transfers at up to 1 Million samples/second. (No re-writes! Older software fully supported!)

#INST 1000A Standard GPIB Controller with IEEE 488.2 Support.....**$395**
#INST 1004 AT-Bus, 1 MHz Turbo GPIB Controller.....**$495**
#INST 1011 Micro-Channel, 1 MHz Turbo GPIB Controller.....**$495**

Circle 301 on Inquiry Card.

Low-Cost Data Acquisition with the PCL 812

Advantech has made data acquisition extremely affordable. Their PCL 812 boards offer 16 input channels and high speed acquisition; despite their low cost these boards have not sacrificed anything in terms of performance or advanced capabilities.

- 16 Single-Ended Analog Input Channels and 2 Analog Output Channels.
- Up to 30,000 Samples Per Second with 12-bit Resolution.
- 16 Digital Input Lines and 16 Digital Output Lines

#PCL 812 30 KHz, 16-Channel, Low-Cost A/D Board w/ BASIC Drivers.....**$395**
#PCL 812G PCL 812 with Software-Programmable Gain Levels.....**$495**
#PCL 1100 Pascal and C Software Driver Package.....**$95**
#PCL 780 Interface Terminal Panel with Included Cable.....**$95**

You CAN Have it All!

Low cost and high performance now go hand-in-hand. The new LCDAS series of Data Acquisition boards from **Analogic** give you all of the features of boards costing several times more money. Dual DMA processing combined with a full 16-bit AT-bus interface lets you process data as fast as your LCDAS board can sample it. A quick glance at the Block Diagram will show you that all recommended internal circuitry has been provided. Free software drivers and extremely flexible control of operating modes makes development efforts a breeze.



#LCDAS 50 50 KHz, AT-Bus Data Acquisition Board.....**$499**
#LCDAS 125 125 KHz, AT-Bus Data Acquisition Board.....**$650**

CyberResearch April

FREE

PC Systems Handbook for Scientists & Engineers



This Combination Tutorial/Catalog Includes Many Examples of PC-based Scientific & Engineering Systems

Have you wanted to enjoy the many benefits of configuring your own PC-based Data Acquisition or Instrumentation system, but didn't know where to begin? The **PC Systems Handbook** will lead you every step of the way, explaining all aspects of systems configuration with easy-to-understand text and clearly documented diagrams. A detailed glossary and two dozen "Tech Notes" help you understand the terminology. Our new **1992 Edition** will be expanded to 196 pages with a hard spine, making it suitable as a permanent addition to your bookshelf. And there is **absolutely no charge** for this invaluable reference book delivered within the United States. A handling charge is required for Handbooks sent overseas. Please call or Fax for information.

Topics Covered Include:

- **Industrial Rack-Mount PC's — AT, 80386, & New 80486 Models**
- **Real-Time Data Acquisition, Analysis, & Process Control Software**
- **PC Plug-in Boards for Analog/Digital, Digital/Analog, & Digital I/O**
- **Connect your PC to Test Instrumentation with IEEE-488, RS-232, RS-422**
- **Stepping and Servo Motor Control with your Personal Computer**

Circle 302 on Inquiry Card.

Notice to International Customers

You can buy direct from CyberResearch and **save 50%** or more! A majority of the leading brands of PC-based engineering products are available for export from CyberResearch at the same low prices as those enjoyed by our customers in the United States.

Due to contractual restrictions, products from some manufacturers are not available for export to certain countries.

Please fax a request for quotation listing brand and/or performance requirements, and we'll fax back a prompt response.

World Radio History

CyberResearch System of the Month Features RTI DAS from Analog Devices



Package includes Labtech Notebook

The **RTI** series of data acquisition boards were designed by **Analog Devices** with industrial users in mind. With the lowest MTBF in the industry, these are the boards to chose when reliability is critical. Designed from the outset to be compatible with the full line of Analog Devices' signal conditioning modules, these boards can be used for the broadest possible range of data acquisition applications.



Labtech Notebook

CyberResearch has now made this top-of-the-line product affordable for everyone. By bundling an **RTI 815A** together with **Labtech Notebook** software at one low price, we've saved over $500 and made it possible for you to afford the very best.

Each combination package contains:

- **RTI 815A** DAS board configured for 32 S.E. or 16 Diff analog input channels with 50 KHz A/D conversion rate, 2 analog output (D/A) channels, 16 Digital I/O and 3 Counter/Timer I/O.
- **Labtech Notebook** menu-driven software with new IconView diagramming user interface and drivers for the RTI 815A board.

#RTI 815LN RTI DAS Combination Package **$1995**

Guarantee Valid Data with Signal Conditioning Modules

Signal conditioning modules serve several purposes; they protect your computer, isolate your signal of interest from noise, amplify low-level signals, and provide power and excitation to transducers.

One name is virtually synonymous with signal conditioning: **Analog Devices**. And CyberResearch is your Analog Devices distributor carrying every signal conditioning line: the versatile **3B** series, the low-cost **5B** series, and the new, intelligent **6B** series with on-board A/D conversion.

Call to receive additional information.



Circle 303 on Inquiry Card.

Product Showcase

PC Products for Scientists & Engineers

When you need PC-compatible equipment for science and engineering, there's only one name to think of: **CyberResearch**. We offer the largest selection of hardware and software for data acquisition, instrumentation, communications, motion control, etc. We stock all your best-known suppliers like those featured on these pages and many more.

FREE Application Engineering

At CyberResearch we have no salespeople. Our engineers have one priority: to help you find the best technical solution to your problems. Calling our Applications Hotline is like having your own free consultant. Call and let our experience work for you.

100% Satisfaction Guarantee

You can order from CyberResearch with confidence. If you are not completely satisfied with your purchase, simply call our toll-free hotline within 30 days of receiving the item. A friendly customer service technician will arrange for a full refund, replacement, exchange, or credit. **No Problem. No Hassle.**

It's Easy to Order

We accept Purchase Orders from:

- Government Agencies
- Fortune 500 companies
- Universities & hospitals

Others may prepay by check or credit card. We also will ship COD with a company check.

©1992 CyberResearch, Inc.

CyberResearch

Mailing Address:
P. O. Box 9565
New Haven, CT 06535

Worldwide
(203) 483-8815
Fax: (203) 483-9024

MasterCard VISA

TOLL-FREE (800) 394-3300

Keithley Metrabyte Sets the Standard — AGAIN

The DAS 16 analog converter board has always set the standard for PC-based data acquisition. **Keithley Metrabyte** has now set a new standard for price and performance. A total redesign using ASIC architecture has resulted in complete backwards compatibility, reductions of cost, size, and power consumption, and the addition of many new features, including:

- Programmable gains • Demand-mode DMA • Burst-mode timing
- 16 Analog inputs, 2 analog outputs, 32 digital I/O lines, 3 counter/timers
- BASIC drivers and pop-up control panel software included free.

#DAS 1601 100 KHz, 16-Channel DAS Board w/Hi-Level Gains (1, 10, 100, 500).**$895**
#DAS 1602 100 KHz, 16-Channel DAS Board w/Lo-Level Gains (1, 2, 4, 8) **$895**
#DAS ASO Advanced Software Option – Windows, C, Visual Basic Drivers **$195**

Circle 304 on Inquiry Card.

EasyPlot II Scientific Graphing Software



Are you tired of using Lotus to create scientific plots? Now **EasyPlot II** helps you create complex graphs and detailed 3-D plots from your data. Easy-to-use **EasyPlot II** is completely menu-driven. Analysis functions, unlimited display options and journal-quality output make this the package of choice. Makes a perfect companion to our Labtech Notebook data acquisition software.

#SPS 215 EasyPlot II Scientific Plotting and Graphing Software.....**$349**

Circle 305 on Inquiry Card.

Rack-Mount Printers are Built to Last for Years

Rack-mount printers manufactured by **Syntest** are IBM Proprinter compatible for easy software compatibility. The Epson dot-matrix print head is driven by a fiberglass belt and high resolution stepper motor for near-perfect dot alignment. The absence of gears and cams reduces the parts count and results in a high MTBF. A rugged 1/8" aluminum shell protects the mechanism from harsh environments. Choose Serial (RS-232), 4-20mA, Parallel, or RS-422/485 connections for great cabling flexibility.

New **#PRO 521** Rack-Mount Thermal Printer uses a fax-type print head to achieve high speed, high dot-density, and quiet operation.

#PRO 500 Ruggedized Rack-Mount Dot-Matrix Printer **$1350**
#PRO 521 Ruggedized Rack-Mount Thermal Printer **$1495**

World Radio History

You May Recognize Some Of Our Customers...

Intel Corporation — N.A.S.A.
U.C. Berkeley — Washington Post
Procter & Gamble — AT & T
Digital Equipment Corp — M.I.T.
Eastman Kodak — DuPont
U.S. Marine Corps — Exxon
U.S. Army/Navy — Xerox
U.S. Veterans Hospital Admin. Ctr.
Lockheed Missile Space Engineering
...and the list goes on and on...

Dealer Inquiries Welcome. Government, Corporate & University P.O.'s Welcome!

FREE ON-SITE Service to most locations.

Hours:
Mon thru Fri - 7:30am to 6:00pm (PST)
Sat - 10:00am to 4:00pm (PST)

- Prices subject to change without notice.
- Prices reflect 3% cash discount.
- Special GSA and Quantity discounts.
- Trademarks belong to their respective companies.
- Not responsible for typographical errors.
- The Intel Inside logo is a trademark of Intel Corporation.

We offer Superior products and the best values in the Industry at *unbeatable prices!*

Intelligent Choices

Standard System Features: (*Unless specified differently in Specials)**

- Motherboard - Intel CPU
- Math co-processor socket
- 4MB 70ns RAM on-board
- 1.2 and 1.44MB FDDs(Teac)
- Dual IDE HDD/FDD controller
- 2 serial/1 parallel/1 game ports
- 101 Keytronics keyboard
- Desktop case w 200W UL/PS

OPTIONS:
Mid-Tower ..... add - $60
Full-Tower (10-bays, 230W Power Supply) ..... add - $100

SYSTEMS: (Prices below do not include Hard disk drive, monitor/card)

486-33 EISA w/64k cache (Micronics MB) $1,955
486-33 ISA w/64k cache (MCI/Symphony) upgradable to 50MHz $1,065
486SX/20 w/64k cache (Symphony) upgradable to 33MHz/50MHz $855
386-33 w/64k cache , (Symphony) upgradable to 40MHz $755
386-25 (Symphony) upgradable to 33MHz/40MHz $685
386-SX20 w/64k cache/ SX-20 non-Cache $695/635
Micro-L/Vanda 386SX-V20 Notebook 2MB RAM, 40MB HDD, 6.2lbs, VGA $1485

MICRO-L ISA 486-33 CACHE (Symphony) $2075

- Intel 80486-33MHz Processor - Upgrades to 50MHz; Socket for removable crystal allows for CPU changes
- AMI BIOS, Symphony™ Chipset, Dallas DS1287 real-time clock (w/10-year warranty)
- 256k Cache SRAM expandable to 1MB
- 4MB RAM 70ns expandable to 32MB onboard
- 1.2MB & 1.44MB FDDs (TEAC) • IDE HD/FD Contrllr
- 130MB, 15ms, 64k Cache IDE HDD
- SpeedStarPlus, 1MB,16-bit VGA card, Hi Sierra color (VESA Standard for Flicker-free display)
- 14" Super Multiscan, 1024x768, non-interlaced 0.28dp, (Relisys-1422)
- 1 Parallel/2 Serial Ports
- Keytronics 101 keyboard (USA)
- Mid-Tower case (heavy duty), 230W UL power supply
- MS-DOS 5.0 • MS Windows 3.0 & MS cmptbl mouse
- OPTION: 210MB IDE HDD add - $235
- OPTION: Sony CPD-1304 monitor add - $265

FCC Class B

MICRO-L 386-33c (Symphony) $1675

- Intel 80386-33MHz CPU - Upgrades to 40MHz; Sckt for removable crystal allows CPU changes
- AMI BIOS, Symphony™ Chipset, Dallas DS1287 real-time clock (w/10 year warranty)
- 128k Cache SRAM expandable to 1MB onboard
- 4MB RAM 70ns expandable to 32MB onboard
- 130MB, 15ms IDE HDD/FDD controller
- 1.2 and 1.44MB Floppy Disk Drives (TEAC)
- 1 Parallel/2 Serial/1 Game Ports
- 16-bit VGA Card w/ 1MB (Genoa 7800, Tseng) (VESA Standard for Flicker-free display)
- 14" Super Multi-scan, non-int,1024x768, 0.28dp (Relisys RE-1422)
- Deluxe Baby Case w/ 200W UL P/S ,6-bays
- Keytronics 101 Keybd (USA) • MS-DOS 5.0
- MS Windows 3.0 & MS compatible mouse
- OPTION: 386-40 SVGA system - add $45
- OPTION: Mid-Tower - add $60

MOTHERBOARDS

486-33 EISA 64K Cache/Micronics	$1535
486-33 AT 64K Cache - Symphony Upg to 50MHz	$645
486-SX/20 64K Cache - Symphony Upg to 33/50MHz	$445
386-33/40 w/64K Cache - Symphony	$335/375
386-25 Non-cache - Symphony Upg to 33/40MHz	$250
386-SX20 w/32k Cache /Non-cache	$245/195

HARD DRIVES

Maxtor 81MB/130MB/213MB IDE HDD	$330/375/645
Maxtor 380MB ESDI/768MB SCSI HDD	$1025/1395
Maxtor 1.02 GB SCSI	$1995
Conner CP-30104 120MB/CP-3204 200MB IDE	$360/625
Quantum ProDr 120MB/240MB IDE	$375/665
DTC-3290 SCSI/EISA,512K	$575
Adaptec Kits-1542B (SCSI)/1740B (SCSI/EISA)	$260/480

MONITORS

Relisys VGA RE-1420, 1024x768 0.28dp	$305
Relisys S Multiscan,NI,1024x768 RE-1422	$360
Nanao 9080-I VGA 16", 1024x768	$1075
NEC MultiSync 4-FG	$ 795
Genoa 7800 VGA Card 1MB, Flicker-free(ET-4000)	$135
SpeedStar+ VGA 1MB, w/Hi Sierra	$178
Orchid ProD IIs 1MB, w/Hi Sierra	$178
Orchid Fahrenheit 1280 w/1MB	$275

MISCELLANEOUS

FAX modem 9600/send-Recv/sftw	$95
U.S Robotics 9600 int V.32 PC/V.42 bis	$445
Colorado DJ-10 T-Back-up 120MB/DJ-20 250MB	$235/305
American Smart UPS 600VA/APC-1250V	$445/845

For your protection, we check thoroughly for stolen credit cards.

Microline Computers - Taiwan
Phone: 011-886-7-345-0025
Fax: 011-886-7-345-0060

Info/CA Orders: (510) 770-1900
Fax: (510) 770-1912

MICROLINE COMPUTERS
INCORPORATED
46757 Fremont Blvd., Fremont, CA 94538

Orders Only Call 1-800-777-2219

AMT INTERNATIONAL

(408) 432-0552 • (408) 432-1790 Fax: (408) 944-9801

LOWEST PRICES
SAME DAY SHIPPING

COMPAQ MEMORY

DeskPro 286-E, 386-20/20E/25
1MB 1*3131-001 ..... $125.00
4MB 1*3132-001 ..... $330.00
DeskPro 286N, 386N and 386SX
2MB 1*8689-001 ..... $200.00
4MB 1*8690-001 ..... $545.00
DeskPro 386S
1MB 113646-001 ..... $125.00
4MB 112534-001 ..... $315.00
DeskPro 386-33, 486-33 & SystemPro
2MB 115144-001 ..... $200.00

AST MEMORY

Bravo-286, Workstation
512K Kit500510-010 ..... $59.00
2MB Kit 500510-002 ..... $150.00
Premium 386-18/20C
1MB Kit 500510-007 ..... $95.00
4MB Kit 500510-008 ..... $275.00
Premium 386-20
1MB Kit 500510-003 ..... $150.00
4MB Kit 500510-004 ..... $350.00
Bravo-386SX
4MB Kit 500510-008 ..... $369.00
Premium 386-SX/25/33 $ 486-25
1MB 500718-002 ..... $80.00

HEWLETT-PACKARD MEMORY

Vectra QS/16S
1MB D1540A $112.00
4MB D1542A $425.00

Vectra QS/20PC, RS/25PC and 20C
1MB D1640A $126.00
4MB D1642A $365.00
Vectra 486PC
1MB D2150A $115.00
4MB D2151A $390.00

IBM PS/2 MEMORY

Models 30-286, Exp. Board 1497259
512 K Kit 30F5348 ..... $54.00
2MB Kit 30F5360 ..... $175.00
Models 70-E61/121, 55SX, 65SX
1MB 6450603 ..... $95.00
Models 70-E61/121, 50Z, 55SX,65SX
2MB 6450604 ..... $179.00
Models 55SX, 65SX, 34F3077 & 34F3011
4MB 34F2933 ..... $370.00
Models 70-A21
2MB 6450608 ..... $150.00
Models 80-141
1MB 6450375 ..... $145.00
Models 80-111/311
2MB 6450379 ..... $220.00
All Models 70 and 80
2-8MB w/2M 6450605 ..... $489.00
2-14MB w/2M 34F3077 ..... $500.00
2-16MB w/4M 34F3077 ..... $925.00
Models 50, 50Z, 55 SX &60
2-8MB 1497259 ..... $599.00

LASER PRINTER MEMORY

Hewlett-Packard Laser Jet IIP, III & IIID
1MB 33474B $110.00
2MB 33475B $150.00
4MB 33477B $215.00
Hewlett-Packard Laser Jet IIP & IID
1MB 33443B $110.00
2MB 33444B $150.00
4MB 33445B $215.00
IBM Laser 4019 and 4019e
2MB 1039137 ..... $369.00
3.5MB 1038675 ..... $469.00
Canon LBP-8II, 8IIR, 8IIT
2MB S63-1880 ..... $225.00
4MB Part #N/A $439.00

LAPTOP AND PORTABLE MEMORY

TOSHIBA MEMORY
1MB Model 1000SE/XE $265.00
2MB Model 1000SE/XE $325.00
2MB Model T1200XE $230.00
2MB Model T1600 ..... $230.00
2MB Model T3100E $175.00
2MB Model T3100SX $175.00
4MB Model T3100SX $395.00
2MB Model T3200SX $175.00
4MB Model T3200SX $395.00
2MB Model 5100 ..... $215.00
2MB Model T5200,T8500 ..... $185.00
8MB Model T5200,T8500 ..... $950.00

ZENITH MEMORY
1MB SuperSport 286 & 286E $199.00
2MB SuperSport 286 & 286E $350.00
2MB SuperSport SX/Alpha $350.00
4MB SuperSport SX/Beta $350.00

COMPAQ MEMORY
1MB Portable LTE 286 ..... $175.00
2MB Portable LTE 286 ..... $225.00
1MB SLT-286 ..... $225.00
4MB SLT-286 ..... $775.00

NEC MEMORY
1MB Prospeed 286 ..... $270.00
2MB Prospeed 386 ..... $450.00

ZENITH MEMORY

Zenith Z-386/20/25/33 & 33E
1MB ZA36/3800ME $100.00
4MB ZA3800MK $525.00
Zenith Z-386/20/20/25 & 33
2MB ZA3600MG $199.00
Zenith Z-386 SX
2MB Z-605-1 ..... $225.00

MATH COPROCESSORS

INTEL
8087-5 MHz $70.00
8087-2 8MHz $70.00
8087-1 10MHz $135.00
80287-6 6MHz $79.00
80287-8 8MHz $79.00
80287XL 8/10MHz $89.00
80287XTL 12MHz (Laptop) $99.00
80287-10 10MHz $89.00
80C287-12 12MHz $109.00
80387SX-16 ..... $129.00
80387SX-20 ..... $135.00
80387DX-20 ..... $140.00
80387DX-25 ..... $185.00
80387DX-30 ..... $195.00
80387DX-33 ..... $195.00

WEITEK
3167-20 20MHz $300.00
3167-25 25MHz $450.00
3167-33 33MHz $500.00
4167-25MHz $600.00
4167-33MHz $700.00

CYRIX
8C87-8 ..... $59.00
8C287-10 ..... 75.00
8C287-12 ..... 85.00
8C2877-20 ..... 85.00
8C387-20 ..... $155.00
8C387-25 ..... $158.00
8C387-33 ..... $175.00

IIT
8C87-8 ..... $69.00
8C287-10 ..... $79.00
8C287-12 ..... $89.00
8C287-20 ..... $99.00
8C387-20 ..... $175.00
8C387-25 ..... $175.00
8C387-33 ..... $200.00

AMD
80C287-10 ..... $89.00
80C287-12 ..... $110.00

SIMM MODULES

IBM TYPE
Add $2.00 for SIPPS

4Mx9-80 ..... $145.00
4Mx9-70 ..... 145.00
1Mx9-60 ..... 40.00
1Mx9-10 ..... 40.00
1Mx9-80 ..... 40.00
1Mx9-70 ..... 40.00
256x9-70 ..... 12.00
256x9—10 ..... 10.00
256x9-80 ..... 11.00
256x9-60 ..... 12.00

APPLE-MAC
1Mx8-70 ..... $50.00
1Mx8-10 ..... $40.00
1Mx8-80 ..... $45.00
4x8-80 ..... $190.00

2393 QUME DRIVE,
SAN JOSE, CA 95131

DRAM - DRAM - DRAM

DRAM 1MGX1
1 MGX -120NS $5.00
1 MGX -100NX 5.25
1 MGX -80NX 5.50
1 MGX -70NX 5.75
1 MGX -60NX 7.50

DRAM 64X1
4164-150 ..... $2.00
4164-120 ..... 2.50
4164-100 ..... 2.75
4164-80 ..... 3.00

DRAM 64X4
4464-15 ..... $1.50
4464-12 ..... 1.99
4464-10 ..... 2.50

DRAM 256X1
256X1-150NS $1.79
256X1-120NS 1.99
256X1-100NS 2.00
256X1-80NS 2.25
256X1-70NS 2.35
256X1-60NS 3.99

DRAM 256X4
256X4-120NS $5.00
256X4-100NS 5.50
256X4-80NS 5.75
256X1-STATIC COL
51258P-10 ..... $2.99

AAA 2800-08 ..... 3.00
AAA 2800-07 ..... 3.25
AAA 2800-60 ..... 4.50
1X4-80 ZIPP 35.00
1X4-80STT ZIPP 39.00
1X4-70STT ZIPP 39.00

World Radio History

Pick A Card



Volante

Draw your winning card from National Design's Volante Series of high speed graphics boards.

PC MAGAZINE EDITORS' CHOICE
June 25, 1991
National Volante AT1000

All Volante high speed graphics boards offer:

- Built on ISA, MicroChannel or VME bus
- Video memory upgrades to 4 MB
- Program memory upgrades to 4 MB
- Razor sharp resolutions from 1024x768 up to 1600x1280
- Blazing color selection from 8-bit to 24-bit true color
- Optional TI TMS34082 floating point processor for enhanced 3D acceleration
- Superior speed of the TI TMS34020 graphics engine paired with National Design's advanced ASIC technology
- LIFETIME WARRANTY - no gamble here!

Whether your game is CAD, Microsoft Windows, graphic arts, multi-media or medical imaging, Volante has a card for you at a fraction of the cost charged by the competition.

See us at COMDEX/Spring '92 West Booth #1742

Call 800-253-8831 now for information on the breathtaking Volante series.
Phone: 512-343-5055 Fax: 512-343-5053

NDI
NATIONAL DESIGN, INC
9171 CAPITAL OF TEXAS HWY, H-230
AUSTIN TEXAS 78759

Circle 203 on Inquiry Card (RESELLERS: 204).

World Radio History

Circle 224 on Inquiry Card.

RIGHTON® COMPUTER SECURITY

AFFORDABLE • EFFECTIVE • MOBILE

SPOTLINK-5™

Righton® patented Spot® Anchors, with their special adhesive, are the best theft deterrents you can buy. Our versatile variety gives you options, easy access, and are easy to use. Spot-Link 5®, unlike competitors, is not dependent on the adhesive strength of a laminated top. Factory-direct prices from $8.20 to $32.50 save you money. Request our free brochure B with prices. Thank you.

SECURTECH CO.

5755 SW WILLOW LANE, LAKE OSWEGO OR 97035-5340
(503) 636-6831 • FAX (503) 636-9642 Made in U.S.A.

Sending Your Computer to Medical School ..... Helps You Stay Healthy!

Is that indigestion ... or a heart attack? ***Doctor Schueler's Home Medical Advisor*** gives you an enormous amount of accurate medical information with a few keystrokes. Developed by Board Certified Emergency Physicians and currently used in doctors' offices.

The Symptom File's question and answer format generates over 600 illustrations and 450 diagnoses.

The Disease File gives info about the symptoms and treatment of over 450 diseases. Know EXACTLY which specialist treats your problem.

Learn how to treat over 130 injuries with the Injury File, everything from frostbite to ankle sprains.

Identify and learn the side effects of over 800 prescription and over-the-counter drugs with the Drug File.

Included are a Test File of medical tests and a Poison File listing household ingestions — great for mothers with toddlers. Registered users will be eligible for updates at a cost of five dollars, so YOUR medical encyclopedia NEVER goes out of date. Call now. This indispensable reference tool prints medical information for family and friends and makes learning FUN!



Manufacturer's suggested price: $99.95

Introductory offer: **$69.95** 512K RAM EGA/VGA

Same Day Shipping! IBM & Compat.

VISA MasterCard

See your software dealer or call **1-800-788-2099**

PIXEL PERFECT, INC.
10460 S. Tropical Tr., Merritt Island, FL 32952

Circle 219 on Inquiry Card (RESELLERS: 220).

World Radio History

TOP OF THE LINE

TOSHIBA & MANCHESTER

WHY MANCHESTER ?

- High quality industry standard products at unbeatable prices.
- Multimillion dollar inventory assuring you prompt delivery.
- 18 years of quality and dependability in the computer business.
- Knowledgeable sales reps who help you plan, design, implement and manage your computing environment.
- A service department that maintains your equipment in first rate condition.
- Support specialists in sophisticated applications such as Networking, CAD/CAM and Connectivity.
- Risk free corporate evaluations, both in house and on location; demonstrations on the newest and most innovative products.

WHY TOSHIBA ?

- Recognized as the standard in providing quality products, high performance and user reliability.
- An industry leader in the research and development of laptop computer products and peripherals.
- Outstanding portable engineering systems designed for current usage and growth potential.
- Portable systems that handle intensive number crunching, complex CAD/CAM programs, Desktop Publishing and complicated databases.
- State of the art, extensive family of feature rich portable and notebook computers.
- All systems designed with the end user in mind.

NETWORKING • CONNECTIVITY • CAD/CAM

SYSTEMS INTEGRATION • DESKTOP PUBLISHING

Authorized **TOSHIBA** *Dealer & Service Center*

MANCHESTER EQUIPMENT COMPANY, INC.

"The Computer Supply and Equipment Experts"

50 MARCUS BOULEVARD ■ HAUPPAUGE, NEW YORK 11788 ■ (516) 435-1199

New York City: (212) 629-6969 ■ Boca Raton: (407) 241-7900 ■ Tampa: (813) 962-8088 ■ Boston: (617) 739-1555

Circle 566 on Inquiry Card.

World Radio History

World Radio History

CAN HOLD A CANDLE TO

PC EXPO in New York

1983: 120 EXHIBITORS, 9,600 ATTENDEES

1984: 211 EXHIBITORS, 16,441 ATTENDEES

1985: 278 EXHIBITORS, 23,869 ATTENDEES

1986: 368 EXHIBITORS, 34,448 ATTENDEES



1987: 452 EXHIBITORS, 41,737 ATTENDEES

1988: 508 EXHIBITORS, 48,445 ATTENDEES

1989: 511 EXHIBITORS, 62,805 ATTENDEES

1990: 606 EXHIBITORS, 67,156 ATTENDEES



1991: 728 EXHIBITORS, 75,104 ATTENDEES

1992 . . .

Be a part of this exciting moment in history as PC EXPO in New York celebrates a decade of growth and excellence. For additional show information, call 800-346-EXPO or 201-346-1400.

June 23 - 25, 1992
Jacob K. Javits Convention Center
New York

Circle 563 on Inquiry Card.

World Radio History

19" RACKMOUNT CHASSIS & COMPONENTS

Buy Direct From Factory & Save (Made in USA)



"19" Expandable Rack Available"

Also Available

- Rackmount Monitors
- Single Board Computers
- Backplane Board
  8 *2 14,
  *8,20 Slots



RACKMOUNT KEYBOARD



RACKMOUNT KEYBOARD DRAWER

• Call for complete rackmount computer system with your configurations.

19" Rackmount Enclosure

• Upto 8 Drive Bays • 2 Fans w/Filter
• 200 - 500W PS • Up To 18 Slots



19" Rackmount Enclosure with 9" Mono or 10" VGA Color Monitor



SCSI Expansion Enclosure

• UP TO 4 FULL HEIGHT HDD

APPRO FILE SERVER SYSTEMS & COMPONENTS

****** *BASIC SYSTEM CONFIGURATION* ******

MOTHERBOARD & CPU W/4 MB RAM, 1.2 & 1.44 FDD,
IDE 2S/P/G PORT, 101 KEYBOARD & FK-105D CASE

486-50 Mhz EISA/ISA	CALL	486-33 Mhz	$1225
486-33 Mhz EISA	$1950	386-33 Mhz	$ 895

CALL OR FAX FOR YOUR CONFIGURATIONS !!

12-Slot 486-33 System $999

- 486-33MHz MB w/128K Cache
- 12-Slot Full Tower Case w/250W PS
- 7 X 5.25" Bays • Additional Fan w/Filter
- FCC Class B Approved • 17" x 8.35" x 23.82
- *Complete System w/Basic Sys. configurations* $1450

Do You Need More Slots In Your Computer ?

Now you can expand your PC-AT system without timing or noise problems and without time-consuming system reconfiguration with the new ETRC-AT Active Expansion Bus Interconnect Kit from APPRO.



- *HARDWARE & SOFTWARE TRANSPARENT.*
- *NO ADDRESS RESTRICTIONS.*
- *NO INITIALIZING SOFTWARE*

Just plug in the cards and you're all set to go.

10 DRIVE BAY FILE SERVER CASE $190



- 2 Cooling Fans • Side Panel Opening
- 250W PS(300W,450W Opt.) • 8 SLOTS
- ROLLING CASTERS • 17.8"x8.7"x27.6

1. Visa and Master card accepted. 2. One year warranty.
3. FOB Santa Clara,CA 4. Pricing & Availability are subject to change without noticce

APPRO International, Inc.
3687 Enochs St., Santa Clara, Ca 95051
408-732-6091 Fax:408-732-6095

Circle 596 on Inquiry Card.

World Radio History

NEET

Quality service you can rely on.

NEET is a high quality hardware & complete solutions supplier

NEW ENGLAND Electronics & Technology Corp.

Tel: (508) 454-9192 10--6 MON--SAT Fax: (508) 454-9319

pick-up or UPS shipping

225 Stedman St, Bldg. 9 & 10
Lowell, MA 01851

I-495 Exit 34, Rt.110 to Lowell
1st lights left turn to
Stedman St., 1 mile on the left

DEALERS' INQUIRIES INVITED

PC & PS/2 & MAC & WRKSTN

---BRAND NEW WITH FACTORY WARRANTY---

HARD DISK DRIVES:

SCSI *complete line of SCSI drives for PC PS/2 Mac workstations*

MAXTOR	P1-17S	1.7GB		$2799
SEAGATE	41650N	1.6GB		$2699
MAXTOR	**PD-12S**	**1.2GB**		**$2099**
MAXTOR	8760S	676MB		$1499
MICROPOLIS	1588-15D	668MB		$1495
MICROPOLIS	1684-7	345MB	HH	$1125
MAXTOR	LXT340SY	340MB	3.5"	$1079
MAXTOR	LXT213S	213MB	3.5"	$619
MAXTOR	7120S	125MB	3.5"	$399
QUANTUM	52S	52MB	3.5"	$229

IDE *all 3.5", 1/2 or 1/3 height*

SEAGATE	1480A	426MB	$1349
SEAGATE	1239A	210MB	$619
SEAGATE	3144A	124MB	$409
SEAGATE	3096A	89MB	$319
SEAGATE	351A	42MB	$235
MAXTOR	LXT340A	340MB	$1059
MAXTOR	LXT213A	213MB	$619
MAXTOR	7120A	125MB	$409
CONNER	CP3204F	210MB	$619
CONNER	CP30104	120MB	$409
QUANTUM	QT425A	425MB	$1390
QUANTUM	QT210A	210MB	$619
QUANTUM	LPS120A	120MB	$409
QUANTUM	QT52A	52MB	$235

MFM SEAGATE 251-1 40MB HH $249

RLL SEAGATE ST-277R-1 60MB HH $289

ESDI

MAXTOR	8760E	676MB	PC/WS	$1499
MAXTOR	8380E	380MB	PC/WS	$1099
MICROPOLIS	1664-7	345MB	HH	$1099
MICROPOLIS	1568-15	676MB	PC/WS	$1495
MICROPOLIS	1518-15	1346MB	PC/WS	$2500

SCSI EXPERT

DRIVE CONTROLLERS:

SCSI *CONTROL 7 DRIVES. install, utilities, cd-rom, tape drv, optical drv, common command set, Novell Unix DOS OS/2-LAN/MGR software drivers with most controllers*

FOR PS/2	M.C.A.	32	$349	B/M SMART CACHE HIGH SPD BURST
ULTRASTOR	24C-16MB	EISA	$799	B/M SCSI-1/2 33MB/S BURST .4ms
ULTRASTOR	24F-64KB	EISA	$499	B/M SCSI-1/2 33MB/S BURST
ADAPTEC	**1542BK**	**16**	**$279**	**B/M SCSI-1/2 UNIX NOVELL OS/2**
ADAPTEC	1522DNK	16	$159	CACHE NOVELL UNIX SCSI-1/2
DTC	3280	16	$135	CACHE XENIX
FUTR DOMN	850	8	$69	



ESDI *ULTRASTOR-----1:1 CACHE UNIX NETWARE LAN/MGR 3FLY QUICK COMPUSURF 24MHz MAPPING*

EISA B/M 33MB/S			ISA 16bits		
22C---16MB	0.4ms	$799	12C---16MB	0.4ms	$399
22F---32KB	track	$489	12F---32KB	track	$149

IDE & FLOPPY CARD

IDE 2 HARD/2 FLPPY $25
IDE 2 HARD W/ROM XT $65

FLOPPY	SPECIAL 4 FLOPPY CARD	$35
FLOPPY	1ST & 2ND/3RD & 4TH	$32
IDE	2 HARD/2 FLPPY/MULTI I/O	$35
IDE	8MB SMART CACHING W/1MB	$299
MFM	16-bit 1:1 $59	8-bit $39

MASS STORAGE DEVICES HEADQUARTER

MAC---MAC---MAC---MAC---MAC---MAC

CMS GOLD RESELLER *drives for MAC, PS/2 NOTEBOOK COMPUTERS SPARC WORKSTATIONS*

PS/2---PS/2---PS/2--PS/2--PS/2

TAPE DRIVES:

COLORADO	120/250MB	FLPY	$229/$289
WANGTEK	1.2/2.5GB	SCSI 4mm HELICAL DAT	$1599+
EXABYTE	2.3/5GB	SCSI 8mm HELICAL	$1850+

UNIX

386--33 & 486--33 SCSI SYSTEM
SCO UNIX & X-WINDOW
SINGLE & MULTI USER

CAD

486--33 FAST GRAPHICS SYSTEM
VIDEO CARD W/COPROCESSOR
HI RESLTN & LOW RADIATION MONITOR

COMPLETE HARDWARE & SOFTWARE SOLUTIONS OF MASS STORAGE

HARDWARE & SOFTWARE COMPLETE FOR PC /PS 2 /MAC /WORKSTATION & UNIX

768MB WORM OPTICAL DRIVE $999

HIGH SPEED SCSI TAPE BACKUP $859

650MB/1GB REWRITEABLE OPTICAL DRIVE

external drives & hardcards available

1.3/2.5GB DAT TAPE DRIVE
2.3/5.0GB 8mm TAPE DRIVE
$2049+

DISK DRIVE & SYSTEM UPGRADES

MOTHER BOARD hi quality hi performance

486-33EISA	256K BURST FAST A20 64MB	1699
486-33 TAG	256K BURST FAST A20 32MB AMI 15MIPS HIDDEN REFRSH DIRECT MAP	$899
386-33 TAG	128K D/MAP FAST A20 32MB AMI	$499
386-25	INTEL & VLSI DESIGN 32MB AMI	$339
386SX-20	multiRAS active FAST A20 AMI	$249
286-12	HIGH QUALITY, SI=16	$89

RAM--SIMM 1Mbx9-70ns--$46 4Mbx9-70ns--$175

MOUSE & KEYBOARD & MULTI I/O

MOUSE------PC & MS COMPATIBLE/3 BOTTON	$25
TRACKBALL--800 DPI PC & MS COMPATIBLE	$35
KEYBOARD---FUJITSU DURABLE 101KEY W/CLICK	$49
MULTI I/O--2 SERIAL/1 PARALLEL/1 GAME	$19
MONOCHROME-W/PRINTER PORT, GRAPHICS	$20

FAX & MODEM

ZOOM 2400 BAUD	INTRNL/EXTRNL	$75	/$79
ZOOM 9600 BAUD	INTRNL/EXTRNL	$365	/$399
ZOOM FAX & MODEM	INTRNL/EXTRNL	$139	/$155

POWER SUPPLY KINGSPAO 200W/220W $59/$65

FLOPPY DRIVE TEAC 5.25" or 3.5" $65

UPGRADES & REPAIR

ETHERNET 16-BIT	$139
AUDIO CARD	$149
MS-DOS	$69
WINDOW w/mouse	$79
CD-ROM	$
MATH COPRCSSR	$

All prices & specs are subject to change without prior notice

ABSOLUTELY HIGH QUALITY HARDWARE

ALL HARDWARE W/ 1 YEAR WARRANTY

GUARRANTY COMPATIBLE WITH NOVELL, UNIX, OS/2, DOS & ALL MAJOR SOFTWARE

100% IBM & COMPAQ COMPATIBLE

BASIC SYSTEMS

INCLUDING:

- HIGH QUALITY SURFACE MOUNT M. B.
- INTEL CPU WITH COPROCESSOR SOCKET
- HIGH SPEED MEMORY ON BOARD
- 2 SERIAL/ 1 PARALLEL / 1 GAME PORT
- HIGH SPEED 2HD/2FD IDE CONTROLLER
- REAL TIME CLOCK/CALENDER
- TEAC 1.2 MB FLOPPY DISK DRIVE
- FUJITSU 101 KEYS ENHANCED KEYBOARD
- CASE WITH RELIABLE POWER SUPPLY
- LED PANEL & DIGITS DISPLAY
- FCC CLASS B

286-12	-----	*$399*	1 MB
386SX-20	-----	*$599*	2 MB
386-33	-----	*$999*	4 MB FULL
486-33	-----	*$1499*	4 MB FULL
EISA 486-33	-----	*$2299*	4 MB FULL

NEET is a high quality hardware & complete solutions supplier

BUILD-UP YOUR OWN SYSTEMS

CASE BEAUTIFUL TOWER CASE W/QUIET DURABLE POWER SUPPLY & LED DIGITAL DISPLAY *(5.25" & 3.5" bays in parentheses)*

SRVR(11)	FULL(6)	MID(3+4)	MINI(2+3)	D/T(3+3
$279	$159	$129	$100	$100

UNISTOR EXTRNL DRIVE CASE
FULL HEIGHT-----$159 HALF HEIGHT----$139
FOR TAPE DRIVE--$149

VGA CARD

TRIDENT CHIP	1MB 1Kx768 NONINTRLC	$99
DIAMOND SPEED STAR ET4000 CHIP	HiColor	$189
ORCHID PRODESIGNER II+	1MB HiColor	$229
ORCHID FAHRENHEIT 1280x1024	fast VRAM	$299
ATI VANTAGE	1MB 1Kx768 CO-PROC,FAST	$369
ATI ULTRA	1MB VRAM EXTREMELY FAST	$599

MONITOR

12" MONO TATUNG	$99
14" VS4 MULTIFREQ.28mm hi quality tube 1024x768-INTRLC 640x480-NONINTRLC	$339
14" VS5 1024x768-NONINTRLC PC & MAC SONY TRINITRON vivid .25mm	**$599**
14" VS6 1024x768-NONINTRLC 72Hz .28mm NO FLICKERING, PC & MAC	$445
17" VS7 1280x1024 .28mm NONINTRLC 110MHz, Fv 90Hz, Fh 64KHz	$1299
NANAO T560i-17".26/T660i-20".31 SONY TRINITRON vivid, hi contrast 1664x1200 90Hz 78KHz 120MHz MPR-II & TCO low emission standard	$1899/$2699

NEC 3FG-$739 4FG-$875 5FG-$1499

World Radio History

ICS

COMPUTER POWER HOUSE

POWERFUL SYSTEMS

ICS 486-33c	$1059
ICS 486-20c	$ 899
ICS 386-40c	$ 699
ICS 386-33c	$ 649
ICS 386-25	$ 499
ICS 386SX-25	$ 449
ICS 286-16	$ 359

1MB RAM, 2S, 1P, 1G Ports
1.1 HD-FD Ctrl, 101 Enhanced
Keyboard, 3.5" or 5.25" FDD

✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦

486-SX20 MHz Intel
64k cache
4 MB RAM
Super VGA Monitor .28dp
SVGA Card (1 MB)
120 MB Hard Drive (15MS)
1.2 & 1.44 Floppy
2S/1PR/1Game Port
101 Keyboard
DOS 5.0

$1799

✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦

386SX-20 NOTEBOOK

2 MB RAM Exp. to 16
3.5" Floppy
60 MB Hard Drive
83 Keyboard
2S, 1P, VGA Parts
Super Twist Backlit
VGA Screen
Carrying Case

$1659

SPECIAL

✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦

486-33 MHz Intel
4 MB RAM
Super VGA Monitor .28dp
Super VGA Card (1MB)
120 MB HD (1.5MS)
1.2 & 1.44 Floppy
2S, 1P Game Port
101 Enhanced Keyboard
DOS 5.0

$1999

✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦ ✦

386-40 MHz
64k cache
4MB RAM
Super VGA Monitor
SVGA Card (1 MB)
120 MB Hard Drive
2S/1 PR/1 Game Port
101 Keyboard
DOS 5.0

$1679

ICS COMPUTERS

1701 N. Greenville,#1000
Richardson, TX 75081

800-852-0614

Tel 214-644-2371 • Fax 214-644-2372

2 Years Labor
1 Year Parts
Prices subject to change

Circle 601 on Inquiry Card (RESELLERS: 602).

World Radio History

Breaking The Foreign Language Barriers!

Globalink Translation Software... incredibly accurate foreign language translations at record speeds.

Up to 100 times faster than human translators, with an accuracy rate often exceeding 90%, ***Globalink Translation Software (GTS)*** makes quick work of foreign language translations. Sentence by sentence — not word by word — in correct grammatical structure, ***GTS*** translates entire documents to and from English and Russian, German, French, Spanish. Producing clear, understandable text easily and automatically, right on your desktop PC. From only $495, ***GTS*** is on the job in thousands of companies worldwide. So what's stopping you? Call Globalink now. And break through your own foreign language barriers in no time — without breaking your budget.

See your software dealer or call Globalink today!

1-800-255-5660

lobalink™
Foreign Language Translation Software

9302 Lee Highway, 4th Floor, Fairfax, Va. 22031 U.S.A.
Phone: (703) 273-5600 • Fax: (703) 273-3866

GTS products run on IBM PCs and compatible computers, 12 MB hard disk, 640K RAM and DOS 3.1 or higher.
Compatible with word processing programs via ASCII text files.
© 1992 Globalink, Inc. All rights reserved. Printed in the U.S.A.

Circle 564 on Inquiry Card (RESELLERS: 565).

World Radio History

TMS™ Introduces... Electronic Document Filing For Your PC

FastCab
DOCUMENT FILING MADE EASY

Instant access to every document in your office is available through FastCab™ electronic filing software. FastCab is an inexpensive solution for filing financial documents, correspondence, contracts, engineering drawings, and any other paper document. Just scan it, file it, and let FastCab retrieve it in a flash!

- **Scan It**
- **File It**
- **Use It!**

- Files millions of pages
- Crossfiles to avoid losing documents
- Network compatible
- Converts image files
- Handles oversized documents, drawings
- No hardware board required

To Order Call
1-800-944-7654
Demonstration Disks Available

TMS, Inc.

Corporate Headquarters
TMS, Inc.
P.O. Box 1358
Stillwater, OK 74076
Telephone 405/377-0880
Fax 405/377-0452

West Coast Office
800 El Camino Real West,
Suite #52
Mountain View, CA 94040
Telephone 415/903-2252
Fax 415/903-2253

FastCab™ and TMS™ are trademarks of TMS, Inc.
Circle 567 on Inquiry Card (RESELLERS: 568).

1988–89
U.S. Delivery $3.00
Foreign Delivery $4.00

1990–91–92
U.S. Delivery $6.00
Foreign Delivery $8.00
Canada & Mexico $6.50

	1988	1989	1990	1991	1992
January					
February					
March					
April					
May					
June					
July					
August					
September					
October					
November					
December					
Special Issues				October '92	

BYTE BACK ISSUES FOR SALE

The above prices include postage in the US. European customers please refer to Back Issue order form in International Advertising section of book.

Please indicate which issues you would like by checking (✓) the boxes. Send requests with payment to:

BYTE Back Issues, One Phoenix Mill Lane, Peterborough, NH 03458, (603) 924-9281

☐ Check enclosed **Charge:** ☐ VISA ☐ MasterCard

Card # _____

Exp. Date _____

Signature _____

Name _____

Address _____

City _____

State _____ Zip _____

All orders must be prepaid. Please allow four weeks for delivery.

☐ Issues Available

World Radio History

The Only Thing More Reliable Than Our Products Is Our Customer Service.

We may carry the widest selection of the most dependable products in the industry but it's our customer service that sets us apart. And when you want to upgrade your computer, that's important.

At Universal, we're knowledgeable about all of our products. So we'll be able to help you figure out what you need and how to install it. And we'll do it in a way that'll be very understandable.

We'll help you in other ways, too.

Our prices are very competitive. And every product is checked for quality before it's shipped. Plus, you can have your order sent same day, overnight or whatever way you want.

And after you receive your order, you won't have anything to worry about either. Because everything we sell comes with a 5 year warranty, a 30 day, money back guarantee and is guaranteed to be compatible with your computer. So you're covered no matter what happens.

Also, you can always phone, fax or mail us with any questions regarding our company or products. And we'll be happy to give you the information you want.

100% COMPATIBILITY GUARANTEED

Overall, no one else works with you as much as we do. So if you want to upgrade your computer and you need more than a product listing, call Universal. We'll provide you with products and service that'll help you every step of the way.

ORCHID · BOCA RESEARCH INC · EVEREX · ATI TECHNOLOGIES INC · Kingston TECHNOLOGY CORPORATION · IBM · intel · MHz Megahertz CORPORATION · AST RESEARCH INC. · PROCOM TECHNOLOGY

EXPANSION BOARDS

Orchid Technology

Kanquest 16/32
OK $229 2MB $329
2-8MB for PS/2 50/55/60/70/80
Kanquest 8/16 OK $149 2MB $245

BOCA Research

Bocaram AT Plus
OK $119 2MB $199 2-8MB LIM 4.0 AT's
Bocaram AT/IO Plus
OK $157 2MB $257 up to 4MB
w/ser & par ports
Bocaram 2 for PS/2's OK $159 2MB $259
Bocaram XT-PS/2 30 1MB $159

AST Research

6pak 286 OK $109 2MB $209
Rampage Plus 286 OK $239 2MB $309
up to 8MB for AT UM 4.0
Fastram 286 1MB $279
Cupid 32 OK $250

Intel

Above Board Plus 8 w/2MB $499

VIDEO GRAPHICS CARDS

ATI

8514 Ultra 1MB PS/2 or ISA BUS $449
Graphics Ultra 1MB & mouse $549
Graphics Vantage w/ 1MB $389
NEW!!! VGA Stereo XL w/1MB $375
VGA Wonder XL 1MB w/ mouse $239

Orchid Technology

Fahrenheit 1280 w/1MB & Sierra $399
Prodesigner IIS 512K 5229 1MB $289
Prodesigner IIMC for PS/2 1MB $399

BOCA Research

BOCA Super VGA 512K $139 1MB $179

PRINTER UPGRADES

Hewlett Packard

Laserjet IIP, Id, IIID, IIIP
1MB $69 2MB $119 4MB $199
Laserjet II, IID
1MB $69 2MB $119 4MB $199

Panasonic 4420 & 4450i

1MB $109 2MB $129 4MB $229
4450 1MB $179 4455 2MB $269

Epson EPL 6000 & EPL 7000

1MB $129 2MB $145 4MB $235

IBM 4019 & 4019E

1MB $115 2MB $139 3.5MB $199

OKI 400, 800, 820, 830, 840

1MB $119 2MB $169 4MB $199

Canon

LBP-4 2MB $209 LBP 8 2MB $119

MEMORY CHIPS & MODULES

DRAM

1X1-70NS $4.25 256X4-80NS $5.15
1X1-80NS $4.95 256X4-100NS $4.95
256X1-80NS $1.99 256X1-120NS $1.75
256X1-100NS $1.85 256X1-150NS $1.50
64X4-80NS $3.00 64X1-100NS $1.75
64X4-100NS $2.75 64X1-120NS $1.60

SIMM/SIPP Modules

4X9-70NS $199 4X9-80NS $169
1X9-70NS $49 1X9-80 $45
1X9-100NS $44

MATH CO-PROCESSORS

IIT

US83C87-16, -25, -20 & -33 $199
US83C87-16SX $115 -20SX $139
New US83C87-40 $279

Intel

80387-16, -20, -25 & -33 $249
80387-16SX $139 -20SX $189
80287-10 $75 80287XL $125

IBM PS/2 UPGRADES

IBM PS/2 Memory

6450604 2MB MOD 50Z, 55SX, 70 $99
6450608 2MB MOD 70A21 $119
34F2933 & 77 4MB PS/2 SIMM $199
30F5360 2MB for 30-286 $99
6450928 4MB MOD 90 & 95 $219
6450902 2MB MOD 90 & 95 $129
6450609 2-8MB MOD 50, 50Z, 60 $298
6450605 2-8MB MOD 70 & 80 $350
34F3077 2-14MB MOD 70 & 80
w/2MB $298
34F3111 4-16MB MOD 70 & 80 4MB $429

PS/2 Hard Drives

Zero Slot for 50, 50Z $795
52MB $395 80MB $495 105MB $599
124MB for 55SX, 70 $740 240MB $999
200MB $1065

Processor Upgrades by Kingston

IBM PS/2 50, 60, 50Z, 30/286, 25/286, AT, XT/286, AST Premium/Bravo 286, Compaq Deskpro 286, Portable III, HP Vectra ES/12, RS/8, NEC PowerMate 286+, Portable +, Epson 286: 20MHZ for $359 25MHZ for $459

COMPAQ UPGRADES

Compaq Deskpro

Deskpro 386/20, 25, 20E, 25E & 386S
4MB Module $229 4MB expboard $327
Deskpro 386/33 486/25 Systempro
2MB Module $149 6 socket exp. brd.
w/2MB $395

1/3 height floppy disk drives

1.44MB $129 1.2MB $139

Portable LTE 286

1MB $99 2MB $169 4MB $449

Portable LTE 386S/20

1MB $209 4MB $399

Portable 386/20

1MB Upgrade kit $145 4MB exp/ext brd $375

SLT 286 1MB $119 4MB $429
SLT 386 1MB $129 2MB $255
4MB $435

LAPTOP UPGRADES

Toshiba

T1200XE/SE, T1600, T3100E, T3100SX, T3200SX, T5100, T5200, 2MB $112
T3200SX, 2MB $159 4MB $329
T1000SE/XE/LE & T2000SX 1MB $119
2MB $229
T1000LE & T2000SX 4MB $419
T3100SX, T3200SX 4MB $229
T3200 3MB $254

Megahertz Laptop Modems

2400 BD internal $149 w/MNP5 $210
2400/9600 FAX/Modem w/MNP5 $319

Same day shipping by UPS, Federal Express or DHL. Order worldwide by P.O., C.O.D., APO, FPO & credit card with no surcharge added. 20% restocking fee on all non-defective returns.

800/678-8648

UNIVERSAL
MEMORY PRODUCTS

VISA · MasterCard · AMERICAN EXPRESS

UNIVERSAL MEMORY PRODUCTS
15451 Redhill, Suite E, Tustin, CA 92680
Phone: 714/258-2018 Fax: 714/258-2818
Hours M-F 6:30-5:00 PST SAT 8:00-2:00

Circle 209 on Inquiry Card (RESELLERS: 210).

World Radio History

Circle 185 on Inquiry Card.

YOU DIDN'T BUY A FAX CARD SIMPLY FOR YOUR READING PLEASURE.

Today's fax cards provide you with an untouchable static image that can only be read.

Before you can revise or edit an incoming computer fax you must retype the entire document into your PC.

That is, unless you have new FAXGrabber,™ the only Windows fax utility that automatically converts fax images into more than 50 word processing, desktop publishing and spreadsheet programs. And because it uses Calera's award-winning OCR technology, accuracy and ease of use are assured. To save $50, order today.

CALERA
RECOGNITION SYSTEMS

Call 1-800-4-FAX-GRAB, Ext. 10 To Get FAXGrabber For Just $99 Before May 30, 1992

Works with all leading fax cards. FAXGrabber is a trademark of Calera Recognition Systems. © 1992 Calera Recognition Systems, Inc. All other trademarks are property of their respective holders

---

ALL IN ONE

Fax, Scanner, Printer, Copier

WHAT-YOU-PRINT-WHAT-YOU-FAX

SEND faxes directly from any Windows application in the same format as if you would print it to LaserJet printer .

RECEIVE faxes as files and print them to your LaserJet printer.

SCAN full page documents, and save them as PCX, TIFF , MSP or DCX files .

COPY documents on plain paper via LaserJet or directly on fax paper.

Or turn off your PC and use ETFAX7 as a

STAND-ALONE FAX MACHINE

$595

COMPEX INTERNATIONAL INC.
312 Broadway Street Cambridge, MA 02139 USA
(617)354-5045, FAX (617)864-9516
AMEX,VISA, MASTER CARD, DINERS

1-800-626-8112
Or call **Get-a-Fax** at **617-354-1133** from your fax machine, and ask for document # 3011

Circle 186 on Inquiry Card.

World Radio History



BayTech steps into the future with . . .

460k BAUD FOR HIGH SPEED PRINTING

BAYTECH INTRODUCES

Tran•x™

A NEW PRODUCT SERIES FOR HIGH SPEED COMMUNICATIONS

The new Tran•x LPT-460 is an expansion/extender card that allows your network file server, graphics workstation, or PC to output data at speeds up to 460k baud at 1000 feet, or even greater distances at lower speeds.

The Tran•x LPT-460 converts parallel data to serial which can then be transmitted to the Tran•x SP-01 serial to parallel converter module. You can also use the LPT-460 with BayTech Model 24SII or LaserShare for the fastest peripheral sharing solutions available anywhere.

TRAN•X LPT-460 FEATURES:

- High speed data output at extended distances
- Easy to install card plugs into your PC expansion slot
- Adds an additional parallel port, configurable as LPT1-LPT3
- Baud rates from 300 to 460k
- EIA-232 or EIA-422 data transmission
- Connects to Tran•x SP-01 converter module, BayTech peripheral sharing devices, or other serial devices

TRAN•X SP-01 FEATURES:

- Connects to your printer's centronics port
- Serial input speeds up to 460k baud
- Reports printer status back to PC
- 128 byte buffer for XON/XOFF handshaking

With more than 1 million connections, BayTech has been serving users for over 15 years. Buy with confidence and let BayTech be your step into the future. For reliable, high performance, affordable printer sharing devices, multiplexers, modems and data acquisition/control devices, contact a BayTech representative toll-free *today!*

Because Resources Should Be Shared

BayTech

Bay Technical Associates, Inc.
Data Communication Products Division
200 N. Second Street, P.O. Box 387
Bay Saint Louis, MS 39520

Fax: 601-467-4551
Phone: 601-467-8231 or toll-free
800-523-2702

Circle 183 on Inquiry Card (RESELLERS: 184).

World Radio History

Accessories/Supplies • Add-In Boards

8 fl. oz.

HI TEC HYGIENE

8 fl. oz.

Clean and Protect your computer with DATA FACE™ CRT Cleaner & Anti-Static. SPEAK EAZZY™ Telephone Fragrance & Cleanser. Remove dirt and germs with a little zing to your business and home telephones.

ORDER DIRECT

Name _____

Address _____

City _____ State _____ Zip _____

DATA FACE: $7.95 ea. ____ QTY. $83.67/cs (12) ____ QTY. $ _____

SPEAK EAZZY: $6.45 ea. ____ QTY. $67.80/cs (12) ____ QTY. $ _____

Scent: ☐ Peppermint ☐ Bubble Gum Shipping $ **FREE**

☐ Mountain ☐ Jasmine ☐ Tangerine Total $ _____

Erin-American Ltd.
Ft. Harrison Industrial Park
Terre Haute, IN 47804 **Phone 812-466-1117** **Fax 812-466-5356**

Payment: Check ☐ VISA/MC ☐

Card No. _____ Exp. Date _____

Signature _____

Circle 285 on Inquiry Card.

Polaroid

Polaroid Corporation introduces a new product to its family of Circular Polarizer Filters for computer monitors. The CP-Workstation Filters provide the ultimate in glare reduction and contrast enhancement by utilizing circular polarizing technology along with top quality, durable optical glass and coatings. The CP-Workstation also includes a transparent conductive coating to reduce Electromagnetic Interference for electric field radiation and eliminate static. The CP-Workstation is an optical quality glass filter with conductive coating, designed to fit 16" to 21" monitors.

Polaroid produces a full range of optical quality anti-glare filters in glass and triacetate to fit most monitors from 9"-21".

Polaroid Corporation, Polarizer Division, N2, 1 Upland Road, Norwood, MA 02062
1-800-225-2770 Fax 617-446-4600

Circle 253 on Inquiry Card.

ROBOFAX

• SALES/MARKETING • CUSTOMER SUPPORT
• PUBLIC INFORMATION • 900 NUMBERS

YOUR 24-HOUR SALES ASSISTANT



800-292-7771
ROBOFAX DEMO LINE: 800-925-7626

ROBOFAX EZ.....$995 Single-line, one call PC kit
ROBOFAX..... $2,995 Multi-line,two call PC kit

ADD★ON AMERICA

433 N. MATHILDA AVE. • SUNNYVALE, CA 94086 • (408) 746-1590 • FAX (408) 746-1593

Circle 226 on Inquiry Card.

Add-In Boards



LOW COST Interface & Data Acquisition/ Control Cards for PC/XT/AT

IEEE-488 Card [PC488A/C].....$145/295

- Includes DOS Device Driver & Sample Comm. program
- PC488C card contains Built-In Bus Analyzer hrdwr & sftwr

RS-485/422 Card [PC485A/B].....$125/175

- Serial Async. Comm up to 4,000 ft; 2 or 4 wires; NS16450
- PC485B card has 2 independent channels (UARTs); Com1-4
- Protected vers. uses trans. volt supress. & auto reset fuses
- High speed AF version (256KB) – $165; All include software

Digital I/O & Counter [PCL720] $175

- 32 Digital Input / Output Channels, 3 channel programmable counter/timer; User-configurable clock source; Breadboard area

12BIT A/D/A Digit. I/O [PCL711s] $295

- 8 single-ended Anlg IN, 2 Anlg OUT; AD574; Conv. time 25µs
- 16 Digital Input/Output channels; Wiring Terminal Board incl.

12Bit A/D/A & Counter [PCL812].....$395

- 16 single-ended Anlg IN, 2 Anlg OUT; AD574; Conv. time 25µs
- ± 10V, ± 5V. ± 1V; Programmable counter/timer (8254)
- DMA and interrupt capability; Utility software for Basic incl.

Call for more Information. MC/VISA/AMEX

B&C MICROSYSTEMS INC.
750 N. Pastoria Ave. Sunnyvale, CA 94086 USA
Tel: (408) 730-5511 Fax: (408) 730-5521

Circle 229 on Inquiry Card.

Industrial PCs and Data Acquisition

- Industrial Workstation and Monitor
- Industrial Computer Chassis
- All-in-one Plug-in CPU Card
- RAM/ROM Disk Card

- Data Acquisition & Control Series
- Industrial I/O Series
- IEEE-488 Interface Card
- 8/16 Port RS232 Interface Card
- Application Software Package

AXIOM® MEASUREMENT & CONTROL
AXIOM TECHNOLOGY CO., LTD.
20418 East Walnut Drive Unit H Walnut, CA 91789, U.S.A.
TEL: 714-598-9495 FAX: 714-598-9975

Circle 292 (RESELLERS: 293) on Inquiry Card.

ROMDISK™

DISK AND DRIVE EMULATORS

New PCE/2-SR SRAM Emulator

- Multiple models. EPROM, flash, battery-backed SRAM technologies
- Capacities from 180K to 14MB, single and dual disk emulation under MS DOS
- Autobooting – On-board programming

CURTIS, INC.
MS DOS is a trademark of Microsoft
2837 No. Fairview Ave. • St. Paul, MN 55113
612/631-9512 FAX 612/631-9508

Circle 234 on Inquiry Card.

World Radio History

VOICE MASTER KEY® SYSTEM II

VOICE RECOGNITION & SPEECH RESPONSE
FOR IBM PC/XT/AT/386, PS/2, LAPTOPS, COMPATIBLES

FOR PRODUCTIVITY, PRESENTATIONS, SOFTWARE DESIGN, ENTERTAINMENT, LANGUAGE TRAINING, EDUCATION, MORE...

SPEECH/SOUND RECORDING AND PLAYBACK. Desktop Audio sound editing allows you to create custom sound applications. Variable sample rate (to 20 KHz) and compression levels. A four-voice music synthesizer is included also!

VOICE RECOGNITION TSR utility allows you to add voice command keyboard macros to your CAD, desktop publishing, word processing, spread sheet, or entertainment programs. Up to 64 voice commands in RAM at once—more from disk.

HARDWARE SYSTEM contains built-in speaker with separate volume and tone controls, external speaker and headphone jacks. Enclosure made of sturdy vinyl-clad steel. Attaches to parallel printer port without affecting normal printer operation (U.S. Patent 4,812,847). Headset microphone, printer cable, 9 volt AC adapter (110 volt UL/CSA listed), and comprehensive user manual included.

QUALITY THROUGHOUT. MADE IN USA. ONLY $219.95
ORDER HOTLINE: (503) 342-1271 MON-FRI, 8 AM TO 5 PM PST

Visa/MasterCard, company checks, money orders, CODs (with prior approval) accepted. Personal checks subject to 3 week shipping delay. Specify computer type when ordering. Add $5 shipping charge for delivery in USA and Canada. Foreign inquiries contact Covox for C&F/CIF quotes. OEM configurations available.

30 DAY MONEY BACK GUARANTEE IF NOT COMPLETELY SATISFIED.

CALL OR WRITE FOR FREE PRODUCT CATALOG

COVOX INC.
675 Conger Street
Eugene, Oregon 97402

TEL (503) 342-1271
FAX (503) 342-1283
BBS (503) 342-4135

Circle 232 (RESELLERS: 233) on Inquiry Card.

"The Disk is DEAD!"

The disk reliability problem is widespread.

There IS an Alternative!

Dust, moisture and vibration kill rotating disks every day. **Instant Access™ No Motion™** solid state memories offer extremely high reliability, light speed access and hermetically-sealed data integrity. **Instant Access** is available in FLASH EEPROM and NVRAM and is programmable in DOS or WINDOWS. Rely on **Instant Access**—the demonstrably superior **No Motion Memory**.

Now Available In S-RAM!!

APPLICATIONS
- Mission Critical
- High Security
- Banking
- Military
- Mobile
- Diskless PC
- Hazardous Environments
- Communications

VISA Master Charge AMEX

PRODUCTIVITY ENHANCEMENT PRODUCTS, INC.

SEE US AT COMDEX!

26072 Merit Circle, Ste. 110 • Laguna Hills, CA 92653
1(800) 451-DISK • FAX (714) 348-1310

Circle 289 on Inquiry Card.

Direct Stepper Drive from PC

- Direct drive
- High speed up to 25,000 s/s
- Power supply fits in PC drive bay
- FREE HPGL interpreter
- 2D and 3D linear and circular interpolation

Call (613) 359-1029 Fax (613) 359-1147

STRADA AUTOTECH INC.

From **$199** Qty 1

P.O. Box 188, Elgin, Ontario, Canada K0G 1E0

Circle 257 on Inquiry Card.

Fax for fast response!

VMAX® TEMPUSTECH, INC.

TEL: (800) 634-0701
FAX: (813) 643-4981

295 Airport Road
Naples, FL 33942

VMAX® DE2 SOLID STATE DISK DRIVE

- FAST, faster than hard disk drive access
- One year warranty/ Made in the U.S.A.
- 100% DOS compatible, bootable
- DURABLE, withstands harsh environments
- PC/AT Bus, fits standard expansion slot
- Software included — program SRAM & FLASH on board
- SMALL size/LOW price
- $135 qty.1; Quantity Pricing Available

Circle 287 on Inquiry Card.



PC POWER SUPPLY MONITOR

WINTEK®

Wintek Corporation
1801 South Street
Lafayette, IN 47904

(800) 742-6809 or (317) 448-1903

Designed as a diagnostic aid for PC/XT/EISA systems, the Wintek PC Bus Power Monitor Card ($195) provides a quick way of checking the power supply in a personal computer. LEDs provide a real-time indication of power quality, as well as remembering momentary out-of-tolerance operation. A deluxe model ($249) has an audible alarm, a system clock monitor, and a refresh signal monitor.

Circle 271 on Inquiry Card.

PC/AT Dual Port Comm. Coprocessor

GMM Sync2/CCP™

- High Performance 16 bit Microprocessor.
- 80X86 code compatible
- 1 or 2 Serial Ports with Full Duplex DMA
- Uses 8530 or 85C30 SCC chip
- 256k Dual Ported RAM (512k, 1Meg - optional)
- 8k, 16k, 32k, 64k Window Size (Programmable)
- RS232/RS422/RS485/V.35
- SOURCE CODE DEBUGGER Kit Available.

GMM Products Are All Made in USA.

Other PC/AT & PS/2 (MCA) 8530 based products available. Extremely competitive pricing. Call for additional information

(714)752-9447 FAX (714)752-7335

GMM Research Corporation
2938 S. Daimler St., Suite 121
Santa Ana, CA 92705

Circle 238 on Inquiry Card.

World Radio History

Communications/Networking • Computer Systems

PCSS-8I Intelligent Serial Coprocessor



- On board processor handles serial communication tasks.
- 32K-128K Dynamemory.
- Eight ports per board.
- High performance – low cost!
- DOS, SCO XENIX, SCO UNIX drivers included.

To order call toll-free 1-800-282-GTEK(4835)

GTEK, INC.
Development Hardware & Software
P.O Box 2310.
Bay St. Louis, MS 39521-2310 U.S.A.
Mississippi & Technical Support (601) 467-8048 • Fax: (601) 467-0935

Circle 240 on Inquiry Card.

THE BEST NAME IN IEEE-488 INTERCONNECT PRODUCTS

L-com is your ONLY complete source for creative IEEE-488 wiring solutions.

L-com has not one, but seven IEEE-488 cable series. Includes all molded, aluminum shells, and in-line types for easy entry into PC ports.

L-com is the only provider of a full series of IEEE-488 adaptors. More than twenty varieties in all, such as slimline, bulkhead, reversers, & right angle. Many other accessory items also!

Call or Fax today for further information.

Call for FREE catalog! Specify - BYTE

L-com Inc. TEL: 508-682-6936 FAX: 508-685-6467

Circle 288 on Inquiry Card.

BLAST YOUR MESSAGE THRU!

Voice Mail • Telemarketing • Call Processing

Transform your PC/XT/AT/386 into a multi-line processing command center. Intelligently process your sales, inquires, and messages. Complete package.

(Developer/OEM packages available)
VISA—MC—AMEX—COD

Multi-Line (Voice Solution) **$995**
SINGLE LINE (BigmOuth) **$295**

For Sales or Information:
Call 1-800-685-4884
CALL: (510) 522-3800 • FAX: (510) 522-5556

TALKING TECHNOLOGY, INC.
1125 ATLANTIC AVE. • ALAMEDA, CA 94501

1992 TALKING TECHNOLOGY

Circle 259 on Inquiry Card.

AT Systems in ROM

Single Board Computers



- Run DOS from ROM
- PC code compatible
- Large memory space
- Passive backplanes

Develop code on a PC. Use standard PC cards for expansion. Burn your code and DOS into ROM and run on our CPU cards.
KS6 CPU: NEC V53 uP(286eq). 5 serial, 2 Parallel, Clock, AT bus Max of 4M Ram, 2M Rom, 512K battery backed Sram. $349-q1 oem
KS3 CPU: V40 uP. 3 Serial, 2 Par., Clock, Flop, Keybd. $249-q1.

303-444-7737
Fax 303-786-9983 655 Hawthorn Ave., Boulder CO 80304 **KILA**

Circle 245 on Inquiry Card.

Computer Systems

50 MHz 80486 ISA/EISA 23 MIPS

FEATURES
- 64/256K Write Back Cache
- Burst Mode Design
- Shadow RAM on Video & BIOS
- 64MB 32 Bit Memory Expansion
- Baby-size with Eight Expansion Slots
- UNIX, OS/2 & Novell 100% Compatible
- One Year Full Warranty
- Made in the USA

ISA SYSTEM BOARD

MODEL	CACHE	MIPS	OK	4M
486/50	64K	22.4	CALL	CALL
486/33	64K	14.9	995	1195
486/25	64K	11.2	895	1095
486/20SX	64K	9.0	695	895
386/40	64K	9.8	525	725
386/33	64K	8.3	495	695

*256 Cache Available

Complete Desktop System with 1.2 MB Floppy HD/Floppy Controller, 101 Keyboard and 4MB Memory

MODEL	BASE	MONO	VGA
486/50	CALL	CALL	CALL
486/33	1595	1770	2045
486/25	1495	1670	1945
486/20SX	1295	1470	1745
386/40	1125	1300	1575
386/33	1095	1270	1545

*FCC, UL & CSA Available
*Tower–Add $200 Hard Drive Available

Third Generation Feather Light SONIC 386/20SL NOTEBOOK

- Latest Intel 386/20SL Chip Set
- Intelligent Power Management
- Total Weight 4.8 lbs.
- 2 Mb of RAM (Max 8 Mb)
- 0/16/64 KB Smart Cache Architecture
- Crisp 640X480 VGA Display
- 1.44 Floppy Disk
- Whisper Quiet 40 MB Hard Disk 60/80 Mb Optional
- 1 Serial, 1 Parallel Port
- 80 Key Keyboard with Full 101 Key Emulation
- J-Key Mouse Design
- 3 Hours Battery Pack
- FCC Class B Pending

386SX with IDE/2S/1P

BOARD	
386SX-16	210
386SX-20	245
386SX-25	248

BARE BONE SYSTEM UL/FCC B

386SX-16	350
386SX-20	385
386SX-25	388

HARD DRIVE

QUANTUM IDE 52MB	215
QUANTUM IDE 105MB	339
QUANTUM IDE 200MB	699

TECHNOLOGY POWER ENT., INC.
47273 Fremont Blvd., Fremont, CA 94538
Tel: 510-623-3818 FAX: 510-623-3840

Circle 265 on Inquiry Card.

LOW–LOW–LOW

Computer Systems / Notebook / Complete Network Solutions

IBM Apple COMPAQ AST
ALR EVEREX and others

SURAH 386/486 ISA/EISA Compatible Computers
AMI/Mylex Motherboards
IOMega Bernouli Drives
CD ROMS Tape Backup
Mini-SCSI • Parallel to SCSI Host Adapter
Trantor Systems

LAN Cards/other products
3COM, Novell, Anthem, Gateway, Proteon & others
Hard Drives/Floppy Drives
IDE (Netware Ready)/SCSI
Also available for IBM, Compaq, Apple
Memory/Upgrades
DRAMS, SIMM Modules
Math coprocessors
Laser Printers/Scanners
Plotters/Digitizers/Software

SURAH inc.
44912 Osgood Road, Fremont CA 94539 *USA*
Phone: (510) 651-5101 Fax: (510) 651-5241
1-800-543-1001 Nationwide Orders
UK Fax: 081-855-9657

Circle 258 on Inquiry Card.

Rackmount Solutions

RACKMOUNT COMPONENTS – QTY 25 PRICING

Rackmount Chassis 19"x7"x17"	$183
Rackmount VGA Monitors	$531
Rackmount Monitor Shelf	$113
Rackmount Keyboard Shelf	$88

RACKMOUNT PLATFORMS – Qty 1 Pricing

RMS286-12	$549	RMS386-33	$1095
RMS386SX-16	$795	RMS486-33	$1695

System Platforms include 7" Rackmount Chassis, 200W Power Supply, Motherboard, 1.0MB Memory, IDE, FDC, 2-Ser, Par, 1.2MB or 1.44MB Floppy Disk Drive, 1 Year Warranty

RACKMOUNT CHASSIS – 15 Models up to 20 Board Slots
SLOT CPU BOARDS – 486, 386, 386SX, 286
RACKMOUNT MONITORS – Super VGA and Monochrome
RACKMOUNT CABINET – Modular from 21" to 96" high

VALLEY TECHNOLOGY INC.
2468 Armstrong Street
Livermore CA 94550
(510) 447-2030 FAX: (510) 447-4559

Circle 275 on Inquiry Card.

World Radio History

Data Acquistion • Disk & Optical Drives

NEW, FREE 288 PAGE DATA ACQUISITION & CONTROL CATALOG/REFERENCE GUIDE FOR IBM PC/XT/AT, PS2, MICROCHANNEL COMPUTERS AND COMPATIBLES.

NEW 1992 CATALOG

* A/D BOARDS
* SIGNAL CONDITIONING
* COMMUNICATION
* INDUSTRIAL CONTROL
* PC INSTRUMENTS
* SCIENTIFIC SOFTWARE

KEITHLEY METRABYTE DATA ACQUISITION

SEND TODAY FOR YOUR FREE 288 PAGE KEITHLEY METRABYTE CATALOG
440 Myles Standish Blvd., Taunton, MA 02780 Tel:(508)880-3000 TLX:503989 Fax:(508)880-0179

Circle 248 on Inquiry Card.

The Intelligent Solution For Data Acquisition

DAP 2400™ Data Acquisition Processor™

ANALOG I/O
DIGITAL I/O
- Inputs to 235K samples per second
- Outputs to 250K samples per second

FFT and FIR-filtering
Digital Signal Processing at 10 MIPS
16 MHz CPU with DRAM to 512K

20 MHz DSP with SRAM to 96K
DAPL™ Operating System
- 100+ standard commands
- Custom commands in C

Send for FREE catalog.
Or call us at (206) 453-2345

MICROSTAR LABORATORIES™
2265 116th Avenue NE
Bellevue, WA 98004
FAX (206) 453-3199

Circle 250 on Inquiry Card.

Put Your Hard Disk In Orbit

With The PCDC-14 Hard Disk Caching Accelerator!

- Makes your computer run 10 times as fast!
- Caches, Reads and Writes!
- No drivers or TRS's required!
- High Performance/Cost Ratio!
- Less wear on your hard disk!
- Non-volatile memory becomes permanent part of hard disk!
- Satisfaction Guaranteed!

OEM & Dealer Inquiries Welcomed!

To Order Call 1-800-282-4835

GTEK INC.
DEVELOPMENT HARDWARE & SOFTWARE
P.O. Box 2310 • Bay St. Louis, MS 39521-2310 U.S.A.
Fax: 601-467-0935
Mississippi & Technical Support 601-467-8048

Circle 239 on Inquiry Card.

Disk & Optical Drives • Fax Boards/Machines

Get the right connections for $179. The MiniSCSI™ Parallel-to-SCSI Adapter

Add a SCSI port to almost any printer port with our pocket-sized, self-contained **MiniSCSI**. Ideal for laptops, notebooks and systems which can't accommodate a standard SCSI interface, the **MiniSCSI** also lets you relocate SCSI devices easily.

- CD-ROM, hard disk, magneto-optical, SyQuest & Bernoulli support
- SCSI tape support available
- Retains use of parallel port
- Powered by SCSI bus
- Lightweight (only 2.5oz.)
- 2-year parts & labor warranty
- Other SCSI adapters available

"Genuinely interesting hardware department... Good idea"
John C. Dvorak, PC Magazine

"The neatest gadget at the CD-ROM show"
Jerry Pournelle, InfoWorld

TRANTOR®

Call: 510-770-1400

Reseller Inquiries Welcome

Trantor Systems, Ltd.
5415 Randall Place
Fremont, CA 94538-3151 USA
(510) 770-1400 • Fax 770-9910

1992 Trantor Systems, Ltd. All product names are trademarks or registered trademarks of their respective owners.

Circle 274 on Inquiry Card.

NEW **SHARE A SIGEN 250MB PORTABLE TAPE BACKUP & REDUCE COST/USER** NEW

No controller card required. Connects to parallel port. Installs in less than 3 minutes. Great for Laptops. 9.5 MB/min transfer rate.

Capacity
60/100 MB 1/4" cartridge
250/500 MB 1/4" cartridge
1200/2000 MB 4mm DAT

NOVELL®

Supports
DOS, OS/2
Novell 286, 386
Unix, Xenix

Industry standard SYTOS Plus software and for file server based NLM and VAP Tapeware.

SIGEN
Phone (408) 737-3904 • Fax (408) 737-3910

Circle 266 on Inquiry Card.

FAX-O-MATIC™ *plain paper fax solution*

A receive-only fax which prints out incoming faxes on plain paper through a laser printer or inkjet printer. 512K memory saves to 30 pages. Prints at 150 dpi or 300 dpi. Scales to receive legal or A4 European size paper. 2-year warranty. 60-day money-back guarantee.

$399

PC WEEK ANALYST'S CHOICE

TALL TREE SYSTEMS
2585 E. Bayshore Road, Palo Alto, CA 94303
(415) 493-1980 Phone (415) 493-7639 Fax

Circle 260 on Inquiry Card.

World Radio History

Keyboards • Laptops & Notebooks • Mail Order

1.1 gigabytes in a Toshiba laptop?

Not yet. But check with us in mid '92 . . .

Right now, we can install the capacity you need, from the smallest Toshiba notebook to the largest laptop.

Our faster (12-25 ms access time), higher-capacity drives won't add bulk or weight. Some are even lighter than the original drives.

Laptop Solutions' unique upgrade packages are thorough and complete. They're installed by appointment only, with a guaranteed 48-hour turn-around, including 24-hour burn-in and stringent testing to industry standards.

Finally, you can put your laptop to work, the way you work!

Quantity discounts available.

UP TO 510 MB FOR LAPTOPS

DOS • OS/2 • UNIX • WINDOWS

UP TO 180 MB FOR NOTEBOOKS

(800) 683-6839

Laptop Solutions, Inc.

10700 Richmond Ave., #114
Houston, Texas 77042
Phone: (713) 789-0878
FAX: (713) 789-8177

Circle 290 on Inquiry Card.

Memory/Chips/Upgrades • Misc. Hardware • Multimedia

Why Pay More For Memory?

MEMORY UPGRADES for Laptops, Notebooks, Desktop computers, and Laser Printers at the LOWEST PRICES!

Save BIG on memory for:
Apple • AST • ALR • AT&T • Brother • Canon • Compaq • Epson • HP Laser & Vectra • IBM • Kyocera • NCR • NEC • OKI • Packard Bell • QMS • Samsung • Sanyo • Sun • TEC • TI • Toshiba • Zenith • Simms • SIPS & Drams

Five-year warranty. Great customer service, quality products, prompt delivery, and the best prices are just a toll-free phone call away...VOLUME DISCOUNTS FOR INSTITUTIONAL, CORPORATE AND GOVERNMENT ACCOUNTS. INTERNATIONAL INQUIRIES WELCOMED.

800-ANA-SIMM or 1-805-984-5683
or in Canada 800-231-SIMM Call Now!
ANACAPA MICRO PRODUCTS, INC.

Circle 284 on Inquiry Card.

ICs PROMPT DELIVERY!!! Same day shipping (usually)
Quantity one prices shown for February 23, 1992

Memory for almost ALL computers

HT 3007-25 $175 | 00867-38 CYRIX $195 | 00387 40 CYRIX $300

DYNAMIC RAM

4M Board for hp LJ's w/2MB			$125.00
SIMM	4Mx9	70 ns	150.00
SIMM	1Mx9	60 ns	49.00
SIMM	1Mx9	80 ns	42.50
4 Mbit	4Mx1	80 ns	25.00
4 Mbit	1Mx4	80 ns	28.00
1 Mbit	1Mx1	70 ns	4.70
41256	256Kx1	80 ns	1.85
41256	256Kx1	100 ns	1.70
44256	256Kx4	80 ns	5.25
4464	64Kx4	100 ns	1.50

EPROM

27C4001	512Kx8	150 ns	$28.00
D28F010	128Kx8	150 ns	24.00
27C1000	128Kx8	200 ns	6.30
27C512	64Kx8	120 ns	4.75
27128	16Kx8	250 ns	3.40

STATIC RAM

1 Mbit	128Kx8	Real	$21.50
62256LP	32Kx8	100 ns	5.60

Sat. del. on Fed-Ex orders received by Th: S-2 1-4 lbs $5.25 Fr P-1 1 lb $17.00
FED-EX COD +$5.00

OPEN 6 ½DAYS, 7:30 AM-8:00PM • SHIP VIA FED-EX ON SAT.

8028/XL INTEL $85 | 80387DX INTEL $195 | 80387-33 INTEL $195

MICROPROCESSORS UNLIMITED, INC
24,000 S. Peoria Ave., Beggs, OK 74421
MasterCard/VISA or UPS CASH COD • No minimum order. $1 for packing materials. Shipping and insurance extra.
(918) 267-4961

Circle 249 on Inquiry Card.

CUSTOM KEYBOARD PRODUCTS

- Custom Key Imprinting—all brands!
- Custom Colored keys for IBM®, DEC®, Wyse®, Key Tronic®, Cherry®, and more!
- Full color keyboard templates made to your exact specifications.
- Custom and stock keytop label kits for software support & languages.
- Custom membrane & full-travel keyboards.
- Express turnaround services.
- A total line of keyboard enhancements.

CUSTOM HOTLINE 800 937-1337
from the leader in Keytop Innovations™

P.O. Box 230 • Dept. BYTE
Cornville, AZ 86325
602 634-7515
FAX 602 634-4620

Hooleon CORPORATION

Circle 241 on Inquiry Card.

SCSI BUS CONDITIONER

- Conditions and Regenerates SCSI Bus
- Isolate Noisy Cables & Peripherals
- Extend Distance to Peripherals
- Increase SCSI Bus Performance
- Supports "Fast SCSI" (10 MBytes/sec)
- SCSI 1 and SCSI 2 Compatible
- No additional software required

$ 295.00

CALL TODAY 1-800-624-5808

APPLIED CONCEPTS

30 DAY MONEY BACK GUARANTEE

APPLIED CONCEPTS, INC.
5350 Eastgate Mall
San Diego, CA 92121
TEL: 619-453-0090
FAX: 619-453-6715

Circle 228 on Inquiry Card.

Industrial PC Solutions

RELIABLE, AFFORDABLE, FLEXIBLE

- Industrial PCs
- 286/386/486 CPU Cards
- RAM/ROM Disks
- Industrial I/O Cards
- PC-Bus Card Cages
- Rack Mount Keyboards

1-800-800-6889
(In California 408-293-6786)

Industrial & Lab Automation with PCs

ADVANTECH

1310 Tully Road, #115, San Jose, CA
FAX: 408-293-4697

FREE! New 140-page PC-based industrial automation reference guide for your system and OEM needs.

Circle 227 on Inquiry Card.

Avocado Computer Video, Inc.

Everything you ever wanted to know about video but didn't know where to ask in a free catalog of computer-related video products. Videotapable VGA cards, video digitizers, splitter amplifiers and extension cables, specialty software for titling and imaging, special effects. Applications range from hobby to Hollywood, and training to research. Our special projects department is unfazed by unusual requests.

Contact Avocado Computer Video, Inc.,
P.O. Box 1655, Wheaton, MD 20902.
We Speak Video
(301) 942-0878
1-800-627-3432 FAX: (301) 942-8076

Circle 277 on Inquiry Card.

World Radio History

REDUCE PC FAN NOISE BY 98%...

THE SILENCER is an electronic device which monitors the internal temperature within your PC/Laser Printer and reduces the fans speed (and noise) to ensure proper cooling is achieved - BUT NO MORE . . . Typical noise reduction is 80% to 98% . . .

Easy to install; built-in fail-safe, and 3 year warranty. *THE SILENCER* has to be heard (or not) to be fully appreciated. Take advantage of our 30 DAY NO RISK TRIAL OFFER . . . and join the thousands of PC users worldwide who now enjoy *THE SILENCER*.



Mini-12VDC Silencer	$69.95
Fail-Safe DC-Silencer	99.95
Laser Printer Silencer	99.95
AC-Fan Silencer	99.95

To Order Call 1-800-SILENCE

QUIET TECHNOLOGY INC.
P.O. Box 8478
Port St. Lucie, FL 34985

Dealer Info./Fax: 407/335-2113

Circle 278 on Inquiry Card.

IMAGING CARDS

MODEL 1-800-292-1160



Video Framegrabbers for the XT/AT/386

- Real time grab/display
- Complete with software
- 60 & 50 Hz. Video
- Quality since 1987!
- Money back guarantee

-512/24 512x480x24 - ***New*** Full 24 bit color board, mult. in, 24 bit RGB out ***$795***

-512 512x480x8 - ***Advanced*** grayscale board. Multi res/multi image, 4 inputs, in/out LUTS, dual ping-pong buffers, RGB out ***$795***

-02 256x240x8 Workhorse 8 bit grayscale. 2 inputs, 24 bit RGB out, cursor ***$495***

-03 256x240x6 Economy 6 bit version of -02 above ***$395***

MC/VISA/COD

Control Vision

Box 596 Pittsburg, KS 66762
316-231-6647 Fax: 231-5816

Circle 231 on Inquiry Card.

COMPUcom

14,400 - 57,600 bps *Speed* Modem™ ...$279

V.32bis, with a raw speed of 14,400 and v.42bis, with up to 4:1 data compression, the *Speedster*™ is a price/technology breakthrough ... just what you would expect from CompuCom. It also features CSP, MNP-5, and Fax option. It's made in USA, has a 30 day money back guarantee and a 5-year warranty. **BYTE** magazine said our CCC modem was "a real deal"*... well we've done it again. The *Speedster* is setting new standards for value and *speedy* performance. *See for yourself!*

(415) 499 7600 *CALL NOW* (800) 748 6840 Fax (415) 499 3366

Circle 230 on Inquiry Card.

MultiMedia Presentations

Created Quickly and Inexpensively

Mix...

- **Full Motion Real-Time Videos**
- **Voice, Music and Audio effects**
- **High Speed Graphic Animations**
- **Text Files and Documents**
- **User Interactive Icons**

Everything you need to create exciting professional MultiMedia PC presentations using your 286/386 PC and your data files is provided by this new MULTIMEDIA TOOL KIT. Yes, even 30 frames/second full motion video, high quality audio, voice, graphics and text can all be mixed and edited into high impact MultiMedia presentations with this user-friendly hardware/software package. The finished MultiMedia presentations can be played-back on any PC equiped with our low cost MP-1500 parallel port audio adapter.

MEdit-2010: **Half-size board (or external peripheral unit for parallel port), development tool kit, Hi-Fi speaker, demos and more...** **$479.95**

PC Audio Playback for... $49.95

Now add High Quality Audio Output to your PC. Playback any audio file created for the PC. This Audio Adapter connects to the Parallel Port which makes it perfect for Laptop or Notebook MultiMedia Presentations. The MP-1500 includes Audio adapter, Speaker + amplifier and software, all for this price!

U.S. Patent Pending 1992

MultiMedia COMPUTER SYSTEMS LTD.

Phone: **708-673-8488**
Fax: **708-673-9244**
Vmail: **708-673-8705**
Skokie, IL 60076

Circle 261 on Inquiry Card (RESELLERS: 262).

New! PC VOICE POWER

Get up to 30 minutes of Voice Recording per 1 MByte!

Add Voice Comments to Text/Spreadsheets

Create "talking" text/spreadsheet/graphics for better communication. Transport the "talking files" by diskette, LAN or modem. The PC internal speaker may be used for playback output without special hardware. Reading and hearing documents is better!

DVA-1020: Half-Size board or Peripheral unit and Software.....$249

Portable/Desktop PC Dictation/Transcription

Easily converts any portable/desktop PC to a dictation system with enormous recording capacity. Standard 40MB hard drive gives the user up to 20 hours of dictation time. The package includes a user friendly transcription software for typist. Dictation files can be saved or transported by diskette, LAN or modem.

DVD-1045: Half-Size board or Peripheral unit and Software.....$279

Create Professional Voice Mail Systems

All the basic Voice mail/messaging functions are provided in this package including the ability to record, playback, tone decoding and more. The routines can be provided for "C" or "Pascal" language programmers. Up to 24 channels can be supported on 286/386 PC.

DVM-1001: 1-Channel half-size board + Development Package..$495
DVM-1004: 4-Channel full-size board + Development Package...$895

U.S. Patent Pending 1992

MultiMedia COMPUTER SYSTEMS LTD.

Phone: 708-673-8488
Fax: 708-673-9244
Vmail: 708-673-8705
Skokie, IL 60076

Circle 263 on Inquiry Card (RESELLERS: 264).

World Radio History

Multimedia • Programmable Hardware

Video Capture and Image Processing

- Low-cost
- Frame Grabber
- S/EVGA-Compatibility
- 8/16 bit Capture
- Full IP Functionality
- Video Calibration
- Radiometric Calibration
- Device Independent

- Windows 3.0
- Easy-to-use

Imaging Automation 603-598-3400 • Fax: 603-598-3422

Circle 279 on Inquiry Card.

IEEE 488.2



Hardware for IBM PC/AT, Micro Channel, Sun, Macintosh, DEC, and NeXT.

Software for DOS, Windows, UNIX, VMS, menu- and icon-driven environments.

IEEE 488 extenders, analyzers, converters, analog I/O, and digital I/O.

Call for your free IEEE catalog

IOtech

IOtech, Inc. • 216.439.4091 • Fax 216.439.4093

Circle 244 on Inquiry Card.

8051 IN-CIRCUIT EMULATOR

NICE-51 from $1195.00 — Hook Pod available



- Up to 12 MHz real time emulation without intruding on any of your device's resources.
- SFR, Code Memory, External Data , Internal Data and Bit Address can all be directly viewed and edited using the full screen editor.
- Down-loads data to external data memory and processes BIN, HEX, and SYM9OL files in code memory.
- Up to 10 conditional software breakpoints and 64K hardware breakpoints
- 16K deep, 48 bit real time trace buffer records Address Bus, Data Bus, Control Bus, and 18 bit external signal.
- Integrated programmer for EPROMs and 8751 available.
- 1-year warranty, 30-day money-back guarantee.

CALL TODAY FOR MORE INFORMATION.
Distributors are welcome!

Tribal Microsystems Inc. Tel (510) 623-8859
44388 S. GRIMMER BLVD., FREMONT, CA 94538 FAX (510) 623-9925

Circle 267 on Inquiry Card (RESELLERS: 268).

EPROM EMULATOR / PROGRAMMER

• High powered and versatile unit combines an emulator with a programmer to allow one step firmware design or trouble shooting. • Operates with any computer or terminal using RS-232 port. • Emulates, programs, copies and verifies 2716-27512 EPROMS and 2816-28256 EEPROMS (no emulation). • Easy to master emulation & programming features. • Battery backed up memory allows unit to auto-run user's firmware on startup. • Simple to use byte exchange feature allows microprocessor register dumps and user break points. • Ideal development or service tool for multi-processor users. • Light weight and portable unit easily fits in tool box or brief case.



$499 Phone: 902-468-5911
Fax: 902-468-5912

OMNITECH ELECTRONICS INC.
10 Akerley Blvd., Dartmouth, Nova Scotia, Canada B3B 1J4

Circle 291 on Inquiry Card.

Programmable Hardware

POWERFUL • AFFORDABLE INSTRUMENTS

200 MHz Logic Analyzer

- 400 MHz max sampling rate
- up to 128 channels
- 16K samples/channel
- 16 level triggering
- Variable threshold voltage
- Sophisticated triggering
- FREE software updates

$799 - LA12100 (100 MHz)
$1299 - LA32200 (200 MHz-32-ch.)
$1899 - LA32400 (400 MHz-32-ch.)

Price is complete. Pods and software included.

Universal Programmer

PAL
GAL
EPROM
FLASH
EEPROM
PROM
87xxx...

$475

- 16V8, 20V8, 22V10, GALs
- 26V12, 20RA10, 18V10 GALs
- 2716-27040 EPROMs
- 87xxx MICROs
- EEPROMs (incl. 8 pin serial)
- 16 bit EPROMs
- Byte Split/Merge (16 & 32 bit)
- JEDEC, INTEL HEX, Motorola 'S' files
- Dallas NVS RAM programming
- FREE software updates on BBS

Call - (201) 808-8990
Link Computer Graphics, Inc.
369 Passaic Ave., Suite 100, Fairfield, NJ 07004 FAX: 808-8786

Circle 247 on Inquiry Card.

UNIVERSAL PROGRAMMER, EMULATOR, & TESTER

TUP-400 $745.00 *NEW*
TUP-300 $645.00

- New Improved hardware and software.
- The most complete PC-based Universal Programmer, Programs PLD (PAL, GAL, FPL, EPLD, PEEL, MAX, MACH...), E(E)PROM, (up to 16Mbit), Flash EPROM, BPROM, Special PROM, MPU (87XX, 68XX, Z8, PSD301, PIC16XX, TMS320EXX, UPD75PXXX, HD637XXX...).
- Covers DIP, PLCC, QFP, SOP, and PGA with 8 to 84 pins. Gang Progamming adapters available also.
- EPROM EMULATION capability.
- Tests digital ICs and DRAMs (SIMM/SIP adapter available).
- Free software updates and new device added upon request.
- IC Manufacturers' approval.
- 1-year warranty, 30-day money-back guarantee.

CALL TODAY FOR MORE INFORMATION.
Distributors are welcome!

Tribal Microsystems Inc. Tel (510) 623-8859
44388 S. GRIMMER BLVD., FREMONT, CA 94538 FAX (510) 623-9925

Circle 269 on Inquiry Card (RESELLERS: 270).

SUPERPRO® now $699 (US only)

Super Value Universal Programmer
Include Free!!!
4 SOCKET ADAPTER ($125),
or PAL COMPILER ($95),
or EPROM ERASER ($95)

- Easy to use menu driven S/W
- Universal programming for Flash E(E)PROM, Bipolar PROM, PAL, GAL, EPLD, & microcontroller, etc.
- Test ICs (TTL,RAM)
- Life time free S/W updates on BBS & 1 year H/W warranty
- Developed & made in U.S.A.

EPROM programmer
• ROM MASTER : $149
Low cost universal programmer
• UNIPRO : $399

764 San Aleso Avenue Sunnyvale, CA 94086 (408) 745-7974
FAX 745-1401 BBS 745-7256

XELTEK

Circle 272 on Inquiry Card.

World Radio History

Programmable Hardware • Tape Drives

Instant Microcontroller + Instant C = Instant New Product

Use our Little Giant™ and Tiny Giant™ miniature microprocessor-based computers to instantly computerize your product. Our miniature controllers feature built-in power supplies, digital I/O, serial I/O (RS232 / RS485), A/D converters (to 20 bits), solenoid drivers, time of day clock, battery backed memory, watchdog, field wiring connectors, and more! Designed to be easily integrated with your hardware and software. Priced from $159. Core modules as low as $59. Low cost, interactive Dynamic C™ makes serious software development easy.

Z-World Engineering
1724 Picasso Ave., Davis, CA 95616 USA (916) 757-3737
Fax: (916) 753-5141 Automatic Fax: (916) 753-0618
(For automatic fax call from **your fax**, request catalog #18)

Circle 273 on Inquiry Card.

9 Track Tape Subsystem for PC/XT/AT/386/PS2

- **Best Quality**
- **Lowest Prices**

800/1600/3200/6250 BPI

CALL 1-800-886-4827

Laguna Data Systems
23151 Alcalde Drive, Suite B-3, Laguna Hills, CA 92653
Tel: 714-586-3010, Fax: 714-586-5538

Circle 246 on Inquiry Card.

PC 9-Track & 3480

- ✔ Widest choice of solutions
- ✔ Modern desktop subsystems
- ✔ Plug-and-play, easy to use
- ✔ Comprehensive software
- ✔ Excellent service and support

Call now for more information and a free catalog.

800-729-8725
OVERLAND DATA
PH: 619-571-5555 San Diego, CA FAX: 619-571-0982

Circle 252 on Inquiry Card.

Tape Drives • UPS • Books/Publications

Desktop 9-Track Tape Subsystem
#1-selling 9-track system on desktop.

Qualstar's low cost 1/2-inch 9-track Streaming tape systems bring full ANSI data interchange to IBM AT, PS/2 or Macintosh, giving your micro the freedom to exchange data files with nearly any mainframe or minicomputer in the world.

Systems include DOS or Xenix compatible software, coupler card and cables. High reliability 1600 or 6250 BPI capability may be used for disk backup as well as data interchange.

QUALSTAR®

Call us today! **For details and to order: Fax (818) 882-4081 Phone (818) 882-5822**

9621 Irondale Ave., Chatsworth CA 91311

©1989 Qualstar Corp.
All product and company names and trademarks are the exclusive property of their respective owners.

Circle 255 on Inquiry Card.

BYTE

Breaks the 4-Color Price Barrier with the Hardware/Software Showcase

See how affordable it is to advertise to BYTE's 500,000 computer professionals in this section!

■

Call for more advertising information:
(603) 924-2695 or (603) 924-2598

COMPUTER BOOKS at a discount

No clubs, memberships, or cards to return. Just the books you want at really great prices!

	COMPARE List	Ours
Windows 3 Secrets, IDG, 838 pgs., 2 disks, 20% off	**39.95**	**31.95**
Windows Systems Programming, Abacus, 1 disk	39.95	34.05
WordPerfect for Windows Bible, SAMS, 1000 pages	29.95	25.55
Winn L. Rosch PC Upgrade Bible, Brady, 608 pages	24.95	21.35
Borland's C++ Program'g for Windows, Bantam, 864 pgs	29.95	25.55
Quattro Pro in Business, SAMS, 400 pages, 1 disk	29.95	25.55
MS-DOS Batch File Programming, TAB, 448 pages	24.95	21.35
Clipper 5: A Developer's Guide, M&T, 400 pages, 1 disk	39.95	34.05
Paradox 3.5 Breakthrough Power, IDG, 842 pages, 1 disk	39.95	31.75
Inside AutoCAD, Spec. Ed., NPR, 1072 pages	34.95	29.85
Using Visual Basic, Addison-Wesley, 432 pages, 1 disk	34.95	34.05
Norton's Windows 3 Power Program'g, Bantam, 960 pgs	29.95	25.55

Call for other titles, or GO CBK on CompuServe.

BOOKS FROM: IDG, Peachpit, Osborne, QUE, NRP, Bantam, Windcrest, Hayden, Brady, MIS:Press, Sybex, Sams, Microsoft, Yourdon, TAB, Microtrend, Abacus, M&T, Prentice-Hall, Addison-Wesley, Wordware

CompuBooks
A Data:PM Company
The Discount Computer Book People
Order Line (800) 880-6818
Hours: 8 AM - 5 PM CST Mon to Fri
512-321-9652 Voice & FAX
Route 1, Box 271-D, Cedar Creek, TX 78612

GO CBK 24 hrs.on CompuServe

Circle 286 on Inquiry Card.

World Radio History

Communications/Networking • Database • Data Acquisition

EM320
WINDOWS

DEC VT320 Emulation for Microsoft Windows 3.0

- 132 column display
- Cut and paste
- Kermit file transfer
- Windows style help
- Local or ANSI color
- Automatic window sizing
- Double high/wide characters
- LAT or TCP/IP support
- Modem dialer/Phone book
- Command language

Diversified Computer Systems, Inc. (303) 447-9251
FAX (303) 447-1406 Tektronix 4105/07 Emulation also available

Circle 236 on Inquiry Card.

PAPER KEYBOARD

Fast, affordable data entry!

OCR, OMR, hand print recognition software
Windows alternative to NCS & Scantron

Data validation, database and DDE integration
HP, Microtek, Pentax and Fujitsu scanners

Datacap Inc. 914 347-7133 Fax: 914 347-7136

Circle 235 on Inquiry Card.

Free Data Acquisition Software Tool

DAQ Designer is a free software tool that helps determine which hardware and software combinations are best for your PC-based data acquisition system. DAQ Designer will (1) ask questions about your application, (2) analyze your answers to determine your system needs, and (3) describe what hardware and software you need to develop your data acquisition system.

National Instruments
6504 Bridge Point Parkway
Austin, TX 78730
(512) 794-0100 • (800) 433-3488

Circle 251 on Inquiry Card.

Education • Engineering/Scientific • Mathmatical/Statistical

EARN YOUR COLLEGE DEGREE AT HOME

B.S. & M.S.
In Computer Science

Get the opportunity and earning power a college degree confers—without leaving home and without spending thousands of dollars.

- Approved for tuition reimbursement by leading corporations
- ALL COURSES BY CORRESPONDENCE
- Most courses interactive
- Approved Ada course available
- Qualified instructors available on telephone help lines

AMERICAN INSTITUTE FOR COMPUTER SCIENCES
The leading edge of learning

Phone: 1-205-323-6191 • FAX: 1-205-328-2229
2101 BYX Magnolia Ave. • Suite 200 • B'ham, AL 35205



Perfect for research papers. See page 80 in the December 91 issue of Byte. 30-Day Money-Back Guarantee.

New
Bibliographies in Seconds!

A powerful database that works with WordPerfect and MS Word for DOS, Windows and the Mac.
Niles and Associates, Inc.,
2000 Hearst Ave. Suite 200
Berkeley, CA 94709
1-800-554-3049

Circle 280 on Inquiry Card.

Make this your "leap" year with

JMP® Statistical Discovery Software



"This application can do the jobs of as many as six separate programs and do them all well. Yet it is not overly complicated or bulky...We believe that JMP is an excellent value and will make short work of all but the most demanding mainframe-oriented data-analysis chores."

MacWEEK

Call today for a free demo disk and Points of Interest from the leading name in data analysis software...SAS Institute Inc. 919-677-8000. Fax 919-677 8166.
JMP is a registered trademark of SAS Institute Inc.
Copyright © 1992

Circle 256 on Inquiry Card.

World Radio History

TURN YOUR PRINTER INTO A PEN PLOTTER

FPLOT™ lets you use your printer as a pen plotter. You get fast, high resolution plots with FPLOT. If you use a CAD or graphics program, you can use FPLOT to produce your plots with the full capabilities of your printer.

- Supports most dot matrix, laser, and ink jet printers
- High resolution output, no jagged lines
- Faster than pen plotters or most laser built-in and cartridge emulations
- Screen preview with zoom and pan
- Supports background plotting
- Device driver mode plots from inside your graphics program
- Stand-alone mode for fastest plotting
- Plot multiple plots with a single command
- Lets you control line thickness
- Full color plotting support
- Plot large plots on wide carriage printers, or as a mosaic
- Compatible with most CAD and graphics programs
- 100% emulation of the HP 7475A pen plotter

List Price $119.00 + S&H 3.00

FPLOT CORP.

24-16 STEINWAY STREET, SUITE 605
ASTORIA, NEW YORK 11103
(718) 545-3505

Circle 237 on Inquiry Card.

Intel Development Tools

Intel Corporation provides a complete line of development tools to support the MCS®-51, MCS®-96, x86, Intel386™, Intel486™, i860™, i960™ architectures. For successful embedded design and development, Intel offers you a complete line of in-circuit emulators, compilers, source-level software debuggers, and lots more. Our Development Tools Catalog lists all our tools in one convenient guide.

Call us at **1-800-874-6835**, FAX us at **503-696-4633**, or contact your local Intel authorized distributor for your copy today.

intel®

Intel Corporation, 5200 N.E. Elam Young Parkway, JF1-15, Hillsboro, OR 97124

Circle 243 on Inquiry Card.

Cross Assemblers, Simulators, Disassemblers

Processor Families:

8051	8096	8048
Z80	64180	6301
6805	6800	1802
6811	6502	68k
8085	6801	Z8

Join Thousands of Satisfied Customers Worldwide.

Call:

PseudoCorp

716 Thimble Shoals Blvd., Newport News, VA 23606
Tel: (804) 873-1947 • Fax: (804) 873-2154

Circle 254 on Inquiry Card.

THE ONLY UNIX AND OPEN SYSTEMS SOURCE



Why look anywhere else?

If it's not in the *1992 UniForum Products Directory*, chances are you won't find it elsewhere. The 1992 Directory features 7,600 products and services from 2,100 vendors. We've got it all. More software. More hardware and peripherals. More developers, consultants, books and headhunters than available anywhere else. Only $95.

To order, call 800-255-5620

UniForum

2901 Tasman Dr., #201, Santa Clara, CA 95054
(800) 255-5620 (408) 986-8840 Fax (408) 986-1645

Circle 282 on Inquiry Card (RESELLERS: 283).

The New Industry Standard in Graphical Menuing Systems!

- Free Form Screen Layout
- Choice of Fonts & Colors
- Automatic Installation
- File Manager
- Icon Editor
- Calculator
- Calendar
- Phone Dialer
- Usage Tracking
- Password Protection
- User Prompting
- NOT Memory Resident
- PCX Background (req. EMS)
- Network Compatible
- Supports CGA/EGA/VGA/Herc
- Does NOT require Windows™

QuikMenu III

$89.95*

30 day money back guarantee

1-800-545-1392

Fax (503) 388-8221

Demo disk available
OEM & Dealer inquires welcome
*Please add $5.00 shipping & handling

354 NE Greenwood Ave., Suite 108 ▲ Bend, OR 97701

Circle 281 on Inquiry Cord.

How to Make Great Color Images!

Image-In-Color software for Windows 3.0 is the most advanced true-color, CGA, VGA or 24-bit image processing system available for the PC! Spectacular functions provide a darkroom on your desk, with precise control of pressure, density and size of retouching tools such as pencil, paint brush, air brush and others. Clone items in an image instantly! Use photographic filters for powerful dimensions in design. CMYK color separations are super fine-tuned and calibrated by Agfa Compugraphic. Supports HSV and RGB color, with intuitive color picking. Supports all popular 16- or 24-bit video boards and scanners including:

IBM 3119, Epson, Microtek, HP, Ricoh, Howtek, Sharp

TRADE IN Z-SOFT'S PAINTBRUSH PRODUCTS FOR FULL CREDIT!

IMAGE-IN INCORPORATED

1-800-345-3540

406 E. 79th St. • Minneapolis, MN 55420 • FAX 612-888-3665
Outside N. America call CPI, Geneva ++41-22-436-800

Circle 242 on Inquiry Card.

World Radio History

THE BUYER'S MART

A DIRECTORY OF PRODUCTS AND SERVICES

THE BUYER'S MART is a monthly advertising section which enables readers to easily locate suppliers by product category. As a unique feature, each BUYER'S MART ad includes a Reader Service number to assist interested readers in requesting information from participating advertisers.

Effective January 1, 1992.

RATES: 3 issues—$625 6 issues—$600 12 issues—$525 13 issues—$500
Prepayment must accompany each insertion. VISA/MC Accepted.

AD FORMAT: Each ad will be designed and typeset by BYTE. Advertisers must furnish typewritten copy. Ads can include headline (23 characters maximum), descriptive text (250 characters is recommended, but up to 350 characters can be accommodated), plus company name, address and telephone number. Do not send logos or camera-ready artwork.

DEADLINE: Ad copy is due approximately 2 months prior to issue date. For example: November issue closes on September 8. Send your copy and payment to THE BUYER'S MART, BYTE Magazine, 1 Phoenix Mill Lane, Peterborough, NH 03458. For more information call Joseph Mabe at 603-924-2656. FAX: 603-924-2683.

ACADEMIC COMPUTING

Transputer Education Kit
Get started with Parallel Processing
$396
Kit Includes ready-to-use PC add-in board with T400 transputer, 1MB of RAM, and PC interface. Complete with Occam2 and C compilers, assembler, source-level debuggers, example programs, and 1500 pages of documentation (incl. schematics). Expandable!
Computer System Architects
950 N. University Avenue, Provo UT 84604
(800) 753-4CSA (801) 374-2300 FAX (801) 374-2306

Inquiry 701.

ACCESSORIES

RADIOACTIVE?
Plot it on your PC with The RM-60 RADIATION MONITOR Serial or printer port. Detects: ALPHA • BETA • GAMMA • X-RAY. MicroR, 1000 times the resolution of standard geiger counters. Excellent for tracking RADON GAS. Find sources. New: Version 2.7 + WINDOWS, Plot: • Background • Cosmic Rays • Clouds • Foods Call/Write for PC MAGAZINE review. • TSR • GM Tube VISA/MC/EURO Phone orders. Not satisfied? Full refund.
800-729-5397 or Tel/Fax: (302) 655-3800
Aware Electronics Corp.
P.O. Box 4299, Wilmington, DE 19807 **$149.50**

CUT RIBBON COSTS!
Re-ink your printer ribbons quickly and easily. Do all cartridge ribbons with just one inker! For crisp, black professional print since 1982. You can choose from 3 models: Manual E-Zee Inker — **$39.50**
Electric E-Zee Inker — **$94.50**
Ink Master (Electric) — **$189.00**
1000s of satisfied users. Money-back guarantee.
BORG INDUSTRIES
525 MAIN ST., JANESVILLE, IA 50647
1-800-553-2404 In IA: 319-987-2976

Inquiry 702.

KEYBOARD, VIDEO, MOUSE
Extension with **EXTENDER**
Splitting with **COMPANION**
Switching with **COMMANDER**
Boosts signals up to 600 feet. Control up to 96 PCs with one keyboard and monitor.
CYBEX CORPORATION
2800H Bob Wallace Ave., Huntsville, AL 35805
Phone 205-534-0011 Fax 205-534-0010

Inquiry 703.

HEWLETT PACKARD
Buy — Sell — Trade
Laser Jet II/IID — Color Pro (7440)
Laser 2000 2 Meg/4 Meg upgrades — HP-7550A
Desk Jet — Draft Pro DXL/EXL
Rugged Writer — Draftmaster I/II
Electrostatic Plotters C1600 (D Size) /C 1601 (E Size)
Science Accessories Corporation Sonic Digitizers
36" x 48" (2750) 60" x 72" (3175)
T. E. Dasher & Associates
4117 Second Ave. S., Birmingham, AL 35222
Phone: (205) 591-4747 Fax: (205) 591-1108
(800) 638-4833

Inquiry 704.

ACCOUNTING SOFTWARE

UNBEATABLE TRIO
THE BUSINESS MANAGER **$199.99/netwk/$239.99**
The most integrated accounting system available. Tracks sales, quotes, inventory, and prints invoices.
PAYMASTER PAYROLL ACCOUNTING **Single $79.95**
Makes all deductions & prints payroll checks & W2 reports.
THE ORDER CENTER **$99.99/netwk/$139.99**
Pop-up windows show inventory, quantity, price and back orders.
PIEDMONT DATA CORP.
5511 Monroe Road, Charlotte, NC 28212
1-800-343-3210

Inquiry 705.

AUTOMATION

VVV PROCESS CONTROL
Real-Time Plant Automation SCADA. Online control specification, dynamic plant mimics, alarm processing, real-time trends, data archiving, reports, recipes, process overview, simulation facilities, Modbus I/O drivers and I/O specifications included. Demo system $90. Prices $1500-$3500.
VVV Process Automation
P.O. Box 695, Parklands 2121, South Africa
Tel (RSA)-11-646-8298 Fax (RSA)-11-646-8298

Inquiry 706.

BAR CODE

LABELING SOFTWARE
On EPSON, IBM, OKI dot matrix or LaserJet. Flexible design on one easy screen. Any format/size. Up to 120 fields/label. 18 text sizes to 3"-readable at 100'. AIAG, MIL-STD, 2 of 5, 128, UPC/EAN, Code 39. File Input & Scanned logos/symbols (PCX)—$279. Other programs from $49. 30-day $$ back.
Worthington Data Solutions
417-A Ingalls St., Santa Cruz, CA 95060
(408) 458-9938 (800) 345-4220

BAR CODE READERS
For PC, XT, AT, & PS/2, Macintosh, and any RS-232 terminal. Acts like 2nd keyboard, bar codes read as keyed data. With steel wand—$399. Top rated in independent reviews. Works with DOS, Xenix, Novell, Alloy, -ALL software. Lasers, magstripe, & slot badge readers. 30-day $$ back.
Worthington Data Solutions
417-A Ingalls St., Santa Cruz, CA 95060
(408) 458-9938 (800) 345-4220

PORTABLE READER
Battery-operated, handheld reader with 64K static RAM, 2x16 LCD display, 32-key keyboard, Real-Time-Clock. Wand or laser scanner. Program prompts and data checking through its own keyboard. Easy data transfer by RS-232 port or PC, PS/2 keyboard. Doubles as On-Line Reader. 30-day $$ back.
Worthington Data Solutions
417-A Ingalls St., Santa Cruz, CA 95060
(408) 458-9938 (800) 345-4220

BAR CODE

PRINT BAR CODES/BIG TEXT FROM YOUR PROGRAM
Add bar codes and big graphics characters to your program. Print from ANY MS-DOS language. Bar codes: UPC, EAN, 2 of 5, MSI, Code 39. Epson, Oki, IBM dot matrix text up to ½". LaserJet up to 2". Font cartridges not required. $179–$239. 30-day $$ back.
Worthington Data Solutions
417-A Ingalls St., Santa Cruz, CA 95060
(408) 458-9938 (800) 345-4220

BAR CODE READERS
Keyboard emulation for PC/XT/AT & PS/2's, all clones and any RS-232 Terminal. Transparent to your operating system. Available with Steel wands, Lasers, Slot & Magstripe Readers. Same day shipping, 30-day money-back guarantee. One-year warranty. Reseller discounts available.
AMERICAN MICROSYSTEMS
2190 A Regal Parkway, Euless, TX 76040
(800) 648-4452 (817) 571-9015 FAX (817) 685-6232

BAR CODE PRINTING SOFTWARE
- MS/PC DOS SYSTEMS
- 9 & 24 PIN DOT MATRIX
- H-P LASER JET/PLUS/SERIES II
- MENU-DRIVEN or MEMORY RESIDENT
- CODE 39, I 2/5, UPC A/E, EAN 8/13
- BIG TEXT & BAR CODE SOFTFONTS

AMERICAN MICROSYSTEMS
2190 A Regal Parkway, Euless, TX 76040
(800) 648-4452 (817) 571-9015 FAX (817) 685-6232

PORTABLE BAR CODE READER
Battery operated, handheld reader with 64K RAM, 54 key keyboard, real-time clock, 2X16 LCD display, and built-in calculator. Supports WAND, CCD, and LASER. Built-in program generator supports multiple programs and data files. Interfaces to PC & PS/2 keyboards, RS-232 terminals, and HAYES compatible modems. 30-DAY MONEY-BACK GUARANTEE.
AMERICAN MICROSYSTEMS
2190 A Regal Parkway, Euless, TX 76040
(800) 648-4452 (817) 571-9015 FAX (817) 685-6232

BAR CODE WEDGE & WAND: $179
AGGRESSIVE PRICING!. . .Reseller discounts. User software-transparent keyboard emulation wedges for PC's, clones, PS/2, and Macintosh. RS-232 bar code readers. LASER, CCD scanners, bar code slot readers, magnetic stripe. Scans all popular bar codes. Label and Bar code printing software. 30-day money back.
DATA HUNTER
6181 Medford, Huntington Beach, CA 92647
(714) 892-5461 Fax 714-892-9768

Inquiry 707.

World Radio History

BAR CODE

I. T. S. Bar Code Solutions

Bar codes are easy using our FULL line of readers & printers. They plug & play with your existing CPU/printer/terminals/software systems in your office, store, truck, factory or warehouse. ITS' bar code DOS programs print on matrix or laser printers. 30 day refund, 1 year warranty. OEM/VAR/Dealer discounts.

International Technologies & Systems Corp.

655-K North Berry St., Brea, CA 92621-Western USA
13 Welwyn Court, Richmond, VA 23229-Eastern USA
(800)228-9487 (714)990-1880 (804)741-6725 (FAX)990-2503

Inquiry 708.

PC BAR CODE SPECIALISTS

Bar code readers designed for fast, reliable, cost-effective data entry. They emulate your keyboard, so scanned data looks just like it was typed in! Choose from stainless steel wand, laser gun, card slot reader, and magnetic stripe scanner. Also, powerful Bar Code and Text printing software. Great warranty. Generous dealer discounts.

Seagull Scientific Systems

15127 N.E. 24th, Suite 333, Redmond, WA 98052
206-451-8966

BAR CODE LABELER

Menu driven program prints Code39, I2x5 Codabar, 128A,B,C, all auto, UPC-A/E, EAN-8/13 & add-ons, DUN-14/16. Avery laser label data supplied. You specify height, resolution. Prints functional, low cost bar code labels! $99.00

SJ Programs

1127 S. Patrick Drive S.18, Satellite Beach, FL 32937
Tel. 407-773-8020 FAX: (407) 773-0457

Inquiry 709.

BAR CODE DECODING SOFTWARE FOR PORTABLES PC'S

BAR-WEDGE is a TSR that allows you to read bar code without a decoder. The bar code read as keyed data. By connecting up the wand on the rs232 port, you just have to start the software and the reading can begin. Easy to use, full programmable, no power required, less than 4k, easy to integrate in your application.

SYMCOD INC.

96 Arcand C.P. 57 Victoriaville, Qc, G6P 6S4
Phone: (819)-751-0095 Fax: (819)-751-1292

Inquiry 710.

DATA INPUT DEVICES

Bar Code, Magnetic Stripe Readers & SmartCard Encoder/Reader for microcomputers & terminals, including IBM PS/2 & others, DEC, Macintosh, AT&T, CT, Wyse, Wang. All readers connect on the keyboard cable & are transparent to all software. UPC & 39 print programs, magnetic encoders, & portable readers are also available.

TPS Electronics

4047 Transport, Palo Alto, CA 94303
415-856-6833 Telex 371-9097 TPS PLA
1-800-526-5920 FAX: 415-856-3843

Inquiry 711.

CAD

PCB & SCHEMATIC CAD—$195

"EASY-PC" for single-sided and multilayer boards to 17" x 17" with up to 1500 ICs including surface mount. Phenomenally fast and easy to use. Over 11,000 copies sold. Needs PC/XT/286/386 HERC/CGA/EGA/VGA. Output to laserjet/inkjet/dot matrix printer, pen-plotter, photo-plotter and NC Drill. Not copy protected. VISA/MC/AMEX welcome. For full info circle inquiry # or contact us direct.

NUMBER ONE SYSTEMS LTD.

Harding Way, St. Ives, Huntingdon, Cambs, England, PE17 4WR
Tel 011-44-480-61778 Fax 011-44-48-494042

Inquiry 712.

CAD

VIEW CAD DRAWINGS

SirlinVIEW Allows non-CAD users to view AutoCAD DWG, DXF & HPGL files on PCs. Print, Plot, attach notes and hyper-link between files. Change views and layers. Accurate! Query databases to locate & highlight objects on the screen.

Also, linkable SirlinVIEW/LIB allows developers to add viewing capabilities to their own applications.

Sirlin Computer Corporation

25 Orchard View Dr., Ste. 14, Londonderry, NH 03053
(603) 437-0727 Fax (603) 437-0737

Inquiry 713.

CAD/CAM

STEPPER MOTOR CONTROL FROM A PRINTER PORT!

NEW Indexer LPT™ software VERSION 2.1 **$249** VISA/MC

- Controls up to six motors simultaneously
- Linear and Circular Interpolation.
- New features to accommodate machine control.
- Easy-to-use DOS device driver. Super Manual.
- CAD-CAM interface available.

Ability Systems Corporation, 1422 Arnold Ave Roslyn, PA 19001 (215) 657-4338 FAX (215) 657 7815

Inquiry 714.

FREE TECHNICAL REPORT!

Just request info about the:
"CAD/CAM Developer's Kit" Series

C Libraries for CAD/CAM, Engineering and GIS Applications 650+ routines for DXF input/output, graphical display, line/arc/ellipse/NURB spline construction/editing, and much more than can be described here.

Phone or FAX (617) 899-4350 for more information.

Building Block Software, Inc.

371 Moody Street, Waltham, MA 02154

Inquiry 715.

CD-ROM

- ► Over 12,000 Dover Clip-Art images for both IBM and Macintosh.
- ► Excellent index—over 80 categories.
- ► A complete tool for Desk Top Publishing.
- ► Sample diskette available.
- ► A really fine product.

Islo Tech Inc. PO Box 431, Excelsior, MN 55331 800/722-9724, 612/934-4239 (Voice) 612/934-2824 (Fax)

Inquiry 716.

FACE THE FACTS!

Discover the Advantages of the New and Improved Wayzata World Factbook 1991

To date, this is Wayzata's highest quality release of the world factbook on CD ROM. It projects our highest standards for maps and the most current information in both text and database or spreadsheet formats. This CD ROM also contains our TextWare retrieval software and is useable for comparisons between countries on all major data and compatible with all spreadsheet and database programs. Available immediately for the Macintosh and IBM PC or compatibles and comes with our standard 60 day money back guarantee. Suggested retail price is $129.00 > Order now for our very special introductory offer price of only $49.00!

WAYZATA TECHNOLOGY INC.

Post Office Box 807 Grand Rapids, Minnesota 55744
Tel: 800-735-7321 (218) 326-0597 Fax: (218) 326-0598

Inquiry 717.

COMMUNICATIONS

SDLC, HDLC AND X.25 SUPPORT

Use Sangoma hardware and software to provide cost effective, robust and easy-to-use SDLC, HDLC and X.25 links from MS-DOS, UNIX, PC-MOS, etc.

All real time communication functions performed by intelligent co-processor card.

Full function SNA emulation packages also available.

Sangoma Technologies Inc.

(416) 474-1990 1-800-388-2475

Inquiry 718.

COMMUNICATIONS

3780 / BISYNC

Emulation software for DOS, UNIX & Windows. OS/2 Coming Soon! Perfect for POS, RJE, EDI, EFT, etc. Linkable API, Script, or Menu-Driven Interface.

End-Users • ISVs • VARs • OEMs

CALL (800) 634-3122 TODAY!

Inquiry 719.

COMPUTER INSURANCE

INSURES YOUR COMPUTER

SAFEWARE Computerowners coverage provides replacement of hardware, media and purchased software. As little as $49 a year covers accidents, theft, power surges and more. One call does it all. Call 8 am–10 pm ET. (Sat. 9 to 5)

TOLL FREE 1-800-848-3469

(Local 614-262-0559)

SAFEWARE, The Insurance Agency Inc.

Inquiry 720.

CROSS ASSEMBLERS

CROSS ASSEMBLERS/SIMULATORS

New unique full-function simulators for the 8096 and 80C196 controllers, featuring ALL MODES of interrupts, plus the HSI, HSO, and A/D functions.

We also support the 8048/49, 8080/85, 8051/52, and Z80 controllers with excellent, reasonably priced Cross Assemblers and Simulators.

Lear Com Company

2440 Kipling St., Ste. 206, Lakewood, CO 80215
(303) 232-2226 FAX: (303) 232-8721

Inquiry 721.

CROSS DISASSEMBLERS

PROFESSIONAL DEVELOPMENT SOFTWARE ASSEMBLERS/DISASSEMBLERS

8051, 8048, 8096, 8080/85, Z80/180, Z8000, SPARC, 6800, 6809, 68HC11, 680X0, 6502/C02, 6301, 9900

COMPLETE, OPTIMIZED DEVELOPMENT TOOL SETS FOR THE ENGINEERING PROFESSIONAL

CALL (408) 773-8465

LOGISOFT PO BOX 61929, SUNNYVALE CA 94086 FAX: (408) 773-8466

Inquiry 722.

DATA RECOVERY

Lst yr dta?

We can find it.

- 95% success rate • Fast turn around
- Priority service available • Clean room
- Servicing Novell, DOS, MacIntosh, SyQuest and removable media, Unix, Xenix, OS/2, Banyan Vines, Bernoulli, Sun and more!

ONTRACK DATA RECOVERY, INC.

6321 Bury Drive, Eden Prairie, MN 55346
1-800-872-2599 • 612-937-5161

Inquiry 723.

Now we're ONTRACK in London Too.

ONTRACK DATA RECOVERY EUROPE, LTD.

Surrey House, 34 Eden St., Kingston upon Thames, Surrey KT1 1ER U.K.
0800-24-39-96 • 44-81-549-3444

Inquiry 724.

World Radio History

THE BUYER'S MART

DATA/DISK CONVERSION

CONVERTING YOUR DISKETTES?
ENTRUST THEM TO US!
2500 Word Processor & Computer formats, 3½", 5¼", 8" Disks, Mag Tapes, Mag Cards, Cartridges, Cassettes & 8MM Custom Conversions, Programming & Applications Development
DISK DUPLICATION
OCR SCANNING SERVICES
Call us for Quality, Best Prices and Quickest Turnaround Time.
COMPANY COMPENDIA, INC., 55 E. Washington St., #237, Chicago, IL 60602 TEL: 1-800-374-DISK FAX: 312-419-1390

Inquiry 725.

THE #1 CHOICE
In disk & tape conversion
for many leading corporations, government agencies, law firms, and companies in every industry—world-wide.
Free test • Satisfaction guaranteed
Graphics Unlimited Inc.
3000 Second St. North, Minneapolis, MN 55411
(612) 588-7571 FAX: (612) 588-8783
1-800-745-7571

Inquiry 726.

QUALITY CONVERSIONS
to or from virtually
ANY TAPE OR DISK FORMAT!
Horan Data Services converts and translates data to/from **9-TRACK TAPE, 3480, 8MM & ¼" CARTRIDGES AND ALL SIZES & DENSITIES OF DISKETTES.**
Thousands of formats supported including EBCDIC, ASCII, databases, dedicated and PC word processors and typesetters.
Call 1-800-677-8885
Hours 8:00 AM to 5:30 PM Eastern Time
817 Main Street, Third Floor, Cincinnati OH 45202

Inquiry 727.

IBM PC ⬅ TO ➡ HP FILE COPY
FASTER EASIER TO USE
Update version uses windows: Call for free demo! IBM PC <to> HP File Copy allows IBM PCs, PS/2, compatibles to interchange files with Hewlett-Packard Series 70, 80, 200, 300, 1000, 9000s.
Oswego Software
Box 310 708/554-3567
Oswego, IL 60543 FAX 708/554-3573

Inquiry 728.

CONVERSION SERVICES
Convert any 9-track magnetic tape to or from over 3000 formats including 3½", 5¼", 8" disk formats & word processors. Disk-to-disk conversions also available. Call for more info. Introducing OCR Scanning Services.
Pivar Computing Services, Inc.
165 Arlington Hgts. Rd., Dept. #B
Buffalo Grove, IL 60089 **(800) Convert**

DATABASE

NOTEBOOK II
• Database mgr. for unlimited text • Research Notes • Inventory • Client profiles • Collectables • Full text editor • Concept analysis • 12 pages text per record • Menu-driven interface • Excellent tutorial • 30-day money-back guarantee. From $189.
Pro/Tem Software, Inc.
3790 El Camino Real, Suite 389, Palo Alto CA 94306
Call toll-free 800/533-6922 FAX: 415/323-0611

Inquiry 729.

DISK DRIVES

IBM PS/2 HARD DRIVES

30MB	MOD 30, 30-286	$350
30MB	MOD 50Z, 55SX	450
60MB	MOD 50Z, 55SX, 70	695
120MB	MOD 50Z, 55SX, 70	795

New, genuine Big Blue Product with 1 yr. Warranty. Call for Model 60/80 drives. Terms: COD/MC/Visa
COMPUTER TECHNIQUES
Merritt Island, FL 32953-3484
Phone/Fax (407) 453-8783

Inquiry 730.

EDUCATION

B.S. & M.S. In COMPUTER SCIENCE
The American Institute for Computer Sciences offers an in-depth correspondence program to earn your Bachelor of Science and Master of Science degrees in Computer Science at home. B.S. subjects covered are: MS/DOS, BASIC, PASCAL, C, Data File Processing, Data Structures & Operating systems. M.S. program includes subjects in Software Engineering and Artificial Intelligence.
AMERICAN INST. for COMPUTER SCIENCES
2101-8Y Magnolia Ave. South, Ste. 200, Birmingham, AL 35205
800-767-2427 205-323-6191

ENTERTAINMENT

DESKTOP MODEL RAILROADING
Lay out some track! Design with precision CAD tools including ruler, grid, zoom, unique auto-curve tool.
Sketch some scenery! Use color art tools to draw trees, structures, rivers, labels, logos.
Run some trains! Make custom trains, operate switches, speed controls, uncouplers, waybills, loads. Watch for tunnels, bridges, crashes!
Design Your Own Railroad ***$59.95***
Abracadata
P.O. Box 2440, Eugene, OR 97402
To order or request free catalog: (800) 451-4871
Inquiries: (503) 342-3030 FAX: (503) 683-1925

Inquiry 731.

FINANCIAL SOFTWARE

Go, NEMESIS, Go
Go - a Zen game. So appealing, it has endured 4,000 years. So useful, governments study it.
NEMESIS Go Junior entices novices of any age. NEMESIS Go Master Deluxe satiates the addicted. Windows, Macintosh and DOS versions available.
Chaos Manor User's Choice Award (BYTE/1990)
Toyogo, Inc. (800) 869-6469
PO Box 25460-Y, Honolulu, HI 96825-0460
(808) 396-5526 fax: (808) 396-4126

Inquiry 732.

BrainMaker:
"The most fascinating computer software I've ever seen. . . learn about this stuff." *John Dvorak, PC Mag.* Predicts stocks, bonds, sales, inventories. Comprehensive manual. Menus. 12,000 sold. PC or Mac.
Still only $195!
Free Flyer: 800/284-8112, 916/477-7481
California Scientific Software

Inquiry 733.

FLOW CHARTS

Have you seen the latest breakthrough in software diagramming?
ADS Diagrammer is a Microsoft Windows 3.0 drawing tool that allows you to create complex software diagrams faster and more easily than ever before!
Call for your free trial disk today!
$250 — Atlantic Design Systems
77 Sprucewood Dr., Gilford, NH 03246
Phone: (800) 745-6095 or (603) 524-2943
FAX (603) 524-3657

Inquiry 734.

FLOW CHARTS

FLOW CHARTING 3
FRIENDLY • High resolution print outs. . . dot matrix or laser
FAST • Multi-page charts. . . portrait or landscape
FLEXIBLE • Import/export capabilities • 35 shapes, 10 fonts, 4 line styles
ONLY $250
Call for free demo disk!
PATTON & PATTON 800-525-0082 ext.1316
Software Corporation 485 Cochrane Cr., Morgan Hill, CA 95037
See our ad on page 90

Inquiry 735.

WINDOWS FLOWCHARTER $129
RFFlow 2.0 is a professional drawing tool for flowcharts & org charts. Requires Microsoft Windows 3.0. 100 shapes auto adjust in size. Diagonal lines and curves. Auto line routing and re-routing. Click on a shape to bring up a sub-chart. Move charts to other apps. via the Clipboard. Call for free trial disk.
RFF ELECTRONICS
1053 Banyan Court, Loveland, CO 80538
Phone: (303) 663-5767 FAX: (303) 669-4889

FONT

Free Font Program (with minor restrictions)
• NewFase 3.0 • Scalable fonts on-the-fly for WordPerfect 5.1/5.0 • Infinite font effects • WYSIWYG previewer • Supports most printer/fax boards • 150 font library • Network version available • Basic package includes 35+ Type I fonts • Cyrillic and APL available • Regular $99 • Call now for FREE working program with minor restrictions
"[NewFase] does what the best software utilities are supposed to do: save you time and money, and make your work look good." Karl Siegnell, Capital PC Monitor, 11/90
MicroPress
41 Witherspoon St., Princeton, NJ 08542
TEL 609-921-0041 FAX 609-497-0917

Inquiry 736.

G.I.S.

Digital Base Maps
Local Street Maps, State Maps, and World Maps for AutoCAD®, MicroStation™, Atlas★GIS, MapInfo™, or DXF™
Gigabytes of Map Data available!
Micro Map & CAD
(303) 988-4940

Inquiry 737.

HARD DRIVE REPAIR

CAPACITY	MFM/RLL/ESDI/SCSI/IDE
10-29Mb	$75
30-39	85
40-49	105
50-85	140
86-120	175
121-160	205
161-350	259
351-700	395
Test & Evaluation	15

LOWEST DISC DRIVE REPAIR PRICES
Jb TECHNOLOGIES, INC.
5105 Maureen Lane
Moorpark, CA 93021
Phone: (800) 688-0908
FAX: (805) 529-7712

Inquiry 738.

HARD DRIVES

MONSTER DRIVE SALE™
PLI External SCSI Hard Drives for PC, Mac, NeXT
These top rated drives are manufactured by Peripheral Land, Inc. (PLI)

Fixed		Removable	
104 mg Connor (Mini)	498.33	44 mg SyQuest	599.53
200 mg Connor (Mini)	819.28	88 mg SyQuest	798.57
320 mg WrenRunner II	1797.08	21 mg Sony Floptical	551.83
635 mg WrenRunner II	2524.08	CD ROM	649.53
PC SCSI Cards & Adapters		Media & Sony Opticals	Call
ISA QuickSCSI (DOS)	166.63	OS/2, Novell, Unix QuickSCSI	199.63
Parallel to SCSI Adaptor	176.75	PS/2 MCA SCSI	220.83

CONCORD MFG & MAGIC
Voice & Fax: (503) 645-0324 PO. Box 190, Beaverton, OR 97075-0190
Shipped FedEx Economy $7 in USA *Visa/MasterCard/Discover billed as Trade Mark*

Inquiry 739.

World Radio History

HARDWARE

AMI/MYLEX MOTHERBOARDS

386	33MHz, 64k, IDE, 2SP&PP	$ 695
386sx	20MHz, IDE, 2SP&PP	349
486	33MHz, 64k Cache (baby) ISA	1259
486	33MHz, 128k, EISA	1695
GXE 020 B	EISA/TIGA Graphics Adapter	1379
DCE 376	EISA/SCSI Adapter	695
LNE 390	Network Interface for EISA 32-Bit	325

2 Year Warranty Factory Service

EXALINX, Inc.
Beautiful Buffalo, New York USA
(800) 992-5469 FAX (716) 882-9650

Inquiry 740.

DOS & WINDOWS PROBLEMS

can be resolved with an Award BIOS ROM Upgrade. Windows 3.0 and DOS 5.0 support. Add IDE drives, 3½" 1.44Mb floppies, more. Call for our FREE Catalog.

KOMPUTERWERK, INC.
851 Parkview Blvd., Pittsburgh, PA 15215
ORDERS 800 423-3400 Tech (412) 782-0384 Fax (412) 782-5017

Inquiry 741.

MAINFRAME POWER

Microcomputer Price!

- Multi-Task
- REAL DOS
- Unlimited Users'
- Ethernet Compatible

ONLY. . .$995.00 Which includes

- New fast 40 MEG HD (17msec) replaces your C drive
- Complete setup with utilities, DOS & DOS files, menu & system manual
- Can boot regular single user DOS also

OCTOPUS SYSTEMS Inc.
"Many DOS arms to serve you"
404-448-4980 FAX: 404-448-5032

Inquiry 742.

PRE-OWNED ELECTRONICS, INC.

THE Independent Provider, serving the Dealer, Professional, Corporate, Government, and Educational Buyer since 1985.

APPLE® II & MACINTOSH®
SYSTEMS • PARTS • EXCHANGE REPAIRS

Call for a Catalog. . . **800-274-5343**
Int'l: 617-275-4600 • Fax: 617-275-4848
205 BURLINGTON ROAD • BEDFORD, MA 01730

Inquiry 743.

HARDWARE/COMPUTERS

SC/FOX™ EMBEDDED COMPUTERS

PC Parallel Coprocessor Plug-in Boards: 15 MIPS avg 50 MIPS burst using the SC32 32-bit CPU or the 16-bit Harris RTX 2000™
VME Master/Slave System Controller SBC: 18 MIPS avg 70 MIPS burst, uses RTX 2000 cpu, SCSI, 2 ser, 1 ptr ports, to 640K bytes.
Stand-Alone Single Board Computers: 18 MIPS avg 60 MIPS burst, 3U or 100x100mm Eurocard-size using either SC32 or RTX 2000.
Ideal for embedded real-time control, data acquisition, robotics, and signal processing. OEM software development system included.

SILICON COMPOSERS INC (415) 322-8763
208 California Avenue, Palo Alto, CA 94306

Inquiry 744.

SDK-386™ *

*386 is a trademark of Intel Corporation. Used by permission.

BRAND NEW AND AVAILABLE ONLY FROM URDA, INC. along with the **URDA SDK-85 and SDK-86** educational trainers and microprocessor development systems. The URDA SDK-51 will be available next year. Other 8, 16, and 32 bit systems are available.

Phone URDA, Inc.
1-800-338-0517 or 412-683-8732

Inquiry 745.

LANS

The $25 Network

Try the 1st truly low-cost LAN

- Connect 2 or 3 PCs, XTs, ATs
- Uses serial ports and 5-wire cable
- Runs at 115K baud
- Runs in background, totally transparent
- Share any device, any file, any time
- Needs only 14K of RAM

Skeptical? We make believers!

Information Modes
P.O. Drawer F, Denton, TX 76202
817-387-3339 Orders 800-628-7992

Inquiry 746.

LANS/SOFTWARE

NetRunner/FreeLAN NOS

The most reliable and lowest cost LAN software

NetRunner: Remote Control, Remote Printing, File Transfer, Remote Execution, Runs on NetBIOS, Novell, and Modem/RS-232. Starter Kit $24.95. Unlimited: $99.95
FreeLAN NOS: File Sharing, Printer Sharing, File/Record Locking, Printer Spooling. NetBIOS based, non-dedicate solution. Runs on Ethernets, Arcnets, and Serial Ports. Starter Kit: $39.95. Unlimited: $149.95

Crystal Computing Corporation
P.O. Box 9527, San Jose, CA 95157-0527
Tel (800) 726-6209 Voice/Fax (408) 996-2899

Inquiry 747.

LAPTOP COMPUTERS

SAVE! **LAPTOPS*NOTEBOOKS** *SAVE!*

TOSHIBA • EVEREX • ZENITH • AT & T • TANDON
AST • SHARP • BONDWELL • ALR • LIBREX
PANASONIC • ALTIMA • LEADING EDGE
PACKARD BELL • SAMSUNG • NEC • TI • COMPAQ

• We *ALSO* carry accessories and software •

Computer Options Unlimited
12 Maiden Lane, Bound Brook, NJ 08805
CALL: (800) 424-7678 Need Help?: 908-469-7959
9-9 M-F 9-5 Sat. **6 days** Worldwide Sales

Inquiry 748.

IBM CONVERTIBLE

MEMORY–128K $79 256K $225 384K $295
MODEMS–Standard $75 Enhanced $175
CRT ADAPTER–for monitors $99
SERIAL/PARALLEL ADAPTER–$120
MONITORS–Monochrome $115 Color $249
COMPACT Carrying Case $39
ENHANCED LCD–$79 **BATTERY** –$89
HARD DRIVES–20 Meg–$495 40 Meg–$695
MORE ACCESSORIES AVAILABLE

COMPUTER RESET
P.O. Box 461782, Garland, TX 75046
Phone (214) 276-8072 BBS & FAX (214) 272-7920

Inquiry 749.

LAPTOP PERIPHERALS

LAPTOP PERIPHERALS

NEW LOW PRICES ON:

- Battery Powered Printers
- Portable Hard Drives
- Laptop Expansion Systems
- Backlites AND MORE!

Call for free catalog

AXONIX CORPORATION
(800) 866-9797

Inquiry 750.

MANUFACTURING/DISTRIBUTION

SQL 4GL CIM SOFTWARE

CimFacts consists of a family of SQL 4GL integrated applications for organizations in manufacturing and/or distribution. The SQL relational database is integral to CimFacts. DOS & UNIX supported. *Dealer Program Available.* Call for 18-page brochure.

- Bill Of Materials
- Numerical Control Programming
- Process Planning
- Production Activity Control
- MRP & Inventory Control
- Cost Estimating
- Product/Process Costing
- Purchase Processing/Invoicing
- Accounts Receivable/Payable
- General Ledger

CimFacts 3300 S. Gessner Dr., Suite 150 Houston, TX 77063, USA (713) 784-4016

Inquiry 751.

MULTI-MEDIA

UPGRADE KITS

MEDIA VISION KIT ($799)—Pro Audio Spectrum Card, Int. Sony Cd Drive, Compton's Encyc. Cd, Jones In The Fast Lane Cd and MS Windows W/Multimedia On Cd. SOUND BLASTER KIT ($679)—Sound Blaster Pro Card, Int. Panasonic Cd Drive, and 5 Cd Titles.

Other Kits And Cd Titles Available
Call for Prices and FREE INFO.

Computech Computer Services
9254 S.W. 38 Street, Miami, FL 33165 (305) 861-2723

Inquiry 752.

NEURAL NETWORKS

i860/486 NEURAL NETWORKS

Industrial strength, no frills, neural training tools aimed at high-end platforms and experienced users. Special features for developing networks with enhanced robustness and stability. Converges reliably. We needed a good training system, were dissatisfied with the commercially available ones, so wrote our own. Interested? Also available: C-Library and pretrained neural network systems for financial forecasting. Contact: Jeffrey Owen Katz, Ph.D.

SCIENTIFIC CONSULTANT SERVICES, INC.
20 Stagecoach Road, Selden, NY 11784 516-696-3333

Inquiry 753.

ON LINE

FOR POLITICAL DISCUSSION JOIN *NATIONAL REVIEW'S* TOWN HALL

the interactive Conservative Meeting Place. More than a BBS. **Town Hall** puts right-thinking computer users in touch with noted columnists and political leaders like William J. Bennett, Joe Sobran, George Gilder and Rick Brookhiser. Access the TH Washington Report daily news wire or National Review on-line. Join high-level debate and discussion or talk with others live!

TAKE AN ON-LINE TOUR TODAY. JUST DIAL 1-800-648-6964 VIA MODEM (Hit <enter> at CONNECT signal) Or call Member Services at 1-800-441-4142
150 E. 35th St., New York, NY 10016

Inquiry 754.

PRINTER UTILITY

NO MORE PAPER SWAPPING

Merge text and PCX files for output on a HP LaserJet or compatible with **FormPrinter 1.0.** Run from DOS or integrate into your app. Preload images in printer memory for increased throughput. Include Code 39 bar codes using escape sequences in the text file. Create the PCX files with the editor of your choice. Fully configurable. .EXE $79.00. With source code (MS-C & MASM) $109.00

TLC TECHNOLOGY
1831 Wells Branch Pky. Suite 222, Austin, TX 78728
(512) 795-3403

Inquiry 755.

PRODUCT MANAGEMENT

Keep Track of Bug Reports

New tool gives instant access to information about pending bug reports/suggestions on the products you maintain or support. Eases planning of new releases. No more paperwork, lost reports or hunting for customers' example files. Multiple users (development, marketing, QA) can independently categorize, prioritize, and rearrange records. KeyTrack $495

C Street Software
(805) 486-7807 • (800) 350-8649 • Fax (805) 483-7809
3L Ltd (UK) +44 506 41 59 59 Fax +44 506 41 59 44

Inquiry 756.

PROGRAMMERS TOOLS

C and C++ DOCUMENTATION TOOLS

- **C-CALL ($59)** Graphic-trees of caller/called hierarchy.
- **C-CMT ($59)** Create, insert, update comment-blocks for each function, listing functions and identifiers used.
- **C-METRIC ($49)** Path complexity, lines/stmts/comments.
- **C-LIST ($49)** List, action-diagram, reformat programs.
- **C-REF ($49)** Local/global/parameter cross-reference.
- **SPECIAL ($189)** All 5 as DOS/OS2 "C-DOC" program

SOFTWARE BLACKSMITHS INC.
6064 St. Ives Way, Mississauga, ONT Canada L5N-4M1
(416) 858-4466

Inquiry 757.

World Radio History

THE BUYER'S MART

PROGRAMMERS TOOLS

DON'T DEVELOP NETWORK APPLICATIONS
without NPPC, a powerful library sub-routine package that handles all the details of NetBIOS or IPX programming! **NPPC** supports high-level program communications at the message level for all server/client and peer-to-peer models. If you are using C or Assembler, **NPPC** allows you to write a single application that runs on BOTH IPX AND NetBIOS without any modifications. **NPPC** is compatible with any true NetBIOS emulator, therefore applications written with **NPPC will** work with most LANs in the marketplace. We offer a 30 day money back guarantee.
NPPC for IPX or NetBIOS: $195.00, with source: $395.00
SOFTWAREHOUSE CORPORATION
326 State Street, Los Altos, CA 94022
(415) 949-0203 FAX: (415) 949-0208

Inquiry 758.

Boost Your BASIC!
ProBas adds 938 new commands to QB and PDS. Written in assembly for blinding speed, ProBas makes your programs fast and professional looking! Easy to use, money-back guarantee. Nine other add-ons for BASIC and Visual Basic available–call for your **FREE** copy of "10 Easy ways To Boost Your BASIC".
TeraTech (800) 447-9120 x104
Dept B4B, Suite 360, 3 Choke Cherry Rd., Rockville, MD 20850
(301) 330-6764 Fax (301) 963-0436

Inquiry 759.

PUBLIC DOMAIN

$1.00 PER DISK
NO MINIMUM ORDER!
Free Catalog of 900+ Programs
Many Unique, Hard-to-Find Titles.
(Many New WINDOWS Programs!)
Northern Micro Systems
16 Main St. Absarokee, MT 59001
(406) 328-4343

Inquiry 760.

FREE SOFTWARE for IBM®
TRY US! GET 15/5.25" or 8/3.5" Disks full of our best selling software — FREE. Games, Windows®, clip art, fonts, utilities, business, educational, desktop publishing, religion, home/health. Pay $5.00 shipping/handling. Credit cards only. Call Today!
SMC SOFTWARE PUBLISHERS
619 931-8111 ext 511

Inquiry 761.

ROM BIOS UPGRADES

AMI, PHOENIX & MR BIOS
Upgrade your IBM PC, XT, AT or compatible. Also 386SX & 386 versions. Supports 2 user-defined hard drives, 101/102 KB, 360, 720, 1.2 & 1.44 floppies, setup in ROM, All Video, Windows 3.0 Diagnostic in ROM AMI 286 & 386 versions only. CALL. New version just came in.
Advanced Software
8 Stiles Road, #1A, Salem NH 03079
800-835-2467 603-898-2362
Fax: 603-890-1185

Inquiry 762.

SECURITY

FIGHT PIRACY!
Since 1986, companies worldwide have been choosing **Az-Tech** security products. If you demand the strongest protection available, why not choose one of these "proven leaders":
- **EVERLOCK** Copy Protection
- **EVERTRAK** Software Security
- **EVERKEY II** "The Lock"

For IBM and Compatibles. 30 day money back guarantee. Free info and demo disk available.
Az-Tech Software, Inc.
201 East Franklin, Richmond, MO 64085
(800) 227-0644 (816) 776-2700 Fax: (816) 776-8398

Inquiry 763.

SECURITY

THE ULTIMATE COPY PROTECTION
- Completely Menu Driven
- Defeats all Hardware/Software Copiers
- No Source Code Changes
- Multiple Layering
- No Damaged Media
- Full Hard Disk & LAN Support
- Unlimited Metering, FREE Demo Disk

Quite Simply The Best Ways To Protect Your Valuable Software Investment

STOPVIEW™ STOPCOPY PLUS™ (800) 879-2224
BBI COMPUTER SYSTEMS, INC. (301) 871-1094
14105 Heritage Lane, Silver Spring, MD 20906
FAX: (301) 460-7545

Inquiry 764.

Cop's CopyLock II
The professional software protection with TRUE Machine Install. Option Board safe. Supports **OS/2, Windows and Trace.**
LINK Computer
Int'l: +45 31232350 Fax +45 31238448
US/CAN: 800-344-2545 Fax 408-923-7061

Inquiry 765.

BIT-LOCK® SECURITY
Piracy SURVIVAL 8 YEARS proves effectiveness of powerful multilayered security. Rapid decryption algorithms. PARALLEL or SERIAL port-transparent security device. Complemented by economical KEY-LOK™ and multifeatured COMPU-LOCK™ including countdown, timeout, data encryption, and multiproduct protection. (Dos/Unix/Mac). Also, access control.
MICROCOMPUTER APPLICATIONS
3167 E. Otero Circle, Littleton, CO 80122
(303) 770-1917

Inquiry 765.

HANDS OFF THE BOARD®
1/2 SIZE SECURITY BOARD
Stop floppy boot — Require password to boot PC
Real-time disk encrypt — prevent boot sector virus
Prevent DOS FORMAT/FDISK and low-level formats
Set hard disk READ ONLY or turn ON/OFF
Turn floppies, printers and COM ports ON/OFF
IBM XT, AT Bus — DOS V3.0+ — $149.95 + $5.00 S/H
SYSTEMS CONSULTING INC.
PO BOX 111209, Pittsburgh, PA 15238
(412) 781-5280

Inquiry 766.

SHAREWARE

THE AMISH OUTLAW
SHAREWARE COMPANY
★★★★★★★★★ **FREE** ★★★★★★★★★
WITH EVERY ORDER YOU WILL RECEIVE A GREAT NEW GAME NOT LISTED IN OUR CATALOG ABSOLUTELY FREE.
ALL DISKS HAVE EASY-TO-USE MENUS
SIMPLY TYPE "GO" TO ACCESS PROGRAMS.
$3.00 PER DISK 1-9 — $2.50 PER DISK 10-UP
3.5" AND 5.25" DISKS SAME PRICE
(IBM PUBLIC DOMAIN AND SHAREWARE ONLY)
3705 RICHMOND AVE., STATEN ISLAND, NY 10312
1-(800)-947-4345 or (718) 317-0198 FAX 1-(718)-966-4766

Inquiry 767.

- Latest versions of Shareware—only quality updated material.
- Available for as low as $99.00/disk.
- Shareware by the disk also available.
- "Win, Place, Show" Lotto disk—Increase odds of winning (free with quantity purchase).
- Catalogs on all products available.

Islo Tech Inc. PO Box 431, Excelsior, MN 55331 800/722-9724, 612/934-4239 (Voice) 612/934-2824 (Fax)

Inquiry 768.

SOFTWARE/ACCOUNTING

dBASE BUSINESS TOOLS
- GENERAL LEDGER
- ORDER ENTRY
- JOB COSTING
- BILL OF MATLS
- PAYROLL
- PURCH ORD/INVNTORY
- ACCOUNTS RECVABLE
- JOB ESTIMATING
- SALES ANALYSIS
- ACCOUNTS PAYABLE

$99/$198 ea. + S&H
dATAMAR SYSTEMS Cred. Card-Check-COD
8586 Miramar Place, San Diego, CA 92121
(619) 452-0044 (800) 223-9963

Inquiry 769.

MULTI-CURRENCY ACCOUNTING
- Keep accounts in any currency
- Evaluate balances with 3 exchange rates
- Compute gain/loss on exchange
- Full-featured LAN G/L $199.95+s&h
- Fully functional Demo $5
- VISA/MC. 30 days money back. Dealers welcome.

vertech Inc.
17 Ch. Chavanne, CH-1196 Gland, Switzerland
Tel 011-4122-364-54-90 Fax 011-4122-364-53-93
BBS 011-4122-364-53-43

Inquiry 770.

SOFTWARE/BUSINESS

DATA ENTRY SOFTWARE
Full featured, heads-down data entry with two-pass verification, edit language, operator stats, much more! Designed for the PS/2®, PC, XT, AT or compatibles.
PCs from $395 LAN version available
FREE 30 day trial
Computer Keyes Tel: 206/776/6443
21929 Makah Rd., Fax: 206/776-7210
Woodway, WA 98020 USA: 800/356-0203

SOFTWARE/ENGINEERING

SPICE Reference Books
- A SPICE Cookbook
- SPICE Applications Handbook
- Simulating with SPICE

A SPICE Cookbook contains over 100 examples of different SPICE simulations. *The SPICE Applications Handbook* contains articles on using SPICE and device modeling. *Simulating With SPICE* is a complete guide for the beginning SPICE user with syntax, tutorial, convergence, and example sections.

intusoft
The leader is low cost, full featured CAE tools
P.O. Box 710 San Pedro, Ca 90733-0710
310-833-0710, **FAX: 310-833-9658**

Inquiry 771.

MICROSTRESS CORPORATION
Announcing **MICROSAFE 2D/3D Rel. 3.10**
Structural Analysis Program for IBM PCs & compatibles. Number of nodes, elements & loading conditions limited by disk space & model bandwidth (11000 d.o.f.) Color graphics support on various display cards (EGA, VGA, VEGA, HERCULES etc.) $350. **SAFEACAD** (bi-directional AUTOCADD interface ver. 9+) $110. **SAFELIBs** (Beam Element Libraries for steel, wood & concrete incl. complete **AISC** Database) $85. Does not include shipping.
P.O. BOX 3194, BELLEVUE, WA 98009
TEL/FAX: (206) 450-0316

Inquiry 772.

MIXED-MODE SIMULATION
TopSPICE $159
Upgrade to the power of true *Analog/Digital/Behavioral* mixed-mode circuit simulation for PC. SPICE2g6/3 compatible. Built-in event-driven logic simulator. Behavioral modeling. Graphics post-processor. FREE demo.
PENZAR DEVELOPMENT
P.O. Box 10358, Canoga Park, CA 91309
(818) 594-0363 (800) 272-0674 Fax (818) 340-6316

Inquiry 773.

World Radio History

SOFTWARE/ENGINEERING

Worstcase Gets Even Better!
ECA-2 Analog Circuit Simulator
Offers the best Monte Carlo and Worst-Case Analyses
TWICE the speed at HALF the cost!
- Interactive/batch modes • Full Nonlinear Simulator
- On line, Real Time Graphics • Multiple Plots
- AC, DC, Transient, Fourier, Temperature

Tatum Labs, Inc.
P.O. Box 1263, Ann Arbor, MI 48106-1263
(313) 663-8810

Inquiry 774.

SOFTWARE/GRAPHICS

SUPER VGA GRAPHICS LIBRARY
for video boards using Tseng Labs ET4000 chip. Over 60 routines callable from MS FORTRAN. Up to 1024x768x256 colors with 1MB video memory. 2-D & 3-D w/perspective. Flat & Gouraud shaded polygons. Mouse & joystick support. Scale and rotate text. Store/retrieve in PCX format. $100 postpaid. Demo $10, refunded w/purchase. Specify 5.25" or 3.5" diskette.

AEROSOFT CORPORATION
5562 Bells Ferry Rd., Suite 233, Acworth, GA 30101
(404) 917-1309

Inquiry 775.

PostScript from C
c__pslib function library
Order today for $195.00
and receive FREE source code!
Barton Creek Software
2222 Western Trails Ste 106, Austin, TX 78745
512-441-8354 **Fax 512-444-4554**

Inquiry 776.

TurboGeometry-Professional 4.0.
"The Ultimate CAD/CAM/CAE Graphics Engine"
TurboGeometry-Professional, the most complete library of 2D & 3D geometric routines available today! Now over 600 routines including NURBS, DXF, Graphics, Surfacing, Hidden Line, Volumes, Areas, Transforms, Perspectives, Polygon (Int/Union/Diff), Clipping, Tangents. Graphics routines for drawing using BGI or MSC Graphics. Source included. 30 day guarantee. $500.00 in USA. $535.00US Foreign. Additional information available upon request.

Disk Software Inc.
2116 E. Arapaho Rd., Suite 487, Richardson, TX USA 75081
PH: 214-423-7288 • 1-800-635-7760 • FAX: 214-423-7288

Inquiry 777.

RAINDROP™
FAST, compact PrtScrn Utility for end users AND developers. Hardcopy as fast as 10 secs. Average binary size - 6 kbyte. 14 video graphic standards. Scale, rotate, colorize and more. 'CALL' from user-written programs. Complete 9- & 24-pin dot-matrix, inkjet, and laserjet library $44.95+$3 s/h.

ECLECTIC SYSTEMS
8106 St. David Ct., Springfield, VA 22153
(703) 440-0064 **Fax (703) 455-8965**

Inquiry 778.

YOUR SALES MESSAGE
about the special computer product or service that you provide belongs in print.
THE BUYER'S MART
can help you reach computer professionals and produce valuable inquiries for your company!
Call Joseph Mabe for more information
603-924-2656
or
Fax: 603-924-2683

Inquiry 779.

SOFTWARE/GRAPHICS

FORTRAN GRAPHICS
GRAFMATIC - FORTRAN callable graphics Library for creating 2-D and 3-D graphics, contour plots and solid models. PRINTMATIC and PLOTMATIC provide high resolution FORTRAN callable printer and plotter drivers for your graphics. NO ROYALTIES. $249.95 ea.
Supports Microsoft/Lahey/RM FORTRAN compilers.

Jewell Technologies, Inc.
130 Nickerson St., Suite 105, Seattle, WA 98109
1 (800) 284-2574

Inquiry 780.

Z-PHIGS Windows
The Standard 3D-Graphics Development System
Use the power of the most sophisticated 3D-graphics system available today. A powerful library with 2D/3D functions saves you years of development time in the fields of CAD, Multimedia etc. Spectacular rendering features like Phong shading, light effects, material definitions, texture-mapping and much more makes it simple and quick to create impressive realistic images.

WISE Software
Seelandstr. 3, D-2400 Lubeck 14, Germany
Tel: (+49)-451-3909-413 Fax: (+49)-451-3909-499

Inquiry 781.

SOFTWARE/LANGUAGES

IntegrAda
Standard Air Force PC Ada Compilers & environments for MS-DOS and UNIX. Integrated programming systems include validated Ada compilers, language sensitive editors, complete libraries and other Ada programming tools. FREE demo.

AETECH, Inc. *From* ***$395***
380 Stevens Ave., Ste. 212 Solana Beach, CA 92075
(619) 755-1277 Fax: (619) 755-7540

Inquiry 782.

SOFTWARE/PACKAGING

FREE SOFTWARE PACKAGING CATALOG
Everything you will need to Package, Distribute, and Ship Your Software!! From manuals and binders to mailers and shippers

LABELS • LABELS • LABELS
For your diskettes, plain or custom printed, dot matrix or laser printers. free samples
. . .FREE CATALOG. . .
Hice & Associates
8586 Monticello Dr., West Chester, OH 45069
Phone/Fax 513-777-8586

Inquiry 783.

SOFTWARE/SCIENTIFIC

Chaos/Nonlinear Dynamics
DYNAMICAL SOFTWARE I and II $250 / $350
Ordinary and Delay Differential Equation Solvers
• Bifurcation Diagrams • Basin Boundaries • 2- and 3-D Plotting • Poincare Sections • Return Maps • Spectral Analysis, Fractal Dimensions, Lyapunov Exponents
NONLINEAR FORECASTING
enhancement to DS $150.00 • stand alone $200.00
DYNAMICAL SYSTEMS, INC.
P.O. Box 35241, Tucson, AZ 85740, (602) 292-1962
Fax (602) 887-0307

Inquiry 784.

FREE CATALOG
A great selection of scientific software products for plotting, non-linear curve fitting, chemical equilibrium, simulation, statistics, symbolic algebra, and more. Prices from $150. Call:
1-801-943-0290
MicroMath, Salt Lake City, UT 84121-0550

Inquiry 785.

SOFTWARE/SCIENTIFIC

VTEX: Scientific Desktop Publishing
• Equations • Tables • Graphics • Scalable Fonts • Supports most printers • WYSIWYG previewer • Foreign Languages • Special Symbols • Font Effects • Indices • Only $299
"TEX of Tomorrow"—Notices of AMS, March 1991.

MicroPress, Inc.
68-30 Harrow Street, Forest Hills, NY
Tel (609) 497-0008 Fax (609) 497-0917

Inquiry 786.

GEOMETRY/TRIGONOMETRY CALCULATOR
Apollonius — Sketch-based geometry/trigonometry solver. State-of-the-art variational geometry system lets you sketch your geometry or trig problem and automatically solves for distances, angles and areas. Integrated equation calculator, graphs and tables plus DDE and clipboard support. Ideal for surveyors, engineers, machine shops, students, architects, or anyone who uses trig. Runs under MS Windows 3.0 $98

Saltire Software 1-800-659-1874

Inquiry 787.

SOFTWARE/SORT

OPT-TECH SORT/MERGE
Extremely fast Sort/Merge/Select utility. Run as an MS-DOS command or CALL as a subroutine. Supports most languages and file types including Btrieve and dBASE. Unlimited file sizes, multiple keys and much more! MS-DOS $149. OS/2, XENIX, UNIX $249.

(702) 588-3737
Opt-Tech Data Processing
P.O. Box 678 — Zephyr Cove, NV 89448

Inquiry 788.

SOFTWARE/VOICE/FAX

MULTI-VOICE® TOOLS
Multi-Voice Tools is a complete development Toolkit for Pascal or "C" to access all the features for most speech processing boards available today. It helps you write MULTI-LINE VOICE APPLICATION systems in minutes. A number of programming examples are provided. All programs and libraries are delivered with source code.
Dialogic, Rhetorex, Pika, VBX: $599, Watson (Single Line): $99. ALSO AVAILABLE: FAX Programmer's Toolkit ($199). Based on CAS specifications. Visa/MC accepted.

ITI Logiciel
4263 Cristophe-Colomb, Montreal, Quebec, Can. H2J 3G2
TEL (514) 597-1692 **FAX (514) 526-2362**

STATISTICS

VISUALIZE YOUR DATA
MCA+ transforms most marketing and social science data to easily understood perceptual maps. Communicate complex relations with ease using presentation quality charts. Most printers supported. Demos available

Bretton-Clark
89 Headquarters Plaza, Morristown, NJ 07960
(201) 993-3135 **FAX: (201) 993-1757**

Inquiry 789.

NCSS 5.x Series — $125
Easy-to-use menus & spread sheet. Multiple regression. T-tests. ANOVA (up to 10 factors, rep. measures, covariance). Forecasting. Factor, cluster, & discriminant analysis. Nonparametrics. Cross Tabulation. Graphics: histograms, box, scatter, etc. Reads ASCII/Lotus. Many new add-on modules.

NCSS
329 North 1000 East, Kaysville, UT 84037
Phone: 801-546-0445 **Fax: 801-546-3907**

Inquiry 790.

World Radio History

THE BUYER'S MART

TRANSLATION

SOFTWARE LOCALIZATION

Since 1980, IDOC has translated hundreds of packages for the world's most prominent computer firms. Ashton-Tate, Borland, HP, Sun Microsystems, Novell and many more. We offer FULL SOFTWARE ADAPTATION WITH IN-HOUSE ENGINEERING, TRANSLATION INTO ALL MAJOR LANGUAGES WITH IN-HOUSE LINGUISTS, DTP SPECIALISTS, AND EDITORS. With production and sales offices in Los Angeles, Dubin, Milan, Atlanta, Buenos Aires, and Tokoyo (Fall 92) IDOC is the leader in worldwide translation services.

IDOC, an International Documentation Company
1-800-336-9898 (U.S.) **353-1-284-4223 (Europe)**
10474 Santa Monica Blvd., Suite 404, Los Angeles, CA 90025

Inquiry 791.

Tradoc translates and localizes your technical documentation into the following languages:

+ *French* + *Russian*
+ *Spanish* + *Arabic*
+ *German* + *Italian . . .*

Turnkey service: Desktop Publishing, typesetting and printing of your brochures and manuals.

205 Gibson Rd., Annapolis, MD 21401
(301) 267-8655 **FAX (301) 267-8180**

Inquiry 792.

TV CAPTION DECODER

TV CAPTION DECODER

Teach children to read. Screen programs for offensive language. Learn English. Make transcripts. Watch TV without disturbing others. Also for hearing impaired. **Caption Master IV** comes with software, 1 year warranty & unlimited tech assistance for $149.
Super Caption V3.2 fully featured software comes with manual & free upgrade for $59. **Order them together for $169.** For all IBM compatibles. Fits short slot.
Available only from **Best Electronics.** 100% American made. Visa & MasterCard, or COD. (800) 292-7021, (607) 277-7002, FAX available.

Inquiry 793.

UNINTERRUPTIBLE POWER

ELIMINATE LAN DOWNTIME AND DATA LOSS

APC protects more LANs than any other brand of UPS. Call for your **FREE** power protection handbook detailing:

- Smart UPS high performance protection. PC Magazine's Editors' Choice
- BackUPS cost effective protection starting at $169
- PowerChute automatic shutdown software for all major OS
- SurgeArrest network grade surge protection

"Our highest marks go to the Smart-UPS 900" BYTE 5/91

American Power Conversion
132 Fairgrounds Road,
West Kingston, RI 02892
800-541-8896

APC Europe
4 Rue St. Claire DeVille Lognes
77447 Marne la Vallee Cedex 2,
FRANCE (+33) 160178400
Fax: (+33) 160178029

Inquiry 794.

UPS

TRUST YOUR PC TO SOLA
UNINTERRUPTIBLE POWER SYSTEMS

Quality manufacturing. Affordable prices.
UL listed/CSA certified. Risk-free guarantee.
Call today for your **FREE** 1992 Power Selection Guide.

1-800-TRY SOLA — Ext. 1033

S O L A

1717 Busse Rd., Elk Grove Village, IL 60007

Inquiry 795.

UTILITIES

$29 MATH COPROCESSOR
- 287, 387, X87 emulator
- See BYTE 3/1991 p. 90, PC Magazine 2/1991 p. 302

$5 SUPER PASSWORD SOFTWARE
- No one can break it • Double lock protection
- Invisible password • Movable password

$49 VIRUS PROTECTION CARD
- Immune to virus after installation
- Support networks • No RAM needed

Buy Math Coprocessor & Virus Card, Get Super Password FREE S&H extra

MULTIX, INC. 4203 Beltway Dr. Suite 7, Dallas TX 75244
Tel: (214) 239-4989 Fax: (214) 239-6826 We accept MasterCard and VISA

Inquiry 796.

UTILITIES

Why You Want BATCOM!

BATCOM is a batch file compiler that transforms your .bat files to .exe files to make them faster. BATCOM extends DOS with many new commands so you can read keyboard input, use subroutines, and much more. In addition, BATCOM protects your source code. No royalties! Only $59.95. Order today!

Wenham Software Company
5 Burley St., Wenham, MA 01984
(508) 774-7036

Inquiry 797.

WINDOWS

FREE—88 WINDOWS™ PROGRAMS FOR IBM®

88 general interest Windows™ programs • Over 70 Windows™ fonts (Adobe Type Manager® required for the fonts). Each collection comes on 15/5.25" or 8/3.5" disks. **It's FREE!** You pay only $5.00 shipping and handling per collection. Credit cards only. **Call Today!**

SMC SOFTWARE PUBLISHERS
619 931-8111 ext 511

Inquiry 798.

WINDOWS TOOLS

Scientific/Engineering Unit Converter for MS Windows
ONLY $19.95 VISA/MC/CHECK/MO

- Thousands of conversions
- Attractive "chiseled steel" interface
- Seamless interface w/other applications
- Editor, calculator included
- Uses minimal desktop space

Call or write to order or for FREE demo disk

(310) 784-7711
Legacy Systems
PO Box 4146, Redondo Beach, CA 90278

Inquiry 799.

No Wild, No Wildlife.

Polar bears, musk-ox, grizzlies, caribou — more animals than you'd find in Yellowstone — can be found on the magnificent coastal plain of the Arctic Refuge in Alaska. Unfortunately, this portion of our last arctic wilderness has caught the eye of the oil industry. Right now Congress is considering proposals that would allow the oil companies to drill there, even though reports indicate there's less than a one-in-five chance oil would be found.

If we allowed drilling in the region, we would jeopardize the culture of the native Alaskans and untold wildlife, including a herd of 180,000 caribou. Our last arctic wilderness would be despoiled.

The Sierra Club works to save wildlife by saving the wilderness. We have a history of victories. And we believe with your help, this arctic wilderness will remain an invaluable refuge.

For information on how you can help:

SIERRA CLUB, DEPT. AR, 730 POLK STREET, SAN FRANCISCO, CA 94109, (415) 776-2211

World Radio History

IBM

PS/2 model 55SX-60 meg 1985
PS/2 model 70-120 meg 3195
IBM model 35-40 meg 1795
PS/2 model 70-A21 4195
PS/2 model 95-320 meg 14950
*** Monitor Extra ***

COMPAQ

DeskPro Models
286E-40/120 meg 1595/1695
386S-20 MHz 120 meg 2375
386/20E-120 meg 2795
386/25E-120 meg 4085
386/33M-120 meg 4995
*Call for other models – Monitor Extra *

NOVELL SPECIALS

Netware Version 2.2
5 users 595
10 users 1395
50 users ..... CALL
100 users ..... CALL
Netware 386 V.3.11
20 users 2195
100 users ..... CALL
250 users ..... CALL

BRAND NAMES LOW PRICES

LEADER SINCE 1983

We export to Europe, Asia & the Far East

We Honor Manufacturer's Warranties

Call for details

AST LAPTOPS

EX386SX20 MDL 60 2375
EX386SX20 MDL 80 ..... CALL
EX386SX25 MLD 60 2575
EX386SX25 MDL 80 ..... CALL
EX386SX25C MDL 60 4395
EX386SX25C MDL 80 ..... CALL

LAPTOPS

Compaq LTE/286 40 meg 1895
Compaq LTE/386 60 meg 3295
Toshiba 2000SXE 40 meg 2650
Toshiba 2200SX 60 meg 3395
Toshiba 3200SXC 120 meg 5650

Call for pricing on other brand name models

EVEREX

MEGACUBE ISA BUS
486-33 System
8 meg 128K Cache ESDI
16 meg 128K Cache ESDI ..... CALL

Step 386-20 MHz System
1 meg RAM, 64K Cache, 1.2 &
40 meg Drive, 640x480 VGA Combo ..... CALL

Step 386-25 MHz System
1 meg RAM, 64K Cache, 1.2 &
40 meg Drive, 640x480 VGA Combo ..... CALL

Step 386-33 MHz System
2 meg RAM, 64K Cache, 1.2 &
150 meg Drive 1024x768 VGA Combo ..... CALL

AST

AST Bravo 386SX20 MDL 1 1070
AST Bravo 386/25 MDL 1 2295
AST Premium 386SX20 MDL 1 1295
AST Premium 386/33 MDL 1 2225

INTEL COPROCESSORS

80287 XL $99.00
80387 SX-16 ..... $135.00
80387 SX-20 ..... $149.00
80387 DX25/33 ..... $205.00

WE STOCK TOSHIBA
CITIZEN
OKIDATA
EPSON
HITACHI
TALLGRASS
ARCHIVE
NEC
ALR
WYSE
HOUSTON INSTRUMENTS
MICROSOFT
SUMMAGRAPHIC
INTEL
PC MOUSE
CALCOMP

ACS Computers

All systems include

Made in USA

- Intel CPU
- 4 meg RAM memory expandable to 64 meg - Desktop or tower case
- 2 serial, 1 parallel
- 101 keyboard
- 1.2 & 1.44 Teac drive
- SVGA card w/1 meg & SVGA monitor
- MS DOS 5.0
- MS Windows & mouse

486/33 with 200 meg HD 2250
386/33 with 120 meg HD 1995
386SX/20 with 40 meg HD 1420

One year limited warranty

NOVELL Authorized Dealer

LAN BOARDS
8 bit Arcnet 75
16 bit Arcnet 160
Novell NE 1000 160
Novell NE 2000 175
8 port Active Hub 325
Token Ring Card 399
Tokenhub 4-port 355
Call for other LAN Accessories

LASER PRINTERS

HP Laser IIISI 3595
Hp Laser IIID ..... CALL
HP Laser III 1525
HP Laser IIIP ..... CALL
OKI OL 400 665
OKI OL 800 ..... CALL
OKI OL 840 P.S. 1720
Panasonic 4420 835
Panasonic 4450 1295
NEC Silentwriter 2 ..... CALL

PRINTERS

Epson LQ 200 245
Epson LQ 570 295
Epson LQ 870 480
Epson LQ 1170 625
OKIDATA 320 330
OKIDATA 390 465
Citizen HSP-500 335

HARD DISKS

CONNOR
CP30104 120 meg ..... CALL
CP3204F 220 meg ..... CALL
QUANTUM, MAXTOR, SEAGATE
CALL FOR ALL MODELS

Corporate Accounts Welcome
Call for Discounts on Volume
And
Consultant Orders
Exports Available

Computerlane inc.

Outside California: 1-800-526-3482

Inside California: 818-884-8644 • FAX: 818-884-8253

7500 Topanga Canyon Boulevard, Canoga Park, CA 91303
Hours: Monday - Friday 9 -6, Saturday 10-6

ALL QUOTED PRICES ARE CASH PRICES ONLY
Visa, MasterCard and American Express are higher
Prices subject to change without notice.
*Quantities are limited

Compaq is a Registered Trademark of Compaq. IBM is a Registrered Trademark of International Business Machines.

World Radio History

Serving you since 1979

JDR Microdevices®

2233 Samaritan Drive, San Jose, CA 95124

BUY WITH CONFIDENCE FROM JDR!
- 30-DAY MONEY BACK GUARANTEE
- 1 YEAR WARRANTY
- TOLL-FREE TECH SUPPORT

MMC

CALL FOR YOUR FREE CATALOG TODAY!

FOR PC'S, MONITORS, DISK DRIVES, KEYBOARDS, MODEMS, CABLES, CONNECTORS, SOFTWARE, ICS, PROGRAMMING PRODUCTS, TEST EQUIPMENT, COMPONENTS & MORE!

INTERFACE CARDS 16-BIT IDE MULTI I/O $69.95

- 286/386/486 COMPATIBLE
- SUPPORTS 2 IDE HARD & 2 FLOPPY DRIVES
- TWO SERIAL, ONE PARALLEL & ONE GAME PORT

MCT-IDEIO		$69.95
MCT-IDEFH	IDE HARD/FLOPPY CARD	$29.95
MCT-IO	MULTI I/O CARD FOR 8088 SYSTEMS	$59.95
MCT-AIO	16-BIT SERIAL/PARALLEL/GAME PORT	$49.95
MCT-EEMS	16-BIT EEMS CARD	$149.95
SIMMPLY-RAM	8MB SIMM MEMORY CARD(OK)	$199.95

Seagate HARD DRIVES 89MB $319

IDE	3-1/2"	ST-351A	44.7MB	28MS	$209
IDE	3-1/2"	ST-3096A	89.1MB	16MS	$319
IDE	3-1/2"	ST-3144A	131MB	16MS	$399
IDE	5-1/4"	ST-1239A	212MB	16MS	$619
IDE	5-1/4"	ST-2383A	338MB	16MS	$1159
IDE	3-1/2"	ST-1480A	426MB	14MS	$1239

NOTE: HD-MHW REQUIRED TO MOUNT IN 5-1/4" SLOT. $9.95

FLOPPY DRIVES

FDD-1.44X	1.44MB 3.5" FLOPPY - BLACK	$79.95
FDD-1.44A	1.44MB 3.5" FLOPPY - BEIGE	$79.95
FDD-1.2	5.25" DOUBLE-SIDED HD 1.2MB	$89.95
FD-55GFV	5.25" TEAC DOUBLE-SIDED HD 1.2MB	$99.95
FDD-360	5.25" DOUBLE-SIDED DD 360K	$69.95

BREADBOARD ON-A-CARD

- 8088 CARD ACCESSES ALL 62 I/O SIGNAL CONNECTIONS; 16-BIT CARD ACCESSES 96 • ACCEPTS UP TO 24 14-PIN IC'S

PDS-600	8-BIT CARD	$49.95
PDS-610	16-BIT CARD VERSION	$59.95

PROTOTYPE CARDS

W/SILK-SCREENED LEGENDS

JDR-PR2	8-BIT WITH I/O DECODE LAYOUT	$29.95
JDR-PR10	16-BIT WITH I/O DECODE LAYOUT	$34.95

UNIVERSAL PROGRAMMER/TESTER



- PROGRAMS EPROMS, EEPROMS, PALS, BI-POLAR PROMS, 8748 & 8751 SERIES, 16V8 & 20V8 GALS • TESTS TTL, CMOS, DYNAMIC & STATIC RAMS

MOD-MUP REQUIRES HOST ADAPTOR BELOW $499.95

EPROM PROGRAMMING MODULES

- PROGRAMS 24-32 PIN EPROMS, CMOS EPROMS & EEPROMS, 16K TO 1024K • HEX TO OBJ CONVERTER

MOD-MEP	REQUIRES HOST ADAPTOR CARD	$119.95
MOD-MEP-4	4-EPROM UNIT	$169.95
MOD-MAC	HOST ADAPTOR CARD	$29.95

POST CODE DISPLAY CARD $49.95

READ DISPLAY AND CHECK MANUAL FOR POWER-ON SELF-TEST CODE
- 286/386/486 COMPATIBLE
- WORKS WHEN SOFTWARE WON'T EVEN BOOT YOUR PC

PCODE $49.95

1024 X 768 VGA CARD $149.95

- 8/16-BIT 8088 & 286/386/486 COMPATIBLE
- 1024 X 768 IN 256 COLORS (REQUIRES 1MB) 800 X 600 IN 256 COLORS
- 512K VIDEO RAM EXPANDABLE TO 1MB
- ANALOG OR MULTISYNCH MONITOR SUPPORT

MCT-VGA-1024+	1024 X 768/256 COLORS	$149.95
MCT-VGA-16	8/16-BIT VGA CARD	$49.95

1024 x 768 VGA MONITOR $349.95

- 1:1 ASPECT RATIO; 0.28 DOT PITCH
- 14" DIAGONAL SCREEN
- COMPATIBLE WITH ALL VGA ADAPTORS

VGA-MON-1024		$349.95
VGA-MON-1024N	NON-INTERLACED VERSION	$389.95

1024 X 768 VGA PACKAGE $469.95

- 8088 & 286/386/486 COMPATIBLE CARD & 1024 X 768 INTER-LACED MONITOR
- 1:1 ASPECT RATIO; 0.28 DOT PITCH

VGA-PKG-1024+		$469.95
VGA-PKG	640 X 480 VGA PACKAGE	$349.95

101-KEY $49.95

BTC-5339		$49.95
MAX-5339	101-KEY ENHANCED MAXI-SWITCH	$69.95
K103-A	101-KEY ENHANCED WITH CLICK	$84.95

3-BUTTON MOUSE $14.95

- ACCURACY 290 -1450 DPI
- MICROSOFT & MOUSE SYSTEMS COMPATABILITY MODES
- OPTO-MECHANICAL DESIGN
- WINDOWS 3.0 COMPATIBLE

JDR-MOUSE-3 ..... $14.95

DYNAMIC RAM

PART #	SIZE	SPEED	TYPE	PRICE
41256-100	262144x1	100ns	DIP	1.49
41256-80	262144x1	80ns	DIP	1.69
41256-60	262144x1	60ns	DIP	2.39
414256-80	262144x4	80ns	DIP	5.95
1MB-100	1048576x1	100ns	DIP	5.49
1MB-80	1048576x1	80ns	DIP	5.99
1MB-60	1048576x1	60ns	DIP	6.49
41256A9B-80	256K x 9	80ns	SIMM	16.95
41256A9B-60	256K x 9	60ns	SIMM	19.95
421000A9B-10	1MB x 9	100ns	SIMM	49.95
421000A9B-80	1MB x 9	80ns	SIMM	54.95
421000A9B-60	1MB x 9	60ns	SIMM	59.95
424000A9B-80	4MB x 9	80ns	SIMM	179.95
424000A9B-60	4MB x 9	60ns	SIMM	219.95

MATH CO-PROCESSORS

MANUAL, SOFTWARE GUIDE & 5 YEAR WARRANTY

	PART #	SPEED	PRICE	PART #	SPEED	PRICE
INTEL	8087	5 MHz	89.95	80287-XLT	12 MHz	94.95
	8087-2	8 MHz	129.95	80387-DXP	33 MHz	199.95
	8087-1	10 MHz	169.95	80387-SX	33 MHz	129.95
	80287-XL	12 MHz	94.95	80387-SX20	20 MHz	149.95
CYRIX	83D87-16	16 MHz	169.95	83D87-40	40 MHz	219.95
	83D87-20	20 MHz	169.95	83S87-16(SX)	16 MHz	99.95
	83D87-25	25 MHz	169.95	83S87-20(SX)	20 MHz	114.95
	83D87-33	33 MHz	179.95	83S87-25(SX)	25 MHz	129.95
IIT	2C87-8	8 MHz	79.95	2C87-12	12 MHz	99.95
	2C87-10	10 MHz	89.95	2C87-20	20 MHz	119.95

MAXIMIZE CO-PROCESSOR SPEED

OUR "2ND STAGE" ALLOWS 10 & 20MHZ CO-PROCESSORS TO RUN AT FULL SPEED IN THE SLOWEST 286 SYSTEMS

2ND-STAGE FOR 10/20 MHZ 80287'S $29.95

MOTHERBOARDS

NEW LOWER PRICES



16MHz MINI 386-SX $249.95

• NORTON SI 11.1 • LANDMARK AT SPEED 20.0

- EXPANDABLE TO 16MB ON-BOARD • AMI BIOS • SIX 16-BIT AND TWO 8-BIT SLOTS • CHIPS & TECHNOLOGY CHIPSET • SOCKET FOR 80387-SX CO-PROCESSOR
- 8.5" X 13" SIZE FITS MINI-286 AND FULL-SIZE 286 CASES

MCT-M386SX		$249.95
MCT-M386SX-20	20MHZ MINI 386 SX	$299.95
MCT-M386-25	25MHZ MINI 386	$399.95
MCT-C386-33	MINI-SIZE 33MHZ CACHE 386	$599.00
MCT-C386-40	MINI SIZE 40MHZ CACHE 386	$699.00
MCT-M486-33	MINI 33MHZ CACHE 486	$995.00
MCT-M286-16	MINI 16MHZ 286	$149.95
MCT-M286-12	MINI 12MHZ 286	$129.95
MCT-TURBO-10	10/4.77MHZ 8088	$69.95

UPRIGHT CASE $99.95

- FOR STD., FULL AND MINI-MOTHERBOARDS
- MOUNTS FOR 3 FLOPPY AND 4 HARD DRIVES
- TURBO AND RESET SWITCHES
- SPEED DISPLAY, POWER, DISK LEDS

CASE-100A		$99.95
PS-250TW	250W POWER SUPPLY	$129.95
PS-300TW	300W POWER SUPPLY	$149.95

POWER SUPPLIES ARE U.L. APPROVED

MORE CASES...

CASE-70	FULL-SIZE 286 STYLE CASE	$89.95
CASE-120	MINI-UPRIGHT W/200W P.S.	$199.95
CASE-JR	MINI FLIP-TOP W/200W P.S.	$149.95
CASE-50	MINI-SIZE 286 STYLE CASE	$59.95

POWER SUPPLIES

- U.L. APPROVED - 110/220V,50/60HZ

PS-150	8088 150 WATT	$69.95
PS-200X	8088 200 WATT	$89.95
PS-200	286/386/486 200 WATT	$89.95
PS-250	286/386/486 250 WATT	$129.95
PS-300	286/386/486 300 WATT	$149.95
PS-250TW	286/386/486 250W, EXTERNAL SWITCH	$129.95
PS-300TW	286/386/486 300W, EXTERNAL SWITCH	$149.95

2400 BAUD MODEM $49.95

- 2400/1200/300 BPS INTERNAL DATA MODEM • FULL HAYES AT COMPATIBILITY • INCLUDES PROCOMM SOFTWARE

MCT-241 ..... $49.95

9600 BAUD V.42 BIS MODEM $399.95

- CCIT V.42BIS/V.32/V.22BIS/BELL 212A AND HAYES AT COMMAND SET COMPATIBLE
- 2 YEAR PROMETHEUS WARRANTY

PRO-96E		$399.95
PCCB6201	INTEL SATISFAXTION 16-BIT FAX CARD	$399.95
PCEM7296	INTEL 9600 BAUD EXTERNAL MODEM	$479.95
VIVA-24E	VIVA 2400BPS EXTERNAL MODEM	$119.95
VIVA-24MNP	VIVA 2400 BPS W/ ERROR CORREX	$149.95

VISA MasterCard

SALES 800-538-5000

Customer Service 800-538-5001 Local/Int'l 408-559-1200
Technical Support 800-538-5002 Fax 408-559-0250

TERMS: For shipping & handling include $5.00 for ground and $7.50 for air. Orders over 1 lb. and foreign orders may require additional shipping charges—contact our Sales Dept. for the amount. CA residents must include applicable sales tax. Prices subject to change without notice. We are not responsible for typographical errors. We reserve the right to limit quantities and to substitute manufacturer. All merchandise subject to prior sales. A full copy of our terms is available upon request. Items pictured may only be representative. JDR, the JDR logo, JDR Microdevices, and the MCT logo are registered trademarks of JDR MICRODEVICES, INC. Modular Circuit Technology, is a trademark of JDR MICRODEVICES, INC. Copyright 1992 JDR MICRODEVICES.

KEY CODE 1028

Circle 6 on Inquiry Card (RESELLERS: 7).

World Radio History

READER SERVICE

ALPHABETICAL INDEX TO ADVERTISERS

Inquiry No.		Page No.
32	3-D VISIONS	247
33-34	ABACUS SOFTWARE	131
176-177	ABTECH	313
35-36	ACER INCORPORATED	37
178	ACMA COMPUTERS INC	321
560	ACTION COMP SUPPLIES	336MW-6
226	ADD ON AMERICA	340
170	ADDSTOR INC	65
179-180	ADVANCED COMP PROD	315
39	ADVANCED MICRO DEV	210-211
416-417	AGC ELECTRONICS CORP	82IS-47
577	AIMS INFORMATION SYS	336PC-8
38	ALADDIN KNOWLEDGE SYS	164
8	ALDUS	221
418	AMDS EUROPE LTD	82IS-17
*	AME INSTIT FOR COMP SCI	348
227	AMERICAN ADVANTECH	344
40-41	AMERICAN MEGATRENDS	95
42	AMERICAN POWER CONV	248
419	AMERICAN POWER CONV	82IS-10
43	AMERICAN SMALL BUSI COMP	141
181	AMT INTERNATIONAL	334
284	ANACAPA MICRO PRODUCTS	344
576	ANCOT CORPORATION	336PC-4
420-421	AOC INTERNATIONAL	82IS-55
228	APPLIED CONCEPTS	344
589	APPRO INT'L INC	336SO-6
596	APPRO INT'L INC	336NE-4
*	APS TECHNOLOGIES	312
422	ASP COMPUTER PROD	82IS-16
169	ASYMETRIX	132,133
44	ATI TECHNOLOGIES INC	53
408	ATOMSTYLE, LTD	82UK-24
182	ATRONICS	327
159	AVIS	111
277	AVOCADO COMPUTER VIDEO	344
292-293	AXIOM	340
229	B&C MICROSYSTEMS	340
183-184	BAY TECHNICAL ASSOC	339
45-46	BEST POWER TECHNOLOGIES	174
47	BIT SOFTWARE INC	140
450	BIX	367
*	BIX (INT'L)	283
165-166	BLINK INC	113
49-50	BORLAND INTERNATIONAL	11
296-297	BORLAND INTERNATIONAL	33
407	BRAIN BOXES	82UK-16
172	BROWN WAGH PUBLISHING	127
51-52	BUREAU OF ELECT PUBL	100
*	BYTE CARD DECK	144
175	BYTE LISTINGS ON DISK	271
*	BYTE SUB MESSAGE	82IS-46
*	BYTE SUB MESSAGE	260
64	BYTE/DEMOLINK	365
*	C++ REPORT	82IS-56A-B
218	CAD ONE COMP DESIGN	310,311
9	CALERA RECOGNITION SYS	243
185	CALERA RECOGNITION SYS	338
10	CANON USA INC	240
53-54	CAPITAL EQUIPMENT CO	166,167
466	CASE DESIGN	82IS-28
405	CHERWELL SCNTFC PUBL	82UK-14
222	CITITRONICS	326
423-424	CLARION SOFTWARE	82IS-51
552-553	CLARION SOFTWARE	336MW-1
55	COMPAQ COMPUTER CORP	12,13
425-426	COMPEX	82IS-12
186	COMPEX INTERNATIONAL	338
286	COMPUBOOKS	347
427	COMPUCLASSICS	82IS-25
230	COMPUCOM CORP	345
402	COMPUMART	82UK-19
428	COMPUSAVE INT'L	82IS-38
56-57	COMPUSERVE	183-185
58	COMPUTER ASSOCIATES	22
11	COMPUTER ASSOCIATES	239
*	COMPUTER CONNECTIONS B V	82IS-11
429	COMPUTER QUICK	82IS-14
*	COMPUTER/BYTE BK CLB (N.A.)	282A-B
*	COMPUTER/BYTE BOOK CLB (N.A.)	283
187	COMPUTERLANE UNLIMITED	357
223	COMPUTERWORX	306
211-212	COMTRADE	328
558	CONSAN INC	336MW-7
231	CONTROL VISION	346
*	COPIA INTERNATIONAL	130
12	COREL SOFTWARE	251
232-233	COVOX INC	341
154	CREATIVE LABS INC	93
13-14	CTX INTERNATIONAL INC	253
234	CURTIS INC	340
300-302	CYBER RESEARCH	332
303-305	CYBER RESEARCH	333
188	CYBEX CORPORATION	314
294	CYBEX CORPORATION (INT'L)	CIII
452	DAN TECHNOLOGY PLC	82IS-5
235	DATACAP	348
59-60	DATALUX CORPORATION	126
430	DATAPRO INTERNATIONAL	82IS-56
415	DEEPAK SAREEN ASSOC	82UK-23
*	DELL COMPUTER	82UK-5
409	DELL COMPUTER	82UK-7
62	DELL COMPUTER CORP (N.A.)	CIII
63	DELL COMPUTER CORP (N.A.)	CIV
61	DELPHI	301
87	DESCRIBE INC	181
65	DESKTOP DIRECT FROM DIGITAL	82A-F
406	DIGI-DATA LTD	82UK-18
168	DIGITAL CONSULTING INC	177
*	DIGITAL EQUIPMENT CORP	179
*	DIGITAL EQUIPMENT CORP	209
66	DIGITAL RESRCH INC (N.A.)	104,105
431	DIGITAL RESRCH SYS GROUP	82IS-9
189-190	DISTRIBUTED PROCESSING	325
236	DIVERSIFIED COMPUTER	348
432	DR HUGGLE & PARTNER GMBH	82IS-53
67	DRAGON SYSTEMS	155
457	E C G B.V./UNITRON	82IS-31
404	EDINBURGH PORTABLE COMPILER	82UK-10
191	ELEK TEK	316
*	ELONEX	82IS-2
462	EMULTEK	82IS-50
285	ERIN-AMERICAN LTD	340
554-555	EVOLUTION COMPUTING	336MW-4
571-572	EVOLUTION COMPUTING	336PC-7
68-69	EXABYTE CORPORATION	205
433	FAST ELECTRONIC GMBH	82IS-52
453-454	FIRST INT'L COMP	82IS-33
192-193	FIRST SOURCE INT'L	329
70	FOX SOFTWARE INC	78,79
237	FPLOT CORP	349
71	FRAME TECHNOLOGY	278
72-73	FTP SOFTWARE (N.A.)	201
410	GANDLAKE GROUP	82UK-13
*	GATEWAY 2000	CII,1
*	GATEWAY 2000	43–50
74-75	GLENCO ENGINEERING	296
564-565	GLOBALINK INC	336NE-7
*	GLOBALINK INC	336SO-A-B
581-582	GLOBALINK INC	336SO-1
238	GMM RESEARCH CORP	341
434	GREY MATTER LTD	82IS-27
240	GTEK INC	342
239	GTEK INC	343
575	GUIDEWARE CORP	336PC-4
583-584	H & W MICRO LABS, INC	336SO-8
413	HIT	82UK-16
194-195	H. CO. COMPUTER PRODUCTS	323
*	HARD DRIVES INT'L	307
276	HAUPPAUGE COMP WRKS	115–118
15	HERCULES COMPUTER TECH	241
221	HI-TECH USA	330
76	HIGH-RES TECHNOLOGIES	128
241	HOOLEON	344
435	I-COM	82IS-44
*	IBM CORP	24,25
*	ICS	336PC-A-B
573	ICS	336PC-1
599-600	ICS COMPUTERS	366MW-8
601-602	ICS COMPUTERS	336NE-6
242	IMAGE IN INC	349
157-158	IMAGE NORTH TECH	112
279	IMAGING AUTOMATION, INC	345
79	INTEGRAND RESEARCH	261
77-78	INTEGRATED INFO TECH	69
80-81	INTEL CORPORATION	20,21
243	INTEL CORPORATION	349
160	INTERACTIVE IMAGE TECH	92
196-197	INTERSYS	324
244	IO TECH	346
298-299	ISLAND SYSTEMS (INT'L)	CIV
82	JAMECO ELECTRONICS	264-265
6-7	JDR MICRODEVICES	358
83	KEA SYSTEMS LTD	84
248	KEITHLEY METRABYTE	343
245	KILA	342
84-85	KINGSTON TECHNOLOGY	170
463-464	KYE SYSTEMS CORP	82IS-42
288	L-COM, INC	342
246	LAGUNA DATA SYSTEMS	347
86	LAHEY COMPUTER SYSTEMS	102
198	LANCAST	308
206-207	LANDMARK RES INT'L CORP	317
290	LAPTOP SOLUTIONS	344
150-151	LIANT SOFTWARE CORP (N.A.)	285
152-153	LIANT SOFTWARE CORP (INT'L)	285
146-147	LIANT SOFTWARE CORP (N.A.)	287
148-149	LIANT SOFTWARE CORP (INT'L)	287
164	LIGHTHORSE TECHNOLOGIES	215
247	LINK COMPUTER GRAPHICS	346
217	LODE STAR COMPUTER	304,305
436	LOGIC PROGRAMMING ASSOC	82IS-46
461	M.L.L. S/W & COMP IND. LTD	82IS-32
30-31	MAG INNOVISION	234-235
*	MANCHESTER EQUIP CO	336NE-A-B
566	MANCHESTER EQUIP CO	336NE-1
*	MARK WILLIAMS CO	145
460	MARKUS SOFTWARE DIST	82IS-54
16-17	MATHEMATICA INC	224-225
89	MATHSOFT INC	157
90	MATHSOFT INC	263
556-557	MAXIMUM STORAGE	336MW-5
585-586	MAXIMUM STORAGE	336SO-4
*	MCGRAW HILL NRI (N.A.)	294A-B
439-440	MDBS INC	82IS-19
437-438	MEGADATA	82IS-34
200-201	MERRITT COMPUTER PROD	320
202	MICRO SOLU COMP PROD	319
216	MICRO-L COMPUTERS INC	334
249	MICROPROCESSORS UNLTD	344
*	MICROSOFT CORP	7,19
*	MICROSOFT CORP	86,87
*	MICROSOFT CORP	153
*	MICROSOFT CORP	169
250	MICROSTAR LABORATORIES	343
91-92	MICROTEST	258
94	MICROWAY	159
93	MICROWAY	266
595	MICROWORLD	336PC-5
441	MIX SOFTWARE	82IS-37
442	MORTICE KERN (MKS)	82IS-21
456	MOUNTAIN NETWORK SOLU	82IS-35
261-264	MULTIMEDIA COMP SYS	345
18-19	NANAO USA CORP	147
203-204	NATIONAL DESIGN	335
251	NATIONAL INSTRUMENTS	348
*	NAT'L INSTRUMENTS	82IS-56A-B
96	NEC	29–31
95	NEC	72,73
20	NEC	245
199	NEVADA COMPUTER	309
569	NEW ENGLAND ELECT	336NE-5
412	NEXTBASE LTD	82UK-15
280	NILES & ASSOCIATES INC	348
*	NORTHGATE COMP SYS	162,163
*	NORTHGATE COMP SYS	190,191
*	NORTHGATE COMP SYS	256,257
*	NORTHGATE COMP SYS	288,289
97	NORTON-LAMBERT	125
21	NOVA INC	242
161-162	ODYSSEY DEVELOPMENT	206
291	OMNITECH ELECTRONICS, INC	346
281	OSCS	349
98	OUTPUT TECHNOLOGY CO	97
252	OVERLAND DATA INC	347
*	PACIFIC DATA PRODUCTS	8,9
*	PACIFIC DATA PRODUCTS	249
99	PANASONIC	66,67
100	PARA SYSTEMS	85
22	PATTON & PATTON	90
551	PC EXPO/NEW YORK	336MW-2,3
563	PC EXPO/NEW YORK	336NE-2,3
570	PC EXPO/NEW YORK	336PC-2,3
580	PC EXPO/NEW YORK	336SO-2,3
101-102	PC POWER & COOLING	71
145	PC PROS	89
597-598	PC-EASE INC	336SO-5
103-104	PERISCOPE COMPANY, THE	222
414	PERSONAL WORKSTA LTD	82UK-22
105	PHAR LAP SOFTWARE INC	55
106	PIONEER COMMUNICATIONS	98
219-220	PIXEL PERFECT/MEDICAL ADV	336
107	PKWARE INC	198
253	POLAROID CORPORATION	340
108	POPKIN SOFTWARE	290
289	PRODUCTIVITY ENHANCEMENT	341
88	PROGRAMMER'S PARADISE	61–63
*	PROGRAMMER'S SHOP	274–277
109-110	PROTECH MARKETING INC	161
254	PSEUDOCORP	349
205	QUA TECH INC	302
255	QUALSTAR CORP	347
155-156	QUANTECH INT'L	204
113	QUANTUM SOFTWARE	281
114	QUARTERDECK OFFICE SYS	91
278	QUIET TECHNOLOGY	345
115	RAIMA CORP	75
116-117	RAINBOW TECHNOLOGIES	103
*	REASONABLE SOLU	82IS-56A-B
*	ROSE ELECTRONICS	220
121	S'NW ELECTRONICS	102
443	S'NW ELECTRONICS	82IS-20
256	SAS INSTITUTE INC	348
118-119	SECURE IT INC	128
224	SECURTECH COMPANY	336
455	SEQUELINK/GNOSIS NV	82IS-45
120	SEQUITER SOFTWARE INC	189
266	SIGEN	343
214-215	SII MICROS	318
*	SILICON GRAPHICS	56,57
*	SOFTLINE CORP	82IS-15
*	SOFTWARE PUBLISHING	123
122	SOFTWARE SECURITY INC	150
403	SOLIDISK TECH LTD	82UK-2
574	SONERA TECHNOLOGIES	336PC-6
*	SONY (N.A.)	207
123	SPECTRUM SOFTWARE	186
124-125	STATSOFT	273
444-445	STONY BROOK SOFTWARE	82IS-6
126	STORAGE DIMENSIONS	88
257	STRADA AUTOTECH, INC	341
127	STRATEGIC MAPPING	101
458	STRUCTURED SOFTWARE SOLU	82IS-20
128	SUMMAGRAPHICS CORP	171
559	SUMMIT MICRO DESIGN	336MW-7
594	SUMMIT MICRO DESIGN	336SO-8
174	SUNSOFT	2,3
171	SUPRA CORPORATION	81
258	SURAH INC	342
129	SYMANTEC	40
587	SYNERCO INC	336SO-7
*	SYS ADMIN	82IS-56C-D
23-24	SYSTAT INC	255
259	TALKING TECHNOLOGY INC	342
260	TALL TREE SYSTEMS	343
265	TECHNOLOGY POWER ENTER	342
446-447	TECHPOWER CO LTD	82IS-48
25	TEKTRONIX	231
26-27	TELEX COMMUNICATIONS	229
287	TEMPUSTECH INC	341
173	TERATECH	172
130	TEXAS INSTRUMENTS	77
578	TLC COMPONENTS	336PC-6
567-568	TMS	336NE-8
131	TOSHIBA AMERICA INC	16,17
208	TOTE-A-LAP	331
274	TRANTOR SYSTEMS LTD	343
275	TRI VALLEY TECHNOLOGY INC	342
267-270	TRIBAL MICROSYSTEMS	346
448	TULIN TECHNOLOGY	82IS-44
459	UCM	82IS-36
163	ULSI SYSTEMS INC	173
167	ULTRATEK PRODUCTS	129
449	UNIBIT SPA	82IS-18
282-283	UNIFORUM ASSOCIATION	349
209-210	UNIVERSAL MEMORY PROD	337
*	UNIXWORLD	217–219
*	US ROBOTICS S.A.	82IS-56C-D
465	USA SOFTWARE	82IS-49
132	VERBATIM CORPORATION	199
133	VERMONT CREATIVE S/W	15
134	VIDEX	139
28-29	VIEWSONIC	223
401	VOGON ENTER LTD	82UK-17
411	VOGUE COMPUTER CO LTD	82UK-9
451	WALKER, RICHER & QUINN	82IS-23
135	WATCOM PRODUCTS INC	27
271	WINTEK CORP	341
136-138	WOLFRAM RESEARCH	121
272	XELTEK	346
142	Z-NIX COMPANY INC	143
273	Z-WORLD ENGINEERING	347
141	ZEOS INTERNATIONAL	6,6A-D
143-144	ZYLAB/DIVISION OF IDI	203

* *Correspond directly with company.*

World Radio History

To get further information on the products advertised in BYTE, fill out the reader service card by circling the numbers on the card that correspond to the inquiry number listed with the advertiser. This index is provided as an additional service by the publisher, who assumes no liability for errors or omissions.

*Correspond directly with company.

INDEX TO ADVERTISERS BY PRODUCT CATEGORY

HARDWARE

926 ACCESSORIES/SUPPLIES

Inquiry No.		Page No.
560	ACTION COMP SUPPLIES	336MW-6
285	ERIN-AMERICAN LTD	340
*	PACIFIC DATA PRODUCTS	8,9
253	POLAROID CORPORATION	340
118-119	SECURE IT INC	128
224	SECURTECH COMPANY	336

927 ADD-IN BOARDS

226	ADD ON AMERICA	340
40-41	AMERICAN MEGATRENDS	95
292-293	AXIOM	340
229	B&C MICROSYSTEMS	340
407	BRAIN BOXES	82UK-16
425-426	COMPEX	82IS-12
232-233	COVOX INC	341
154	CREATIVE LABS INC	93
234	CURTIS INC	340
189-190	DISTRIBUTED PROCESSING	325
453-454	FIRST INT'L COMPUTER	82IS-33
15	HERCULES COMPUTER TECH	241
76	HIGH-RES TECHNOLOGIES	128
77-78	INTEGRATED INFO TECH	69
80-81	INTEL CORPORATION	20,21
82	JAMECO ELECTRONICS	264,265
94	MICROWAY	159
93	MICROWAY	286
103-104	PERISCOPE COMPANY, THE	222
289	PRODUCTIVITY ENHANCEMENT	341
205	QUA TECH INC	302
257	STRADA AUTOTECH, INC	341
259	TALKING TECHNOLOGY INC	342
287	TEMPUSTECH INC	341
448	TULIN TECHNOLOGY	82IS-44
271	WINTEK CORP	341

928 BAR CODING

134	VIDEX	139

929 COMMUNICATIONS/NETWORKING

35-36	ACER INCORPORATED	37
226	ADD ON AMERICA	340
408	ATOMSTYLE, LTD	82UK-24
425-426	COMPEX	82IS-12
238	GMM RESEARCH CORP	341
240	GTEK INC	342
583-584	H & W MICRO LABS, INC	336SO-8
463-464	KYE SYSTEMS CORP	82IS-42
288	L-COM, INC	342
91-92	MICROTEST	258
259	TALKING TECHNOLOGY INC	342

930 COMPUTER SYSTEMS

176-177	ABTECH	313
35-36	ACER INCORPORATED	37
178	ACMA COMPUTERS INC	321
416-417	AGC ELECTRONICS CORP	82IS-47
577	AIMS INFORMATION SYS	336PC-8
589	APPRO INT'L INC	336SO-8
598	APPRO INT'L INC	336NE-4
182	ATRONICS	327
218	CADONE COMPUTER DESIGN	310,311
222	CITITRONICS	326
186	COMPEX INTERNATIONAL	338
223	COMPUTERWORX	306
211-212	COMTRADE	328
452	DAN TECHNOLOGY PLC	82IS-5
59-60	DATALUX CORPORATION	128
*	DELL COMPUTER	82UK-5
409	DELL COMPUTER	82UK-7
62	DELL COMPUTER CORP (N A)	CIII
63	DELL COMPUTER CORP (N A)	CIV
65	DESKTOP DIRECT FROM DIGITAL	82A-F
*	DIGITAL EQUIPMENT CORP	179
*	DIGITAL EQUIPMENT CORP	209
431	DIGITAL RESRCH SYS GROUP	82IS-9
457	E C G B.V./UNITRON	82IS-31
191	ELEK TEK	316
*	ELONEX	82IS-2
453-454	FIRST INT'L COMPUTER	82IS-33
410	GANDLAKE GROUP	82UK-13
*	GATEWAY 2000	CII,1
*	GATEWAY 2000	43-50
221	HI-TECH USA	330
*	IBM CORP	24-25
599-600	ICS COMPUTERS	336MW-8
601-602	ICS COMPUTERS	336NE-6
80-81	INTEL CORPORATION	20,21
196-197	INTERSYS	324
245	KILA	342
*	MANCHESTER EQUIP CO	336NE-A-B
566	MANCHESTER EQUIP CO	336NE-1
437-438	MEGADATA	82IS-34
216	MICROLINE COMPUTER INC	334
595	MICROWORLD	336PC-5
569	NEW ENGLAND ELECT	336NE-5
*	NORTHGATE COMPUTER SYS	162,163
*	NORTHGATE COMPUTER SYS	190,191
*	NORTHGATE COMPUTER SYS	256,257
*	NORTHGATE COMPUTER SYS	288,289
101-102	PC POWER & COOLING	71
145	PC PROS	89
597-598	PC-EASE INC	336SO-5
214-215	SII MICROS	318
*	SILICON GRAPHICS	56,57
403	SOLIDISK TECHNOLOGY LTD	82UK-2
559	SUMMIT MICRO DESIGN	336MW-7
594	SUMMIT MICRO DESIGN	336SO-8
258	SURAH INC	342
587	SYNERCO INC	336SO-7
265	TECHNOLOGY POWER ENTER	342
446-447	TECHPOWER COMPANY LTD	82IS-48
576	TLC COMPONENTS	336PC-6
275	TRI VALLEY TECHNOLOGY INC	342
167	ULTRATEK PRODUCTS	129
449	UNIBIT SPA	82IS-18
411	VOGUE COMPUTER CO LTD	82UK-9
141	ZEOS INTERNATIONAL	6,6A-D

931 DATA ACQUISITION

248	KEITHLEY METRABYTE	343
250	MICROSTAR LABORATORIES	343
*	NATIONAL INSTRUMENTS	82IS-56A-B

932 DISK & OPTICAL DRIVES

40-41	AMERICAN MEGATRENDS	95
*	APS TECHNOLOGIES	312
558	CONSAN INC	336MW-7
68-69	EXABYTE CORPORATION	205
239	GTEK INC	343
*	HARD DRIVES INT'L	307
556-557	MAXIMUM STORAGE	336MW-5
585-586	MAXIMUM STORAGE	336SO-4
202	MICRO SOLUTIONS COMP PROD	319
106	PIONEER COMMUNICATIONS	98
266	SIGEN	343
*	SONY (N A.)	207
258	SURAH INC	342
274	TRANTOR SYSTEMS LTD	343
132	VERBATIM CORPORATION	199

933 DISKETTES/DUPLICATORS

200-201	MERRITT COMPUTER PROD	320

934 FAX BOARDS/MACHINES

260	TALL TREE SYSTEMS	343

935 GRAPHICS TABLETS/MICE/PEN INPUT

463-464	KYE SYSTEMS CORP	82IS-42
128	SUMMAGRAPHICS CORP	171
142	Z-NIX COMPANY INC	143

936 KEYBOARDS

59-60	DATALUX CORPORATION	126
241	HOOLEON	344
83	KEA SYSTEMS LTD	84
*	NORTHGATE COMPUTER SYS	162,163
*	NORTHGATE COMPUTER SYS	190,191
*	NORTHGATE COMPUTER SYS	256,257
*	NORTHGATE COMPUTER SYS	288,289

937 LAN HARDWARE

188	CYBEX CORPORATION	314
294	CYBEX CORPORATION (INT'L)	CIII
410	GANDLAKE GROUP	82UK-13
456	MOUNTAIN NETWORK SOLU	82IS-35
101-102	PC POWER & COOLING	71
258	SURAH INC	342

938 LAPTOPS & NOTEBOOKS

35-36	ACER INCORPORATED	37
65	DESKTOP DIRECT FROM DIGITAL	82A-F
453-454	FIRST INT'L COMPUTER	82IS-33
410	GANDLAKE GROUP	82UK-13
290	LAPTOP SOLUTIONS	344
164	LIGHTHORSE TECHNOLOGIES	215
95	NEC	72,73
131	TOSHIBA AMERICA INC	16-17
401	VOGON ENTERPRISES LTD	82UK-17

939 MAIL ORDER

179-180	ADVANCED COMP PROD	315
227	AMERICAN ADVANTECH	344
181	AMT INTERNATIONAL	334
408	ATOMSTYLE, LTD	82UK-24
229	B&C MICROSYSTEMS	340
222	CITITRONICS	326
402	COMPUMART	82UK-19
428	COMPUSAVE INTERNATIONAL	82IS-38
429	COMPUTER QUICK	82IS-14
187	COMPUTERLANE UNLIMITED	357
300-302	CYBER RESEARCH	332
303-305	CYBER RESEARCH	333
65	DESKTOP DIRECT FROM DIGITAL	82A-F
192-193	FIRST SOURCE INT'L	329
194-195	H. CO COMPUTER PRODUCTS	323
82	JAMECO ELECTRONICS	264,265
6-7	JDR MICRODEVICES	358
288	L-COM, INC	342
217	LODE STAR COMPUTER	304,305
20	NEC	245
199	NEVADA COMPUTER	309
208	TOTE-A-LAP	331
209-210	UNIVERSAL MEMORY PROD	337

940 MEMORY/CHIPS/UPGRADES

39	ADVANCED MICRO DEVICES	210,211
418	AMDS EUROPE LTD	82IS-17
284	ANACAPA MICRO PRODUCTS	344
53-54	CAPITAL EQUIPMENT CO	166,167
192-193	FIRST SOURCE INT'L	329
276	HAUPPAUGE COMP WORKS	115-118
80-81	INTEL CORPORATION	20,21
82	JAMECO ELECTRONICS	264,265
84-85	KINGSTON TECHNOLOGY	170
249	MICROPROCESSORS UNLIMITED	344
209-210	UNIVERSAL MEMORY PROD	337

941 MISCELLANEOUS HARDWARE

560	ACTION COMP SUPPLIES	336MW-6
228	APPLIED CONCEPTS	344
154	CREATIVE LABS INC	93
279	IMAGING AUTOMATION, INC	345
79	INTEGRAND RESEARCH	261
278	QUIET TECHNOLOGY	345
224	SECURTECH COMPANY	336
269-270	TRIBAL MICROSYSTEMS	346
163	ULSI SYSTEMS INC	173

942 MODEMS/MULTIPLEXORS

230	COMPUCOM CORP	345
91-92	MICROTEST	258
171	SUPRA CORPORATION	81
*	US ROBOTICS S.A.	82IS-56C-D

943 MONITORS & TERMINALS

32	3-D VISIONS	247
420-421	AOC INTERNATIONAL	82IS-55
55	COMPAQ COMPUTER CORP	12,13
13-14	CTX INTERNATIONAL INC	253
30-31	MAG INNOVISION	234,235
18-19	NANAO USA CORP	147
96	NEC	29-31
28-29	VIEWSONIC	223

944 MULTIMEDIA

277	AVOCADO COMPUTER VIDEO	344
10	CANON USA INC	240
231	CONTROL VISION	346
154	CREATIVE LABS INC	93
76	HIGH-RES TECHNOLOGIES	128
279	IMAGING AUTOMATION, INC	345
261-264	MULTIMEDIA COMPUTER SYS	345
25	TEKTRONIX	231
26-27	TELEX COMMUNICATIONS	229
459	UCM	82IS-36

945 PRINTERS/PLOTTERS

422	ASP COMPUTER PRODUCTS	82IS-16
65	DESKTOP DIRECT FROM DIGITAL	82A-F
98	OUTPUT TECHNOLOGY CO	97
*	PACIFIC DATA PRODUCTS	249
99	PANASONIC	66,67
25	TEKTRONIX	231
130	TEXAS INSTRUMENTS	77

946 PROGRAMMABLE HARDWARE

243	INTEL CORPORATION	349
244	IO TECH	346
247	LINK COMPUTER GRAPHICS	346
291	OMNITECH ELECTRONICS, INC	346
267-268	TRIBAL MICROSYSTEMS	346
272	XELTEK	346
273	Z-WORLD ENGINEERING	347

947 SCANNERS/OCR/DIGITIZERS

463-464	KYE SYSTEMS CORP	82IS-42

948 TAPE DRIVES

40-41	AMERICAN MEGATRENDS	95
*	COMPUTER CONNECTIONS B.V.	82IS-11
406	DIGI-DATA LTD	82UK-18
246	LAGUNA DATA SYSTEMS	347
456	MOUNTAIN NETWORK SOLU	82IS-35
252	OVERLAND DATA INC	347
255	QUALSTAR CORP	347
155-158	QUANTECH INT'L	204
401	VOGON ENTERPRISES LTD	82UK-17

949 UPS

42	AMERICAN POWER CONV	248
419	AMERICAN POWER CONV	82IS-10
183-184	BAY TECHNICAL ASSOC	339
45-46	BEST POWER TECHNOLOGIES	174
100	PARA SYSTEMS	85
101-102	PC POWER & COOLING	71

SOFTWARE

950 BUSINESS

9	CALERA RECOGNITION SYS	243
185	CALERA RECOGNITION SYS	338
415	DEEPAK SAREEN ASSOC	82UK-23
66	DIGITAL RESEARCH INC (N.A.)	104,105
431	DIGITAL RESRCH SYS GROUP	82IS-9
67	DRAGON SYSTEMS	155
413	H I T	82UK-16
*	MICROSOFT CORPORATION	86,87
412	NEXTBASE LTD	82UK-15
22	PATTON & PATTON	90
116-117	RAINBOW TECHNOLOGIES	103
127	STRATEGIC MAPPING	101
129	SYMANTEC	40

951 CAD/CAM

43	AMERICAN SMALL BUSI COMP	141
44	ATI TECHNOLOGIES INC	53
47	BIT SOFTWARE INC	140
554-555	EVOLUTION COMPUTING	336MW-4
571-572	EVOLUTION COMPUTING	336PC-7

952 COMMUNICATIONS/NETWORKING

408	ATOMSTYLE, LTD	82UK-24
47	BIT SOFTWARE INC	140
236	DIVERSIFIED COMPUTER	348
198	LANCAST	308
97	NORTON-LAMBERT	125
261	OSCS	349
116-117	RAINBOW TECHNOLOGIES	103
451	WALKER, RICHER & QUINN	82IS-23

953 DATA ACQUISITION

251	NATIONAL INSTRUMENTS	348

954 DATABASE

165-166	BLINK INC	113
49-50	BORLAND INTERNATIONAL	11
296-297	BORLAND INTERNATIONAL	33
58	COMPUTER ASSOCIATES	22
*	COPIA INTERNATIONAL	130
235	DATACAP	348
70	FOX SOFTWARE INC	78,79
413	H I T	82UK-16
*	MICROSOFT CORPORATION	86,87
161-162	ODYSSEY DEVELOPMENT	206
115	RAIMA CORP	75
120	SEQUITER SOFTWARE INC	189
*	SOFTWARE PUBLISHING	123

955 EDUCATIONAL

33-34	ABACUS SOFTWARE	131
*	AME INSTIT FOR COMP SCI	348
51-52	BUREAU OF ELECTRONIC PUBL	100
*	BYTE CARD DECK	144
*	MCGRAW HILL NRI	294A-B
219-220	PIXEL PERFECT/MEDICAL ADV	336

956 ENGINEERING/SCIENTIFIC

405	CHERWELL SCNTFC PUBL	82UK-14
432	DR HUGGLE & PARTNER GMBH	82IS-53
462	EMULTEK	82IS-50
206-207	LANDMARK RES INT'L CORP	317
16-17	MATHEMATICA INC	224,225
89	MATHSOFT INC	157
90	MATHSOFT INC	263
280	NILES & ASSOCIATES INC	348
123	SPECTRUM SOFTWARE	186
126	STORAGE DIMENSIONS	88
23-24	SYSTAT INC	255
136-138	WOLFRAM RESEARCH	121

957 GRAPHICS

32	3-D VISIONS	247
8	ALDUS	221
11	COMPUTER ASSOCIATES	239
12	COREL SOFTWARE	251
237	FPLOT CORP	349
71	FRAME TECHNOLOGY	278
157-158	IMAGE NORTH TECH	112
16-17	MATHEMATICA INC	224,225
18-19	NANAO USA CORP	147
203-204	NATIONAL DESIGN	335
21	NOVA INC	242
261	OSCS	349
*	PACIFIC DATA PRODUCTS	249
414	PERSONAL WORKSTA LTD	82UK-22
127	STRATEGIC MAPPING	101
25	TEKTRONIX	231

958 MACINTOSH

414	PERSONAL WORKSTA LTD	82UK-22

959 MAIL ORDER

427	COMPUCLASSICS	82IS-25
434	GREY MATTER LTD	82IS-27
88	PROGRAMMER'S PARADISE	61-63
*	PROGRAMMER'S SHOP	274-277
121	S'NW ELECTRONICS	102
443	S'NW ELECTRONICS	82IS-20
455	SEQUELINK/GNOSIS NV	82IS-45
*	SOFTLINE CORP	82IS-15
465	USA SOFTWARE	82IS-49

World Radio History

To get further information on the products advertised in BYTE, fill out the reader service card by circling the numbers on the card that correspond to the inquiry number listed with the advertiser. This index is provided as an additional service by the publisher, who assumes no liability for errors or omissions.

*Correspond directly with company.

INDEX TO ADVERTISERS BY PRODUCT CATEGORY

960 MATHEMATICAL/STATISTICAL

Inquiry No.		Page No.
256	SAS INSTITUTE INC	348
124-125	STATSOFT	273
23-24	SYSTAT INC	255

961 MISCELLANEOUS SOFTWARE

Inquiry No.		Page No.
560	ACTION COMP SUPPLIES	336MW-6
172	BROWN WAGH PUBLISHING	127
175	BYTE LISTINGS ON DISK	271
9	CALERA RECOGNITION SYS	243
434	GREY MATTER LTD	82IS-27
219-220	PIXEL PERFECT/MEDICAL ADV	336
127	STRATEGIC MAPPING	101

962 ON-LINE SERVICES

Inquiry No.		Page No.
450	BIX	367
*	BIX (INT L)	283
64	BYTE/DEMOLINK	365
56-57	COMPUSERVE	183-185
61	DELPHI	301
435	I-COM	82IS-44

963 OPERATING SYSTEMS

Inquiry No.		Page No.
66	DIGITAL RESEARCH INC (N A)	104,105
431	DIGITAL RESRCH SYS GROUP	82IS-9
*	MARK WILLIAMS CO	145
113	QUANTUM SOFTWARE	281
114	QUARTERDECK OFFICE SYS	91

964 PROGRAMMING LANGUAGES/TOOLS

Inquiry No.		Page No.
49-50	BORLAND INTERNATIONAL	11
466	CASE DESIGN	82IS-28
66	DIGITAL RESEARCH INC (N A)	104,105
404	EDINBURGH PORTABLE COMPILER	82UK-10
72-73	FTP SOFTWARE (N A)	201
434	GREY MATTER LTD	82IS-27
575	GUIDEWARE CORP	336PC-4
243	INTEL CORPORATION	349
160	INTERACTIVE IMAGE TECH	92
298-299	ISLAND SYSTEMS (INT'L)	CIV
86	LAHEY COMPUTER SYSTEMS	102
146-147	LIANT SOFTWARE CORP (N A)	287
148-149	LIANT SOFTWARE CORP (INT'L)	287
150-151	LIANT SOFTWARE CORP (N A)	285
152-153	LIANT SOFTWARE CORP (INT'L)	285
436	LOGIC PROGRAMMING ASSOC	82IS-46
461	M L L S/W & COMP IND LTD	82IS-32
460	MARKUS SOFTWARE DIST	82IS-54
439-440	MDBS INC	82IS-19
*	MICROSOFT CORP	153
441	MIX SOFTWARE	82IS-37
21	NOVA INC	242
105	PHAR LAP SOFTWARE INC	55
108	POPKIN SOFTWARE	290
254	PSEUDOCORP	349
444-445	STONY BROOK SOFTWARE	82IS-6
173	TERATECH	172
135	WATCOM PRODUCTS INC	27

965 SECURITY

Inquiry No.		Page No.
38	ALADDIN KNOWLEDGE SYS	164
433	FAST ELECTRONIC GMBH	82IS-52
74-75	GLENCO ENGINEERING	296
109-110	PROTECH MARKETING INC	161
116-117	RAINBOW TECHNOLOGIES	103
122	SOFTWARE SECURITY INC	150

966 SHAREWARE

Inquiry No.		Page No.
413	H I T	82UK-16
*	REASONABLE SOLU	82IS-56A-B

967 UNIX

Inquiry No.		Page No.
*	MARK WILLIAMS CD	145
442	MORTICE KERN (MKS)	82IS-21
414	PERSONAL WORKSTA LTD	82UK-22
458	STRUCTURED SOFTWARE SOLU	82IS-20
174	SUNSOFT	2,3
*	SYS ADMIN	82IS-56C-D
282-283	UNIFORUM ASSOCIATION	349
136-136	WOLFRAM RESEARCH	121

968 UTILITIES

Inquiry No.		Page No.
170	ADDSTOR INC	65
423-424	CLARION SOFTWARE	82IS-51
552-553	CLARION SOFTWARE	336MW-1
281	DSCS	349
107	PKWARE INC	198
574	SONERA TECHNOLOGIES	336PC-6
133	VERMONT CREATIVE SOFTWARE	15
401	VOGON ENTERPRISES LTD	82UK-17

969 WINDOWS

Inquiry No.		Page No.
169	ASYMETRIX	132,133
9	CALERA RECOGNITION SYS	243
425-426	COMPEX	82IS-12
242	IMAGE IN INC	349
157-158	IMAGE NORTH TECH	112
206-207	LANDMARK RES INT L CORP	317
90	MATHSOFT INC	283
*	MICROSOFT CORP	7
*	MICROSOFT CORP	87
*	MICROSOFT CORP	153
18-19	NANAO USA CORP	147
136-138	WOLFRAM RESEARCH	121
143-144	ZYLAB/DIVISION OF IDI	203

970 WORD PROCESSING/DTP

Inquiry No.		Page No.
87	DESCRIBE INC	181
581-582	GLOBALINK INC	336SO-1
*	GLOBALINK INC	336SO-A-B
564-585	GLOBALINK INC	336NE-7
*	MICROSOFT CORP	7
*	MICROSOFT CORP	19
*	MICROSOFT CORP	86
*	MICROSOFT CORP	169
*	MICROSOFT CORP	153
161-162	ODYSSEY DEVELOPMENT	206
*	PACIFIC DATA PRODUCTS	249
*	ROSE ELECTRONICS	220
143-144	ZYLAB/DIVISION OF IDI	203

971 BOOKS/PUBLICATIONS

Inquiry No.		Page No.
*	C++ REPORT	82IS-56A-B
286	COMPUBOOKS	347
*	COMPUTER/BYTE BOOK CLUB (N A)	282A-B
*	COMPUTER/BYTE BOOK CLUB (N A)	283
430	DATAPRO INTERNATIONAL	82IS-56
*	SYS ADMIN	82IS-56C-D
*	UNIXWORLD	217-219

972 MISCELLANEOUS

Inquiry No.		Page No.
576	ANCOT CORPORATION	336PC-4
159	AVIS	111
*	BYTE SUB MESSAGE	82IS-46
*	BYTE SUB MESSAGE	260
168	DIGITAL CONSULTING INC	177
*	ICS	336PC-A-B
573	ICS	336PC-1
551	PC EXPO/NEW YORK	336MW-2,3
563	PC EXPO/NEW YORK	336NE-2,3
570	PC EXPO/NEW YORK	336PC-2,3
580	PC EXPO/NEW YORK	336SO-2,3
567-568	TMS	336NE-8

BYTE ADVERTISING SALES STAFF:

Jennifer L. Bartel, National Sales Manager, 14850 Quorum Drive, Suite 380, Dallas, TX 75240, tel. (214) 701-8496
Liz Coyman, Inside Advertising Sales Director, One Phoenix Mill Lane, Peterborough, NH 03458, tel. (603) 924-2518

NEW ENGLAND
ME, NH, VT, MA, RI, CT, ONTARIO
CANADA & EASTERN CANADA
(617) 860-6344
Patricia Payne (603) 924-2654
McGraw-Hill Publications
24 Hartwell Avenue
Lexington, MA 02173
FAX: (617) 860-6899

EAST COAST
NY, NYC, NJ, DC, DE, MD, VA, WV, PA
Kim Norris (212) 512-2645
Ariane Casey (212) 512-2368
Patricia Payne (603) 924-2654
McGraw-Hill Publications
1221 Avenue of the Americas—
28th Floor
New York, NY 10020
FAX: (212) 512-2075

SOUTHEAST
NC, SC, GA, FL, AL, TN, MS, AR, LA, KY
John Y. Schilin (404) 843-4762
Patricia Payne (603) 924-2654
McGraw-Hill Publications
4170 Ashford-Dunwoody Rd., Suite 520
Atlanta, GA 30319
FAX: (404) 252-4056

MIDWEST
IL, MO, KS, IA, ND, SD, MN,
WI, NE, IN, MI, OH
Kurt Kelley (312) 616-3328
MaryAnn Goulding (603) 924-2664
McGraw-Hill Publications
Two Prudential Plaza
180 North Stetson Ave
Chicago, IL 60601
FAX: (312) 616-3370

SOUTHWEST, ROCKY MOUNTAIN
CO, OK, TX,
Jennifer Walker **(214) 701-8496**
Barry Echavarna **(603) 924-2574**
McGraw-Hill Publications
14850 Quorum Dr., Suite 380
Dallas, TX 75240
FAX: (214) 991-6208

NORTH PACIFIC: San Francisco, CA
NORTHERN CA, OR, ID, MT,
WY, NORTHERN NV
Roy J. Kops (415) 954-9728
Leslie Hupp (415) 954-9705
McGraw-Hill Publications
425 Battery Street
San Francisco, CA 94111
FAX: (415) 954-9786

NORTH PACIFIC: Campbell, CA
SILICON VALLEY, HI, WA, AK,
W. CANADA
Bill McAfee (408) 879-0381
Leslie Hupp (408) 879-0381
McGraw-Hill Publications
1999 South Bascom Ave., Suite 210
Campbell, CA 95008
FAX: (408) 879-9067

SOUTH PACIFIC: Los Angeles, CA
LOS ANGELES COUNTY, AZ,
NM, SOUTHERN NEVADA
Alan El Faye (213) 480-5243
Jonathan Sawyer (603) 924-2665
McGraw-Hill Publications
3333 Wilshire Boulevard #407
Los Angeles, CA 90010
FAX: (213) 480-5249

SOUTH PACIFIC: Costa Mesa, CA
ORANGE COUNTY,
SAN DIEGO COUNTY, UT
Beth Dudas (714) 753-8140
Jonathan Sawyer (603) 924-2665
McGraw-Hill Publications
15635 Alton Pky., Suite 290
Irvine, CA 92718
FAX: (714) 753-8147

Peterborough, NH Office: Inside Sales FAX: **603-924-2683** Advertising FAX: **603-924-7507**

Hardware/Software Showcase
Mark Stone (603) 924-2695
Ellen Perham (603) 924-2598
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

The Buyer's Mart (1x2)
Joseph Mabe (603) 924-2656
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

BYTE Deck
Ed Ware (603) 924-2596
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

EURO-DECK
James Bail (603) 924-2533
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

Regional Advertising
Brian Higgins (603) 924-2651
Barry Echavarria (603) 924-2574
Larry Levine (603) 924-2637
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

BYTE International Direct Response Postcards
Ellen Perham (603) 924-2598
BYTE Publications
One Phoenix Mill Lane
Peterborough, NH 03458

International Advertising Sales Staff:

McGraw-Hill Publishing Co., Wimbledon Bridge House, One Hartfield Road, Wimbledon, London, SW19 3RU, England, Tel: 44 81 543 1234, Fax: 44 81 540 3833

GERMANY, SWITZERLAND, AUSTRIA, UNITED KINGDOM
Ron Cordek, Managing Director
European Operations
Christina Barion (44 81 545 6270)
McGraw-Hill Publishing Co.
Wimbledon Bridge House
One Hartfield Road
Wimbledon, London SW19 3RU
England
Tel: 44 81 543 1234
FAX: 44 81 540 3833
TELEX: 892191

JAPAN
Masaki Mori
McGraw-Hill Publishing Co.
Overseas Corp.
Room 1528
Kasumigaseki Bldg
3-2-5 Kasumigaseki,
Chiyoda-Ku
Tokyo 100, Japan
Tel: 81 33 581 9811
FAX: 81 33 581 4018

BENELUX
Ellen Pardede
Batenburg 105
3437 AB Nieuwegein
The Netherlands
Tel: 31 34 02 49496
FAX: 31 34 02 37944

FRANCE, ITALY
Zena Coupé, Amanda Blaskett
A-Z International Sales Ltd
70 Chalk Farm Road
London NW1 8AN
England
Tel: 44 71 284 3171
FAX: 44 71 284 3174

ISRAEL
Dan Ehrlich
Ehrlich Communication
International
P O Box 11297
Tel Aviv 61112, Israel
Tel: 972-52-586 245
Tel: 972-52-586 246
FAX: 972-52-585 685

HONG KONG
William Chu
Seavex Ltd.
503 Wilson House
19-27 Wyndham St
Central, Hong Kong
Tel: (852) 868-2010
FAX: (852) 810-1283
TELEX: 60904 SEVEX HX

TAIWAN
Summer Chien
Candice Lo
Acer TWP Corp.
19-2, Lane 231,
Fu Hsing North Road
Taipei 10445, Taiwan
R O C
Tel: (886) 2 713 6959
FAX: (886) 2 715 1950

AUSTRALIA
Ian McDonald
Hugh Anderson Pty Ltd
119 Market Street
South Melbourne, Australia
Tel: (61) 3-696-5411
FAX: (61) 3-696-5692

David Strike
Sandell Strike Skinner
Whipp Pty Ltd
64 Victoria Street
Box 109, North Sydney
NSW 2060, Australia
Tel: (61) 2-922-2977
FAX: (61) 2-922-1100

INDIA
Ronny Mistry
Ronny Mistry Associates Pvt Ltd
Shinnabad
581 Jam-E-Jamshed Rd
Matunga
Bombay 400019, India
Tel: (91) 22-413-7396
FAX: (91) 22-204-4973

KOREA
Jeon-Gwon Seo
DooBee International Limited
Center Building (Byulgwan)
1-11 Jeong-dong, Choong-ku
C.P.O. Box 4557
Seoul, Korea
Tel: (82) 2 776-2096
FAX: (82) 2 755-9860
TELEX: 787-27117

PHILIPPINES
Luis Nunez
Far East Media Consultants
806-B Filipinas Life Bldg.
6786 Ayala Ave.
1200 Makati
Metro Manila, Philippines
Tel: (63) 2-810-1330
FAX: (63) 2-818-1974

SINGAPORE
Jocelyn Domingo
Seavex Ltd.
400 Orchard Road, #10-01
Singapore 0923
Republic of Singapore
Tel: 65 734 9790
FAX: 65 732 5129
TELEX: RS35539 SEAVEX

PAKISTAN
Arif Salahuddin
INS Media Sales (Pvt) Ltd.
205, 2/F, Panorama Centre
Fatima, Jinnah Road
Karachi, Pakistan
Tel: (92) 21-526-901
FAX: (92) 21-526-207

INDONESIA
Paula Kalangie
Pacific Intermedia
14/F, Arthaloka Bldg
Jalan Jend. Sudirman No. 2
Jakarta Pusat, Indonesia
Tel: (62) 21-586-611
FAX: (62) 21-720-2609

World Radio History

EDITORIAL INDEX BY COMPANY

Index of companies covered in articles, columns, or news stories in this issue.
Each reference is to the first page of the article or section in which the company name appears.
IS pages appear in the International and UK editions; UK pages appear in the UK edition.

Company, Page # Inquiry #

A

AccuSoft, 226 1105
Acorn, 82IS-3, 82UK-11
Adept Scientific Micro Systems, 82IS-34 1331
Adobe Systems, 34, 226, 299, 82IS-7 1106
Advanced Micro Devices, 83 1170
Advanced Micro Technology Computers, 60 1281
The AG Group, 70 1297
Aicom, 187 1174
Aldus, 82, 226 1107 1314
ALR, 106 1131
Amadeus Music Software, 82IS-30 1329
Amaze, 83 1172
Amstrad, 82UK-3
Animated Voice, 187 1175
Antex Electronics, 187 1176
Aox, 299
Apex Voice Communications, 187 1177
Apple Computer, 23, 83, 106, 187, 279, 291, 82IS-3, 82UK-11 1132 1156 1173 1178
Apple Programmers and Developers Association, 279
Apple's Advanced Technology Group, 82UK-11
ARDIS, 291
Arkay Technologies, 187 1179
Artic Technologies International, 187, 82IS-43 1180
Asante Technologies, 70 1298
Ascension, 134
ASG, 82 1316
Ashton-Tate, 82UK-3
Association for Software Design, 175
AT&T, 23, 38, 82UK-3
AT&T Bell Laboratories, 134
AT&T Graphics Software Labs, 106 1133
Atari, 82UK-11
ATI Technologies, 68, 83, 262, 299 1152 1291
Austin, 82UK-3
Automated Design Systems, 34

B

Belgian Post Telephone & Telegraph, 165
Bell Atlantic Thinx Software, 83 1164
Bell Computer, 58 1274
Bellcore, 165
Bell Laboratories, 134
Berkeley Speech Technologies, 165, 187, 82IS-43 1181
Berkeley Systems, 165, 187, 82IS-43 1182
Best Power Technology, 64 1288
BICC Communications, 291
Big Apple, 134
Blackwell Scientific Software, 82UK-8 976
Blinkline, 74 1301
Blue Dolphin Computers, 51 1217
Boca Research, 60 1282
Borland International, 82UK-3
Boxer Software, 51 1218
British Petroleum, 82IS-39
BSDI, 23
Bull World-Wide Information Systems, 175
Bureau of Electronic Publishing, 83 1158

C

Caere, 82 1317
Cal Abco, 82UK-3
CalComp, 59 1276
California Institute of Technology, 82IS-3, 82UK-21
Canon, 23, 82IS-7
Canon USA, 106 1134
Caplin Cybernetics, 82IS-39
Centigram Communication, 165
Cettlan, 70 1296
Cheyenne Software, 192 1318
Chips & Technologies, 23
Citizen Europe, 82IS-7 980
Claris, 226, 82UK-11 1108
Commodore Business Machines, 106, 82UK-11 1135
Communication Intelligence, 99, 212
Compaq Computer, 23, 41, 119, 269 1234
Compass Technology, 187, 82IS-43 1183
Compression Labs, 51 1216
CompuAdd, 82UK-3
Computer Associates International, 226 1109
Computer Design Center, 82IS-3
Computer Peripherals, 70 1294
Computer Support, 226 1110
Comwave, 82IS-32 1330
Corel Systems, 23, 226, 299 1111
Courtauld Institute, 82IS-13
Covox, 187, 82IS-43 1184
Cray Research, 23, 82IS-39
Creative Labs, 34

D

DacEasy, 82UK-3
Dantz Development, 192 1319
Dartmouth College, 134
DEC, 23, 165, 187, 82IS-43 1186
Deico Electronics, 60 1279
Dell Computer, 23, 82UK-3
Delta Microsystems, 192 1320
DeltaPoint, 82, 226 1112 1315
Denaba Software, 226 1113
DFM Systems, 212 1231
Dialogic, 187 1185
Digidesign, 82UK-11
Diquest, 106 1136
Display Industry Association, 82UK-3
Distributed Processing Technology, 83 1159
Dragon Systems, 151, 187 1187
Dynalink Technologies, 83 1171

E

East Coast Software, 82IS-26 978
Eden Group, 212
Edinburgh University, 82IS-39
Electronic Dream Company, 82UK-11
Emerson & Stern Associates, 165, 187 1188
Envisio, 60 1283
Epson, 82IS-7
Ericsson AB, 291
Event One, 226 1114
Exabyte, 192
Exos, 134
Extended Graphics, 34
Extended Systems, 68 1290

F

Farallon Computing, 187, 82IS-43 1189
FCC, 23
Finansa, 82IS-3
First Byte, 165, 187, 82IS-43 1190
Fluent Machines, 267 1221
Fotec, 64 1285
Fractal Design, 226 1115
Franklin Home Electronics, 165
Frogdesign, 23
Frye Computer Systems, 70 1295
Fuji Xerox, 151
Fujitsu, 23, 82IS-7 979

G

Genovation, 59 1277
Genus Microprogramming, 299
Geographical Information Systems, 82IS-3
Getty Trust, 82IS-13
Globalink, 76 1307
Go, 23, 99, 212, 291 1228
Grid Systems, 212
Groupe Bull, 82IS-3
Guideware, 74 1299
Gupta Technologies, 82IS-3
GW Micro, 165, 187, 82IS-43 1191

H

Headland Technology, 23
Helsinki University of Technology, 134
Hewlett-Packard, 34, 83, 291, 299, 82IS-7 1154
Human Interface Technology Laboratory, 175
Hursley Park Development Laboratory, 82IS-39
Husky Computers, 82UK-3

I

IBM, 23, 38, 119, 187, 259, 291, 299, 82IS-3, 82IS-39 1192
IBM Palo Alto Research Center, 82IS-39
IBM Thomas J. Watson Research Center, 151
Iconclass Research and Development Group, 82IS-13 1060
IDG Books, 83 1188
Image-In, 297 1147
ImageSoft, 297 1146
Infinidisc, 68 1289
Infralink of America, 272 1225
Institute of Defense Analyses, 151
Intel, 23, 267, 82IS-3
Intelligent Instrumentation, 80 1310
InterActive, 187, 82IS-43 1193
IQ International, 82UK-3

J

JSB Computer Systems, 82UK-3

K

Kalieda, 82UK-11
Kay Elemetrics, 187 1194
Kingston Technology, 299
Knowledge Garden, 74 1300
Kurzweil Applied Intelligence, 151, 187 1195
Kyocera Electronics, 82IS-36 1332

L

Landmark Research International, 187, 82IS-43 1196
LaserMaster, 83 1155
Latitude, 23
Legato Systems, 192 1323
Lernout & Hauspie Speech Products, 151, 165, 187, 82IS-43 1197
Link, 82UK-3
Logitech, 83, 134 1165
Longman Logotron, 82UK-11
Lotus Development, 23
Lucas Management Systems, 76 1304

M

MacVonk•USA, 76 1306
Magee Enterprises, 76 1308
Magenta Seven, 64 1284
Malibu Software Group, 165
Map-Info, 82IS-3
Marubeni, 38
Mastersoft, 83 1189
The MathWorks, 80 1311
Maynard Electronics, 192 1321
Media Cybernetics, 226 1116
Medisoft, 187 1198
Microcomputer Systems, 187, 82IS-43 1199
Microdeal, 82UK-11
Micro Express, 58 1273
MicroFrontier, 226 1117
Micrografx, 226 1118
Micronics, 58 1271
Micropolis, 106 1137
MicroProse Software, 83 1151
MicroSlate, 212 1229
Microsoft, 23, 34, 83, 259, 297, 82IS-3, 82UK-11 1148 1157 1220 1224
Microsystems Engineering, 226 1119
Microvitec, 82UK-3
MIDI Manufacturers Association, 82UK-11
Mimic, 187 1200
MIT, 165, 175
MIT CAD Lab, 134
MIT Media Lab, 134
Momenta, 10, 212 1230
Morningstar, 76 1305
Motorola, 279, 291, 82IS-3
Mountain Network Solutions, 192 1322
Multimedia Marketing Council, 82UK-11
Mustang Software, 68 1293

N

NASA-Ames, 175
National Council for Educational Technology, 82UK-11
National Institute of Standards and Technology, 295
Natural MicroSystems, 187 1201
NCR, 38, 187, 212, 272 1202 1226 1233
NEC, 23, 262 1222
NEC Technologies, 59, 269 1223 1275
New England Software, 226 1120
NewQuest Technologies, 83 1150
NewTek, 106 1138
New Video, 60 1280
Next, 23, 134
Nippon Telegraph & Telephone, 134
NoRad, 64 1287
Novell, 23, 119, 259, 82IS-3
Nu-Mega Technologies, 297 1149

O

Oak Solutions, 82UK-11
Ohio State University, 175
Olivetti, 291, 82IS-7
On Technology, 23
Opcode Systems, 82UK-11
Open Systems, 291
Orchid Technology, 299
Osaka University, 134
Otis Elevator, 291
Oxford University, 82IS-3
Oxford University Press, 82UK-6 977

P

Pacific Gold Coast, 51 1219
Palindrome, 192 1324
Panasonic, 82UK-11
Panasonic Broadcast and Television Systems, 106 1139
Paradise, 299
Passport Designs, 23, 82UK-11
Patton Electronics, 68 1292
Perceptive Solutions, 83 1153
Performance Technology, 192 1325
Pericom Technology, 82UK-3
Personal Data Systems, 187 1203
Philips, 82UK-11
Phoenix Technology, 165
Photonics, 291
PK Electronics, 82IS-3
Polhemus, 134
Positive, 58 1272
Power Up Software, 226 1121
Prudential, 82UK-3
Psion Dacom, 82IS-3

Q

Quantum, 42 1236
Quarterdeck Office Systems, 83 1161
Quorum Software Systems, 23

R

Rambus, 23
RAM Mobile Data, 291
Research Machines, 82UK-3
RF Data, 291
Rhetorex, 187 1204
Rockwell International, 187 1205
Roykore, 226 1122

S

Safari Systems, 38, 83 1162
Safety Power Group, 82IS-29 1327
Sage, 82UK-3
Samsung, 23, 212
The Santa Cruz Operation, 23
Sanyo, 82IS-3
Sequential Circuits, 82UK-11
Server Technology, 64 1286
Sharp, 23
Shiva, 259
Signalysys, 82IS-29 1326
Silicon Graphics, 23
Slate, 212
SoftSource, 82 1313
Software Interphase, 74 1303
Software Publishing, 226 1123
Software Research, 187 1206
Sony, 262
Sota Technology, 83 1163
Spectral Synthesis, 187 1207
Specular International, 23
Spinnaker Software, 226 1124
Spyglass, 80 1309
Stacey, 82UK-11
Stanford University, 134
Street Electronics, 165, 187 1208
Studio Vision, 82UK-11
SunSoft, 23
Symantec, 83, 279 1160
Syracuse University, 175

T

Tandy, 267
Technical Aesthetics Operations, 59 1277
Telepresence International, 175
TeleSensory Systems, 187, 82IS-43 1209
Televideo, 82UK-3
Texas Instruments, 34, 83, 165, 187 1166 1210
Threadz, 82UK-3
Tilcon Software, 226 1125
Toshiba, 23
Trantor Systems, 83 1167
TriGem, 212 1232
Truevision, 106 1140
Tseng Laboratories, 299
Tskuba University, 134
Turtle Beach Systems, 187, 82IS-43 1211

U

University of California at San Diego, 134
University of Leiden, 82IS-13
University of North Carolina at Chapel Hill, 175
University of Utrecht, 82IS-13
UNX, 175

V

Video Electronics Standards Association, 269
Video Seven, 299
Visual Business Systems, 226 1126
Visual Solutions, 80 1312
Voice Computer, 187 1212
Votrax, 187 1213
Voyetra Technologies, 187, 82IS-43 1214
VPL, 134

W

Wang Laboratories, 187, 82IS-43 1215
Ward Systems, 74 1302
Western Digital Imaging, 299
Western Systems, 82UK-3
West Point Creative, 82UK-11
Wright-Patterson Air Force Base, 175
Wyse, 82UK-3

X

Xerox Palo Alto Research Center, 134
Xios Systems, 82IS-30 1328
Xircom, 291

Y

Yamaha, 82UK-11

Z

Zenith Data Systems, 82IS-3
ZSoft, 226 1127

World Radio History

FREE Software *Instantly* On-Line With BYTE DEMOLINK

Download free demo software from top publishers directly to your computer. . .for just the cost of a phone call!

BYTE DEMOLINK lets you preview software instantly by calling the telephone number in the city nearest you. All you need to access BYTE DEMOLINK is a PC, a modem and a telecommunications program. The latest demo software is at your fingertips for your evaluation.

Call BYTE DEMOLINK today to connect with these free software demos—It's only a phone call away!



BYTE DEMOLINK Free Demo Download 617•861•9767*

*Call the nearest DEMOLINK office anytime. Telecom settings: 2400 or 1200 baud, 8 data bits, 1 stop bit, and no parity. Enter DEMOLINK at the prompt.

Chicago	Denver	Los Angeles	New York	San Francisco	Toronto	Washington, DC
312-616-1071	303-220-0328	213-383-9856	212-797-5620	415-434-4510	416-960-3187	202-463-4920

Circle 64 on Inquiry Card.

Here are the newest software packages available on DEMOLINK:

AutoPACK Tutor
A powerful interactive computer-based AutoCAD training program for novice or experienced users. Tutor starts with an introductory module on the basics of AutoCAD, includes an exercise module that takes the user through step-by-step instructions of object snap, dimensioning, blocks, etc., and has a complete on-line reference system that replaces AutoCAD "Help" with animated examples and clear explanations. AutoPACK Tutor by Grabert Systems, Inc.
Select the file aptdemo.exe

TropicSoft C++ Classes
A set of the most efficient and complete C++ classes for building MS-DOS Windows application interfaces. Designed to dramatically reduce memory and exe size, increase execution speed and reduce lines of code by as much as 80%. Also features the flex "C" programming to compile in any memory model and run in any Windows mode. (Source code available.)
Select the file tsdemo.exe

WINFAX PRO 2.0
Send and receive laser quality faxes from any Windows 3 application directly to any fax device or your PC. WINFAX PRO is recognized by Windows as a print device so a single fax can be composed from within pages of different Windows applications. Specify at what date and time the fax will be sent, and WINFAX PRO will send the fax to either one recipient or a group of recipients. Faxes can be printed or viewed upon receipt. WINFAX PRO manages fax numbers, recipients and groups with its built-in phonebooks. Cover pages can be fully customized to include log files, ASCII text files and fax merge capabilities. Call 1-800-268-6082 for more information.
Select the file winfax.exe

ZyINDEX
ZyINDEX, by ZyLAB Corp., is the premiere text retrieval system for DOS and Windows. Search thousands of documents in seconds, regardless of where documents are located or with what word processor they were created.
Select the file zyindex.exe

DEMOLINK Windows
Use our new Windows front-end software to automate your DEMOLINK sessions.
Select the file dlwin.exe

Other Software Packages Available:

ASQ, by Qualitas
C++/Views, CNS, Inc.
C-Scape with Look & Feel, Liant Software Corp.

World Radio History

PRINT QUEUE

HUGH KENNER

Ways to Keep It Lucid

There's more to desktop publishing than meets the eye

Gabble-gabble, as in the old CP/M manuals, wasn't written *for* anybody; just "for the record." But a writer ought to envisage a breathing person. The first question should be, "Who'll want it?"

No, rephrase that. People may not know they want it. Let's hope luck will steer them our way. In that hope, the writer's guiding question becomes, "Who needs it?"

Example: You've combined a PC with, say, WordPerfect and a laser printer. Your modest intent is to generate good-looking term papers. You naturally assume you're using an automated typewriter. "Wrong. Professional typesetters know things we don't.... The purpose of this book is to let you in on some of the secrets that have been used for centuries to make type pleasing, beautiful, readable, legible, and artistic—secrets we just weren't taught in Typing 1A." If you lighted on that passage, you were lucky.

It's from the page headed "Read me first" in a book called *The PC Is Not a Typewriter* by Robin Williams. The very look of that page helps Williams make her first point; the book, we're told, was itself produced on a PC. One guiding theme: A typewriter's conventions (e.g., two spaces at sentence breaks, underlining for italics, and dittos for quotation marks) derive from a small set of characters, all the same width. Proportional spacing leaves such dodges looking terrible. Eighteen short chapters show us what we need to know; more important, they convince us, visually, of our need to know it.

James Felici's *A Desktop Style Guide* contains information of the same order, but it seldom makes you imagine you're being talked to. It's "a quick reference, one to keep on your desk next to your dictionary." A sentence informs us, "Punctuation marks, including periods, commas, and semicolons, should be followed by only one word space." That's the substance of a whole chapter by Williams. ("Word space" means the space you leave after a word, as distinguished from the gaps between letters, which you'd not be aware of till you'd gotten as far as "kerning," by which time you're an advanced student already.) No, not that he is crabbed or she verbose; it's just that she has a reader in mind, still typewriter-oriented, whereas reference manuals assume you know what you're after.

Visit a different niche for another model opening: "Object-oriented technology is arguably the most exciting and least understood development in software today. Given the amount of hype coming from both media and manufacturers, it's hard for corporate managers to assess its true potential." Managers will need that understanding to decide about investing in a massive switchover. In *Object-Oriented Technology: A Manager's Guide*, David A. Taylor offers a crisp 146 pages of help. It's the best overview of object-oriented programming I've found.

Each paragraph in Taylor's nine chapters has a summary in the margin: "Corporations are drowning in data"; "The failure lies in software"; "Most software is delivered late and over budget"; "We need better software, and we need it faster." That's a neat device for tracking the argument. The diagrams are neat, too. So is a crisp paragraph like this: "It's possible to be quite conversant in 'object-speak' using no more than ten basic terms." (He lists them.) "The appendix at the back of this guide defines these ten concepts." (As it does, with clarity.)

What makes the book exemplary is Taylor's exact conception of just what order of help he's offering to whom. We nonmanagers may profitably eavesdrop.

And in *Advanced Windows Programming*, Martin Heller informs the intrepid that whereas "hello, world" in C needs but five lines, even counting two brackets, the equivalent Windows version uses 80-odd lines in three files. Clearly, we're venturing into something deep; Heller adduces "the dreaded map designation terra incognita" that confronted fifteenth-century sailors.

Those sailors were committed to getting somewhere. Likewise, Heller assumes a reader committed to achieving something venturesome but needing help with vast unknown areas; Windows programming is a *very* new discipline. Fresh from braving such seas himself, he's comfortable with an author-reader relationship subsumed by "we." We readers are comfortable, too.

Toy programs make points but seldom do anything useful; no one ever pretended that "hello, world" had a use, apart from illustrating elements of syntax. In the real world of Windows, code size is an overarching concern, so we'll work on a long program (an image processor). Most of the book shows how it's developed, chunk by chunk.

I've never used Windows, and know little of C, but I didn't need to spot BYTE's Barry Nance in the list of "beta readers" to feel confident. Deft exposition—not syntactic smoke and mirrors—has an authority you can't mistake. Heller's work, like the others, is serene in its understanding of whom it's for and why. ■

The PC Is Not a Typewriter, Robin Williams, Peachpit Press, 1991, $9.95, 92 pp., ISBN 0-938151-49-5.
A Desktop Style Guide, James Felici, Bantam, 1991, $11.95, 129 pp., ISBN 0-553-35445-0.
Object-Oriented Technology: A Manager's Guide, David A. Taylor, Addison-Wesley, 1991, $19.50, 146 pp., ISBN 0-201-56358-4.
Advanced Windows Programming, Martin Heller, John Wiley & Sons, 1992, $32.95 ($72.90 with disks), 370 pp., ISBN 0-471-54711-5.

Hugh Kenner is Franklin and Callaway Professor of English at the University of Georgia. He writes for publications ranging from the New York Times *to* Art & Antiques. *His recent books include* Mazes *and* Historical Fictions. *He can be contacted on BIX as "hkenner."*

World Radio History

Where Do You Go for Help When You're the Expert?

BIX – the On-Line Service for People Who Know Computers!

Get answers, advice and code from top programmers, designers, and consultants. BIX is home to hardware and software engineers, systems designers, independent consultants, technology buffs and computer industry celebrities. ***All sharing information on their favorite subject ... computing!*** And the resources on BIX are substantial.

More High-Quality Tools and Information on BIX.

Our software libraries are packed with the latest high-quality tools, programs and code to help you do a better job. So, whether you're looking for a special utility, TSR, highly qualified advice or just stimulating conversation, you'll find it on BIX.



Get Answers in These Conferences and Many Others:

borland	Borland International official technical support
c.plus.plus	Discuss the C++ programming language
ibm.windows	IBM/Microsoft Windows
ibm.os2	OS/2 Operating System
ibm.utils	Utility software for IBM Computers
microsoft	Products from Microsoft

Subscribe to BIX On-line for Only $39 a Quarter Now!

Just set your telecommunications program for full duplex, 2400 or 1200 baud, 7 bits, even parity, 1 stop bit. Get your Visa, MasterCard, or American Express card ready. Have your modem call 617-861-9767*, enter **"bix"** at the prompt. When you are prompted for **"Name?"** enter **"bix.deal"** and complete on-line registration.

Money-Back Guarantee!

Try BIX for 30 days and if you're not completely satisfied, call Customer Service and we'll refund your subscription fees. **But if you decide BIX is for you, we'll give you an *additional 30 days* on your annual subscription.**

*Connect to BIX locally via BT Tymnet—call 800-336-0149 for your local access number; fees are outlined on-line. Bix handles billing for BT Tymnet connect fees. Other access available. Call BIX at 800-227-2983 or 617-354-4137 for more information.

Circle 450 on Inquiry Card.

World Radio History

STOP BIT

MARSHALL BRAIN

HIDDEN PERSUADERS

We all know how different types of people gravitate toward different types of computers, and I see this process every day walking around campus. In the design school, they use Macs. In engineering, networked Unix workstations dominate the scene. In the business school, you see lots of PCs and clones. Each machine attracts a certain type of person because of its operating system, applications base, and features.

The computer you use has a strong effect on how you work and think

But have you ever thought about how the machine you use affects you as a programmer or developer? The design of the operating system creates an environment, and this environment directly manipulates your thoughts. Your machine controls your brain.

When you create a program, you are forced to make decisions. The operating system controls those decisions by making certain things easy and other things hard. Being human, we tend to go down the easy path as often as we can, and this directly affects the code and applications that we create on a given machine. All you have to do is look at the applications and utilities on a system to see the long-term effects of these paths.

Take, for example, TSR programs on the PC. Where in the world did they come from? There were none, then there was Sidekick, and then there were a thousand of them almost overnight.

DOS contains a function—the terminate-but-stay-resident function—that lets a piece of code be loaded into memory permanently. Another part of DOS makes it possible for the programmer to inspect incoming keystrokes in the background so that a certain hot-key sequence can be used to activate the TSR even if another application is loaded and running. As soon as someone figured this out, TSRs exploded onto the scene.

Of course, there is a downside to the TSR capability: It makes viruses easy to create as well. And, as you might expect, they also exploded. Unix makes viruses much harder to create so you rarely see them there.

Here's another example. You are writing code and you want to do a `malloc(4000000)`—an allocation request for a 4-MB block of memory. The PC laughs at this request. So does the Mac. But Unix says, "OK." You can bet that controls the way people think! Having access to an almost unlimited memory space changes your brain. It is very freeing.

What about the much-heralded "look and feel" of the Mac? It is quietly imposed on any developer because it is the only easy way to do things. You can create a Mac-style menu, button, or dialog box with a few lines of code. Doing things any other way would take months of work, so why bother?

And then there is the case of the talking moose. This public domain program runs on a Mac. Every so often, a little dialog box with a moose head in it pops onto the screen, and the moose says something witty using the Mac's voice-synthesis library. Many people who see this program wonder why. I believe that the existence of the talking moose was preordained by the Mac's operating system. The talking moose *had* to be created. Given an operating system that contains a voice-synthesis module, easy drawing and animation facilities, background processing, and desk accessories, the talking moose's existence was as predictable as frost on a cold morning.

No one thought about rotating three-dimensional graphics when computers were as big as barns and executed 20,000 instructions per second. But in a 20-million-instruction-per-second world, 3-D becomes possible, and people think about it all the time. If the operating system supplies a set of canned routines that make it easy, everyone will use it.

Don't be fooled into underestimating the system's effect on you. For example, I distinctly remember seeing a Mac for the first time. I was in college, and three of us piled into my pickup truck to go see the one Mac in Albany, New York. I remember sitting down and using the spray-paint tool in the original MacPaint and feeling my brain explode. It was amazing! You could do *anything* with this machine. I had never even conceived of the things this machine could do, which shows how much of a constraint the PC had put on my mind. It is hard to have graphical dreams in a textual world.

The choices you make as you are creating an application are directly controlled by the environment you work in. Choose carefully. ■

Marshall Brain is a faculty member at North Carolina State University and the author of Motif Programming: The Essentials and More *(Digital Press). You can reach him on BIX c/o "editors."*

Stop Bit is a forum for informed opinion on personal computing topics. The opinions expressed are those of the author and not necessarily those of BYTE. Your contributions and comments are welcome. Write to: Editor, BYTE, One Phoenix Mill Lane, Peterborough, NH 03458.

ILLUSTRATION: MIKE QUON © 1992

World Radio History

WE COULD CHALLENGE THE COMPETITION TO MATCH OUR NEW 4 HOUR ON-SITE SERVICE, BUT THEY WOULDN'T SHOW UP UNTIL TOMORROW.

Call for emergency computer service from the other guys and what do you get? Often, an agonizing wait, watching your business slowly grind to a halt.

Which is why Dell is introducing Critical Care℠ service in 17 major metropolitan areas. Beginning March 30, if you have a mission-critical problem, you'll be able to get a technician on-site in no more than 4 hours.△

And not just some guy with a set of screwdrivers. We're talking about a full-fledged Novell-certified field engineer trained on every Dell system.

When he arrives, he will have been briefed on your problem. Given a history of your system. And equipped from a multi-million dollar parts inventory.

In short, a computer commando.

But the best part about Critical Care is that you'll probably never have to use it. Our award-winning technical hotlines solve 90% of problems reported over the phone, usually in 10 minutes or less.

So call us and ask for more details about Critical Care. Or call the other guys and ask about their emergency service. They'll get back to you.

Eventually.

800-545-3604

TO ORDER, CALL PLEASE REFERENCE #11E64
HOURS 7AM-9PM CT MON-FRI, 9AM-4PM SAT, 10AM-3PM CT SUN
IN CANADA, CALL 800-668-3021 IN MEXICO 95-800-010-0664

Same-day 4-hour on-site service available provided that Dell initiates service dispatch by 2pm CT. 4-hour service contract must be purchased. Critical Care is a service mark of Dell Computer Corporation.

World Radio History

AFTER YOU PUT YOUR JAW BACK IN ITS PLACE, CALL US.

You'll find the Dell® 486P/16 as surprising as our competitors find it shocking.

It delivers full-fledged i486™SX performance at the price of an i386™DX machine; up to 40% more processing power at virtually no additional cost.

And that's just for starters. Because the 16 MHz i486SX processor easily upgrades all the way up to a high-end 33 MHz i486DX system, and even beyond.



In other words, this is a computer that comes with the future built in. Along with some Dell technical innovations you'll be amazed to get at a price like this.

Features like programmable Flash EPROMs, for example, that make BIOS upgrading a matter of slipping in a diskette. 32-bit SIMMs with gold-plated connectors for greater reliability. And built-in 1024 x 768 video support for high resolution graphics.

All this, starting at an unbelievable $1,749 for a complete system.

intel inside™

So when you've finished staring at this page, call and ask about the support that comes along with the Dell 486P/16. And be prepared to be speechless again.

$1,749 (Lease : $66/Month**)
Dell 486P/16 16 MHz i486SX System
System includes 50 MB Hard Drive, VGA Color Monitor, 2 MB RAM and 1 Floppy Drive

800-545-3607

TO ORDER, CALL PLEASE REFERENCE #11ED2
HOURS 7AM-9PM CT MON-FRI, 9AM-4PM SAT, 10AM-3PM CT SUN
IN CANADA, CALL 800-668-3021 IN MEXICO, 95-800-010-0664

Circle 63 on Inquiry Card.

World Radio History

SOME MORE LOW BLOWS TO THE COMPETITION.

Here's news that's going to make a lot of computer manufacturers wince. We've dramatically reduced the prices of our entire range of Dell systems. So now you can buy one of the best computers on the market without knocking out your budget.

And while other companies' standards often go down along with their prices, we'll still give you the service and support package described by *PC Week's* editors as "overkill." Our toll-free technical hotlines solve 90% of reported problems over the phone, usually in 10 minutes or less. Our TechFax℠ line offers system information 24 hours a day. And if needed, a trained technician can be at your desk-side with a solution in hand, usually by the next business day.△

Perhaps this is why Dell comes so highly recommended. After all, we've won *PC Week's* Corporate Satisfaction Poll for PCs, portables and servers an unprecedented eight times.

So call us and find out why over two-thirds of the FORTUNE 500® now use Dell computers. But don't bother talking to our competitors; they're a little short of breath.

We just took the wind out of their sales.

DELL COMPUTER CORPORATION

800-232-5620

TO ORDER, CALL PLEASE REFERENCE #11E65.
HOURS: 7AM-9PM CT MON-FRI, 9AM-4PM SAT, 10AM-3PM CT SUN
IN CANADA, CALL 800-668-3021. IN MEXICO, 95-800-010-0664.

LOWERED BY $300

NX20 from Dell 20 MHz i386™SX System
System includes
2 MB RAM, 40 MB Hard Drive, VGA LCD

- 60 MB Hard Drive also available
- 8.3 x 11" footprint
- 6.8 lbs.
- 2-3 hour battery life
- CCFT edgelit triple supertwist display
- 32 Gray levels
- Full size keys with 3mm travel
- Modem, memory and coprocessor options
- One year return to factory service

LOWERED BY $300

Dell 486P*/20 20 MHz i486™SX System
System includes
4 MB RAM, 80 MB Hard Drive,
UltraScan™ 14C Color Monitor

- Upgradeable processor design
- Up to 40% faster performance than 386DX systems
- Keyboard Password Protection
- RAM expansion to 64 MB
- 1024 x 768 non-interlaced monitor with 70 Hz refresh rate for flicker free operation
- 1 floppy drive

LOWERED BY $800

Dell 486P/33 33 MHz i486 System
System includes
4 MB RAM, 100 MB Hard Drive,
UltraScan 14C Color Monitor

- Upgradeable processor design
- Programmable Flash EPROM for easy BIOS upgradeability
- Expands to 64 MB RAM using 32-bit SIMMs with gold-plated connectors
- 1024 x 768 non-interlaced monitor with 70 Hz refresh rate for flicker free operation
- 1 floppy drive

LOWERED BY $1,000

Dell 486D/33 33 MHz i486 System
System includes
4 MB RAM, 230 MB Hard Drive,
UltraScan 14C Color Monitor

- 5 storage bays, 6 16-bit slots
- 8 KB internal cache
- RAM expands to 64 MB using 32-bit SIMMs with gold-plated connectors
- 1024 x 768 non-interlaced monitor with 70 Hz refresh rate for flicker free operation
- 1 floppy drive

INTRODUCING

Dell 325SX 25 MHz i386SX System
System includes
2 MB RAM, 50 MB Hard Drive,
VGA Color Monitor

- 1024 x 768 integrated video support
- Novell certified
- Expandable to 8 MB RAM
- 3 16-bit expansion slots
- Keyboard Password Protection
- 1 floppy drive

INTRODUCING

Dell 486D/16 16 MHz i486SX System
System includes
2 MB RAM, 50 MB Hard Drive,
VGA Color Monitor,

- Upgradeable processor design
- Programmable Flash EPROM for easy BIOS upgradeability
- RAM expands to 64 MB using 32-bit SIMMs with gold-plated connectors
- SmartVu™ Diagnostic Display
- Can support 5 storage devices
- 6 16-bit expansion slots
- 1 floppy drive

intel inside

All prices and specifications are subject to change without notice. **Payment based on 36 month open end lease. Leasing arranged by Leasing Group, Inc. In Canada and Mexico, configurations and prices may vary. Dell is a registered trademark. UltraScan and SmartVu are trademarks, and TechFax is a service mark of Dell Computer Corporation. i386, i486 and the Intel Inside Logo are trademarks of Intel Corporation. FORTUNE 500 is a registered trademark of The Time, Inc. Magazine Company. Dell disclaims proprietary interest in the marks and names of others. Service provided by BancTec Service Corp. On-site service may not be available in certain remote locations and is not available with NX20. Shipping and handling and applicable sales tax not included in the price. ©1992 Dell Computer Corporation. All rights reserved.

World Radio History

Circle 62 on Inquiry Card.

WE COULD CHALLENGE THE COMPETITION TO MATCH OUR NEW 4 HOUR ON-SITE SERVICE, BUT THEY WOULDN'T SHOW UP UNTIL TOMORROW.

Call for emergency computer service from the other guys and what do you get? Often, an agonizing wait, watching your business slowly grind to a halt.

Which is why Dell is introducing Critical Care℠ service in 17 major metropolitan areas. Beginning March 30, if you have a mission-critical problem, you'll be able to get a technician on-site in no more than 4 hours.△

And not just some guy with a set of screwdrivers. We're talking about a full-fledged Novell-certified field engineer trained on every Dell system.

When he arrives, he will have been briefed on your problem. Given a history of your system. And equipped from a multi-million dollar parts inventory.

In short, a computer commando.

But the best part about Critical Care is that you'll probably never have to use it.

Our award-winning technical hotlines solve 90% of problems reported over the phone, usually in 10 minutes or less.

So call us and ask for more details about Critical Care. Or call the other guys and ask about their emergency service. They'll get back to you.

Eventually.

800-545-3604

TO ORDER, CALL PLEASE REFERENCE #11E64
HOURS 7AM-9PM CT MON-FRI, 9AM-4PM SAT, 10AM-3PM CT SUN
IN CANADA, CALL 800-668-3021 IN MEXICO, 95-800-010-0664.

△Same-day 4-hour on-site service available provided that Dell initiates service dispatch by 2pm CT. 4-hour service contract must be purchased. Critical Care is a service mark of Dell Computer Corporation.

AFTER YOU PUT YOUR JAW BACK IN ITS PLACE, CALL US.

You'll find the Dell® 486P/16 as surprising as our competitors find it shocking.

It delivers full-fledged i486™SX performance at the price of an i386™DX machine; up to 40% more processing power at virtually no additional cost.

And that's just for starters. Because the 16 MHz i486SX processor easily upgrades all the way up to a high-end 33 MHz i486DX system, and even beyond.



In other words, this is a computer that comes with the future built in. Along with some Dell technical innovations you'll be amazed to get at a price like this.

Features like programmable Flash EPROMs, for example, that make BIOS upgrading a matter of slipping in a diskette. 32-bit SIMMs with gold-plated connectors for greater reliability. And built-in 1024 x 768 video support for high resolution graphics.

All this, starting at an unbelievable $1,749 for a complete system.

intel inside™

So when you've finished staring at this page, call and ask about the support that comes along with the Dell 486P/16. And be prepared to be speechless again.

$1,749 (Lease : $66/Month**)
Dell 486P/16 16 MHz i486SX System
System includes 50 MB Hard Drive, VGA Color Monitor, 2 MB RAM and 1 Floppy Drive

800-545-3607

TO ORDER, CALL PLEASE REFERENCE #11ED2
HOURS 7AM-9PM CT MON-FRI, 9AM-4PM SAT, 10AM-3PM CT SUN
IN CANADA, CALL 800-668-3021 IN MEXICO, 95-800-010-0664

Circle 63 on Inquiry Card.

World Radio History